# VT520/VT525 Video Terminal

# **Programmer Information**

digital

Order Number: EK-VT520-RM. A01

#### July 1994

Digital Equipment Corporation makes no representations that the use of its products in the manner described in this publication will not infringe on existing or future patent rights, nor do the descriptions contained in this publication imply the granting of licenses to make, use, or sell equipment or software in accordance with the description.

DEC, OpenVMS, VT, and the DIGITAL logo are trademarks of Digital Equipment Corporation.

ADDS is a trademark of Applied Digital Data Systems, Inc.

IBM, ProPrinter, and PS/2 are registered trademarks of International Business Machines Corporation.

MS-DOS is a registered trademark and Windows is a trademark of Microsoft Corporation. SCO is a trademark of Santa Cruz Operations, Inc.

TVI is a trademark of TeleVideo, Inc.

UNIX is a registered trademark of UNIX System Laboratories, Inc.

WY and WYSE are registered trademarks of Wyse Technologies.

All other trademarks and registered trademarks are the property of their respective holders. The Energy Star emblem does not represent EPA endoresement of any product or service.

Copyright © Digital Equipment Corporation 1994. All Rights Reserved. Printed in U.S.A.

For copies of manuals, contact your local sales office.

This document was prepared using VAX DOCUMENT Version 2.1.

# **Preface**

### Introduction

This manual provides detailed information for advanced users, consultants, and programmers. This manual has the following parts, chapters, and appendices:

- Part I, VT520 Video Terminal
  - Chapter 1, Overview
  - Chapter 2, Set-Up
  - Chapter 3, Desktop Features
- Part II, VT520 ANSI Mode
  - Chapter 4, ANSI Control Functions Summary
  - Chapter 5, ANSI Control Functions
  - Chapter 6, SCO Console Emulation
  - Chapter 7, Character Sets
  - Chapter 8, Keyboard Processing
  - Chapter 9, Communications
  - Chapter 10, Printer Port
- Part III, VT520 ASCII Emulation
  - Chapter 11, ASCII Emulations and Control Functions
  - Chapter 12, ASCII Escape Sequences
  - Chapter 13, Defining and Loading ASCII Character Fonts
- Appendix A, VT Keyboard Legend Data
- Appendix B, Enhanced PC Keyboards
- Appendix C, ASCII Keycodes and Local Functions
- Appendix D, VT520 Termcap Data
- Appendix E, ANSI Control Function Index

#### Conventions

The following conventions are used in this manual:

Set-Up features	Termin	al Set-U <sub>l</sub>	menu se	elections	appear in <b>boldface</b> type.
Alt/Ctrl/Print Screen	Multiple keys are separated by a slash (/) and should be pressed in combination. That is, all three keys Alt, Ctrl, and Print Screen are pressed down at the same time.				
Characters in control functions	each cl	Control function characters are in <b>boldface</b> type. Below each character is a column/row number that indicates the character's position in a standard code table. For example:			
	ESC	#	6	<b>=</b>	Control function
	1/11	2/3	3/6	<b>=</b>	Column/row numbers
Parameters	Param	eters app	ear in ita	lic type.	
Note	Provides general information.				

#### **How to Use This Manual**

The *VT520 Video Terminal Programmer Information* is written for four audiences: an advanced user, who needs to know more about the terminal Set-Up features; a programmer, who develops application programs; a software product support person, who provides assistance to application programmers and users; and a hardware systems engineer, who need more information on terminal connections.

#### **Advanced User**

If you have read the *VT520 Video Terminal Installation and Operating Information* manual and need more information on the terminal Set-Up features, you may wish to refer to the following:

- Index
- Chapter 1—Overview—Provides a brief summary of the product.
- **Chapter 2—Set-Up**—Describes each entry in the Set-Up menus in the order that is displayed in the terminal.
- Chapter 3—Desktop Features—Provides a more in-depth description of the desktop features of the terminal.
- Chapter 6—Keyboard Processing—Describes the differences in the types
  of keyboard layouts supported, local functions, and accessibility aids.

#### **Programmer**

If you are using <u>ANSI control functions</u> for your program, then you may wish to start with Part II of the manual:

- Chapter 4—ANSI Control Function Summary— Provides a tutorial section on Control Functions and information on designing and down-line loading a Soft Character set (soft font). In this chapter, the Control Functions are grouped according to the task to be performed. The information on each Control Function is very brief. If you need more information, the mnemonic at the end of the line item refers to a command section in Chapter 5.
- **Chapter 5—ANSI Control Functions**—Provides in-depth information on each control function listed in alphabetic order according to the mnemonic.
- **Chapter 2—Set-Up**—Lists the Set-Up factory defaults at the end of this chapter, with their host control code mnemonic.

- Chapter 6—Keyboard Processing—Describes the keyboard layouts, keyboard-to-host interface, keypad sequences, local functions, LEDs controls, languages, accents, scan codes, and control codes.
- **Chapter 9—Communications**—Describes the serial communications from the terminal to the host ports and the hardware and software handshaking.
- **Chapter 10—Printer Port**—Describes the parallel printer port and the switching sequences for the modes supported.
- Appendix A—VT Keyboard Legend Data
- Appendix B—Enhanced PC Keyboard Legend Data
- Appendix D-VT500 Termcap Data

If you are developing a application program for a <u>SCO Console</u>, then you may wish to refer to:

• **Chapter 6—SCO Console Emulation**—Describes the SCO Console mode, including the Control Functions relative to the SCO Console applications.

If you are using <u>ASCII control functions</u> for your program, then you may wish to start with Part III of the manual:

- Chapter 11—ASCII Emulations and Control Functions— Provides an
  overview of the ASCII emulation, the coding notation, and the symbols used
  in the ASCII sequence tables.
- **Chapter 12—ASCII Escape Sequences**—Summarizes the ASCII escape and control sequences for the various ASCII emulation modes, according to the task to be performed.
- Chapter 13—Defining and Loading ASCII Character Fonts Provides specific information on loading font banks and designing an ASCII character font.
- Appendix C—ASCII Keycodes and Local Functions

#### **Software Product Support**

If you are helping a user or programmer with an application, then you may wish to refer to the following:

- Appendix E—ANSI Control Function Index—Lists the control functions
  by their final character, which makes them easier to find in a program. The
  mnemonic at the end of the line item refers to a command in Chapter 5, listed
  in alphabetic order.
- **Index**—Lists control functions by mnemonic or by name and lists other subjects by topic.
- **Chapter 5—ANSI Control Functions**—Provides in-depth information on specific control functions.
- **Chapter 6—Keyboard Processing**—Lists the scan codes Make and Break sequences.
- Appendix D—VT500 Termcap Data—Provides the Termcap information for ANSI emulations.

#### **Hardware Systems Engineer**

If you are helping a user to install the terminal or to operate within a specific environment, then you may wish to refer to the following:

- **Index**—Search by topic.
- **Chapter 1—Overview** Provides a brief summary of the product.
- **Chapter 2—Set-Up** Describes each entry in the order that is displayed in the terminal, starting with the **Actions** menu and lists the modes supported. Also lists the Set-Up factory defaults.
- **Chapter 9—Communications**—Describes the serial communications from the terminal to the host ports, pin numbers and signals, and the hardware and software handshaking.
- **Chapter 10—Printer Port**—Describes the parallel printer port, pin numbers and signals, and modes supported.

# **Contents**

Preface		
Part I	VT520 Video Terminal	
1 Ov	erview	
	Communications Features Keyboard Features Printer Port Features Display and Text Capabilities ANSI ANSI Enhanced Set-Up Desktop Productivity Features Character Set Support Ergonomics (Human Factors) Features Field-Upgradable Firmware	1-1 1-2 1-3 1-3 1-3 1-4 1-4 1-4 1-4 1-5 1-6
2 Set	-Up	
2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2.	1.1 Effects of Entering Set-Up 1.2 Set-Up Languages 1.3 Power-On Settings and Defaults 1.4 Self-test Error Messages 1.5 Context Sensitivity 1.6 Set-Up Summary Line 1.7 Set-Up Status Messages 1.8 Status Line 1.9 Keyboard Indicator Line 2 Set-Up Screen Text 3 Main Menu 3.1 On-Line 3.2 Save Settings 3.3 Restore Settings 3.4 Exit Set-Up	2-1 2-2 2-2 2-3 2-3 2-5 2-5 2-6 2-6 2-7 2-8 2-9 2-9 2-9 2-9 2-10 2-10 2-11

2.4.6	Banner Message	2–11
2.5	Multiple Sessions	2–11
2.5.1	Enabling and Controlling the Session Configuration	2–12
2.5.2	Multiple Sessions using a Terminal Server with TD/SMP	2–12
2.5.3	Multiple Sessions using SSU Host Software	2–12
2.5.4	Opening Another Session	2-12
2.5.5	Restoring an Interrupted Session	2-13
2.5.6	Session Management	2-13
2.6	Session Menu	2-13
2.6.1	Select Session	2-14
2.6.2	Session Name	2–14
2.6.3	Pages per Session	2–14
2.6.4	Soft Character Sets/Session	2–16
2.6.5	Save Settings for All and Restore Settings for All	2–16
2.6.6	Copy Settings from Menu	2–17
2.6.7	Update Session	2–17
2.7	Resetting and Restoring Defaults	2–18
2.7 2.7.1	Reset Session	2–18
2.7.2	Restore Factory Defaults	2–18
2.7.2 2.8	Display Menu	2–10
2.8.1	Lines per Screen	2–19
	•	2–20
2.8.1.1	Auto Resize	
2.8.2	Lines per Page	2–20
2.8.3	Review Previous Lines Buffer	2–21
2.8.4	Columns per Page, Clear on Change	2–22
2.8.5	Status Display	2–22
2.8.6	Scrolling Mode	2–22
2.8.7	Screen Background	2–22
2.8.8	Cursor Display	2–22
2.8.9	Cursor Coupling	2–22
2.8.10	Writing Direction	2–23
2.8.11	Zero	2–23
2.8.12	Auto Wrap	2–23
2.8.13	New Line Mode	2–23
2.8.14	Lock User Preferences	2–23
2.8.15	Show Control Characters	2–24
2.8.16	CRT Saver	2–24
2.8.17	Energy Saver	2–24
2.8.17.		2-25
2.8.18	Overscan	2-25
2.8.19	Framed Windows	2-25
2.8.20	Screen Alignment	2-27
2.9	Color Set-Up	2-28
2.9.1	Assign Colors	2-28
2.9.2	Alternate Text Colors	2-30
2.9.3	Define Colors Dialog Box	2-31
2.9.4	Select Color Mode	2-32
2.9.5	ASCII Color Mode	2–32
2.9.6	Bold and Blink Style	2–32
2.9.7	Erase Color	2–32
2.9.8	Reverse and Blank Attributes	2–33
2.9.9	Intensity Attributes	2–33
2.10	Terminal Type Menu	2–33
2.10.1	Emulation Mode	2–33

2.10.2	Terminal ID to Host	2–34
2.10.3	VT Default Character Set	2–34
2.10.4	PCTerm Character Set	2–34
2.10.5	7-Bit NRCS Characters	2-34
2.10.6	Transmit 7-Bit Controls	2-34
2.11 AS	CII Emulation Menu	2-35
2.12 Key	yboard Menu	2-36
2.12.1 °	Keyboard Language	2-37
2.12.2	Define Key Editor	2-37
2.12.2.1	Copy of Key Default—Moving a Standard Function	2-38
2.12.2.2	Customization	2–39
2.12.2.3	Modifier Keys	2–39
2.12.2.4	Creating a New Function	2–39
2.12.2.5	Examples of Creating New Functions	2–39
2.12.2.6	Correcting a Mistake	2–40
2.12.2.7	Creating A New Alphanumeric Key or Keyboard Layout	2–40
2.12.2.7	Examples of Creating New Alphanumeric Keys	2–40
2.12.2.0	User-Defined Keys	2-40
2.12.2.9	Programming Notes	2-41
2.12.2.10		2-41
2.12.3 2.12.4	Save Key Definitions	2-42
	Recall Key Definitions	
2.12.5	Lock Key Definitions	2–42
2.12.6	Caps Lock Function	2–42
2.12.7	Keyclick, Warning Bell, and Margin Bell Volume	2–42
2.12.7.1	Visible Bell	2–43
2.12.8	Keyboard Encoding	2–43
2.12.9	Auto Repeat	2–43
2.12.10	Data Processing Keys	2–43
2.12.11	Application Cursor Keys	2–43
2.12.12	Application Keypad Mode	2–44
2.12.13	Map PC Keyboard to VT	2–44
2.12.14	Ignore Missing Keyboard	2–44
2.13 Cor	mmunication Menu	2–45
2.13.1	Communication Port Select	2–46
2.13.2	Word Size	2–47
2.13.3	Parity	2-47
2.13.4	Stop Bits	2-47
2.13.5	Transmit Speed	2-48
2.13.6	Receive Speed	2-48
2.13.7	Transmit Flow Control	2-48
2.13.8	Receive Flow Control	2-49
2.13.9	Flow Control Threshold	2-49
2.13.10	Transmit Rate Limit, Fkey Rate Limit	2–49
2.13.11	Ignore Null Character	2–50
2.13.12	Local Echo	2–50
2.13.13	Half Duplex	2–50
2.13.14	Auto Answerback	2–50 2–50
2.13.14	Answerback Message	2–50 2–50
2.13.15	Answerback Message	2–50 2–51
	dem Menu	2–51 2–52
2.14 M0 2.14.1		2–52 2–52
	Enable Modem Control	2–52 2–52
2.14.2	Disconnect Delay	2–52 2–53
2.14.3 2 14 4	Modem Low Speed	2-53 2-53
<i>,</i> 144	IVIDOETH LOW SDEED	/-0.3

	2.15	Printer Menu	2-54
	2.15.1	Port Select	2-54
	2.15.2	Print Mode	2-54
	2.15.3	Printer Type	2–55
	2.15.4	Printer Character Sets	2–55
	2.15.4.1		2–56
	2.15.4.2		2–56
	2.15.5	Print Extent	2–56
	2.15.6	Print Terminator	2-56
	2.15.7	Serial Print Speed	2-56
	2.15.8	2-Way Communication	2–57
	2.15.9	Transmit Flow Control	2–57
	2.15.10		2–57
	2.15.11	Word Size	2–57
	2.15.12		2–58
	2.15.13	J	2–58
	2.15.14	1	2–58
	2.16	Tabs	2–58
	2.17	Sound	2–59
	2.18	Set-Up Factory Defaults	2–61
	20	Set of Lactory Behavior.	
2	Dealste	n Factures	
3	Deskto	p Features	
	3.1	Introduction	3–1
	3.2	Invoking Desktop Features	3–1
	3.3	Calculator	3–2
	3.4	Clock	3–5
	3.5	Review Previous Lines	3–7
	3.6	Character Set Tables	3–7
	3.6.1	Show Character Sets feature	3–7
	3.6.2	Banner message	3–8
	3.7	Keyboard Summary	3–8
Pa	art II VT	520 ANSI Mode	
	ANCLO	Santual Franctions Community	
4	ANSI C	ontrol Functions Summary	
	4.1	Introduction	4–1
	4.2	Control Characters	4–1
	4.3	Control Functions	4–5
	4.3.1	Sequence Format	4–5
	4.3.2	Escape Sequences	4–6
	4.3.3	Control Sequences	4–6
	4.3.3.1	Control Sequence Introducer	4–6
	4.3.3.2	Parameters	4–7
	4.3.3.3	Intermediate Characters	4–8
	4.3.3.4	Final Character	4–8
	4.3.4	Device Control Strings	4–8
	4.3.5	Using Control Characters in Sequences	4–9
	4.3.6	7-Bit Code Extension Technique	4–9
	4.4	Working with 7-Bit and 8-Bit Environments	4–10
	4.4.1	Conventions for Codes Received by the Terminal	4–10
	4.4.2	Conventions for Codes Sent by the Terminal	4–10
	4.5	Showing Control Characters	4–11

	4.6	Terminal Management Functions	4–15
	4.7	ANSI Control Function Tables	4–16
	4.7.1	Sessions Management Control Functions	4–16
	4.7.2	Window Management Control Functions	4–17
	4.7.3	Audible Attributes Control Functions	4–18
	4.7.4	Color Selection Control Functions	4–18
	4.7.5	Visual Attributes Control Functions	4–20
	4.7.6	Editing Control Functions	4–21
	4.7.7	Text Processing Control Functions	4–22
	4.7.8	Graphic Character Sets Control Functions	4–25 4–27
	4.7.9 4.7.10	Keyboard Processing Control Functions	4–27
	4.7.10	Printer Control Functions Terminal Management Control Functions	4–33
	4.7.12	Terminal Management—Communications Control Functions	4–39
	4.7.13	Terminal Synchronization Control Functions	4–41
	4.7.14	Reports Control Functions	4–42
	4.8	VT52 Mode Escape Sequences	4–45
5	ANGI C	Control Functions	
J	ANSIC		
		ANSI Conformance Levels	5–1
		CBT—Cursor Backward Tabulation	5–3
		CHA—Cursor Horizontal Absolute	5–3
		CHT—Cursor Horizontal Forward Tabulation	5–4
		CNL—Cursor Next Line.	5–4
		CPL—Cursor Previous Line	5–5
		CPR—Cursor Position Report	5–5
		CRM—Show Control Character Mode	5–6
		CUB—Cursor Backward	5–7
		CUD—Cursor Down	5–7
		CUF—Cursor Forward	5–7
		CUP—Cursor Position	5–8
		CUU—Cursor Up	5–8
		DA1—Primary Device Attributes	5–9
		DA2—Secondary Device Attributes	5–11
		DA3—Tertiary Device Attributes	5–12
		DCH—Delete Character	5–13
		DDD1, DDD2, DDD3	5–14
		DECAAM—Set/Reset Auto Answerback Mode	5–15
		DECAC—Assign Color	5–16
		DECALN—Screen Alignment Pattern	5–17
		DECANM—ANSI Mode	5–18
		DECANM Exit—Exiting ANSI (VT52) Mode	5–19
		DECARM—Autorepeat Mode	5–19
		DECARR—Select Auto Repeat Rate	5–20
		DECARSM—Set/Reset Auto Resize Mode	5–21
		DECATC—Alternate Text Color	5–22
		DECATCBM—Set/Reset Alternate Text Color Blink Mode	5–23
		DECATCUM—Set/Reset Alternate Text Color Underline Mode	5–23
		DECAUPSS—Assigning User-Preferred Supplemental Sets	5–24

DECAWM—Autowrap Mode	5–25
DECBBSM—Bold and Blink Style Mode	5–25
DECBI—Back Index	5–26
DECBKM—Backarrow Key Mode	5–26
DECCANSM—Conceal Answerback Message Mode	5–27
DECCAPSLK—Caps Lock Mode	5–28
DECCARA—Change Attributes in Rectangular Area	5–28
DECCIR—Cursor Information Report (Terminal to Host)	5–30
DECCKD—Copy Key Default	5–31
DECCKM—Cursor Keys Mode	5–32
DECCKSR—Memory Checksum Report	5–33
DECCOLM—Selecting 80 or 132 Columns per Page	5–34
DECCRA—Copy Rectangular Area	5–35
DECCRTST—CRT Saver Timing	5–36
DECCRTSM—Set/Reset CRT Save Mode	5–37
DECDC—Delete Column	5–37
DECDHL—Double-Width, Double-Height Line	5–38
DECDLD—Dynamically Redefinable Character Sets Extension	5–39
DECDMAC—Define Macro	5–45
DECDLDA—Down Line Load Allocation	5–47
DECDWL—Double-Width, Single-Height Line	5–48
DECECM—Erase Color Mode	5–48
DECEKBD—Extended Keyboard Report	5–49
DECELF—Enable Local Functions	5–51
DECERA—Erase Rectangular Area	5–52
DECES—Enable Session	5–53
DECESKM—Enable Secondary Keyboard Language Mode	5–53
DECFI—Forward Index	5–54
DECFRA—Fill Rectangular Area	5–55
DECFWM—Set/Reset Framed Windows Mode	5–56
DECHDPXM—Set/Reset Half-Duplex Mode	5–56
DECHEM—Hebrew Encoding Mode	5–57
DECHEBM—Hebrew/N-A Keyboard Mapping Mode	5–58
DECHWUM—Host Wake-Up Mode (CRT and Energy Saver)	5–59
DECIC—Insert Column	5–59
DECID—Identify Device	5–60
DECINVM—Invoke Macro	5–61
DECIPEM—Enter/Return from IBM ProPrinter Emulation Mode	5–62
DECKBD—Keyboard Language Selection	5–63
DECKBUM—Typewriter or Data Processing Keys	5–65
DECKLHIM—Keyboard LED's Host Indicator Mode	5–65
DECKPAM—Keypad Application Modes	5–66
DECKPM—Key Position Mode	5–66
DECKPNM—Keypad Numeric Modes	5–67
DECLANS—Load Answerback Message	5–68
DECLBAN—Load Banner Message	5–69
DECLERC Local Function Key Control	5-70

DECLL—Load LEDs	5–71
DECLRMM—Left Right Margin Mode	5–72
DECLTOD—Load Time of Day	5–72
DECMCM—Modem Control Mode	5–73
DECMSR—Macro Space Report	5–73
DECNAKB—Greek/N-A Keyboard Mapping Mode	5–74
DECNCSM—No Clearing Screen On Column Change Mode	5–74
DECNKM—Numeric Keypad Mode	5–75
DECNRCM—National Replacement Character Set Mode	5–75
DECNULM—Null Mode	5–76
DECNUMLK—Num Lock Mode	5–76
DECOM—Origin Mode	5–77
DECOSCNM—Set/Reset Overscan Mode (VT520 only)	5–77
DECPAK—Program Alphanumeric Key	5–78
DECPCCM—Page Cursor-Coupling Mode	5-80
DECPCTERM—Enter/Exit PCTerm or Scancode Mode	5–81
DECPEX—Print Extent Mode	5-83
DECPFF—Print Form Feed Mode	5-83
DECPFK—Program Function Key	5–84
DECPKA—Program Key Action	5–87
DECPKFMR—Program Key Free Memory Report	5–88
DECPS—Play Sound	5–89
DECRARA—Reverse Attributes in Rectangular Area	5–90
DECRC—Restore Cursor	5–92
DECRLCM—Right-to-Left Copy Mode	5–92
DECRLM—Right-to-Left Mode	5–93
DECRPAK—Report All Modifiers/Alphanumeric Key State	5–94
DECRPDE—Report Displayed Extent	5–95
DECRPFK - Report Function Key Definition	5–96
DECRPKT—Report Key Type	5–96
DECRPL—Review Previous Lines Mode	5–97
DECRPM—Report Mode - Terminal To Host	5–98
DECRPSS—Report Selection or Setting	5-102
DECRPTUI—Report Terminal Unit ID	5-104
DECRQCRA—Request Checksum of Rectangular Area	5-105
DECRQDE—Request Displayed Extent	5-105
DECRQKD—Request Key Definition	5-106
DECRQKT—Request Key Type	5–107
DECRQM—Request Mode - Host To Terminal	5-108
DECRQPKFM—Request Program Key Free Memory	5–111
DECRQPSR—Request Presentation State Report	5–111
DECRQSS—Request Selection or Setting	5–112
DECRQTSR—Request Terminal State Report	5–113
DECCTR—Color Table Request	5–114
DECRQUPSS—Request User-Preferred Supplemental Set	5–115
DECRSPS—Restore Presentation State	5–116
DECRSTS—Restore Terminal State	5–117

DECRSTS—Restore Terminal Color Table State	5–118
DECSACE—Select Attribute Change Extent	5–119
DECSASD—Select Active Status Display	5-120
DECSC—Save Cursor	5-120
DECSCA—Select Character Protection Attribute	5-121
DECSCL—Select Conformance Level	5-122
DECSCLM—Scrolling Mode	5-123
DECSCNM—Screen Mode: Light or Dark Screen	5-123
DECSCP—Select Communication Port	5–124
DECSCPP—Select Columns Per Page	5–125
DECSCS—Select Communication Speed	5–126
DECSCUSR—Set Cursor Style	5–127
DECSDDT—Select Disconnect Delay Time	5–128
DECSDPT—Select Digital Printed Data Type	5–129
DECSED—Selective Erase in Display	5–129
DECSEST—Energy Saver Timing	5–130
DECSEL—Selective Erase in Line	5–131
DECSERA—Selective Erase Rectangular Area	5–132
DECSFC—Select Flow Control	5–133
DECSIN—Set Icon Name	5–134
DECSKCV—Set Key Click Volume	5–135
DECSLCK—Set Lock Key Style	5–135
DECSLPP—Set Lines Per Page	5–136
DECSLRM—Set Left and Right Margins	5–137
DECSMBV—Set Margin Bell Volume	5–138
DECSMKR—Select Modifier Key Reporting	5–139
DECSNLS—Set Number of Lines Per Screen	5–140
DECSPMA—Session Page Memory Allocation	5–141
DECSPP—Set Port Parameters	5–142
DECSPPCS—Select ProPrinter Character Set	5–143
DECSPRTT—Select Printer Type	5–144
DECSR—Secure Reset	5–144
DECSRC—Secure Reset Confirmation	5–146
DECSSCLS—Set Scroll Speed	5–146
DECSSDT—Select Status Display (Line) Type	5–147
DECSSL—Select Set-Up Language	5–148
DECST8C—Set Tab at Every 8 Columns	5–149
DECSTBM—Set Top and Bottom Margins	5–149
DECSTR—Soft Terminal Reset	5–150
DECSTGLT—Select Color Look-Up Table	5–151
DECSTRL—Set Transmit Rate Limit	5–152
DECSTUI—Setting Terminal Unit ID	5–153
DECSWBV—Set Warning Bell Volume	5–154
DECSWL—Single-Width, Single-Height Line	5–154
DECSZS—Select Zero Symbol	5–155
DECSWT—Set Window Title	5–156
DECTABSR—Tab Stop Report	5–157
DECTIDOR TO DUP INPOIL	0 101

DECTCEM—Text Cursor Enable Mode	5-157
DECTID—Select Terminal ID	5-158
DECTME—Terminal Mode Emulation	5-159
DECTSR—Terminal State Report—Terminal to Host	5-160
DECTSR—Terminal State Report (Color Table Report)	5–161
DECTST—Invoke Confidence Test	5-162
DECUDK—User Defined Keys	5–163
DECUS—Update Session	5–169
DECVCCM—Vertical Cursor-Coupling Mode	5–170
DECXCPR—Extended Cursor Position Report	5–170
DECXRLM—Transmit Rate Limiting	5–171
DL—Delete Line	5–172
DSR—Device Status Reports	5–173
DSR—Cursor Position Report (CPR)	5–173
DSR—Data Integrity Report	5–174
DSR—Extended Cursor Position Report (DECXCPR response)	5–174
DSR—Keyboard Report	5–175
DSR—Macro Space Report	5–176
DSR—Memory Checksum Report (DECCKSR)	5–177
DSR—Operating Status Report	5–177
DSR—Printer Port Report	5–178
DSR—User-Defined Keys Report (VT Level 4 or higher)	5–179
ECH—Erase Character	5–179
ED—Erase in Display	5–180
EL—Erase in Line	5–180
HPA—Horizontal Position Absolute	5–181
HPR—Horizontal Position Relative	5–181
HT—Horizontal Tab	5–182
HTS—Horizontal Tab Set	5–182
HVP—Horizontal and Vertical Position	5–183
ICH—Insert Character	5–183
IL—Insert Line	5–184
IND—Index	5–184
IRM—Insert/Replace Mode	5–185
KAM—Keyboard Action Mode	5–185
LNM—Line Feed/New Line Mode	5–186
LS—Locking Shift	5–187
MC—Media Copy	5–188
NEL—Next Line	5–191
NP—Next Page	5–191
PP—Preceding Page	5–192
PPA—Page Position Absolute	5–192
PPB—Page Position Backward	5–193
PPR—Page Position Relative	5–193
RIS—Reset to Initial State	5–194
RM—Reset Mode	5–195
S7C1T Sand C1 Control Character to the Hest	5_106

		S8C1T—Send C1 Control Character to the Host	5–196
		SCS—Select Character Set	5–197
		Designating Character Sets (SCS Sequences)	5–197
		SD—Pan Up	5–200
		SGR—Select Graphic Rendition	5–201
		SRM—Local Echo: Send/Receive Mode	5–204
			5–205
		SS—Single Shifts	
		SM—Set Mode	5–206
		SU—Pan Down	5–207
		TBC—Tab Clear	5–207
		VPA—Vertical Line Position Absolute	5–208
		VPR—Vertical Position Relative	5–208
6	SCO C	onsole Emulation	
	6.1	SCO Console Emulation Mode	6–1
	6.1.1	Keyboard	6–2
	6.1.1.1	Local Function Keys in SCO Console Mode	6–2
	6.1.1.2		6–2
	6.1.1.3	VT Keyboard Key Mapping	6–6
	6.2	VT520 SCO Console Control Sequences	6–7
		SCODFK—Define Function Key	6–7
		SCODPCC—Display PC Characters	6–8
		SCORC—Restore Saved Cursor Position	6–9
		SCOSC—Restore Saved Cursor Position	6–9
		SCOSC—Save Current Cursor Fosition	0-9
7	Charac	eter Sets	
	7.1	Overview	7–1
	7.2	Character Sets Supported	7–1
	7.2.1	VT Graphic Character Sets	7–1
	7.2.2	PCTerm Graphic Character Sets	7–2
	7.2.3	Control Character Sets	7–3
	7.2.4	Character Set Structure	7–3
	7.2.5	Characters Not in a Character Set	7–3
	7.3 7.3.1	VT Mode	7–4 7–4
	7.3.1	Selecting Character Sets	7–4 7–4
	7.3.2 7.4	Character Set Mappings	7–4 7–4
	7.4 7.4.1	Selecting Character Sets	7–4 7–4
	7.4.2	Character Set Mappings	7-5
	7.5	SCO Console Mode	7–5
	7.6	Soft Character Sets	7 -5 75
	7.6.1	Designing a Soft Character Set	7–6
	7.6.2	Coding the Soft Character Set	7–9
	7.6.3	Downloading Soft Characters	7–13
	7.6.4	Designating the Soft Character Set	7–14
	7.6.5	Soft Character Set Example	7–15
	7.6.6	Clearing a Soft Character Set	7–16

# 8 Keyboard Processing

	8.1	Overview—Keyboard Layout	8–1
	8.2	DEC VT Layout	8-2
	8.3	VT Layout - PC Term Mode	8–2
	8.4	Enhanced PC Layout - PCTerm Mode	8–3
	8.5	Enhanced PC Layout - VT Mode	8–3
	8.5.1	DEC VT Style	8–3
	8.5.2	IBM PC Style	8–4
	8.6	Main Key Array	8–4
	8.6.1	Character Sets	8–4
	8.6.2	Tab Key	8–4
	8.6.3	Modifier Keys	8–4
	8.6.4	Caps Lock	8–5
	8.6.5	Left Alt	8–5
	8.6.6	Right Alt	8–6
	8.6.7	Alt Gr	8–6
	8.7	Top Row Function Keys	8–6
	8.8	Editing Keypad Keys	8–6
	8.9	Cursor Keypad Keys	8–7
	8.10	Numeric Keypad Keys	8–7
	8.11	Local Function Key Defaults	8–9
	8.11.1	Numeric Keypad Compose	8–14
	8.11.2	Accessibility Aids	8–15
	8.12		8–16
	8.13	Controlling Keyboard LEDs	8–17
	8.14	Keyboard Languages	8–18
	8.14.1	Switching Between Keyboard Languages	
		Keystroke Processing	8–20
	8.14.2	Non-Spacing Accent Marks	8–20
	8.14.3	German	8–21
	8.14.4	Hebrew	8–21
	8.15	Keystation Numbers	8–21
	8.16	Scan Codes Sent in PCTerm Mode for EPC Keyboards	8–23
	8.17	Scan Codes Sent in PCTerm Mode for VT Keyboards	8–27
	8.18	Control Codes and Keystrokes	8–28
9	Commi	unications	
	9.1	Introduction to Communications	9–1
	9.2	Physical Link Layer	9–2
	9.2.1	25-Pin Connectors	9–2
	9.2.2	DEC Corporate Modular Jacks (MMJ)	9–3
	9.2.3	Connector Pins Description	9–3
	9.2.3.1	Transmitted Data-TXD L	9–4
	9.2.3.2	Received Data-RXD L	9–4
	9.2.3.3	Request to Send-RTS	9–4
	9.2.3.4	Clear to Send-CTS	9–4
	9.2.3.5	Data Terminal Ready-DTR	9–5
	9.2.3.6		9–5
	9.2.3.6.	.1 Modem Initiated Disconnect	9–5
	9.2.3.6.		9–5
	9.2.3.6.		9–6
	9.2.3.7	Receive Line Signal Detector-RLSD	9–6
	9.2.3.8	Speed Indicator-SPDI	9–6
	9.2.3.9	Speed Select-SPDS	9–7

	9.2.4	Half-Duplex Mode	9–7
	9.2.5	Supported Modem Configurations	9–7
	9.2.5.1	CCITT Public Switched Telephone Network (2-wire only)	9–7
	9.2.5.2	CCITT Dedicated Line (2-Wire / 4-Wire) Data Network	9–7
	9.2.5.3	European Public Circuit Switched Data Network	9–8
	9.2.5.4	European Public Packet Switched Data Network (PSDN)	9–8
	9.3 Da	ata Link Layer	9–9
	9.3.1	7- /8-Bit VT100/VT520 Operation	9–9
	9.3.2	Flow Control	9–10
	9.3.2.1	Receive Buffer	9–10
	9.3.2.2	Flow Control Selection	9–10
	9.3.2.2.1	No Flow Control	9–11
	9.3.2.2.2	XOFF/XON or XPC Flow Control	9–11
	9.3.2.2.3	DSR/DTR Flow Control	9–12
	9.3.2.2.4	Software and Hardware Combined Flow Control	9–12
	9.3.2.2.5	Flow Control Threshold	9–12
	9.3.2.3	Show Control Character Mode	9–13
	9.3.2.4	Set-Up on Flow Control Handling	9–13
	9.3.2.5	When Disconnect Occurs	9–13
		eatures that Affect Communications	9–13
	9.4.1	Clear Communications	9–14
	9.4.2	Connection	9–14
	9.4.3	Line Disconnection	9–14
	9.4.4	Break	9–15
	9.4.4.1	Received Break	9–15
10	Printer P	Port	
	101 0-	verview	10–1
			10-1
	10.2 Se 10.2.1	erial Port	10-1
			10-1
	10.3 Pa	rallel Port	10-2
		Parallel Port Flow Control	
		int Modes	10–3
	10.4.1	Printer Controller Mode	10–4
		int Operation	10–4
		ansmitting Print Data	10-4
	10.6.1	DEC ANSI	10-4
	10.6.2	IBM ProPrinter or Compatible Printer	10–5
	10.6.2.1	Data Transmission	10–5
	10.6.3	DEC ANSI with IBM ProPrinter Emulation	10–6
	10.6.3.1	Data Transmission	10–7
		inter Status	10–7
		spending Print Operations	10–7
	10.9 Ab	porting Print Operations	10–7

# Part III VT520 ASCII Emulation

11 ASCII Emulations and Control Functions			
	11.2       ASCII Emulations         11.2.1       Enhanced Mode         11.3       Coding Notation         11.3.1       Communication Flow Control with PCTerm Mode	11-1 11-1 11-2 11-2 11-3 11-3	
12	ASCII Escape Sequences		
	12.2       Terminal Management         12.3       Keyboard Processing         12.4       Screen Processing         12.4.1       Rectangular Area Operations         12.4.1.1       Draw Rectangle         12.4.1.2       Swap/Copy/Move         12.5       Printing/Sending Data         12.5.1       Sending Data         1       1	12-1 12-5 12-5 2-10 2-28 2-31 2-31 2-32 2-36	
13	Defining and Loading ASCII Character Fonts		
	13.1.1PCTerm on US Keyboard13.1.2WYSE and ADDS Enhanced Personalities13.2Loading, Defining, and Selecting Character Sets	13–1 13–1 13–1 13–3 13–5	
Α	/T Keyboard Legend Data		
	A.1 Compose Processing and Non-spacing Diacritical Marks	A-1 A-1	
В	Enhanced PC Keyboards		
	B.1 Summary of Non-Spacing Diacritical Marks	B–1 B–2	
С	ASCII Keycodes and Local Functions		
	C.1 PC Keyboard	C-1 C-6 C-9	
D	/T520 Termcap Data		
	D.1 Termcap Emulations	D-1 D-1 D-2	

E ANSI	Control Function Index
E.1	ANSI Index by Final Character
Glossary	
Index	
Figures	
1–1	Sample VT Keyboard Layout
1–2	Sample PC Keyboard Layout
2–1	Set-Up
2–2	Set-Up Language Selection
2–3	Set-Up Summary Line
2–4	Main and Terminal Actions Menu
2–5	Session Menu
2–6	Session Page Memory Allocation
2–7	Lines per Page
2–8	Framed Windows
2–9	Screen Alignment Display
2-10	Color Set-Up Menu
2–11	Assign Colors
2–12	Alternate Colors
2-13	Define Colors
2–14	ASCII Emulation Menu
2–15	Keyboard Menu
2–16	Define Key Editor, Select Function
2–17	Communication Menu
2–18	Communications—Port Select
2–19	Communication Transmit Speed Menu
2-20	Communication Fkey Rate Limit Menu
2–21	Communication Answerback Dialog Box
2-22	Modem Menu
2-23	Modem High Speed Menu
2-24	Printer Menu
2-25	DEC/ISO Character Sets Menu
2-26	PC Character Sets Menu
2-27	Tab Set-Up Dialog Box
3–1	Calculator with VT Keyboard Layout
3–2	Calculator with PC Keyboard Layout
3–3	Clock Function
4–1	7-bit ASCII Code Table with C0 Control Characters Font (Left Half)
4–2	8-bit ASCII Code Table with C1 Control Characters Font (Right Half)
7–1	Character Cell Sizes for 24-Line by 80- and 132-Column Fonts

7–2	Character Body Sizes for 24-Line by 80- and 132-Column Fonts	7–8
7–3	Example of an Uppercase D (24-Line by 80-Column Font)	7–10
7–4	Sixel-to-ASCII Conversion	7–13
8–1	VT Keyboard Layout	8–1
8–2	PC Keyboard Layout	8–1
8–3	Editing Keypad Legends on DEC and PC Layouts	8–7
8–4	VT Layout - Keystation Numbers	8–21
8–5	VT Layout - Typical North American Key Legends	8–22
8–6	Enhanced PC Layout - Map Numbers	8–22
8–7	Enhanced PC Layout - Typical North American Key Legends	8–22
9–1	25-Pin Port Pin Numbers	9–2
9–2	MMJ Modular Jack Pin Numbers	9–3
10–1	Parallel Printer Port	10–2
13–1	Process of Selecting Character Sets	13–2
A-1	Austrian/German VT Keyboard	A-2
A-2	Belgian/French VT Keyboard	A-3
A-3	British/U.K./North American VT Keyboard	A-4
A-4	Canadian-French VT Keyboard	A-5
A-5	Czech VT Keyboard	A-6
A–6	Danish VT Keyboard	A-7
A-7	Dutch VT Keyboard	A-8
A–8	Finnish VT Keyboard	A-9
A-9	Flemish VT Keyboard	A-10
A-10	Greek VT Keyboard	A-11
A-11	Hebrew VT Keyboard	A-12
A-12	Hungarian VT Keyboard	A-13
A-13	Italian VT Keyboard	A-14
A-14	Norwegian VT Keyboard	A-15
A-15	Polish VT Keyboard	A-16
A-16	Portuguese VT Keyboard	A-17
A-17	Romanian VT Keyboard	A-18
A–18	Russian VT Keyboard	A-19
A–19	SCS VT Keyboard	A-20
A-20	Slovak VT Keyboard	A-21
A-21	Spanish VT Keyboard	A-22
A-22	Swedish VT Keyboard	A-23
A-23	Swiss-French VT Keyboard	A-24
A-24	Swiss-German VT Keyboard	A-25
A-25	Turkish-F VT Keyboard	A-26
A-26	Turkish-Q VT Keyboard	A-27
B–1	Austrian/German Enhanced PC Keyboard	B-3
B-2	Belgian Enhanced PC Keyboard	B-4
– – В–3	British/U.K. Enhanced PC Keyboard	B-5
B-4	Canadian-English/North American Enhanced PC Keyboard	B-6
 В–5	Canadian-French Enhanced PC Keyboard	B-7
Б-6	Czech Enhanced PC Keyboard	B-8
B_7	Danish Enhanced DC Kayboard	B_0

B-8	Dutch Enhanced PC Keyboard	B-10
B-9	Finnish Enhanced PC Keyboard	B-11
B-10	French Enhanced PC Keyboard	B-12
B-11	Greek Enhanced PC Keyboard	B-13
B-12	Hebrew Enhanced PC Keyboard	B-14
B-13	Hungarian Enhanced PC Keyboard	B-15
B-14	Italian Enhanced PC Keyboard	B-16
B-15	Latin American Enhanced PC Keyboard	B-17
B-16	Norwegian Enhanced PC Keyboard	B-18
B-17	Polish Enhanced PC Keyboard	B-19
B-18	Portuguese Enhanced PC Keyboard	B-20
B-19	Romanian Enhanced PC Keyboard	B-21
B-20	Russian Enhanced PC Keyboard	B-22
B-21	SCS Enhanced PC Keyboard	B-23
B-22	Slovak Enhanced PC Keyboard	B-24
B-23	Spanish Enhanced PC Keyboard	B-25
B-24	Swedish Enhanced PC Keyboard	B-26
B-25	Swiss-French Enhanced PC Keyboard	B-27
B-26	Swiss-German Enhanced PC Keyboard	B-28
B-27	Turkish Enhanced PC Keyboard	B-29
Tables		
1–1	VT520/25 Font Sizes	1–5
1–1 2–1		2–3
2–1	Error Messages	2–3 2–4
2–2 2–3	Display Set-Up Features and Control Functions	2–4 2–19
2–3 2–4	Lines per Page vs. Lines per Screen When Auto Resize is Set	2–19
2–4 2–5	Default Graphic Renditions	2–20
2–6	ASCII Emulation Features	2–35
2–0 2–7	Keyboard Features and Control Functions	2–36
2–7 2–8	Communication and Modem Features and Control Functions	2–30 2–45
2–6 2–9	Printer Features and Control Functions	2–45 2–55
2–9 2–10	Set-Up Factory Defaults	2–55 2–61
2–10 3–1	ASCII Emulation Character Sets	3–7
3–1 4–1	CO (7-Bit) Control Characters Recognized	3–7 4–2
4–1 4–2	C1 (8-Bit) Control Characters Recognized	4–2
4–2 4–3	8-Bit Control Characters and Their 7-Bit Equivalents	4–3 4–4
4–3 4–4	Control Character Displayed on Screen	4–11
4–5	VT52 Mode Escape Sequences	4–45
5–1	VT52 Escape Sequences	5–18
5–1 5–2	DECDLD Parameter Characters	5–10 5–41
5–2 5–3	Settings Supported by DECRQM, DECRPM, RM, and SM	5–100
5–3 5–4	ANSI Modes for DECRQM, DECRPM, SM, and RM	5–100
5–4 5–5	DEC Private Modes for DECRQM, DECRPM, SM, and RM	5–109
5–5 5–6	Terminal's Default Settings	5–110 5–150
5–6 5–7	Terminal Emulation Modes	5-150 5-150
	reconstat promaton (vidues	) <b>—</b> 174

5–8	VT Keyboards	5–165
5–9	PC Keyboards	5–166
5–10	VT and PC Keyboard Function Keys Compared	5–167
5–11	Keyboard Languages	5–175
5–12	Mapping Character Sets with Locking Shifts	5–187
5–13	Designating a Character Set	5–198
5–14	Character Set Codes	5–198
5–15	Visual Character Attribute Values	5-201
6–1	SCO Console Mode with ASCII Keycodes and Scancodes	6–1
6–2	Local Functions on VT and Enhanced PC Layouts	6–2
6–3	SCO Console Mode Function Key Default Codes	6–3
6–4	SCO Console Mode Main Keypad Default Codes	6–3
6–5	SCO Console Mode Numeric Keypad Default Codes, Num Lock Off	6–5
6–6	SCO Console Mode Numeric Keypad Default Codes, Num Lock On	6–5
6–7	SCO Console Mode Editing Keypad Default Codes	6–6
6–8	SCO Console Mode Cursor Keypad Default Codes	6–6
7–1	Character Cell Sizes	7–7
7–2	Guidelines for Designing Soft Characters	7–8
7–3	Converting Binary Code to an ASCII Character	7–11
8–1	Scan Codes for VT Layout in PCTerm Mode	8–2
8–2	VT Style Layout vs. Enhanced PC Style Layout Modifier Keys	8–5
8–3	Editing Keypad Sequences for Enhanced PC Layout	8–7
8–4	PC Layout Numeric Keypad Sequences - VT Style	8–8
8–5	PC Layout Numeric Keypad Sequences - PC Style, Numeric Mode	8–9
8–6	Local Functions	8–9
8–7	VT Keyboard Languages	8–17
8–8	Enhanced PC Keyboard Languages	8–17
8–9	8-bit Character Set Initialization when Keyboard Language is	
	Changed	8–18
8–10	7-bit Character Set Initialization	8–19
8–11	Non-Spacing Accent Marks	8–20
8–12	Control Codes and Keystrokes	8–28
9–1	EIA Interface Signals and Functions	9–2
9–2	MMJ Interface Signals	9–3
9–3	Flow Control Threshold Points	9–13
10–1	Parallel Connector Signals	10–2
11–1	Symbols Used in ASCII Terminal Escape Sequences	11–2
11–2	Commands that may Carry Protect Mode Features through Pages	11–4
11–3	Commands that Can Move the Cursor to Protected Area	11–5
11–4	Commands that Cannot Move Cursor into Protected Area	11–5
12–1	Serial Port Control Functions	12–1
12–2	Terminal Management Control Functions	12–4
12–3	Keyboard Processing Control Functions	12–5
12–4	Redefinable Keys	12–9
12–5	Screen Processing Control Functions	12–10
12–6	Data Protection Control Functions	12–20
12–7	Cursor Control Functions	12-21

12–8	ASCII Editing Control Functions	12-25	
12–9	Local Edit Mode Function Keys	12-25	
12–10	Tab Stop Control Functions	12-26	
12–11	Page Edit Control Functions	12–27	
12–12	Rules for Locating Rectangle	12-29	
12–13	Rectangle Area Control Functions	12-30	
12–14	Send Data Delimiters	12-32	
12–15	Delimiters for Other Personalities	12–33	
12–16	Print/Send Control Functions	12–33	
12–17	Printing Data Control Functions	12–35	
12–18	Graphic Characters	12-36	
13–1	Display and Load Character Sets	13–1	
13–2	Loading Font Bank	13–3	
13–3	Design a Character Font	13–5	
A-1	VT Keyboard Non-Spacing Diacritical Marks	A-1	
B-1	Enhanced PC Keyboard Non-Spacing Diacritical Marks	B-1	
C-1	WYSE and TVI Modes Function Keys for PC Keyboard	C-1	
C-2	WYSE and TVI Modes Function Keys for PC Keyboard	C-1	
C-3	WYSE and TVI Modes Editing Keys for PC Keyboard	C-2	
C-4	WYSE and TVI Modes Cursor Keys on PC Keyboard	C-2	
C-5	WYSE and TVI Modes Numeric Keys for PC Keyboard, NumLock =		
	Off	C-2	
C–6	WYSE 160 and TVI Modes Numeric Keys for PC Keyboard, NumLock		
<u> </u>	= On	C-3	
C-7	ADDS A2 Function Keys on PC Keyboard	C-3 C-4	
C–8	ADDS A2 Cursor Keys on PC Keyboard		
C-9	ADDS A2 Mode Numeric Keynord Keys on PC Keyboard: NumLock -		
C-10	ADDS A2 Mode Numeric Keypad Keys on PC Keyboard; NumLock =	C-4	
C-11	Off	C-4	
C-11	On	C-5	
C-12	WYSE and TVI Modes Function Keys for DEC VT Keyboard	C-6	
C-13	WYSE and TVI Modes Editing Keys on DEC VT Keyboard	C–6	
C-14	WYSE and TVI Modes Cursor Keys on DEC VT Keyboard	C-7	
C-15	WYSE and TVI Modes Numeric Keypad PF Keys on DEC VT	0.	
0 10	Keyboard	C-7	
C-16	ADDS A2 Function Keys on DEC VT Keyboard	C-7	
C-17	ADDS A2 Editing Keys on DEC VT Keyboard	C-8	
C-18	ADDS A2 Cursor Keys on DEC VT Keyboard	C-8	
C-19	ADDS A2 Numeric Keypad PFKeys on DEC VT Keyboard	C-8	
C-20	Local Functions in ASCII Code Mode	C-9	
C-21	Local Functions in PC Scancode Mode	C-11	
E-1	ANSI Control Functions Index by Final Character	E-1	

# Part I

# VT520 Video Terminal

This part includes the following chapters:

- Chapter 1, Overview
- Chapter 2, Set-Up
- Chapter 3, Desktop Features

# **Overview**

#### 1.1 Introduction

The VT520 is a low-cost, multi-session, text video terminal featuring enhanced keyboard and communications flexibility, providing up to four sessions at a time. Two or more sessions can be assigned to the same communication port when Terminal Device/Session Management Protocol (TD/SMP) is used to multiplex the sessions. Each session has its own framed window, window title, and icon name.

The VT520 has a define key editor that allows you to reprogram any key on the keyboard.

The VT525 color terminal allows you to assign different colors to the various windows and to combinations of character attributes. You can select colors from color look-up tables or create your own color combinations. Unless specifically mentioned in this manual the term VT520 also refers to the VT525 color model.

The product has a 25-pin stacked male/female RS-232 connector (EIA-232), two 6-pin EIA-423 (MMJ) connectors, and a Centronics parallel connector. The RS-232 and the EIA-423 ports are used.

The VT520 also has power management features that exceed the Environmental Protection Agency (EPA) Energy Star requirements for saving energy.

#### 1.2 Communications Features


The terminal provides:

- Three bidirectional, asynchronous serial communication ports; one of which (Comm 3) can be used for a local printer.
- Baud rates from 300 to 115.2K baud
- Centronics parallel printer port
- 25-pin serial connectors
- Two MMJ serial connectors
- Expanded flow control options:
  - Software flow control using XON/XOFF or XPC
  - Hardware flow control using DTR/DSR

## 1.3 Keyboard Features


The VT520 offers a choice of two keyboard layouts—a VT keyboard layout (LK411) or an enhanced PC keyboard layout (PCXAL). The VT keyboard (Figure 1–1) and the PC keyboard (Figure 1–2) differ in the placement of some of the keys, like the Control key. A VT keyboard has 20 function keys,  $\boxed{\texttt{F1}}$  through  $\boxed{\texttt{F20}}$ , above the main keypad, while a PC keyboard has 12 function keys,  $\boxed{\texttt{F1}}$  through  $\boxed{\texttt{F12}}$ .

Figure 1-1 Sample VT Keyboard Layout



MA-1520a-92.PS

Figure 1-2 Sample PC Keyboard Layout



LJ-00226a-TI0.F

The keyboard has the following features:

- An IBM PS/2-compatible 6-pin mini DIN connector.
- Keyboard keys that can be reprogrammed to send single characters, to send character sequences, or to invoke local functions (Hold, Copy and Paste, Remove, Insert, Print Page, Toggle Autoprint, Set-Up, Break, and so on).
- A local user-defined key editor. Key definitions can be saved in nonvolatile memory.
- Eight levels of user-defined function keys using any combination of Shift, Control, and Alt.
- 971 bytes of nonvolatile memory available for custom user-defined keys (UDKs)/Session, which cannot be reallocated. The maximum length for a UDK definition is 255 bytes.

#### 1.4 Printer Port Features

The terminal has the following printer port features:

- A Centronics parallel printer port.
- IBM ProPrinter support.
- Bidirectional serial communication ports.
- Baud rates from 300 to 115.2K baud.
- Null characters that can pass as data to the printer port.

# 1.5 Display and Text Capabilities

The terminal has both ANSI and ASCII display and text processing capabilities. The features of each are listed below.

#### 1.5.1 ANSI

- Macro capability
- Display: 26, 42, or 53 data lines
- Selectable page size: 24, 25, 36, 42, 48, 50, or 72 lines
- Full status line (occupies one data line)
- · Separate keyboard indicator line
- Three pages of 24 lines
- SCO Console mode

#### 1.5.2 **ASCII**

• Terminal emulations:

WYSE: 325 (color model only), 50, 50+, 60 native, 160 text only, 120, 150, PCTerm

Televideo: TVI 950, 925, 910+

Applied Digital Data Systems: ADDS A2

· Dim and invisible character attributes

### 1.6 Enhanced Set-Up

The terminal provides an enhanced menu-based Set-Up, allowing common features to be accessed easily from a single screen. All Set-Up features are host controllable to allow remote configuration. The terminal also has a means to lock out the local setup key.

Set-Up menus are available in English, French, German, Italian, or Spanish. For details, see Chapter 2, Set-Up.

# 1.7 Desktop Productivity Features

The terminal has the following desktop productivity features:

- Local copy and paste (not available in PCTerm mode)
- Time of day clock (host or locally set, no battery back up)
- Desktop calculator with decimal, octal, and hex conversions
- Display character set tables.
- Review previous data lines.

For details, see Chapter 3, Desktop Features.

## 1.8 Character Set Support

In addition to the traditional Digital graphic character sets (DEC Multinational, NRCS, and so on), the VT520 supports Cyrillic, Greek, Hebrew, Turkish, most Eastern European languages, and PC character sets. For details, see Chapter 7, Character Sets.

# 1.9 Ergonomics (Human Factors) Features

The terminal is designed to provide a high-quality human interface and long-term reliability at low cost. The VT520 offers 72 Hz refresh, full overscan. The terminal has the following features:

- 35.5 cm (14 in) flat face, antiglare CRT screen
- Improved resolution of 802  $\times$  480 pixels. (The mono VT520 also has 800  $\times$  432 with overscan.)
- 72 Hz refresh
- Overscan<sup>1</sup>
- Additional fonts (see Table 1–1)
- Tilt/swivel base
- Choice of keyboards
- · Accessibility aids


Not available in color model.

Table 1-1 VT520/25 Font Sizes

80 Columns	132 Columns	Maximum Number of Lines
10 × 16	6 × 16	26 lines + keyboard indicator line
$10 \times 10$	$6 \times 10$	42 lines + keyboard indicator line
$10 \times 8$	$6 \times 8$	53 lines + keyboard indicator line

### 1.10 Field-Upgradable Firmware

All VT520 models include support for a 4 Mbit (512 KByte) ROM cartridge option. The base unit comes with a factory-installed ROM. The ROM cartridge connector is protected by a ROM cartridge cover. To install new code, the ROM cartridge cover is removed, and a ROM cartridge with attached cover is plugged into the ROM connector. The new code completely supersedes the factory-installed ROM code. It does not overlay or extend the factory code.



To install a ROM cartridge with new firmware, use the following steps:

- 1. Turn the power off before installing the ROM cartridge.
- 2. Turn the power on and press F3.
- 3. Select Actions ▶ Restore factory defaults and press Return.
- 4. Select **Sessions** ▷ **Save all sessions** and press Return.

The installation is now complete. When you power-on the terminal, the message "ROM card active" is displayed in the upper-left corner of the display. Note that steps 3 and 4 are necessary to initialize the terminal's non-volatile memory for use with the ROM cartridge firmware. Failure to perform these steps may cause the terminal to report an NVR error.

#### 1.11 Comparison with previous VT Terminals

### 1.11 Comparison with previous VT Terminals

The VT520 is functionally compatible with other ANSI products with the following exceptions:

#### Terminal ID

The Primary Device Attributes can report additional extensions to cover new features. See Chapter 4 for a summary of the control functions. The Secondary Device Attributes are different.

Where Pv is the firmware version number.

#### • Dynamically Redefinable Character Set (DRCS) Fonts

The VT520 has four buffers, which can load up to two dynamically redefinable character sets, each with an 80-column font and a 132-column font.

#### Keyboards

VT420 keyboards cannot be used on the VT520; however, the VT520 can emulate the VT420 keyboard behavior when configured accordingly.

#### Four Sessions

The VT520 is a multi-session terminal. You can have up to <u>four</u> sessions enabled. More than one session can be established on the same communication port.

#### • PC Character Sets

PC character sets are available in PC Term and SCO Console mode only.

# Set-Up


This chapter describes VT520 Set-Up features. Set-Up is used to examine or change terminal operating features, such as transmit/receive speeds, type of cursor, or key definitions.

# 2.1 Entering Set-Up

You enter Set-Up by pressing the key designated as the Set-Up key. Pressing this key alternately places the terminal in Set-Up mode or returns it to the operating mode.

On a	The Set-Up key is	
VT keyboard	F3 on the top row.	
SCO Console mode	Caps Lock F3	
PC keyboard	Caps Lock   Print Screen	
	or Alt Print Screen .	

Figure 2-1 Set-Up



The Set-Up display consists of pull-right menus. You can move back and forth with the arrow keys. Pressing Enter, Return, Do, or Select invokes the action or setting for the current menu item.

The Set-Up function may be reassigned to other key combinations or can be disabled it for local entry into Set-Up. When you press  $\boxed{3}$  as the first key after the terminal is powered on, you <u>always</u> enter Set-Up, regardless of which keyboard you use or how  $\boxed{5}$  is defined.

#### 2.1.1 Effects of Entering Set-Up

Placing the terminal in Set-Up mode causes no loss of data if a Flow Control protocol is in use on the communications port. The first Set-Up menu is displayed on the screen. Upon exiting Set-Up, the previous text is restored.


Entering Set-Up has the following side effects:

- · Any compose sequence in progress is aborted and the keyboard is unlocked.
- A Set-Up Summary Line is displayed.
- Press Shift to show the Indicator Status Line.
- Printer operations are suspended and are resumed upon exiting Set-Up.

#### 2.1.2 Set-Up Languages

The VT520 Set-Up menus can be displayed in five languages using a Set-Up feature. A menu allows you to choose the language in which all subsequent Set-Up menus and displays are written. Selections from this Set-Up language menu (Figure 2–2) take effect immediately. This feature can also be invoked by DECSSL.

Figure 2-2 Set-Up Language Selection



#### 2.1.3 Power-On Settings and Defaults

The VT520 terminal stores many of its feature settings in nonvolatile memory (NVM). Nonvolatile memory retains these settings even when power is shut off. In addition to storing operator-selected features, the terminal retains the factory default settings in permanent memory. By using Set-Up, you can modify individual terminal features, recall the feature settings stored in nonvolatile memory, or recall the factory default settings.

In this chapter, the defaults are shown with a solid bullet (•) in lists and in **boldface** in text.

#### 2.1.4 Self-test Error Messages

At power-up, the VT520 terminal executes a series of self-tests, displays a message indicating whether the self-tests were successful, and displays a banner message. (To change the banner message, see Section 2.4.6.)

If the self-tests detect an error, one of the following messages is displayed on the terminal in place of "Selftest OK."

Table 2-1 Error Messages

Message	Meaning
NVR Error - 1	A firmware update, or loss of power while writing to the NVR during a <b>Save settings</b> process may cause this error. Try <b>Actions</b> > <b>Recall factory defaults</b> followed by <b>Session</b> > <b>Save settings for all</b> .
RS-232 Port Data Error - 2	Communications problem inside terminal. Call for service.
RS-232 Port Controls Error - 3	Communications problem inside terminal. Call for service.
DEC-423 Port Error - 5	Communications problem inside terminal. Call for service.
Parallel Port Error - 6	Communications problem inside terminal. Call for service.
ROM Cartridge Error - 7	Turn the terminal off, and make sure the ROM cartridge is seated firmly on its connector pins. Turn the terminal on. If the problem continues, try another ROM cartridge. If the new ROM cartridge does not work, the problem is inside the terminal; in which case, call for service.
Keyboard Error - 8	Turn the terminal off, and make sure the keyboard cable is plugged in. Turn the terminal on. If the problem continues, try another keyboard. If the new keyboard does not work, the problem is inside the terminal; in which case, call for service.

#### 2.1.5 Context Sensitivity

On the screen, a check box  $\boxed{1}$  or radio button ( $\bullet$ ) indicates the current user selection and normally reflects the operating state of the terminal.

Certain feature selections overlap and could contradict each other, so they cannot be active at the same time. These are called *context sensitive* features, which are displayed with the dim video attribute in Set-Up. Example:

You cannot select *Comm3* as a printer port if it is selected as a communications port.

Table 2–2 lists the set-up features that are context sensitive.


Table 2–2 Context Sensitive Set-Up Features

	Menu Item	Dimmed when
<b>Session</b> ⊳	Pages per session Page memory allocation	Page selection exceed the number of unassigned pages available.
<b>Display</b> ⊳	Lines per screen Lines per page	Sizes are not available based on the current page memory allocation.  WYSE is selected; use <b>ASCII emulation</b> > <b>Data lines</b> and <b>Pages</b> .
	Cursor direction	Keyboard language is not Hebrew.
	Energy saver	<b>CRT saver</b> = never is selected.
	Overscan	Terminal is a color terminal.
Color ⊳	ASCII color mode, Reverse and blank attributes, and Intensity attributes	<b>Emulation mode</b> is set to other than an ASCII terminal emulation.
	Alternate text colors	<b>Select color mode</b> is other than <b>Alternate color</b> .
	Select color mode	<b>Terminal type</b> ▷ <b>Emulation mode</b> is other than a VT or SCO console.
Terminal type ⊳	Terminal ID to host	<b>Terminal type</b> ▷ <b>Emulation mode</b> is other than a VT or SCO console.
	7-bit NRCS characters	<b>Emulation mode</b> is set to VT100/VT52; or <b>Communication</b> ▷ <b>Word size</b> is 7-bits; or no 8-bit NRC set exists for the keyboard language.
<b>ASCII emulation</b> ⊳		<b>Terminal type</b> ▶ <b>Emulation mode</b> is set to VT or SCO console.
	TVI page-flip	<b>Terminal type</b> ▷ <b>Emulation mode</b> is other than TVI.
Keyboard ⊳	Key encoding > Character, Scan code and Key position	<b>ASCII emulation</b> is selected, or a PC keyboard is connected.
	Data processing keys	A PC keyboard is connected.
	Map PC keyboard to VT	The keyboard is not a PC keyboard.
<b>Communication</b> ⊳	Port select Comm3	Comm3 is selected as a communications port. (It can be either a comm port or a printer port but not both.)
	Half duplex	The host <b>Communication</b> ▶ <b>Port select</b> is set to <b>S1=comm2.</b>
	Transmit flow control ⊳ DSR and Both	The <b>Modem &gt; Enable modem control</b> is selected.
	Receive flow control ⊳ DTR and Both	The <b>Modem</b> ▶ <b>Enable modem control</b> is selected.
<b>Modem</b> ⊳	<b>Disconnect delay</b> and <b>Modem speed</b>	The <b>Modem &gt; Enable modem control</b> is not selected.
Printer ⊳	Serial print speed, 2-way communication, Transmit flow control, Receive flow control, Word size, Parity, and Stop bits	The <b>Communication</b> ▶ <b>Port select</b> is set to one of the <b>Print</b> = <b>parallel</b> selections.
	DEC/ISO char sets	IBM ProPrinter is selected.
	PC character sets	<b>DEC ANSI</b> printer is selected.
	<b>Print mode ⊳ Controller</b>	<b>Display &gt; Show control characters</b> is selected.

# 2.1.6 Set-Up Summary Line

The Set-Up Summary Line (Figure 2–3) shows the important set-up features that affect whether the terminal can successfully communicate with the host. If the terminal is not working, the Set-Up Summary Line allows you to quickly verify if the communication features are set appropriately. The summary line is displayed below the last data line, where the status line would normally appear.

Figure 2-3 Set-Up Summary Line



The Set-Up Summary Line contains the following set-up information extracted from the Set-Up displays.

Item	Information Displayed	Communication Feature	
0	S1=comm1	Port selected: comm1, comm2, or comm3	
<b>2</b> 9600 Transmit speed: 9600 b		Transmit speed: 9600 baud	
	N	Parity: N=none, E=even, O=odd, M=mark, S=space	
	8	Word size: 7 or 8 bits	
	1	Stop bits: 1 or 2 bits	
8	ISO Latin-1	Default character set or PC set in PCTerm mode	
<b>4</b>	North American	Keyboard language	
6	VT520	Emulation mode	
<b>6</b>	V2.1	Firmware version	

The summary line is visible whenever the terminal is in Set-Up, except under the following conditions:

- You press a Shift key. Pressing either Shift key causes the normal Indicator Status Line to replace the Set-Up Summary Line.
- The Set-Up Summary line is temporarily replaced by an error or status message from the terminal. In this case, the error or status message is shown in place of the Set-Up Summary line until you type another key.

The Set-Up Summary Line appears in the currently selected set-up language.

### 2.1.7 Set-Up Status Messages

The Status or Set-Up Summary line is sometimes replaced by a Set-Up status message until the next user keystroke. Set-Up status messages are displayed whenever the effect of a set-up action would not otherwise be apparent. Example: "Done" is displayed after the Reset terminal action has completed.

The following are set-up status messages:

- Done
- NVR Error
- Incompatible settings not restored check pages per session and lines per page

### Set-Up

## 2.1 Entering Set-Up

- Incompatible settings not restored check comm port selection
- Page memory reallocated
- Sessions not enabled No Session Management response from host
- Session # terminated abnormally
- · Insufficient terminal resources to open Session
- · Sessions not enabled Unable to run with host Session Management version
- Session open request pending
- Session opened
- · No response from host for Session Management
- Data overrun occurred on Session #
- Sessions not enabled Sessions not selected
- Session # terminated normally
- Insufficient host resources to open Session
- · Sessions disabled
- Sessions enabled Restoring previous sessions

Set-Up functions that require additional time to process display the message "Please wait" until they have completed. **Save settings for all** and **Restore settings for all** display this message.

### 2.1.8 Status Line

The VT520 terminal has a status display with the following features:

- The clock time appears on the status display if the local clock has been initialized since the terminal was last powered on.
- In the ASCII emulation modes, the host-writable status line becomes the WYSE Editing status line.
- When enabled, the Accessibility Aids feature ("sticky keys") displays icons in the Keyboard Indicator line. For details, see Section 8.11.2.

The VT520 Indicator status line includes the Active Position Indicator, Printer Status Indicator, Modem Status Indicator, and local clock time in the desired format. Example:

1(24,008) Printer: None Modem: DSR 3:15 PM

# 2.1.9 Keyboard Indicator Line

The Keyboard Indicator Line has the following features:

- It is displayed in the Set-Up language.
- It has active keyboard layout. Nothing is displayed for Group 1. "G2" is displayed for Group 2, along with a small icon representing the right side of the top of the keycap. (To see this icon, press Ctrl/Alt/F2]. To return from Group 2, press Ctrl/Alt/F1].)
- For Greek, Hebrew, and Russian, "G2" is replaced by "Grk", "Heb", and "Rus", respectively.

- Visible bell—This feature flashes a bell ringing font whenever a sound is generated.
- When the Num Lock state is active on an EPC keyboard, "Num Lock" is displayed.
- When an EPC keyboard is operating in VT style, "VT" is displayed in place of the Num Lock indicator.
- In French and Spanish, an icon replaces the word "Lock" on the indicator line.

### Example:

Heb Num Lock Copy Hold Lock Compose Wait


# 2.2 Set-Up Screen Text

The main menu, shown in Figure 2–4, is the first menu displayed whenever you enter Set-Up. As the first menu, it holds the main directory of Set-Up features and those features which are commonly accessed and must be easy to find at all times. The Actions submenu is also displayed, since the Actions menu item is currently selected.

Unless stated otherwise, the following general descriptions apply:

- Changes to feature settings do not take effect until you exit Set-Up. Only net changes have an effect—a change to a new value and back to an old value has no effect.
- The setting choices for some features are shown in the corresponding Set-Up displays. Where all the choices could not be displayed, additional choices are listed immediately under the figure.





### 2.3 Main Menu

The following descriptions refer to Figure 2–4.

The items above the dividing line in the main menu form a directory to the major functional areas of set-up features. Each item has a corresponding submenu or dialog box.

Pressing the Set-Up key from within a dialog box will flash the OK button as if it were pressed and accept the corresponding changes before exiting Set-Up.

Below the dividing line are features that need to be easy to find from any menu.

#### 2.3.1 On-Line

The **On-line** feature allows you to select whether the terminal directs keyboard input to its host port UART to communicate with a remote host (On-Line), or directs keyboard input directly to the screen (receive character parser) without sending to a remote host (off-line or local).

Note

The **On-line** selection is different from the Local echo mode in the Communications Set-Up submenu. When **On-line** is disabled (local mode), nothing is sent to the host. Any keyboard input is directed to the receive character parser, which updates the screen.

In contrast, **Local echo** causes characters sent to the host port to also

be directed back to the receive character parser, as if they had been received (echoed) from the host. Local echo is temporarily disabled when the terminal is in either Local mode or Local Controller mode, because keyboard input is already being redirected to the screen or printer port.

If an NVR error occurs during power-up, the terminal switches to Local mode.

Terminal reports, such as Answerback, DA, CPR, DECTSR, DECRPM, DECRPSS, DECAUPSS, DECCIR, DECTABSR and DSR, are not directed to the display. While in "local", host communications are put on "hold": All data received is buffered. If necessary, an XOFF is sent (or DTR is deasserted) to prevent buffer overflow. This buffered data is directed to the display when On-line mode is reentered. Note that the received character buffer (silo) is responsible for sending XON and XOFF when needed, not the On-line/Local state.

When in Local mode, modem signals, including DTR, are unaffected. No disconnect is performed. The functions of the printer port remain unchanged in Local mode. They function the same as in On-line mode.

When in Local mode and Printer To Host mode is selected, data from the printer port is displayed on the video terminal.

When both Local mode and Printer Controller mode are selected, the terminal is in Local Controller mode. Keyboard characters are sent to the printer port. Note that in "regular local" mode, any keyboard output is directed to the screen, but in "regular controller" mode, the keyboard output is directed at the host port. When Local Controller mode is exited to Local mode, the terminal redirects keyboard output from the printer to the screen (and parser). When you change from Local Controller mode to Printer Controller mode, the terminal transmits the characters accumulated in the receive silo to the printer.

### 2.3.2 Save Settings

The **Save settings** menu item, when invoked by pressing Return or Enter, causes the settings for most Set-Up controlled operating features to be saved in nonvolatile memory, where they become the power-on settings.

The following settings are not saved.

- · Keyboard encoding mode
- Application cursor keys when set by a host control function.
- Application keypad mode when set by a host control function.

# 2.3.3 Restore Settings

**Restore settings** is an action field that is used to replace all saved Set-Up parameters with the values stored in the NVR. As a side effect, this feature performs a disconnect sequence, clears the screen, reinitializes the user-definable keys (as saved), clears the soft character set, returns the cursor to the upper left corner, aborts any print operation in progress, aborts ESC, CSI, and DCS sequences (and control strings), and shows "Done" on the status line. This action can also be invoked by the RIS control function.

### 2.3.4 Exit Set-Up

The **Exit Set-Up** menu item, when invoked by pressing **Enter**, causes the terminal to exit Set-Up. The effect is identical to pressing the Set-Up key while in Set-Up.

### 2.4 Actions Menu

The following descriptions refer to Figure 2–4. Certain Set-Up features instruct the terminal to perform an immediate action when they are invoked. These features are grouped in the terminal Actions menu.

# 2.4.1 Clear Display

The **Clear display** feature clears the active page (including the lines which have temporarily disappeared while the you are in Set-Up).

#### 2.4.2 Clear Communications

This feature is used to clear communication buffers and flags. It does not affect the On-Line/Local state. It is not invoked by any control functions.

### **Clear communications**:

- Aborts any print operation in progress
- Aborts any escape sequence, control sequence, control string, or character string processing (ESC, CSI, DCS, APC, OSC, PM, SOS)
- Clears the keyboard buffers
- · Clears the receive silo
- Clears the transmit silo
- · Takes the terminal out of Printer Controller mode
- Sends XON on to the host port
- Sends XON to the printer port if Printer To Host and XOFF are enabled

# Set-Up 2.4 Actions Menu

- · Resets XOFF received flags on both ports
- Does not clear the screen
- Clears KAM locked condition
- Clears the "printer port has seen DSR since power up" flag. When in Set-Up, Ctrl Enter disables sessions and clears TD/SMP.

# 2.4.3 Reset this Session

The **Reset this session** menu selection only resets the active session.

То	Press
Reset all four sessions,	Control Reset this session.
Perform a power-up reset,	Control Set-Up from within Set-Up.

The **Reset this session** Set-Up feature resets the terminal to a "known state." This function is like Soft Terminal Reset (DECSTR), except DECSTR resets the Character Set mode to "8-bit Characters" and **Reset terminal** does not.

#### Additions:

- Keyboard encoding is reset to "character."
- PCTerm mode is not selected.

Note		
From Set-Up, a soft reset using <b>Reset terminal</b> always works regardless of the terminal mode; but using mode changing control functions (DECSCL, S8C1T, S7C1T, DECANM), the soft reset is sometimes not performed.		

# 2.4.4 Restore Factory Defaults

The **Restore factory defaults** menu selection restores the factory default settings for all four sessions. There is no provision to restore factory defaults to a single session. Restore settings on the main menu only restores the active session's settings from NVM.

As a side effect, Restore factory defaults does the following:

- · Performs a disconnect sequence
- · Clears the screen
- Reinitializes the user-definable keys
- · Clears the soft font
- · Returns the cursor to upper-left corner
- Aborts print operations in progress
- Aborts ESC, CSI and DCS sequences
- Displays the "Done" message on the status line

### 2.4.5 Clock, Calculator, Show Character Sets

The **Clock, Calculator,** and **Show character sets** menu items are used to invoke the corresponding desktop productivity features. Refer to Chapter 3.

# 2.4.6 Banner Message

The **Banner message** menu item invokes a dialog box with a 30-character limit. When this feature is selected, a dialog box is displayed with a reverse video text entry area 30 characters long. If a **Banner message** is currently defined, the message is displayed in the text entry area. The  $\triangleleft$  or Delete key can then be used to delete backwards and enter a new **Banner message**.

All characters that can be generated by the keyboard are legal in this field (including primary and secondary keyboard language characters). As such, no errors are reported, except when trying to enter more than 30 characters. In this case, the bell rings (if enabled), and no more characters are accepted. The factory default message is no message at all (a blank field).

From the Actions menu, select Banner message....

- 1. Press Return or Enter to display a dialog box.
- 2. Enter your banner message.
- 3. Press the ↓ to select OK button.
- 4. Press Return or Enter to return to the Set-Up menu.
- 5. Use the **Save settings** menu item to save the Banner message.

# 2.5 Multiple Sessions

Multiple sessions extends the VT520 to act like four terminals in one. A *session* is an active connection between the terminal and a host system. The Session Set-Up menu controls the use of more than one session. See Figure 2–18.

The VT520 supports up to four sessions using virtual terminals. Each virtual terminal maintains the full keyboard and display state of a real physical terminal but shares a single keyboard and display with other virtual terminals. Before you can login using a virtual terminal, it must be connected to a host computer.

VT520 session virtual terminals can be connected directly to a host computer through any of the three serial communication ports on the back of the terminal. Since there are only three comm ports, this method alone can only support three sessions.

To use a fourth session or reduce the number of serial comm lines needed, more than one session must be connected through a single comm port. The VT520 allows this using a session management protocol, called TD/SMP (Terminal Device/Session Management Protocol). TD/SMP allows two or more sessions to share a single comm line, as long as the other end of the comm line supports the protocol. To enable TD/SMP at the terminal, you simply assign more than one session virtual terminal to the same comm port in Set-Up.

TD/SMP is standard on most terminal servers. If you are using a terminal server, check with its documentation to determine if it can run TD/SMP.

# 2.5.1 Enabling and Controlling the Session Configuration

The VT520 provides three serial communication ports which may be assigned to session virtual terminals in any combination. When only one virtual terminal is assigned to a communications port, the terminal functions as a single session terminal. The other three session selections are dimmed. The single session may be allocated 8 pages of 25 lines each by 80 or 132 columns. The color terminal supports 9 pages.

As session virtual terminals are assigned to physical communication ports, the terminal's firmware allocates the necessary structures to create the virtual terminals up to a maximum of four. When more than one virtual terminal is assigned to a single communication port, the Terminal Device/Session Management Protocol (TD/SMP) is used.

# 2.5.2 Multiple Sessions using a Terminal Server with TD/SMP

#### Procedure:

1. At the Local> prompt, enter the following command:

```
Local> set port multi enable Return
```

2. Continue with your login procedure.

To permanently set a terminal server port to use TD/SMP, you would type:

Local> define port multi enable Return

# 2.5.3 Multiple Sessions using SSU Host Software

If your VT520 is connected directly to a host computer without a terminal server, use can still use TD/SMP by running the Session Support Utility (SSU) on your host computer. On a system that has SSU software, such as OSF or OpenVMS, open the first session as follows:

```
$ mcr ssu Return
```

On an UNIX-style system, open the first using:

% ssu

# 2.5.4 Opening Another Session

Once TD/SMP is enabled, you can open a new session and switch between them as follows:

1. Press the F4 (Session) key on a VT keyboard; or press Caps Lock 0 on the numeric keypad on a PC keyboard.

F4 is used as the Session key on the VT keyboard (factory default). For consistency, Caps Lock F4 also works on the VT keyboard.

On Enhanced PC layout keyboards (PC style), Caps Lock F4 or Caps Lock Scroll Lock are used as the Session keystroke and may be substituted for the VT Session key (F4) anywhere it is used.

2. To go directly to a particular session, press Caps Lock 1, 2, 3 or 4 on the numeric keypad.

The currently selected session is indicated on the Set-Up Summary line along with its corresponding communications port assignment (S1=comm1 for example).

# 2.5.5 Restoring an Interrupted Session

When a session is interrupted, the VT520 or the host system may lose the context of the current session. After the terminal and system regain communication, you can restore the context of the interrupted session without canceling the session and starting over again.

To restore a session, press the  $\boxed{\texttt{F4}}$  key; or press  $\boxed{\texttt{Caps Lock} \ 0}$  on the numeric keypad. Or you can enter Set-Up **Communications**  $\triangleright$  **Port Select** and assign the session to a comm port.

### 2.5.6 Session Management

Assigning more than one session virtual terminal to a single comm port automatically allows session management.


Reducing the number of session virtual terminals assigned to a single comm port from two to one automatically disables session management if it was enabled.

When **Display** > **Framed windows** is selected in Set-Up, you can assign a name for each session up to 30 characters for the window title. The first 12 characters become the default icon name, which you can change in Set-Up.

### 2.6 Session Menu

The Session Set-Up (Figure 2–5) controls the use of the more than one session.

Figure 2-5 Session Menu



On a VT keyboard,  $\boxed{\texttt{F4}}$  is used as the Session key (factory default). On a PC keyboard,  $\boxed{\texttt{CapsLock} \ 0}$  kpd is used as the Session keystroke and may be substituted in this text for VT Session key (F4) anywhere it is used. For consistency,  $\boxed{\texttt{CapsLock} \ 0}$  kpd also works on the VT keyboard.

### 2.6.1 Select Session

The **Select session** submenu is used to select the active session. All Set-Up selections apply to the currently active session. Most settings are kept independently for each session and may be saved in non-volatile memory. Exceptions are made for settings that control the physical hardware that is shared between sessions. Example:

A single communications port cannot be used for both a session connection and a printer port simultaneously.

The terminal ensures that conflicts like this do not happen by disabling (displaying as dim) or resetting certain selections. All such exceptions are noted explicitly.

A disabled session has its session selection dimmed but can still be configured in Set-Up if it was active when Set-Up was entered. At least one session is always enabled. If the currently active session is disabled, the previous enabled session becomes the active session when you exit Set-Up.

While the terminal is in Set-Up, the Session key can be used to cycle between sessions in order. You can also use  $\cite{CapsLock} \cite{1} kpd$  through  $\cite{CapsLock} \cite{4} kpd$  to select enabled sessions explicitly. The currently selected session is indicated on the Set-Up Summary line along with its corresponding communications port assignment (S1=comm1 for example).

Selecting a different session within Set-Up does not affect the active session at the host until you exit Set-Up.

### 2.6.2 Session Name

The **Enter session name** dialog box allows a 30 character descriptive name to be entered for the active session. Depending on the windowing option selected, this name is displayed with the corresponding session window to help you identify each session. See also Section 2.8.19.

Entering a session name is similar to entering an answerback message. A session name is not saved automatically; you must use the **Save settings** menu item.

**Icon name** — The first 12 characters of the session name is used as the icon name, but this name may be overwritten if a separate icon name is specified by a host control function. The session name is included as the "application\_ parameter" in the TD/SMP OPEN\_SESSION command and may be used to select a desired service.


# 2.6.3 Pages per Session

The **Pages per session** dialog box displays a Session Page Memory Allocation screen (Figure 2–6), which allows you to control how the terminal's page memory is allocated among the enabled sessions. The VT520 provides 8 pages of 25 lines by 80 or 132 columns as standard (9 pages on the color terminal). A disabled session (Comm = session off) is dimmed and does not use any page memory.

Page selections which are not available in the current configuration are dimmed and cannot be selected. Thus, you may have to decrease the number of pages assigned to one session before you can increase the number of pages assigned to another. Any data on these pages is erased.

Figure 2-6 Session Page Memory Allocation

Terminal Set-Up



The "o \_\_pages" selections in Figure 2–6 allow you to enter a number of pages not shown as one of the other choices. The number in parenthesis below these selections is maximum number of pages available to each session. When you select this radio button, this maximum number is used as the number of pages for this session unless you enter a new value. Pressing Enter selects the radio button and maximum number of pages in a single operation. Alternatively, any number up to the maximum number of pages available can be typed in directly.

The maximum number of pages available to each session change as the allocation to other sessions changes. If only one session is enabled, the maximum number of pages in a standard VT520 is 8.

A session that is currently disabled (Comm = session off) is dimmed and shows Max pages as zero to remind you that it is not using any page memory. (Zero is the factory default for S3 and S4.) A disabled session can be re-enabled at any time by assigning it to a communications port. When a disabled session is re-enabled, its initial page memory allocation is the previous allocation for that session if available from the free resource pool; otherwise, it is one page of 25 lines. If all pages are currently assigned, the terminal reduces by one the allocation to the highest numbered session with more than one page. This automatic adjustment of page allocation ensures that you can always enable another session without worrying about memory management. If a session requires a fixed number of pages for compatibility, you can assign that number to S1 and S2. We recommend that you allocate page memory for the number of sessions to be used ahead of time to avoid losing data in an existing session when creating a new one.

In case you cause the terminal to re-assign page memory while sessions are in use, the pages assigned to a new session is first erased. If the cursor was on that page, it goes to page one. The terminal issues a warning message to indicate what may have changed for you to check, such as:

"Page memory reallocated, check pages per session and lines per page." The terminal created a new session forcing page memory to be re-allocated.

"Incompatible settings not restored, check pages per session and lines per page." The terminal is unable to copy or restore a requested setting.

### 2.6.4 Soft Character Sets/Session

The **Soft char sets/session** submenu allows you to specify the allocation of DRCS character set buffers to multiple sessions on the VT520 mono terminal only.

- **Two each S1 and S2** allocates two character set buffers each to S1 and S2 making S1 and S2 compatible with terminals, like the VT510, VGB10, or WS510 video terminals. In this case, S3 and S4 do not support the DRCS extension, which is reported in their primary device attributes response.
- One each gives each session a single DRCS character set buffer making each session compatible with terminals, like the VT420.

This submenu is not included in the color terminal since it has enough memory to give all four sessions **Two each**.

# 2.6.5 Save Settings for All and Restore Settings for All

The **Save settings for all** and **Restore settings for all** menu items are like the Save settings and Restore settings items in the main menu except that they operate on all four sessions at once.

Since restoring settings for four sessions can take some time, the screen is cleared and a "Please wait" message is displayed in the center of the screen for one second to begin the restore operation. A "Done" or "Incompatible setting not restored" message is displayed upon completion.

When restoring settings saved in non-volatile memory, it is possible that the number of pages saved for a session is larger than the number of pages available in the free resource pool. In this case, the same approach is used as when a session is newly enabled. The process can be summarized as follows:

- 1. When restoring settings for more than one session, settings for each session are restored in order (S1, S2, S3, S4).
- 2. The saved page memory allocation is restored if that number of pages is available from the free resource pool, otherwise the page memory allocation is set to one page of 25 lines.
- 3. If no pages are available from the free resource pool, the terminal reduces by one the allocation to the highest numbered session with more than one page.
- 4. If a previously saved setting is not restored, the terminal displays the information message "Incompatible setting not restored, check pages per session and lines per page" on the error line. The message is cleared on the next keystroke.

The principle used is to restore all the settings possible, replace those individual settings that can't be restored with some reasonable default, and display the information message "Incompatible setting not restored..." if necessary. This same principle is used in all cases where settings cannot be copied or restored due to resource limitations or conflicts with other settings.

The active session number is not saved in NVM. Restore settings for all does not change the active session.

# 2.6.6 Copy Settings from Menu

The **Copy settings from** menu allows you to copy settings from another session to the current one. The currently active or in-use settings are copied so it is not necessary to save settings in one session before copying them to another.

The communications port selection and print port selection are not copied. The VT520 conceptual model is four terminals sitting on your desk. Copying settings from one terminal to another does not transfer the communication cables. Copying settings to a disabled session does not automatically enable it since the "Comm = session off" setting is not changed.

The session name if any is not copied. Since the conceptual model is four terminals, copying settings does not copy the label on each terminal. The page memory allocation is copied unless there are not sufficient pages available in the free resource pool. In this case, the page memory allocation remains unchanged, and the information message "Incompatible settings not restored, check pages per session and lines per page" is displayed.

# 2.6.7 Update Session

The **Update session** menu controls how a session is updated when it is not the active session.

- **Only when active** prevents the session from being updated unless it is the active session.
- **When available** allows the page memory of this session to be updated when the VT520 is not otherwise busy with the active session (factory default).
- At regular intervals ensures that the page memory of this session is updated on a regular basis. Updating an inactive session at regular intervals slows down the active session as necessary.

Note
Increasing the number of sessions assigned to a communication port from
1 to 2 causes the terminal to send the TD/SMP ENABLE_SESSIONS
command. Conversely reducing the number of sessions from 2 to 1 sends
a TD/SMP DISABLE_SESSIONS command. Pressing Control while
selecting "Clear comm" in Set-Up also sends DISABLE_SESSIONS.
•

# Set-Up

# 2.7 Resetting and Restoring Defaults

# 2.7 Resetting and Restoring Defaults

### 2.7.1 Reset Session

The **Reset this session** menu selection only resets the active session. To reset all four sessions, press the Control key while you select Reset this session. Pressing Control/Set- Up from within Set-Up initiates a power-up reset.

# 2.7.2 Restore Factory Defaults

The **Restore factory defaults** menu selection restores the factory default settings for all four sessions. There is no provision to restore factory defaults to a single session. Restore settings on the main menu only restores the active session's settings from NVM.

# 2.8 Display Menu

Many of the features in the Display menu can be controlled by the host control functions listed in Table 2–3. The control functions listed by function in Chapter 4 and are described fully in Chapter 5.

Table 2-3 Display Set-Up Features and Control Functions

Display Set-Up Feature	Factory Default	Host Control Code
Lines per screen	24, 25 or 26	DECSNLS
[] Auto resize		DECARSM
Lines per page	24 lines x 3 pages	DECSLPP
[] Review previous lines		-
Columns per page	80 Columns	DECCOLM
[/] Clear on change		DECNCSM
Status display	Local status	DECSSDT
Scrolling mode	Jump	DECSCLM DECSSCLS
Screen background	Dark	DECSCNM
Cursor display	Block	DECSCUSR
[/] Blink		-
[/] Enable cursor		DECTCEM
Cursor coupling		-
[/] Vertical coupling		DECVCCM
[/] Page coupling		DECPCCM
Cursor direction	Left to right	DECRLM
Copy direction	Left to right	DECRLCM
Zero	0	DECSZS
[] Auto wrap		DECAWM
[] New line mode		LNM
[ ] Lock user preferences		-
[] Show control characters		CRM
CRT saver	15 minutes	DECCRTSM
[/] Host wake-up		-
Energy saver	15 minutes	DECEST
[] Overscan		DECOSCNM (mono model only)
[] Framed windows		-
Screen alignment		DECALN

### 2.8.1 Lines per Screen

This menu chooses a font that enables the selected number of lines to be viewed. Note that you cannot view more lines than the number of lines on a page (**Lines per page**).

If the **Status display** is enabled, it is displayed using one of the same **Lines per screen** as the text for the corresponding session.

This is an operator preference feature and cannot be changed by control functions if the operator preference is set to **Lock user preferences**; however, if **Auto resize** is enabled at the same time, then the number of **Lines per screen** changes when the page size changes.

This feature can be changed from the host using the DECSNLS control function. Or, it may be changed indirectly from the host if **Auto resize** is selected and the page configuration is changed using DECSLPP.

#### 2.8.1.1 Auto Resize

When **Auto resize** is enabled, the number of lines per screen changes automatically each time the page arrangement changes, either by the host or through Set-Up. Table 2–4 shows how the screen size changes whenever the page size changes when Auto Resize is set.

Table 2–4 Lines per Page vs. Lines per Screen When Auto Resize is Set

Lines per Page	Lines per Screen
24	26
25	26
36	43
42	43
43	43
48	52
52	52
72	52

If **Auto resize** is enabled in Display Set-Up, switching to two windows will set **lines per screen** to 48 and switching to one window will set **lines per screen** to correspond with the most recent lines per page setting, as if DECSLPP had been received. This applies to all sessions with auto-resize enabled.


### 2.8.2 Lines per Page

This menu allows you to select the page size in lines and number of pages. The page size determines the addressing range for cursor positioning and scroll regions. The number of lines that can be displayed depends on the current setting of the **Lines per screen** feature.

Lines per page sizes not available based on the current page memory allocation are dimmed. If the page memory allocation is changed such that the currently selected number of lines per page is not available, the factory default page size is used (24 lines per page for the VT emulations).

When the **Review previous lines** feature is selected, the **Lines per page** selections show the corresponding number of lines by only one page (Figure 2–7).

Figure 2-7 Lines per Page



This field is also invoked by the DECSLPP control function.

#### 2.8.3 Review Previous Lines Buffer

The **Review previous lines** feature when selected re-arranges page memory into a single page and a scroll back buffer (transcript). Lines of text scrolled up from the first line of the page are saved in the scroll back buffer (replacing the oldest lines saved if any). Pressing Control with the up or down arrow keys pans the screen window up or down allowing you to view lines previously scrolled off the top of the page up to the number of lines saved in the scroll back buffer. If the page size is larger than the window size, pressing Control with the up arrow key first pans to the top of the page and then pans into the scroll back buffer.

Any time lines in the scroll back buffer are available, a small down and/or up arrow appears at the lower right position of the status line to indicate there are additional unseen lines of the page below or above. When any text is received from the host for this session, the screen window is automatically repositioned to show the single page before the display is updated. Switching sessions does not automatically reposition the screen allowing you to view the scroll back data in one window while working in another. The number of lines that can be saved in the scroll back buffer is one page less than the total number of lines (in 25 line pages) allocated to the session virtual terminal. The factory default for Review previous lines is *disabled*.

You cannot copy and paste from the scroll back buffer.

# 2.8.4 Columns per Page, Clear on Change

This menu allows you to select an 80- or 132-column display for text. If **Clear on change** is disabled, changing this feature does not clear page memory, except when changing from 132 columns to 80 columns; then, columns 81 through 132 of each page are cleared. Changes to this field take effect immediately.

This field is also invoked by the DECSCPP and DECCOLM control functions. The **Clear on change** feature affects the behavior of the DECCOLM sequence or 80/132 column mode setting only. *It does not erase page memory.* The factory default is "clear on change" for backward compatibility with previous terminals.

## 2.8.5 Status Display

The **Status display** can be enabled in the following selections:

- Local status
- Host writable or editing
- None

### 2.8.6 Scrolling Mode

The **Scrolling mode** menu allows you to select how fast lines appear on the screen.

Scroll Selection	Scroll Rate
Slow smooth	Smooth steady scroll at approximately 9 lines per second (two scan lines per frame time).
Fast smooth	Smooth scrolls at approximately 18 lines per second.
Jump	Displays new lines as fast as they are received, causing a jump scroll on the screen.

This is a user-preference feature. If **Lock user preferences** is set, then this field is not invoked by any control functions.

### 2.8.7 Screen Background

The **Screen background** can be either dark or light, with **dark** as the default.

### 2.8.8 Cursor Display

The **Cursor display** can be enabled in the following selections:

- Block
- o Underline
- M Blink
- Enable cursor

# 2.8.9 Cursor Coupling

**Cursor coupling** can be **Vertical** and/or Page coupling selectable from a single submenu.

### **Vertical Coupling**

Vertical coupling selects whether the user window automatically pans to follow the cursor when the cursor is moved vertically to a part of the page that is not in the currently displayed user window. Panning does not occur until the input buffer becomes empty and the cursor is displayed.

When **Vertical coupling** is disabled, the user window does not follow the cursor. If the cursor moves above or below the visible portion of the page, the cursor is no longer visible.

#### **Page Coupling**

**Page** coupling selects whether the user window automatically follows the cursor when the cursor is moved to a page that is not currently in the user window. When page coupling is enabled, moving the cursor to a page that is not currently displayed causes that page to be displayed. Panning does not occur until the input buffer becomes empty and the cursor is displayed.

When **Page** coupling is disabled, the user window does not follow the cursor. If the cursor moves to a page that is not currently displayed, the cursor is no longer visible.

### 2.8.10 Writing Direction

The **Writing direction** and copy direction defaults are **left to right**. If a Hebrew keyboard is connected to the terminal, a selection is available for advancing or copying right to left.

The writing direction and the copy direction should be matched.

### 2.8.11 Zero

A **Zero** feature allows you to select the style of the zero character: oval, zero with a slash, or zero with a dot.

#### 2.8.12 Auto Wrap

**Auto wrap** selects where a received character is displayed when the cursor is at the right margin.

This is not a user-preference feature, so you cannot lock this feature.

This field can be invoked by the DECAWM control function. The **Auto wrap** setting can be saved in NVM.

#### 2.8.13 New Line Mode

When enabled, **New line mode** selects the characters transmitted by Return, CR, or CR+LF. It also determines the action taken by the terminal when receiving line feed, form feed, and vertical tab, LF, or CR+LF.

**New line mode** is not a user-preference feature, so you cannot lock it. This feature can be invoked by the DECNLM (SM/RM) control function.

# 2.8.14 Lock User Preferences

The **Lock user preferences** feature allows you to prevent the host from modifying user-preference features. If set to lock, the user-preference features cannot be changed by host control functions.

The following user-preference features are locked and unlocked by this feature and when locked, cannot be changed by control functions:

Auto repeat

# Set-Up 2.8 Display Menu

- · Scrolling mode
- Screen background
- Tab stops
- Keyboard definitions
- Lines per screen
- Auto resize
- Overscan

#### 2.8.15 Show Control Characters

**Show control characters** allows you to select a normal display or a display called Control Representation mode or CRM. This "monitor and show all" display includes graphic representation of control characters,

When **Show control characters** is enabled, special CRM symbols are used for the C0 and C1 control areas of ISO 2022 conforming character sets. Other characters are displayed using the current user preference supplemental set (DEC default character set).

#### 2.8.16 CRT Saver

If the **CRT saver** feature is enabled the screen goes blank after the specified interval of no keyboard activity or receive character activity. This feature is intended to prevent phosphor aging and prolong the useful life of the CRT. When the CRT saver is active, the monitor goes into *stand by mode*.

Any keystroke instantly restores the display to show its previous contents.

If **Host wake-up** is enabled, any character received from the host also restores the display.

The factory default setting is **CRT saver** enabled.

If **CRT saver** = **Never** is selected, the Energy saver is dimmed and not available.

Monitor Mode	VT520 Terminal	Color Terminal
On	Normal operation	Normal operation
Stand by	Screen saver (~4 W)	Video blank, no horizontal sync
Suspend	Energy saver (<15 W)	Video blank, no vertical sync
Off	Same as Suspend	Video blank, no sync

# 2.8.17 Energy Saver

The **Energy saver** feature switches the monitor to **suspend mode** after the specified interval of CRT saver active. Monitor suspend mode blanks the screen like CRT saver but also switches off the synchronization and deflection circuits of the monitor significantly reducing the terminal's power consumption. A keystroke may take several seconds to restore the display from suspend mode.

On the color model, **Energy saver** switches the monitor to **off mode** after 30 minutes in suspend mode. The monitor off mode is like suspend mode but also turns off the CRT cathode (heater) further reducing power consumption. From the monitor off mode, it can take 15 to 30 seconds to restore the display upon

detecting a keystroke. The color model follows the VESA convention for driving Energy Star<sup>1</sup> compliant PC monitors.

Received characters power the monitor back on from the Energy saver suspend or monitor off state only if CRT Saver **Host wake-up** is selected. Otherwise it is necessary to press a key to power the monitor back on.

#### 2.8.17.1 Warning Bell

The terminal's warning bell still operates normally in all energy saver states. Many host systems ring the warning bell to indicate new mail has arrived or to draw attention to an important system message. Upon hearing the bell, press any key to see the corresponding host message.

**Energy saver** = **Never** allows power to continue to be supplied to the monitor.

#### 2.8.18 Overscan

**Overscan** can be enabled for the monochrome VT520. It is dimmed and not available for the color model.

#### 2.8.19 Framed Windows

When the **Framed windows** check box is selected in the Display menu, window frames with title bars are added to each displayed window. The VT520 has a flip screen and a two-window style with adjustable split. Window frames with titles and icons help you keep track of up to four sessions.

On the mono VT520, the Framed windows check box controls whether session windows are displayed with title bars and session icons.

 $802 \times 480$  no overscan, or

 $800 \times 432$  with optional overscan.

When Framed windows is selected, the overscan check box is dimmed. Framed windows is the factory default.

On the color terminal, only the  $802 \times 480$  no overscan format is available. The Framed windows check box controls whether session windows are displayed with title bars and session icons ( $802 \times 480$  no overscan), or the window frame and icon scan lines are left blank. There is no overscan selection on the color terminal.

When the Framed windows check box is selected in the Display menu, window frames with title bars are added to each displayed window. The title bar shows the previously entered session name if any and is highlighted (filled in) when the session is active. A row of icons is presented across the top of the screen to help you to keep track of the other sessions.


An icon is displayed for each session in the cycle order followed by the icon name which consists of the first 12 characters of the session name unless overwritten by host control function. The icon for the active session is displayed with the reverse video attribute. If the page memory of a session that is not currently visible is updated so that it contains new data which has not yet been seen, the corresponding session icon is displayed with the blink video attribute until the session is made active.

<sup>&</sup>lt;sup>1</sup> The Energy Star emblem does not represent EPA endorsement of any product or service.

When one session window is displayed, pressing the Session key alone cycles the active session in forward sequence by session number (S1, S2, S3, S4, S1,...). Pressing Shift/Session cycles the active session in reverse sequence by session number (S4, S3, S2, S1, S4,...). A session that is not assigned to a comm port (communications port select "Comm = session off") is omitted from the cycle order.

Control Session (F4) toggles the display between one window or two windows (Figure 2–8).

Figure 2-8 Framed Windows



A maximum of two of the possible four session windows can be displayed at a time. One of these must be the active session. When switching to two windows, the active session is displayed on top. When two windows are displayed, pressing the session key toggles the active session between the two sessions displayed. To activate a session not currently displayed, you can use <a href="CapsLock">CapsLock</a> <a href="I kpd">I kpd</a> through <a href="CapsLock">CapsLock</a> <a href="I kpd">I kpd</a> through the new active session's window was not previously visible, it replaces the previously active session's window. Alternatively, you can select any session through the Set-Up Session submenu. Note: CapsLock/F1 is a synonym for F11 on the PC keyboards.

When two windows are displayed, the relative size of each window is adjustable by pressing Control and Shift with the up or down arrow keys to move the border between the windows up or down.

You cannot display the same session in both windows at the same time. Activating a session already displayed makes it the active session. If **autoresize** is enabled in Display Set-Up, switching to two windows will set **lines per screen** to 48, and switching to one window will set **lines per screen** to correspond with the most recent lines per page setting as if DECSLPP had been received. This applies to all sessions with auto-resize enabled.

### 2.8.20 Screen Alignment

#### Screen Alignment on the VT520 Monitor

The **Screen alignment** menu item is used to invoke a screen alignment display (Figure 2–9) for the monochrome monitor only. With the screen alignment display, you can:

- Center the border using Shift and arrow keys.
- Rotate the border using Ctrl ← and Ctrl ⇒.

Screen rotation compensates for any magnetic field in the area.

Figure 2-9 Screen Alignment Display

Hold down the Shift key while using the four arrow keys to center the border on the screen.

Hold down the Control key while using the left and right arrow keys to rotate the border on the screen.

Press Enter to return to the Set–Up menu.

MA-0022-93.GRA

#### Screen Alignment on the VT525 Color Monitor

For VT525 color monitors, **Display** ▷ **screen alignment** . . . displays gray scale bars and color bars for the monitor alignment.

- 1. Press Enter to display the gray scale bars.
- 2. Press Enter again to display the color bars.

# 2.9 Color Set-Up


The **Color** Set-Up allows you to control the use of color by the terminal.

The **ASCII color mode, Reverse and blank attributes**, and **Intensity attributes** are only available in ASCII terminal emulation modes.

**Select color mode** is only available in the non-ASCII terminal emulation modes besides SCO Console mode which always uses ANSI SGR color.

**Alternate text colors...** is only available when **Select color mode = Alternate color.** 


Figure 2-10 Color Set-Up Menu



### 2.9.1 Assign Colors

The **Assign colors** dialog box allows you to select normal display colors for text and windowing features. As the slider moves to select a color within the select color box, the corresponding item is displayed using that color. Changing the normal text background only re-writes the "Normal text" caption. It does not otherwise affect the color of text already displayed.

Figure 2-11 Assign Colors



The normal text background and foreground selections determine the writing color used when all SGR attributes are turned off. The other ANSI color SGR attributes are "hard wired" to corresponding color indexes. Each session maintains its own color assignments for normal text and other data within its window.

The window frame colors are global affecting all session windows and icons. The window frame includes the title bar and adjacent separator lines, the sides, and the bottom separator line.

The session icons and keyboard indicator line foreground are displayed using the Window frame foreground color (or background color when dark text on a light background is selected). The icon and keyboard indicator line background uses the screen background color to merge with the screen border rather than the window title bar.


New color assignments do not take affect until you press OK. Color assignments can be saved in NVM or restored to their factory defaults the same as other Set-Up features.

It is possible to assign text foreground and background colors that make subsequent text difficult to read. Set-Up is displayed using the factory default colors with the exception of those dialog boxes that affect color selections. This ensures that Set-Up is always usable.

### 2.9.2 Alternate Text Colors

Figure 2–12 Alternate Colors

### Terminal Set-Up



The **Alternate Text Colors** dialog box allows you to specify colors for any combination of text renditions (bold, reverse, underline, blink) when the Color mode is set to Alternate text colors. Operation of the dialog box is similar to the Assign Colors dialog box described above. If Underline text is selected, text with the underline attribute will be underlined as well as displayed using the specified color. If Blink text is selected, text with the blink attribute will blink as well as appearing in the specified colors.

- The attributes are displayed in the selected colors allowing you to see the effect desired.
- All combinations can be specified, providing backward compatibility with other video terminals.
- The foreground color of text with the invisible attribute becomes the background color.

### 2.9.3 Define Colors Dialog Box

Figure 2-13 Define Colors

Terminal Set-Up

Actions	5		
Define Colors			
O 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15  AAA BBB CCC DDD EEE FFF GGG HHH III JJJ KKK LLL MMM NNN 000 PPP  AAA BBB CCC DDD EEE FFF GGG HHH III JJJ KKK LLL MMM NNN 000 PPP  EEEEEEEEEEEEEEEEEEEEEEEEEEEEEE			
	00 01 02 03 04 05 06 07 08 09 10 11 12 13 14 15		
Red: Green:	[1]		
Blue:	[1]		
OK To observe	Cancel Save Restore Use default		
To change a color, select the color map entry, then adjust the values for Red, Green, and Blue.			

The **Define colors** dialog box allows you to define the terminal's color map with 16 colors from a palette of 4096 colors. This dialog box is intended for adjusting the appearance of individual colors. Radical changes to the terminal's color map may adversely affect the appearance of ANSI color SGR parameters. In the VT520, each session uses its own independent color map which is not affected by the others.

The boxed areas containing capital letters A-P represent the 16 colors currently defined. The selected color number (0-15) remains highlighted in reverse video while the highlighting cursor moves to the RGB sliders and then down to the labeled buttons.

Color definition changes become visible immediately since the terminal has a single active color map. Cancel restores the color map to the settings in effect when the OK or Save button was last pressed. The OK and Cancel buttons exit this dialog box. Pressing Save is similar to pressing OK but also writes the settings to NVM to be used as the power-on settings. Restore recalls the power-on settings from NVM. Use default recalls the factory default settings.

It is possible to define colors that make subsequent text difficult to read. Set-Up is displayed using the factory default colors with the exception of those dialog boxes that affect color selections. This ensures that Set-Up is always usable.

### 2.9.4 Select Color Mode

The **Select color mode** feature allows you to select how applications will display text colors.

- When ANSI SGR color is selected, color text is specified using the ANSI defined SGR color parameters. The terminal uses factory default renditions for text attributes as defined in Table 2–5.
- When **Alternate color** is selected, the terminal displays text renditions as defined in the Alternate Text Colors dialog box.
- When Mono is selected, the terminal uses a default monochrome or gray level map designed to maintain the appearance of applications that were not designed to use color.

Table 2-5 Default Graphic Renditions

Graphic Rendition	Factory Default Display	
Normal text background	Color index 0	
Normal text foreground	Color index 7	
Bold text foreground	Color index + 8	
Bold text background	Color index (unchanged)	
Reverse text	Write text foreground with background color and background with foreground color.	

The **Color** selection maintains a current graphic rendition that includes a text background color and text foreground color. Reverse text does not exchange the foreground and background colors stored as part of the graphic rendition, rather, it causes the text foreground to be written with the background color and vice versa. Specifying a new foreground color always modifies the "foreground rendition." Subsequent text written with the Reverse attribute will write this color as its background.

#### 2.9.5 ASCII Color Mode

The **ASCII color mode** determines the use of color in the ASCII terminal emulation modes. Color emulates WYSE 325 color. Mono uses a default monochrome or gray level map designed to maintain the appearance of ASCII terminals using applications that were not designed to use color.

### 2.9.6 Bold and Blink Style

**Bold and blink style** selects whether the bold and blink attributes bold and blink the text foreground only, or both foreground and background. By default, bold adds 8 to the corresponding color index value to select a brighter or dimmer color, and blink cycles the text color between its non-blink rendition and a dimmer less saturated shade of the non-blink rendition.

### 2.9.7 Erase Color

The **Erase color** selection controls the background color used when text is erased or new text is scrolled on to the screen. **Screen background** causes newly erased areas or scrolled text to be written using color index zero, the screen background. This is VT and DECterm compatible. **Text background** causes erased areas or scrolled text to be written using the current text background color. This is PC console compatible and is the factory default.

#### 2.9.8 Reverse and Blank Attributes

The **Reverse and blank attributes** selection controls whether the reverse or blank text attributes are mapped to different colors in WYSE 325 emulation.

#### When Map reverse attribute is selected:

- 1. The characters with reverse attribute are displayed by the color which is assigned to the REVERSE/BLANK map in the color palette.
- 2. The characters with blank attribute are displayed by the color which is assigned to the NORMAL map in the color palette.

#### When Map blank attribute is selected:

- 1. The characters with reverse attribute are displayed by exchanging the foreground and background of the NORMAL map in the color palette.
- 2. The characters with blank attribute are invisible; that is, the foreground falls back to the background of the REVERSE/BLANK map in the color palette.

### 2.9.9 Intensity Attributes

The Intensity attributes check box operates in WYSE 325 color mode. When Enabled:

- 1. The characters with dim attribute are displayed in a lower intensity.
- 2. The characters without dim attribute, but were written in intensity disabled mode are displayed in a lower intensity when intensity mode is changed to enable.

#### When Disabled:

All characters are displayed with their normal intensity.

# 2.10 Terminal Type Menu

You can select terminal type and emulation modes using this menu.

### 2.10.1 Emulation Mode

**Emulation mode** is the primary means of selecting different terminal modes or emulations. Changing terminal modes or emulations usually performs some initialization of the terminal state.

Changes to the terminal emulation mode take effect immediately (as soon the emulation mode submenu is exited). Other Set-Up parameters are updated accordingly based on the new emulation mode without exiting Set-Up.

Example: Selecting a VT mode performs a soft terminal reset (DECSTR).

PCTerm mode can be selected or deselected independently from the other emulations. The ASCII modes use WYSE PCTerm. The ANSI modes use VT PCTerm. The ASCII color mode uses WYSE 325 emulation.

This feature corresponds to the DECPCTERM, DECTME, DECANM, and DECSCL control functions described in Chapter 5.

Changing the conformance level (DECSCL) does not change the operating level reported to identify the terminal to the host. It only changes the way extensions are reported.

# 2.10 Terminal Type Menu

- Printer operations are not affected or halted by a change in mode.
- A soft reset is always performed as a result of a mode change from Set-Up.
- Changes resulting from most, but not all, of the above sequences also cause a soft reset. Exception: Entering VT52 mode (via DECANM) does not cause a soft reset from VT100 mode, but does cause a soft reset from VT500 mode.

### 2.10.2 Terminal ID to Host

**Terminal ID to host** selects how the terminal identifies itself to host software, specifically the Primary Device Attributes response (DA). The default ID is **"VT520.**"

For a list of the responses, see the Device Attributes sections in Chapter 5. This field has no effect when the terminal is in VT52 mode. The feature corresponds to the DECTID control function described in Chapter 5.

#### 2.10.3 VT Default Character Set

This feature selects the default international character set to use for output as initialized in G0-G3 and GL/GR. It corresponds to the DECAUPSS (Assign User Preference Supplemental Set) control function described in Chapter 5.

Only ISO Latin-1 and DEC Multinational are available on the North American terminal.

#### 2.10.4 PCTerm Character Set

This feature selects the PC code page, ISO character set, or DEC character set to be used in PCTerm mode and SCO Console mode. This feature is also invoked by the DECPCTERM control function described in Chapter 5.

#### 2.10.5 7-Bit NRCS Characters

This feature enables National Replacement Character Set mode (DECNRCM), as described in Chapter 5. When **7-bit NRCS characters** are selected, a corresponding 7-bit NRC set is used depending on the keyboard language. See Chapter 8 for details. Group 2 or secondary keyboard language characters may still be used if they are in the 7-bit character set. This feature is dimmed unless there is a corresponding NRC set available. This feature is not available on the North American terminal.


### 2.10.6 Transmit 7-Bit Controls

**Transmit 7-bit controls** selects whether C1 control codes are sent in their original 8-bit form (disabled) or converted to their 7-bit ESC Fe form.

This field is invoked by a parameter to the DECSCL control function and by the S7C1T and S8C1T control functions.

# 2.11 ASCII Emulation Menu

Figure 2-14 ASCII Emulation Menu




The features, shown in Figure 2–14 and listed in Table 2–6, are specific to the ASCII emulation modes supported in the VT520. The default is shown in **boldface** type. Refer to Part III for details.

Table 2-6 ASCII Emulation Features

Feature	Selections	Determine
Data lines	<b>24</b> , 25, 42, 43 lines	The number of data display lines visible, not counting any status lines.
Pages	$egin{array}{l} 1  imes lines \ 2  imes lines \ 4  imes lines \ * \end{array}$	The page size and number of pages. $1 \times$ lines selects each page to be the number of data lines visible on the screen. The * makes the display of a single page invisible.
Attribute	<b>Character</b> , line, or page	How visual attributes are applied per character, line, or page.
Write protect attributes	<b>Dim</b> , blank, reverse, underline, and/or blink.	The visual attributes used to highlight and specify write protected data.
Received CR	CR or CRLF	Carriage return or carriage return line feed.
Block Mode	<b>Conversation</b> or Block	Transfer method.
Block End	US/CR or CRLF/ETX	At the end of a block transfer, transmit a carriage return or an end-of-text character.

# 2.12 Keyboard Menu

Figure 2-15 Keyboard Menu



Several of the features shown in Figure 2-15 are self-explanatory and correspond directly to control functions listed in Table 2-7. For additional information, see Chapters 4 and 5.

Table 2–7 Keyboard Features and Control Functions

Set-Up Feature	Control Function
Keyboard language	DECKBD
Switch between primary and secondary keyboard language	DECESKM (general), DECHEBM (Hebrew), DECNAKB (Greek), DECCYRM (Cyrillic)
Caps lock function	DECLCK
Keyclick volume	DECKCV
Warning bell volume	DECWBV
Margin bell volume	DECMBV
Keyboard encoding	DECKPM
Auto repeat	DECARM
Data processing keys	DECKBUM
Application cursor keys	DECCKM
Application keypad mode	DECKPNM, DECKPAM, DECNKM

### 2.12.1 Keyboard Language

Some keyboards allow you to select two different keyboard layouts and easily switch between them (English and Hebrew, for example). This feature allows the VT520 to support both existing conventions and emerging standards for extending the graphic input and/or switching between languages in dual language environments. (The North American keyboard has only one keyboard language, English.)

The primary keyboard language corresponds to Group 1 (per DIN 2137) and generally references the legends on the left half of the keytops.

The secondary keyboard language corresponds to Group 2 (Group Shift per DIN 2137) and generally references the legends on the right half of the keytops.

Unless overridden, Ctrl/Alt/F1 makes the primary keyboard language active, and Ctrl/Alt/F2 makes the secondary keyboard language active. (These are factory defaults, standard on PCs.)

Selecting a new keyboard language in Set-Up automatically initializes the keyboard character set, as described in Chapter 8.

Changes to this field take effect immediately. Changing this field to North American or Dutch and then exiting Set-Up or going to another menu resets the **7-bit NRCS characters** feature to disabled. There is no "7-bit characters" mode for the North American or Dutch keyboards. This field affects the language of the keyboard indicator line.

### 2.12.2 Define Key Editor

The Define Key Editor is an advanced function that allows the terminal to adapt to environments that do not match the preprogrammed settings.


Caution	
This function is designed to be easy to use; however, unless you understand the consequences of remapping various key combinations, use caution when using this feature.	

The **Define key** menu invokes the Define Key Editor.

To ensure consistent access to Set-Up features, the following rules apply for interpreting keystrokes.

- Within Set-Up and the Define Key Editor, the four arrow keys along with <a href="Enter">[Enter</a>, <a href="Return">[Return</a>, <a href="Do">[Do]</a>, <a href="Select">[Select</a> and delete key <a href="X">X</a> are interpreted according to their standard definitions, regardless of how they may be redefined at other times. The delete key will erase a field when defining an alphanumeric key. The one exception is when pressing the key to be defined.
- When you press [3] as the first key after the terminal is powered on, you always enter Set-Up, regardless of which keyboard you use or how [53] is defined.
- When copying one key definition to another, the standard key definition for a key is copied, not the current definition. This copy method ensures that keyboard functions are not lost within the Define Key Editor.

Figure 2-16 Define Key Editor, Select Function



MA-0324-93.GRA

### 2.12.2.1 Copy of Key Default—Moving a Standard Function

The simplest way to reprogram a key is to copy the behavior of another key. You can use **Copy of key default** to copy the factory default for a key to be defined to any position on the keyboard. You cannot, however, use this feature to edit the code transmitted by individual keys. To move factory default key functions:

- 1. From the **Keyboard** menu item, select the **Define key . . .** function and press Return; the **Define Key Editor** menu will appear.
- 2. Press the key for which you want to assign a new behavior. If the key is a function key, a screen similar to Figure 2–16 is displayed. Names are displayed in the Set-Up language selected (not according to keyboard language). The ± symbol indicates a toggle feature. Names are truncated to 12 characters in the definition field.
- 3. Press  $\Rightarrow$  to highlight the **Copy of key default** radio button (•) and press Enter.
- 4. Press the key whose factory default behavior is what you want your defined key to do.
- 5. Press ↓ to highlight the OK or Apply button and press Enter.

### 2.12.2.2 Customization

If you want to program a key to behave differently than one of the factory defined keys, then you will need to know about the following key categories:

Function: Keys such as the arrow keys ( $\uparrow$ ,  $\downarrow$ ,  $\Leftarrow$ ,  $\Rightarrow$ ), the Shift modifier key, or the

Set-Up key, used to transmit function key sequences or to perform local

terminal functions.

Alphanumeric: Keys used to transmit alphanumeric characters.

### 2.12.2.3 Modifier Keys

Modifier keys vary from within the Function and Alphanumeric categories. A modifier key is a key that modifies the behavior of other keys when it is pressed and held down. For example, pressing an alphanumeric key in combination with the Shift modifier key will normally send the shifted or uppercase characters for that key.

Modifier keys are treated as a special kind of local terminal function. The VT520 function modifier keys are: Shift, Ctrl, and Alt. VT520 alphanumeric keys can also be modified by pressing Group Shift (Alt Gr) on enhanced PC keyboards) and Alt/Shift (Shift-2). Modifier keys themselves cannot normally be modified by other keys. A key assigned to act as the Shift modifier, for example, cannot transmit a function sequence when pressed in combination with Alt. Defining a key as a modifier key makes all assignable combinations of that key act as a modifier.

#### 2.12.2.4 Creating a New Function

To define a new function key:

- 1. From the **Keyboard** menu item, select the **Define key . . .** function and press Return; the **Define Key Editor** menu will appear.
- 2. Press the key for which you want to assign a new behavior.
- 3. Press the ← or ⇒ key to highlight the **Function** radio button (•) and press Enter.
- 4. Press the ↑ and ↓ keys to highlight the modifier combination that you want to define (Unshifted, Shifted, Control, and so on) and press Enter.
- 5. Press the ⇒ key to move to the **Select function** scroll box. Press the ↑ and ↓ keys to highlight the desired keystroke function from the list and press Enter.
- 6. Press the  $\leftarrow$  key to return to the **Modifiers**.
- 7. Repeat steps 4 through 6 to define other modifier combinations as desired.
- 8. Use the arrow keys  $(\uparrow, \downarrow, \Leftarrow, \Rightarrow)$  to highlight the OK or Apply button and press Enter.

#### 2.12.2.5 Examples of Creating New Functions

Examples of when to create new functions include:

- Changing the or Delete key to delete when unshifted and to backspace when shifted.
- Disabling the Compose, Break, and Set-Up keys by assigning them to have no function.

### 2.12.2.6 Correcting a Mistake

If you make a mistake or want to start over, choose the **Cancel** button. Use **Actions** ▷ **Restore factory defaults** to restore the factory default settings.

# 2.12.2.7 Creating A New Alphanumeric Key or Keyboard Layout

The method for creating a new alphanumeric key is similar to that for function keys, except that you can define different modifier combinations and you enter alphanumeric values differently.

If the key was previously programmed as a function key, the function definition will be empty. Once any function definition is applied, all the alphanumeric definitions for that key are lost. A single key cannot act as both a function key and an alphanumeric key simultaneously.

To define a new alphanumeric key:

- 1. From the **Keyboard** menu item, select the **Define key . . .** function and press Return; the **Define Key Editor** menu will appear.
- 2. Press the key for which you want to assign a new behavior.
- 3. Press the ← or ⇒ key to highlight the **Alphanumeric** radio button (•) and press Enter. The character transmitted when this key is unshifted is highlighted.
- 4. To select a different character, press the corresponding key on the keyboard, or use the numeric compose key to generate a new character.
- 5. If desired, press the ⇒ key to move to the **Non-spacing accent** scroll box. Press the ↑ and ↓ keys to highlight any non-spacing accent from the list and press Enter.
- 6. The code transmitted by the unshifted alphanumeric key when pressed in combination with the Control key is calculated automatically and displayed in the **Definition** column. If desired, you may redefine this function.
- 7. If desired, select an Alt Function modifier combination for the alphanumeric key from the **Select Function** scroll box. You may choose a function, including a user-defined key (UDK) sequence. The default for the Alt Function is **None**.
- 8. Press the ⟨= key to return to the modifier selection.
- 9. Use the arrow keys ( $\uparrow$ ,  $\downarrow$ ,  $\Leftarrow$ ,  $\Rightarrow$ ) to highlight the OK or Apply button and press Enter.

To enter alphanumeric values you can type the desired character or numeral, you can compose the desired character including numeric keypad compose, or you can select a nonspacing accent from the nonspacing accent scroll box.

#### 2.12.2.8 Examples of Creating New Alphanumeric Keys

Examples of when to create new alphanumeric keys include:

- Making the comma and period keys send comma and period instead of angle brackets when shifted.
- Changing the keyboard from a QWERTY to QWERTZ layout.
- Defining an alternate key layout to match your own preference or local typing conventions (Dvorak, or Russian Cyrillic, instead of Bulgarian Cyrillic).

#### 2.12.2.9 User-Defined Keys

The **UDK** radio button allows any key to be programmed with a user-defined sequence. UDKs are a subset of function keys. A separate UDK dialog box is provided for simplicity. Selecting **UDK** causes a **UDK**: text field to be displayed so you can enter a key sequence. This text field can scroll left or right as needed to allow longer strings to be entered.

Enter control codes by holding the Compose or Alt key down and entering the decimal value for the code on the Numeric keypad. Codes may also be entered on the Numeric keypad in column/row format as follows:

Compose 1	[. [1] [1]
Press 取 again UDK directions:	to move the highlighting cursor to select one of the following
• Normal	The sequence is sent to the host and/or to the screen depending on the communication settings (On-line, Local echo, Half duplex, and so on).
o Terminal only	The sequence is sent only to the screen, as if it had just been received from the host.
o Host only	The sequence is sent only to the host, regardless of the communication settings.
Press ↓ again	to select one of the following buttons:
OK A	pply Cancel

When you select Cancel, you only cancel the changes to the currently selected modifier combination.

#### 2.12.2.10 Programming Notes

- When you press [3] as the first key after the terminal is powered on, you always enter Set-Up, regardless of how [5] is defined.
- The factory default Break function (unshifted F5) <u>cannot</u> be reprogrammed by host control sequence. This is necessary to support secure attention. If the sequence is received, the factory default keystroke table entry for Break is not overwritten.
- If a key is programmed to act as a modifier key, it operates as a modifier with any combination of Shift, Alt, or Control.
- If a key is programmed to be a modifier key and modifier key reporting is enabled using DECSMKR, the key sends the VT sequence for the left modifier key when there is more than one.
- Caps Lock combinations such as Caps Lock/Print Screen are local keyboard extensions and cannot be reprogrammed by DECPFK. The Caps Lock key acts as a modifier. The Caps Lock function can be moved to another key, but Pause must still send the Break.
- Use of the Define Key Editor to redefine keys on the numeric keypad affects
  only the Num Lock off state of these keys. When Num Lock is engaged, these
  keys will always send their factory default ASCII numerals (and related
  characters) intended for numeric input. The Num Lock behavior of these
  keys cannot be reprogrammed. (This Num Lock behavior does not apply to
  numeric keypad mode on the VT keyboard or PC keyboard in VT style.)

# 2.12 Keyboard Menu

- The toggle Num Lock function can be assigned to any single key combination.
   Although the Num Lock state modifies other keys, the toggle Num Lock function is not a modifier key. This means modifier combinations of
   Num Lock/Key
   can be assigned to any other function or user-defined sequence.
- Use of the numeric keypad to compose characters by entering their decimal code in combination with Alt Gr or Compose (held down) should continue to work regardless of any reprogramming of keys on the numeric keypad, unless such reprogramming directly conflicts with use of the keypad in this manner. Example: A numeric keypad key has been defined as Compose or Alt Gr.
- Function keys also work in VT100 mode.

# 2.12.3 Save Key Definitions

To save your key definitions so they will be available the next time you turn the power on, select the **Save key definitions** menu item from the **Keyboard** menu.

This action field on the keyboard menu (Figure 2–15) causes the **Define key** modifications to be saved to nonvolatile memory independently from any other Set-Up features. Key definitions are saved on a first-come first-served basis and are limited by the total amount of nonvolatile memory available.

This feature cannot be invoked by a host control function.

# 2.12.4 Recall Key Definitions

This action field causes previously saved **Define key** modifications to be recalled from nonvolatile memory independently from any other Set-Up features.

# 2.12.5 Lock Key Definitions

The **Lock key definitions** menu item operates as a check box. When key definitions are locked, they cannot be reprogrammed from the host.

#### 2.12.6 Caps Lock Function

This function allows you to enable the Lock or Caps Lock key to do the following:

• Caps lock Lock alpha keys on main keypad in uppercase setting.

Shift lock
 Reverse lock
 Works the same as Caps Lock, except that pressing the Shift key will send the lowercase or unshifted character assigned to a key.

#### 2.12.7 Keyclick, Warning Bell, and Margin Bell Volume

The volume of these settings can be set to high, low, or off, with **high** as the default.

**Suppress repeated warnings** causes the terminal to ignore Control-G warning bells encountered within two seconds of a previously sounded warning bell. When using multiple sessions, this feature prevents broadcast messages sent to more than one session from sounding the warning bell repeatedly for each session. Alternatively, if several broadcast messages are pending in an inactive session, the warning bell sounds once when the session is made active.

#### 2.12.7.1 Visible Bell

The terminal provides a **Visible bell** feature, which flashes a bell ringing font whenever a sound is generated. The fonts will flash six times and disappear in 2 seconds automatically. In ANSI mode, the bell is displayed at column 16 of the keyboard indicator line (same place as the sticky keys indicator). In ASCII mode, the bell is displayed at column 23 of the status line These bell fonts may temporarily replace another indicator on the screen.

#### 2.12.8 Keyboard Encoding

The **Keyboard encoding** menu allows you to select from the following:

• Character (ASCII) The keyboard uses normal ANSI/ISO character encoding.

• Scancode The terminal transmits make and break codes for each

keystroke corresponding to the hardware scan codes used

by PC keyboards (scan set 1).

• Key position The keyboard transmits key position codes for each down

transition. This menu allows alternate keyboard layouts to be

supported by application software.

This feature corresponds to the DECKPM (key position mode) control function described in Chapter 5.

# 2.12.9 Auto Repeat

The **Auto repeat** feature selects whether keys begin auto repeating if still held down after a delay interval:

- Fast (30/sec)
- o Slow (10/sec)
- o Off

The repeat rate is the number of "keystrokes" per second, not characters per second. Changes to this field take effect immediately.

This is a user-preference feature. When it is unlocked, this feature can be invoked by the DECARM control function.

# 2.12.10 Data Processing Keys

This feature corresponds to the DECKBUM control function described in Chapter 5. Changes to this field take effect immediately.

# 2.12.11 Application Cursor Keys

This feature corresponds to the DECCKM control function described in Chapter 5. This feature is reset to the factory default setting by DECSTR.

Changes to this field take effect immediately.

Settings for **Application cursor keys** (AppCK) and **Application keypad mode** (AppKM) selected in Set-Up can be saved to NVM and used as the power-on settings. Settings for AppCK and AppKM selected by host control functions affect the current operating state, as shown by the check boxes, but are not saved in the NVM.

# 2.12.12 Application Keypad Mode

This feature selects whether the numeric keypad sends ASCII numerals or application function sequences. It corresponds to the DECKPNM, DECKPAM, and DECNKM control functions described in Chapter 5.

This field is reset to the power-up setting when a soft reset occurs (Reset Session or receipt of DECSTR).

Changes to this field take effect immediately so you can use the keypad to enter an Answerback message.

# 2.12.13 Map PC Keyboard to VT

**Map PC keyboard to VT** causes the terminal to treat a PC layout keyboard as if it were a VT keyboard. F1-F5 behave as local function keys (Hold, Print, Set-Up, Session, Break). Editing and numeric keypad keystrokes work the same as the corresponding keys on a VT keyboard (PF1-PF4 are recognized instead of NumLock and other PC legends).


This feature is only available when a PC keyboard is used and can be toggled on or off by pressing CapsLock/NumLock.

# 2.12.14 Ignore Missing Keyboard

When selected, **Ignore missing keyboard** causes the terminal to ignore a missing keyboard during power-up selftest instead of displaying a "Keyboard error" message.

# 2.13 Communication Menu

Figure 2-17 Communication Menu



Several of the Communication features shown in Figure 2–17 are self-explanatory and correspond directly to control functions listed in Table 2–8. These functions are described in Chapter 5.

Table 2–8 Communication and Modem Features and Control Functions

Set-Up Feature	Factory Default	Host Control Code	
Communication >			
Port select	S1=comm1, S2=comm2, Print=comm3	DECSCP	
Word size	8 bits	DECSPP	
Parity	None	DECSPP	
Stop bits	1 bit	DECSPP	
Transmit speed	9600	DECSCS	
Receive speed	Transmit speed	DECSCS	
Transmit flow control	XON/XOFF	DECSFC	
Receive flow control	XON/XOFF or XPC	DECSFC	
Flow control threshold	Low (64)	-	

(continued on next page)


Table 2-8 (Cont.) Communication and Modem Features and Control Functions

Set-Up Feature	Factory Default	Host Control Code	
Transmit rate limit	150 cps	DECXRLM DECSTRL	
Fkey rate limit	150 cps	DECSTRL	
[/] Ignore Null character		DECNULM	
[] Local echo		SRM	
[] Half duplex		DECCHDPXM	
[] Auto answerback		-	
Answerback message		DECLANS	
[] Answerback concealed		DECCANSM	
Modem ⊳			
[] Enable modem control		DECMCM	
Disconnect delay	2 seconds	DECSDDT	
Modem high speed	Ignore	-	
Modem low speed	Ignore	-	

#### 2.13.1 Communication Port Select

The **Communication**  $\triangleright$  **Port Select** dialog box (Figure 2–18) allows you to specify which of the VT520's serial communication ports (comm1..comm3) are used by each session. The sessions are identified across the top of the dialog box with the session icon name.

Figure 2–18 Communications—Port Select



If more than one session is assigned to a single communications port, the Terminal Device/Session Management Protocol (TD/SMP) is used. Pressing the Session key (F4) cycles through each session 1 through 4 in order making it the active session and establishing the corresponding connection as needed.

If sessions are not yet enabled on the corresponding port, the TD/SMP enable sessions command is issued and the first session connection on this port is established. If the corresponding session connection has not yet been established or the session is not the active session on this port, the TD/SMP open session or select session command is sent. If opening a new session fails, the terminal reverts back to the previous session.

#### **Comm Radio Buttons**

Selecting **Comm** = **session off** completely disables the corresponding session virtual terminal such that it can no longer be made active, it is not included in the switch session cycle order, and its icon does not appear in the framed windows display. Resources previously assigned to this virtual terminal become available to the others. At least one session must always be enabled. The terminal does not allow "Comm = session off" to be set for the last remaining session. Notice that selecting "Comm = session off" does not dim the corresponding session selection in this dialog box.

#### **Print Radio Buttons**

This set of radio buttons control the printer port assignments. They are described below with the Printer Port Select dialog box. This same dialog box appears in both Communications and Printer Set-Up and affects all sessions. If comm3 is assigned as the printer port for one or more sessions, it is dimmed and is not available as a comm selection. Alternatively, if comm3 is assigned as the comm port for any session, it is dimmed and is not available as a printer port selection. The factory default is "Print=none" for all four sessions.

The **Printer Port Select** dialog box allows you to specify which port is to be used for local print operations: serial port comm3 or the Centronics parallel port. If more than one session is assigned to use a single printer port, the printer will be shared on a first-come-first- served basis. The Print Page operation and Printer Controller Mode can not be interrupted. If a session is using the printer for either of these, other sessions attempting to use this printer port are forced to wait (printer status: busy) until the previous operation completes. A session assigned "Print = none" will have "printer status: no printer". Any print operations attempted from this session will be ignored.

#### 2.13.2 Word Size

The communication word size can be 8 bits (default) or 7 bits.

#### 2.13.3 Parity

You can select any of the following parity checks:

- None
- Even
- o Odd
- Even, unchecked
- o Odd, unchecked
- o Mark
- Space

# **2.13.4 Stop Bits**


For communication, 1 (default) or 2 stop bits can be enabled.

#### 2.13 Communication Menu

# 2.13.5 Transmit Speed

The communication **Transmit speed** is set to 9600 baud. You can select transmit speeds from the menu shown in Figure 2–19.

Figure 2-19 Communication Transmit Speed Menu



# 2.13.6 Receive Speed

Like the communication **Transmit speed**, you can select the **Receive speed** from 300 to 115.2K baud. The default receive speed matches the transmit speed selection.

#### 2.13.7 Transmit Flow Control

The **Transmit flow control** method can be one of the following:

- o None
- XON/XOFF
- DSR (Data Send Ready)
- o Both

\_\_\_\_\_ Note \_\_\_\_

When an ASCII emulation is selected, the default **Transmit flow control** is **None**.

#### 2.13.8 Receive Flow Control

The **Receive flow control** method can be one of the following:

- o None
- XON/XOFF or XPC
- o DTR (Data Transmit Ready)
- Both

#### 2.13.9 Flow Control Threshold

You can set the **Flow control threshold** to Low (64 characters) or to High (768 characters).


# 2.13.10 Transmit Rate Limit, Fkey Rate Limit

The **Transmit rate limit** choice limits the character rate from the keyboard to between 30 and 150 characters per second (selectable with fairly uniform separation), regardless of baud rate. This is fast enough to allow any keystroke to auto repeat at 30 Hz (baud rate permitting). The default is **150**.

This feature allows you to limit the transmit rate from the terminal so as to reduce the interrupt burden on the operating system.

You can select a different transmit rate for graphic keys and function keys using **Fkey rate limit**. The F keys transmit more than 1 byte per key press. This function may be selected through the DECXRLM and DECTRL control function. Refer to Chapter 5, for details.

Figure 2-20 Communication Fkey Rate Limit Menu



# 2.13.11 Ignore Null Character

The Ignore Null setting causes the terminal to discard Null characters immediately without buffering them. This allows NUL to be used as a time fill character to pace terminal output without overflowing the receive character buffer. To pass NUL control codes to a printer, you must deselect the **Ignore Null character** check box.

#### 2.13.12 Local Echo

With **Local echo** enabled, most characters sent from the keyboard to the host are also displayed on the screen. The answerback message and XON/XOFFs are not echoed locally. Everything else is.

This feature corresponds to the SRM control function described in Chapter 5.

Note
<b>Local echo</b> is different from the "Local" setting of <b>On-line</b> in the main menu of the Set-Up directory. <b>Local echo</b> causes keystrokes to be echoed on the screen, but it does not direct keyboard input to the ANSI parser, which also updates the screen. <b>Local echo</b> is temporarily disabled when the terminal is in either Local mode or Local Controller mode, because the keyboard input is already being redirected to the screen through the parser or to the printer.

# 2.13.13 Half Duplex

You can enable or disable **Half duplex** communication. The default is **disabled**. Half duplex communication is available only on the Comm1 communications port. If communication is set for the Comm2 port, this feature is disabled (dimmed).

#### 2.13.14 Auto Answerback


This item is used to enable or disable **Auto answerback** on power-up or upon connection. The factory default is **disabled**.

#### 2.13.15 Answerback Message

Each session can have an answerback message. The **Answerback message . . .** menu item invokes a dialog box with a 30-character limit. All characters that can be generated by the keyboard are legal in this field (including primary and secondary keyboard language characters). As such, no errors are reported, except when trying to enter more than 30 characters. In this case, the bell rings (if enabled), and no more characters are accepted. The factory default message is no message at all (a blank field).

If an Answerback message is currently defined, the message is displayed in the text entry area. The  $\triangleleft$  or  $\square$  or  $\square$  delete key can then be used to delete backwards and enter a new Answerback message.

Figure 2–21 Communication Answerback Dialog Box



Control characters are displayed using the CRM font. Pressing Return enters a return character in the Answerback message. Pressing with the highlighting cursor in the Answerback text field moves to the OK button.

The current Answerback message is displayed in the answerback dialog box unless **Answerback concealed** is selected. In this case, the previous Answerback message is not shown. Choosing the OK button to enter a new Answerback message clears the Answerback concealed check box.


#### 2.13.16 Answerback Concealed

Changes to this field take effect immediately. The factory default is **disabled**.

If disabled, the Answerback message is visible in Set-Up. If enabled, the message is not visible and the text "<concealed>" replaces the message. The only way to return this field to disabled (visible) is to enter a new message.

# 2.14 Modem Menu

Figure 2–22 Modem Menu



#### 2.14.1 Enable Modem Control

The field allows you to select whether the additional hardware control signals at the interface connector are used for modem control. Modem control disabled is also referred to as "Data leads only." Refer to Chapter 9 for details on modem control signals.

This feature corresponds to DECMCM in Chapter 5.

# 2.14.2 Disconnect Delay

When modem control is enabled, the **Disconnect delay** feature determines the time allowed before the terminal disconnects from the communications line when the received line signal detect (RLSD) is lost. Disconnect delay is in effect only when RLSD (CD) is lost. If DSR is lost, the terminal performs a disconnect immediately. The following selections are available:

- 2 seconds
- o 60 ms
- o No disconnect

All countries except the United Kingdom should use a delay of 2 seconds. The 60 ms delay is for use in the United Kingdom.


If the VT520 detects a loss of carrier and you selected No disconnect, the VT520 ignores RLSD (CD) after the beginning of the connection.

If you try to disconnect and reconnect the line, the VT520 checks to "see" if RLSD is asserted before granting the connection. Once it is connected, the terminal ignores the loss of carrier.

You can select disconnect delay through Set-Up or through control function DECDDT. Refer to Chapter 9 for details on the connect and disconnect process.

# 2.14.3 Modem High Speed

Figure 2–23 Modem High Speed Menu



When modem control is enabled, the speed indicator signal (SI) from the modem may be used to select the communication rate. This feature sets the communication rate to be used when the speed indicator line is "on." Selecting Ignore causes the terminal to use its regular transmit and receive speeds as it would when modem control is disabled.


This feature can be invoked by DECSCS.

# 2.14.4 Modem Low Speed

These selections are the same as the modem high speed selections shown in Figure 2–23. When modem control is enabled, the speed indicator (SI) signal from the modem may be used to select the communication rate. This feature sets the communication rate to be used when the speed indicator line is "off." Selecting Ignore causes the terminal to use its regular transmit and receive speed as it would when modem control is disabled. This feature can be invoked by DECSCS.

# 2.15 Printer Menu

Figure 2-24 Printer Menu



Printer features shown in Figure 2–24 correspond to the control functions listed in Table 2–9. These functions are described in Chapter 5 and Chapter 10.

#### 2.15.1 Port Select

The **Port select** menu is the same one that appears in the **Communication** menu (see Figure 2–18). It is displayed in both areas to be easy to find whether you are selecting the printer port or the host port. Having a single feature avoids complex interactions between printer port and host port selections.

#### 2.15.2 Print Mode

The **Print mode** menu allows you to select the printer operating mode as follows:

- Normal
- Autoprint
- Controller

Note	
NOIE	

We recommend that you do not save the Controller mode selection in NVR because this may result in a "hung" terminal if the printer does not have DTR asserted.

Local echo is temporarily disabled when the terminal is in either Local mode or Local Controller mode, because the keyboard input is already being redirected to the screen through the parser or to the printer.

Table 2-9 Printer Features and Control Functions

Set-Up Feature	Factory Default	<b>Host Control Code</b>	
Printer ⊳			
Port select	S1=comm1, S2=comm2, Print=comm3	DECSCP	
Print mode	Normal	MC	
Printer type	DEC ANSI	DECSPRTT DECSDPT	
DEC/ISO char sets	National only	DECSDPT	
PC character sets	PC International (437)	DECSPPCS	
Same as receive			
Print extent	Full page	DECPEX	
Print terminator	None	DECPFF	
Serial print speed	4800 baud	DECSCS	
[] 2-way communication		MC	
Transmit flow control	XON/XOFF	DECSFC	
Receive flow control	XON/XOFF	DECSFC	
Word size	8 bits	DECSPP	
Parity	None	DECSPP	
Stop bits	1 bit	DECSPP	

# 2.15.3 Printer Type

You can select the printer type as follows:

- DEC ANSI
- o IBM ProPrinter
- ∘ DEC + IBM

# 2.15.4 Printer Character Sets

The printer character set menus allow you to match the characters printed to the character sets the printer is capable of supporting.


# 2.15 Printer Menu

#### 2.15.4.1 DEC/ISO Character Sets

You can enable the character set categories shown in Figure 2-25.

Figure 2-25 DEC/ISO Character Sets Menu

#### Set-Up



#### 2.15.4.2 PC Character Sets

The numbers in parentheses in this menu refer to standard PC code pages. Refer to Chapter 10 for a listing of the PC character sets.

**Same as receive—**Use IBM ProPrinter sequences with control codes or without host control codes.

#### 2.15.5 Print Extent

This selection allows you to print a **full page** or just the scroll region.

#### 2.15.6 Print Terminator


The print terminator can be **None** or FF (form feed).

# 2.15.7 Serial Print Speed

Like the **Communication** menu speed selection (see Figure 2–19), you can select the serial printer speed from 300 to 115.2K baud. The default is **4800** baud.

Figure 2-26 PC Character Sets Menu

#### Set-Up



# 2.15.8 2-Way Communication

This item allows you to enable and disable bidirectional communications on the *serial* printer port. The default is 2-way communication **disabled**.

#### 2.15.9 Transmit Flow Control

The printer transmit flow control method can be one of the following:

- None
- XON/XOFF
- o DSR (Data Send Ready)
- o Both

#### 2.15.10 Receive Flow Control

The printer receive flow control method can be one of the following:

- o None
- XON/XOFF
- DTR (Data Terminal Ready)
- $\circ$  Both

#### 2.15.11 Word Size

The printer word size can be **8 bits** (default) or 7 bits.

# Set-Up 2.15 Printer Menu

# 2.15.12 Parity

You can select any of the following parity checks to the printer:

- None
- o Even
- $\circ$  Odd
- o Mark
- Space

# 2.15.13 Stop Bits

For the printer, 1 (default) or 2 stop bits can be enabled.

#### 2.15.14 Same as Receive

This item allows you to set the transmit speed to be the same as the receive speed on the printer port.

# 2.16 Tabs . . .


The **Tabs** ... menu item is used to invoke the Tab Set-Up dialog box, displaying a 132-column tab ruler. Figure 2–27 shows that tab stops are indicated by the letter T.

The highlighting cursor is initially displayed over the entire tab field. The normal character cursor appears in column 1 of the tab field.

The  $\Leftarrow$  and  $\Rightarrow$  keys move the cursor within the tab field. Pressing Tab advances the cursor to the next tab stop in the tab field (if any). The character cursor automatically wraps between the end of the first row and the beginning of the second row in the tab field.

Figure 2-27 Tab Set-Up Dialog Box

### Set-Up



The labeled buttons allow you to clear all tabs or to set 8-column tabs directly. To set individual tabs:

- 1. Position the cursor in the desired column.
- 2. Press Enter to set or clear a tab in that column.

Tab setting can also be invoked by the HTS and DECCTS control functions.

# **2.17 Sound**

The VT520 is capable of producing a range of sound frequencies. Examples:

To communicate	Sound used
Power on	125 ms beep
Attention warning (also ^G)	125 ms beep
Programmable Alarm	Four short beeps in rapid succession, pause 0.5 seconds repeat. Alarm 1 uses C. Alarm 2 uses Eb.
Sticky keys on	Series of three rising notes (short beeps Eb Ab C)
Sticky keys off	Series of three falling notes (C Ab Eb)
Hourly chime	125 ms beep
Keyclick	2 ms beep
Margin bell	125 ms beep

# Set-Up 2.17 Sound

Pnote	Note	~F (Hz)	Pnote	Note	~F (Hz)
1	C5		14	C#6	1047
2	C#5		15	D6	
3	D5		16	D#6	
4	D#5(Eb)	632	17	E6	
5	E5		18	F6	
6	F5		19	F#6	
7	F#5		20	G6	
8	G5		21	G#6	
9	G#5	847	22	A6	
10	A5		23	A#6	
11	A#5	944	24	B6	
12	B5		25	C7	
13	C6				

There is no local sound editor or customize dialog box as the terminal's sound capability is rather simple and does not justify sophisticated editing features. A control function is defined to allow applications to generate custom sounds. The general form is

```
ESC [ Pvolume ; Pduration ; Pnote ; ... FINAL
```

#### Where:

Pvolume specifies the sound volume (0=off, 1-3=low, 4-7=high).

Pduration specifies the note duration in 1/32 of a second.

Pnote;...Pnote specifies one or more notes to sound at the specified volume and duration (0=silent, 1=Eb, 2=Ab, 3=Bb, 4=C).

The final characters of the sequence are , $\sim$  (2/12 7/14).

The terminal's sound buffer can store 16 notes of specified volume and duration. Additional sound controls are held in the communications input buffer invoking receive data flow control as needed.

# 2.18 Set-Up Factory Defaults

Table 2–10 lists the default for the features in the Set-up Menu and their corresponding host control code if available.

Table 2-10 Set-Up Factory Defaults

Set-Up Feature	Factory Default	Host Control Code	
Actions ⊳			
Clear display		ED	
Clear communications			
Reset this session		DECSTR RIS	
Restore factory defaults			
Clock		DECLTOD	
Calculator			
Show character sets			
Banner message		DECLBAN	
Session ⊳			
Select session			
Session name		DECSWT DECSIN	
Pages per session	S1=3,S2=3	DECSPMA	
Save settings for all			
Restore settings for all			
Copy settings from			
Update session	When available	DECUS	
Display ⊳			
Lines per screen	24, 25 or 26	DECSNLS	
[] Auto resize		DECARSM	
Lines per page	24 lines x 3 pages	DECSLPP	
[] Review previous lines		DECRPL	
Columns per page	80 Columns	DECCOLM	
[/] Clear on change		DECNCSM	
Status display	Local status	DECSSDT	
Scrolling mode	Jump	DECSCLM DECSSCLS	
Screen background	Dark	DECSCNM	
Cursor display	Block	DECSCUSR	
[/] Blink			
[/] Enable cursor		DECTCEM	
Cursor coupling			
[/] Vertical coupling		DECVCCM	
[/] Page coupling		DECPCCM	
		(continued on next page)	

# Set-Up 2.18 Set-Up Factory Defaults

Table 2–10 (Cont.) Set-Up Factory Defaults

Set-Up Feature	Factory Default	Host Control Code	
Cursor direction	Left to right	DECRLM	
Copy direction	Left to right	DECRLCM	
Zero	0	DECSZS	
[] Auto wrap		DECAWM	
[] New line mode		LNM	
[ ] Lock user preferences			
[] Show control characters		CRM	
CRT saver	15 minutes	DECCRTSM	
[/] Host wake-up		DECHWUM	
Energy saver	15 minutes	DECEST	
[] Overscan		DECOSCNM (mono model only)	
[] Framed windows			
Screen alignment		DECALN	
Color ⊳			
Assign colors		DECAC DECCTR	
Alternate text colors		DECATC	
Define colors		DECRSTS	
Select color map	ANSI SGR color	DECSTGLT SGR	
ASCII color mode	Color		
Blink and Bold style	Foreground	DECBBSM	
Erase color	Text background	DECECM	
Reverse and Blank attributes			
[/] Intensity attributes			
Terminal type ⊳			
Emulation mode	VT520	DECTME	
Terminal ID to host	VT520	DECTID	
VT default char set	ISO Latin-1	SCS	
PCTerm character set	PC International (437)	DECPCTERM	
[] 7-bit NRCS characters		DECNRCM	
[/] Transmit 7-bit controls		S7C1T	
ASCII emulation >			
Data lines	24 Lines		
Pages	1 x Lines		
Attribute	Char		
Write protect attributes			
[] Blank			
[] Underline			
		(continued on next p	

Table 2–10 (Cont.) Set-Up Factory Defaults

Set-Up Feature	Factory Default	Host Control Code
[] Reverse		
[] Blink		
[/] Dim		
[] Page edit		
Received CR		
[] Recognize DEL		
[/] Enhance		
[/] Autoscroll		
[] Autopage		
[/] Send ACK		
[] Answerback mode		
[/] TVI page-flip		
[] Font load		
Block mode	Conversation	
Block end	US/CR	
Keyboard ⊳		
VT Keyboard language	North American	DECKBD
PC Keyboard language	North American	DECKBD
Define key		DECPFK DECPAK DECUDK DECNUMLK DECCAPSLK DECKLHIN DECLL
Save key definitions		
Recall key definitions		
[] Lock key definitions		DECPKA
Caps lock function	Caps Lock	DECSLCK
Keyclick volume	High	DECSKCV
Warning bell volume	High	DECSWBV
Suppress repeated warnings		
Margin bell volume	Off	DECSMBV
Keyboard encoding	Character (ASCII)	DECPCTERM
Auto repeat	Fast (30/sec)	DECARM
[] Data processing keys		DECBUM
[] Application cursor keys		DECCKM
[] Application keypad mode		DECPAM DECKPNM
[] Map PC keyboard to VT		
[] Ignore missing keyboard		

(continued on next page)

# Set-Up 2.18 Set-Up Factory Defaults

Table 2–10 (Cont.) Set-Up Factory Defaults

et-Up Feature	Factory Default	<b>Host Control Code</b>	
Communication >			
Port select	S1=comm1, S2=comm2, Print=comm3	DECSCP	
Word size	8 bits	DECSPP	
Parity	None	DECSPP	
Stop bits	1 bit	DECSPP	
Transmit speed	9600	DECSCS	
Receive speed	Transmit speed	DECSCS	
Transmit flow control	XON/XOFF	DECSFC	
Receive flow control	XON/XOFF or XPC	DECSFC	
Flow control threshold	Low (64)		
Transmit rate limit	150 cps	DECXRLM DECSTRL	
Fkey rate limit	150 cps	DECSTRL	
[/] Ignore Null character		DECNULM	
[] Local echo		SRM	
[] Half duplex		DECCHDPXM	
[] Auto answerback			
Answerback message		DECLANS	
[] Answerback concealed		DECCANSM	
<b>Iodem</b> ⊳			
[] Enable modem control		DECMCM	
Disconnect delay	2 seconds	DECSDDT	
Modem high speed	Ignore		
Modem low speed	Ignore		
rinter ⊳			
Port select	S1=comm1, S2=comm2, Print=comm3	DECSCP	
Print mode	Normal	MC	
Printer type	DEC ANSI	DECSPRTT DECSDPT	
DEC/ISO char sets	National only	DECSDPT	
PC character sets  Same as receive	PC International (437)	DECSPPCS	
Print extent	Full page	DECPEX	
Print terminator	None	DECPFF	
Serial print speed	4800 baud	DECSCS	
		(continued on next p	

# Set-Up 2.18 Set-Up Factory Defaults

Table 2-10 (Cont.) Set-Up Factory Defaults

Set-Up Feature	Factory Default	<b>Host Control Code</b>
[] 2-way communication		MC
Transmit flow control	XON/XOFF	DECSFC
Receive flow control	XON/XOFF	DECSFC
Word size	8 bits	DECSPP
Parity	None	DECSPP
Stop bits	1 bit	DECSPP
<b>Tabs</b> ⊳		DECST8C HTS
Set-Up language ⊳	English	DECSSL
Save settings ⊳		
<b>Restore settings</b> ⊳		
Exit set-Up >		

# **Desktop Features**

# 3.1 Introduction

To enhance productivity, the VT520 provides local desktop features that can be used at any time the terminal is powered up, even when the terminal is not connected to a host. These features are:

- Calculator
- Clock
- Show character sets
- Banner message
- Copy and paste

This chapter describes these desktop features and their interaction with the terminal.


# 3.2 Invoking Desktop Features

#### Overview

The local functions can be accessed through Set-Up or through a user-programmable key combination. Chapter 2, Set-Up, describes how to invoke these desktop features and how to assign a key combination to a specific feature. When one is invoked, the screen is partially obscured by that feature. Pressing  $\boxed{\text{Ctr}/Z}$ ,  $\boxed{\text{F10}}$  ( $\boxed{\text{Exit}}$ ), or  $\boxed{\text{ESC}}$  exits the current desktop feature and reveals the entire screen contents.

From the **Actions** menu, you can invoke **Clock, Calculator, Show character sets** and the **Banner message**. When the feature is highlighted (displayed in reverse video), press Enter or Return to enable the feature. A quick start summary of some keyboard features is provided, as well as how to implement the **Copy and Paste** function. You can copy and paste within a session and between sessions.

# **Desktop Features** 3.2 Invoking Desktop Features



While these desktop features are enabled, other terminal functions are disabled. Press CtrlZ, F10, Exit, or Esc to exit the feature.


# 3.3 Calculator

You can enable the **Calculator** function in Set-Up by pressing Caps Lock Alt/F12 if you are not in an ASCII emulation mode.

When you select the Calculator function, the terminal displays a simple calculator. See the leftmost layout in Figures 3-1 and 3-2. The keypad keys map directly to the calculator keys. The layout depends on whether a VT or Enhanced PC keyboard is attached, and whether a modifier key (Shift or Alt) is currently held down.

When a keypad key is pressed, the corresponding key is highlighted (shown in reverse video) on the screen. If a modifier key is pressed down, the display changes to show the new keypad assignment. See the two rightmost layouts in Figures 3–1 and 3–2. All keys not associated with the calculator are ignored.

Figure 3-1 Calculator with VT Keyboard Layout



In addition to the numbers on the numeric keypad, you can use the following keys with the calculator:


Key	Function
H, O, or D	Select hexadecimal, octal, or decimal modes, respectively. The radix is indicated by a radio button. The first letter of each choice is underlined to remind the user of how to select it.
Arrow keys	Move the position of the calculator on the screen.
Shift	Changes the keypad display to allow you to select STO, RCL, $1/x$ , $X^2$ , and Insert Result (Shift/Enter).
Alt	Changes the keypad display to hexadecimal and allows you to select keys A through F on the numeric keypad.
C/E	Clears the entry.
STO	Stores the number from the display in memory.
RCL	Recalls the number from memory and places it in the display.
Shift/Enter (Insert Results)	Inserts the result at the current cursor position after exiting the calculator feature.

Some keys on the main keypad can also be used for calculator functions:

# **Desktop Features** 3.3 Calculator

Main Keypad Key	Calculator Function	
+	, (VT keyboard); + (PC keyboard)	
-	-	
*	X	
/	÷	
=	same as Enter	
<b>&lt;</b> X	C/E	

Figure 3-2 Calculator with PC Keyboard Layout



While the calculator is on the screen, all other terminal operations are suspended. The first time the calculator is invoked after the terminal is powered on, the display and memory registers contain 0. The display is eleven characters wide: eight characters are used to display the number's digits, one is used for the decimal point, one for the leading sign bit, and the one in the rightmost position is left blank.

The calculator allows the user to add, subtract, multiply, and divide real numbers in the range [-99,999,999. through +99,999,999.]. While one of these operations is in progress, the calculator displays the corresponding symbol [+ -  $\times$   $\div$ ] to the right of the display. (See the  $\times$  in the figures.) You can also compute the reciprocal or the square of a number by pressing the 1/X or  $X^2$  keys, respectively.

All calculator math operations have equal priority except 1/X and  $X^2$ . If a result is wider than the display, then a rounded number will be displayed. The unrounded result will continue to be used in subsequent calculations.

The calculator has a memory register in which an intermediate result can be stored. When you press  $\boxed{\text{STO}}$ , you replace the content of this register with the number in the display. When you press  $\boxed{\text{RCL}}$ , you place the number from memory in the display. If any value is stored in memory, the calculator displays the letter M to the left of the display.

The number in the display (usually the last result) can be inserted at the current cursor position by pressing Shift/Enter (Insert Result), which exits the calculator and transmits the data to the host.

The calculator can also be used with hexadecimal and octal numbers in addition to the default (decimal). The H, O, or D keys put the calculator in hexadecimal, octal, or decimal modes, respectively. The current mode is in plain text and the other two modes are displayed with the dim attribute. In hexadecimal mode, the numbers A through F are entered by holding down and typing the corresponding keypad key. See Figures 3–1 and 3–2. The decimal point cannot be used in the hexadecimal or octal modes, and any fractional part is truncated in these two modes.

# 3.4 Clock

You can enable the **Clock** feature without entering Set-Up by pressing Caps Lock Alt F11 if you are either in a VT or an SCO console emulation mode.

The current time is displayed in the status line, if this feature is enabled. If the 12-hour format is selected, an A or P is displayed after the minutes.

The **Clock** function allows the current time to be set, the hourly chime to be enabled or disabled, and the alarms to be set and armed or disarmed. The current time can also be set from the host through an escape sequence. When the clock function is selected, the window shown in Figure 3–3 is displayed on the screen.

# **Desktop Features** 3.4 Clock

Figure 3-3 Clock Function

Time	12:34P	☐ 24 hour format
⊠ Alarm1	12:00	Message 1
☐ Alarm2	12:00	Message 2
☐ Hourly d	hime	
☐ Request	time at power-up	

MA-0325-93.GRA

The following keys have these functions:

Key(s)	Function
⇒ and Tab	Move the cursor to the next text field or check box.
↑ and Shift/Tab	Move the cursor to the previous text field or check box.
⇐ and ⇒	Move the cursor inside a text field.
Return and Enter	Toggle the state of the check box.
← and ⇒	Move the cursor inside the current input field. To change the contents of a field, type in the new information.
A or P	If the 24-hour time format is selected, these keys are ignored. If the 12-hour time format is selected, sets the time to either AM or PM.
Caps Lock Enter	Input the clock time at the cursor position and exit the clock.

You do not need to type the colon (:) character in the time field; the cursor skips over that character position. The check boxes next to the alarms are used to enable or disable the alarms. When an alarm time comes due and the alarm is enabled, the terminal sounds the alarm for 5 seconds or until you type any key.

The terminal also flashes "Alarm1" or "Alarm2" in the error line and the corresponding message associated with the alarm. The maximum size of the alarm messages is 20 characters. When the alarm is cleared (either by typing a key or after the 5 second timeout), the error line also disappears, revealing the status line if it was enabled.

If the hourly chime check box is enabled, the terminal emits a double beep every hour on the hour.

The state of the alarms, the alarm times, and the alarm messages are saved in NVM if the user chooses Save settings from Set-Up. The clock feature is disabled when the terminal is turned off.

# 3.5 Review Previous Lines

In Set-Up or through software, you can allocate the pages that are assigned to each session, up to a total of eight pages or nine pages on the color model. When **Review previous lines** is selected, the page memory allocation for a session becomes a *single page* and a *scroll back buffer*. You can then use the location for a session keys to scroll up or down to review lines previously scrolled off the screen. (Note: When this feature is enabled, the host cannot write to specific pages, and control codes from the host are ignored.)

# 3.6 Character Set Tables

#### 3.6.1 Show Character Sets feature

When you select **Show character sets**, the current character set is shown on the screen. Nonprinting characters are shown in control representation mode wherever possible.

If you are in either a VT or an SCO console emulation mode, you can enable the **Show character sets** desktop feature without entering Set-Up by using <a href="Caps Lock Alt|F10">Caps Lock Alt|F10</a>. When the character set is displayed, you can use the following keys with this feature:

Key	Function
Next or Prev Page Up or Page Down	Looks through the available character sets.
Shift A	Restores the ASCII character set (when the Line Drawing set is displayed.)
Shift L	Displays the line drawing character set, if you are using a VT character set.
Shift T	Displays the technical character set.
Shift Enter	For the current character set, inserts the highlighted character into text at the current cursor position, if you are using a VT character set.

ASCII terminal emulations support the character sets listed in Table 3–1. They do not support any 8-bit or ISO standard character sets.

Table 3-1 ASCII Emulation Character Sets

Emulation Mode	Character Set
WYSE 325	Native/WY-50+
WYSE 160/60 Native	Native/WY-50+
WYSE PCTerm	PC Multilingual (Code Page 850)
WYSE 50+, 150/120	Native/WY-50+
TVI 950, 925, 910+	Native/WY-50+
ADDS A2	Native/WY-50+

# **Desktop Features** 3.6 Character Set Tables

# 3.6.2 Banner message

The Banner message is the message that is displayed when you turn the terminal on. You can change this message as desired. From the Actions menu, select Banner message....

- 1. Press Return or Enter to display a dialog box.
- 2. Enter your banner message.
- 3. Press the ↓ to select the OK button.
- 4. Press Return or Enter to return to the Set-Up menu.

# 3.7 Keyboard Summary

The following table provides a quick start summary of some keyboard features.

То	VT Keyboard, press	PC Keyboard, press
Hold the screen	F1	Scroll Lock
Print the screen	F2	Print Screen
Enter/Exit Set-Up	F3	Caps Lock   Print Screen
Switch session	F4 or Caps Lock KP0	Caps Lock KP0
Select specific session	Caps Lock KP1, 2, 3, or 4	Caps Lock KP1, 2, 3, or 4
Break	F5	Caps Lock Pause
Toggle split screen	Ctrl F4	Ctrl Caps Lock 0 kpd
Adjust window size	Ctrl Shift ↑ or ↓	Ctrl Shift  or  ₩
Pan previous lines	Ctrl↑↑ or ₩	Ctrl∱ or ₩
Review previous lines	Ctrl↑↑ or ₩	Ctrl∱ or ₩
Copy and paste:		
Start copy	Hold down F1†	Hold down Scroll Lock
Move to beginning of text	<b>⇐</b> , <b>⇒</b> , <b>↑</b> , or <b>↓</b>	<b>⇐</b> , <b>⇒</b> , <b>↑</b> , or <b>↓</b>
Select beginning of text	Select ‡	Home ‡
Select end of text	Remove	End
Finish copy	Release F1	Release Scroll Lock
Move to different session if desired.		
Paste	F1 Insert Here	Scroll Lock Insert

†For SCO console, press Caps Lock F1.

‡If you press the Select key (or Home key) twice, the keyboard will toggle the copy direction between left-to-right and right-to-left directions for use with right-to-left scripts.

Note \_

The copy and paste buffer is limited to 6K bytes, which is about 24 lines × 132 columns of data. You also cannot copy and paste from the scroll back buffer.

# **Part II**

# VT520 ANSI Mode

# This part includes the following chapters:

- Chapter 4, ANSI Control Functions Summary
- Chapter 5, ANSI Control Functions
- Chapter 6, SCO Console Emulation
- Chapter 7, Character Sets
- Chapter 8, Keyboard Processing
- Chapter 9, Communications
- Chapter 10, Printer Port

### **ANSI Control Functions Summary**

#### 4.1 Introduction

This chapter provides a general description of ANSI control functions. This chapter provides information on working with 7- and 8-bit environments and the conventions used in each, and it describes the **Show control characters** Set-Up feature. In addition, this chapter provides summary tables of the ANSI control functions.

For	See page
Control characters	4-1
Control functions	4-5
Working with 7-Bit and 8-Bit environments	4-10
Showing control characters	4-11
ASCII code tables	4-14,15
ANSI control function tables	4-16
VT52 mode escape sequences	4-45

#### 4.2 Control Characters

The purpose of a control character is to control an action such as line spacing, paging, or data flow. The terminal does not display control characters unless you select **Show control characters** from the **Display** Set-Up menu. There are two groups of control characters.

- C07-bit control characters, in columns 0 and 1 of the 8-bit code table
- 8-bit control characters, in columns 8 and 9 C1 of the 8-bit code table

Table 4–1 lists the C0 control characters the VT520 recognizes. Table 4–2 lists the C1 control characters the VT520 recognizes. You can also code C1 control characters as 7-bit escape sequences. Table 4-3 lists the equivalent 7-bit sequences for 8-bit control characters. All three tables give column/row locations as an unambiguous character representation.

# ANSI Control Functions Summary 4.2 Control Characters

Table 4-1 C0 (7-Bit) Control Characters Recognized

Name	Mnemonic Column/Row	Function
Null	<b>NUL</b> 0/0	NUL has no function (ignored by the terminal). May be used as a fill character.
Enquire	<b>ENQ</b> 0/5	Sends the answerback message. (Communications Set-Up)
Bell	<b>BEL</b> 0/7	Sounds the bell tone if the bell is enabled in Keyboard Set-Up.
BS	<b>BS</b> 0/8	Moves the cursor one character position to the left. If the cursor is at the left margin, no action occurs.
Horizontal tab	<b>HT</b> 0/9	Moves the cursor to the next tab stop. If there are no more tab stops, the cursor moves to the right margin. HT does not cause text to auto wrap.
Line feed	<b>LF</b> 0/10	Causes a line feed or a new line operation, depending on the setting of line feed/new line mode.
Vertical tab	<b>VT</b> 0/11	Treated as LF.
Form feed	<b>FF</b> 0/12	Treated as LF.
Carriage return	<b>CR</b> 0/13	Moves the cursor to the left margin on the current line.
Shift out (locking shift 1)	<b>SO</b> (LS1) 0/14	Maps the G1 character set into GL. You designate G1 by using a select character se (SCS) sequence.
Shift in (locking shift 0)	<b>SI</b> (LS0) 0/15	Maps the G0 character set into GL. You designate G0 by using a select character se (SCS) sequence.
Device control 1 (XON)	<b>DC1</b> 1/1	Also known as XON. If XON/XOFF flow control is enabled in Communications Set-Up, DC1 clears DC3 (XOFF). This action causes the VT520 to continue sending characters.
Device control 3 (XOFF)	<b>DC3</b> 1/3	Also known as XOFF. If XON/XOFF flow control is enabled in Communications Set-Up, DC3 causes the VT520 to stop sending characters. The terminal cannot resume sending characters until it receives a DC1 control character.
Cancel	<b>CAN</b> 1/8	Immediately cancels an escape sequence, control sequence, or device control string in progress. In this case, the VT520 does not display any error character.
Substitute	<b>SUB</b> 1/10	Immediately cancels an escape sequence, control sequence, or device control string in progress, and displays a reverse question mark as an error character.

Table 4-1 (Cont.) C0 (7-Bit) Control Characters Recognized

Name	Mnemonic Column/Row	Function
Escape	<b>ESC</b> 1/11	Introduces an escape sequence. ESC also cancels any escape sequence, control sequence, or device control string in progress.
Delete	<b>DEL</b> 7/15	Ignored when received, unless a 96-character set is mapped into GL. DEL is not used as a fill character. Digital does not recommend using DEL as a fill character. Use NUL instead.

Table 4-2 C1 (8-Bit) Control Characters Recognized

Name	Mnemonic Column/Row	Function
Index	IND 8/4	Moves the cursor down one line in the same column. If the cursor is at the bottom margin, the page scrolls up.
Next line	<b>NEL</b> 8/5	Moves the cursor to the first position on the next line. If the cursor is at the bottom margin, the page scrolls up.
Horizontal tab set	HTS 8/8	Sets a horizontal tab stop at the column where the cursor is.
Reverse index	<b>RI</b> 8/13	Moves the cursor up one line in the same column. If the cursor is at the top margin, the page scrolls down.
Single shift 2	<b>SS2</b> 8/14	Temporarily maps the G2 character set into GL, for the next graphic character. You designate the G2 set by using a select character set (SCS) sequence.
Single shift 3	<b>SS3</b> 8/15	Temporarily maps the G3 character set into GL, for the next graphic character. You designate the G3 set by using a select character set (SCS) sequence.
Device control string	<b>DCS</b> 9/0	Introduces a DCS control string. DCS control strings are used for loading function keys or a soft character set.
Start of string	<b>SOS</b> 9/8	Ignored.
DEC private identification	<b>DECID</b> 9/10	Makes the terminal send its device attributes response to the host (same as an ANSI device attributes (DA) sequence). Programs should use the ANSI DA sequence instead. If the printer is in controller mode, the terminal sends the sequence to the printer.
Control sequence introducer	<b>CSI</b> 9/11	CSI introduces a control sequence.

(continued on next page)

### **ANSI Control Functions Summary 4.2 Control Characters**

Table 4–2 (Cont.) C1 (8-Bit) Control Characters Recognized

Name	Mnemonic Column/Row	Function
String terminator	<b>ST</b> 9/12	Ends a control string. ST is normally used in combination with DCS, OSC, PM, or APC.
Operating system command	<b>OSC</b> 9/13	OSC introduces an OSC control string.
Privacy message	<b>PM</b> 9/14	PM introduces a PM control string. The VT520 ignores all PM control strings.
Application program command	<b>APC</b> 9/15	APC introduces an application program command. The VT520 ignores all APC control strings.

Table 4–3 8-Bit Control Characters and Their 7-Bit Equivalents

Name	8-Bit Character	7-Bit Sequer	nce
Index	IND 8/4	<b>ESC</b> 1/11	<b>D</b> 4/4
Next line	<b>NEL</b> 8/5	<b>ESC</b> 1/11	<b>E</b> 4/5
Horizontal tab set	HTS 8/8	<b>ESC</b> 1/11	H 4/8
Reverse index	<b>RI</b> 8/13	<b>ESC</b> 1/11	<b>M</b> 4/13
Single shift 2	<b>SS2</b> 8/14	<b>ESC</b> 1/11	<b>N</b> 4/14
Single shift 3	<b>SS3</b> 8/15	<b>ESC</b> 1/11	<b>O</b> 4/15
Device control string	<b>DCS</b> 9/0	<b>ESC</b> 1/11	<b>P</b> 5/0
Start of string	<b>SOS</b> 9/8	<b>ESC</b> 1/11	<b>X</b> 5/8
DEC private identification	<b>DECID</b> 9/10	<b>ESC</b> 1/11	<b>Z</b> 5/10
Control sequence introducer	<b>CSI</b> 9/11	<b>ESC</b> 1/11	[ 5/11
String terminator	<b>ST</b> 9/12	<b>ESC</b> 1/11	\ 5/12
Operating system command	<b>OSC</b> 9/13	<b>ESC</b> 1/11	] 5/13
Privacy message	<b>PM</b> 9/14	<b>ESC</b> 1/11	^ 5/14
Application program	<b>APC</b> 9/15	<b>ESC</b> 1/11	- 5/15

#### 4.3 Control Functions

You use control functions to make the terminal perform special actions in your applications. Examples:

Move the cursor.

Delete a line of text.

Select bold or underlined text.

Change character sets.

Make the terminal emulate a VT52 or VT100 terminal.

There are single-character and multiple-character control functions.

The single-character functions are the C0 and C1 control characters. You can use C0 characters in a 7-bit or 8-bit environment. C1 characters provide a few more functions than C0 characters, but you can only use C1 characters directly in an 8-bit environment.

Multiple-character control functions provide many more functions than the C0 and C1 characters. Multiple-character functions can use control characters and graphic characters. There are three basic types of multiple-character control functions.

Escape sequences

Control sequences

**Control strings** 

The structure of control functions are defined by ANSI and ISO standards. Many individual sequences are defined by these same standards and are used throughout the industry. Others are private sequences, created by manufacturers in accordance with ANSI and ISO standards for use in their own products.

In this manual, control functions created by Digital have the prefix DEC in their mnemonic name. For example, column mode has the mnemonic DECCOLM. All other control functions used in the ANSI VT emulations are standardized by ISO.

The following sections describe the format for escape sequences, control sequences, and device control strings.

#### **Programming Tip**

When you use control functions, remember that the binary codes define a function—not the graphic characters. This manual uses graphic characters from the DEC Multinational character set to show control functions. If you use another character set, the graphic characters for control functions may change, but the code is always the same.

### 4.3.1 Sequence Format

This manual shows escape and control sequences in their 8-bit format. You can also use equivalent 7-bit sequences (Table 4-3).

The 8-bit format uses the C0 and C1 control characters and ASCII characters from the DEC Multinational character set. The sequences also show each character's column/row position in the character set table, below the character. The column/row code eliminates confusion over similar-looking characters such as 0 (3/0) and O (4/15).

#### ANSI Control Functions Summary 4.3 Control Functions

Note	
Spaces appear between characters in a sequence for clarity. The are not part of the sequence. If a space is part of the sequence (2/0) character appears.	

#### 4.3.2 Escape Sequences

An escape sequence uses two or more bytes to define a specific control function. Escape sequences do not include variable parameters, but may include intermediate characters. Here is the format for an escape sequence.

<b>ESC</b> 1/11	I 2/0 to 2/15	<b>F</b> 3/0 to 7/14
Escape character	Intermediate characters (zero or more characters)	Final character (one character)

**ESC** introduces escape sequences. After receiving the ESC control character, the terminal interprets the next received characters as part of the sequence.

I represents zero or more intermediate characters that can follow the ESC character. Intermediate characters come from the 2/0 through 2/15 range of the code table.

**F** is the *final character*. This character indicates the end of the sequence. The final character comes from the 3/0 through 7/14 range of the code table. The intermediate and final characters together define a single control function.

For example, the following escape sequence changes the current line of text to double-width, single-height characters:

<b>ESC</b>	#	6	
1/11	2/3	3/6	

#### 4.3.3 Control Sequences

A control sequence uses two or more bytes to define a specific control function. Control sequences usually include variable parameters. Here is the format for a control sequence.

CSI	PP	II	F
9/11	3/0 to 3/15	2/0 to 2/15	4/0 to 7/14
Control sequence	Parameter (zero or more	Intermediate (zero or more	Final (one character)
introducer	characters)	characters)	


#### 4.3.3.1 Control Sequence Introducer

**CSI** is the *control sequence introducer*. You can also use the equivalent 7-bit sequence, ESC (1/11) [ (5/11), as a substitute for CSI. After receiving CSI, the terminal interprets the next received characters as part of the sequence.

#### 4.3.3.2 Parameters

P...P are parameter characters received after CSI. These characters are in the 3/0 to 3/15 range in the code table. Parameter characters modify the action or interpretation of the sequence. You can use up to 16 parameters per sequence. You must use the ; (3/11) character to separate parameters.

All parameters are unsigned, positive decimal integers, with the most significant digit sent first. Any parameter greater than 9999 (decimal) is set to 9999 (decimal). If you do not specify a value, a 0 value is assumed. An omitted parameter indicates a default value for the sequence. For most sequences, the default value is 1.



If the first character in a parameter string is the ? (3/15) character, it indicates that DEC private parameters follow. The terminal interprets private parameters according to ANSI X3.64 and ISO 6429.

The VT520 processes two types to parameters, numeric and selective.

#### **Numeric Parameters**

A numeric parameter indicates a number value such as a margin location. In this manual, numeric parameters appear as actual values or as Pn, Pn1, Pn2, and so on. The following is an example of a control sequence with numeric parameters:

<b>CSI</b> 9/11	<b>5</b> 3/5	; 3/11	<b>2 0</b> 3/2 3/0	r 7/2
Control sequence introducer	First numeric parameter	Delimiter	Second numeric parameter	Final character

This sequence sets the top and bottom margins of the current page. The top margin is at line 5, the bottom is at line 20. The ; (3/11) separates the two parameters.

#### **Selective Parameters**

A selective parameter selects an action associated with the specific parameter. In this manual, selective parameters usually appear as Ps, Ps1, Ps2, and so on. The following is an example of a control sequence using selective parameters:

<b>CSI</b> 9/11	<b>1</b>	;	<b>4</b>	<b>m</b>
	3/1	3/11	3/4	6/13
Control sequence introducer	First selective parameter	Delimiter	Second selective parameter	Final character

This control sequence turns on the bold and underline attribute at the cursor position. The parameters are 1 (indicating the bold attribute) and 4 (indicating the underline attribute). The ; (3/11) delimiter separates the two parameters.

### **ANSI Control Functions Summary** 4.3 Control Functions

#### 4.3.3.3 Intermediate Characters

I...I are zero or more intermediate characters received after CSI. These characters are in the 2/0 to 2/15 range.

#### 4.3.3.4 Final Character

**F** is the *final character* from the 4/0 to 7/14 range. The final character indicates the end of the sequence. The intermediate and final characters together define a control function. If there are no intermediate characters, the final character defines the function.

#### 4.3.4 Device Control Strings

Device control strings (DCS), like control sequences, use two or more bytes to define specific control functions. However, a DCS also includes a data string. Here is the format for a device control string.

DCS	PP	II	$\mathbf{F}$	Data string	ST
9/0	3/0	2/0	4/0	*******	9/12
	to 3/15	to 2/15	to 3/15		
Device control string introducer	Zero or more para- meters	Zero or more inter- mediates	Final	String	String terminator

**DCS** is the device control string introducer. DCS is the C1 control character at position 9/0. You can also use the equivalent 7-bit sequence, ESC (1/11) P (5/0). After receiving DCS, the terminal processes the next received characters as part of the string function.

**P...P** are *parameter characters* received after DCS. The use of parameter characters in a device control string is a Digital extension to the ANSI syntax. According to ANSI standards, any elements included after DCS are part of the data string.

Parameter characters are in the 3/0 to 3/15 range. They modify the action or interpretation of the device control string. You can use up to 16 parameters per string. Each parameter is separated with a ; (3/11) character. These characters follow the same rules as in a control sequence. See the "Section 4.3.3" section in this chapter.

I...I are zero or more intermediate characters received after CSI. These characters are in the 2/0 to 2/15 range.

**F** is the final character in the 4/0 to 7/14 range. The final character indicates the end of the string. The intermediate and final characters define the string. If there are no intermediates, the final character defines the string.

Data string follows the final character and usually includes several definition strings. Each definition string can be several characters in length. Individual strings are separated by the ; (3/11) delimiter.

ST is the string terminator. ST (9/12) indicates the end of a string. You can also use the equivalent 7-bit sequence, ESC  $(1/11) \setminus (5/12)$ .

The following is an example of a device control string:

<b>DCS</b> 9/0	<b>0</b>	!	<b>u</b>	%	<b>5</b>	<b>ST</b>
	3/0	2/1	7/5	2/5	3/5	9/12
Device control string introducer	Para- meter	Inter- mediate	Final	Data string		String terminator

This device control string assigns the DEC Supplemental Graphic set as the user-preferred supplemental set.

#### 4.3.5 Using Control Characters in Sequences

You can use control characters—ESC, CAN, and SUB—to interrupt or recover from errors in escape sequences, control sequences, and device control strings.

- You can send ESC (1/11) to cancel a sequence in progress and begin a new sequence.
- You can send CAN (1/8) to indicate the present data is in error or to cancel a sequence in progress. The VT520 interprets the characters following CAN as usual.
- You can send SUB (1/10) to cancel a sequence in progress. The VT520 interprets the characters following SUB as usual.

The VT520 does not lose data when errors occur in escape or control sequences and device control strings. The terminal ignores unrecognized sequences and strings, unless they end a current escape sequence.

### 4.3.6 7-Bit Code Extension Technique

ANSI and ISO standards define a means whereby all 8-bit data interchange can also be transmitted using 7-bits. ANSI calls this technique "7-bit code extension." To achieve this code extension, the 8-bit C1 control characters each have a corresponding 7-bit representation. 8-bit graphic characters from the right half of the 8-bit code table (GR) can be transmitted in 7-bits by encapsulating them with the SO and SI control functions. Here are some examples.

8-Bit C1 Character	7-Bit Code Extension Escape Sequence			
<b>CSI</b> 9/11	<b>ESC</b> 1/11	[ 5/11		
<b>SS3</b> 8/15	<b>ESC</b> 1/11	<b>O</b> 4/15		
IND 8/4	<b>ESC</b> 1/11	<b>D</b> 4/4		
<b>DCS</b> 9/0	<b>ESC</b> 1/11	<b>P</b> 5/0		

In general, you can use the 7-bit code extension technique in two ways.

- You can represent any C1 control character as a 2-character escape sequence. The second character of the sequence has a code that is  $40_{16}$  or  $64_{10}$  less than the code of the C1 character.
- You can make any escape sequence whose second character is in the range of 4/0 through 5/15 one byte shorter by removing the ESC character and adding 40<sub>16</sub> to the code of the second character. This generates an 8-bit control character. For example, you can change ESC [ to CSI with this method.

### ANSI Control Functions Summary 4.4 Working with 7-Bit and 8-Bit Environments

### 4.4 Working with 7-Bit and 8-Bit Environments

There are three requirements for using one of the terminal's 8-bit character sets.

- · Your program and communication environment must be 8-bit compatible.
- The terminal cannot be in national replacement character set mode (DECNRCM).
- The terminal must operate in VT level 4 (or higher) or PC TERM mode. When the terminal operates in VT level 1 mode or VT52 mode, you are limited to working in a 7-bit environment.)

The following sections describe conventions that apply in VT level 4 or higher.

#### 4.4.1 Conventions for Codes Received by the Terminal

The terminal expects to receive character codes in a form compatible with 8-bit coding. Your application can use the C0 and C1 control characters, as well as the 7-bit C1 code extensions, if necessary. The terminal always interprets these codes correctly.

When your program sends GL or GR codes, the terminal interprets the character codes according to the graphic character sets in use. When you turn on or reset the terminal, you automatically select the ASCII character set in GL and the current user-preferred character set in GR. You select the user-preferred set in the **Terminal type, VT default character set** Set-Up menu. This mapping assumes the current terminal mode is VT level 4.

### 4.4.2 Conventions for Codes Sent by the Terminal

The terminal can send data to an application in two ways.

- Directly from the keyboard
- In response to commands from the host (application or operating system)

Most function keys on the keyboard send multiple-character control functions. Many of these functions start with CSI (9/11) or SS3 (8/15), which are C1 characters. If your application cannot handle 8-bit characters, you can make the terminal automatically convert all C1 characters to their equivalent 7-bit code extensions before sending them to the application. To convert C1 characters, you use the DECSCL commands.)

By default, the terminal is set to automatically convert all C1 characters sent to the application to 7-bit code extensions. However, to ensure the correct mode of operation, always use the appropriate DECSCL commands.

Note
In VT level 4, the terminal can send GR graphic characters to an application, even if the application cannot handle 8-bit codes. However, in a 7-bit environment, the terminal sends C1 controls as 7-bit escape sequences and does not send 8-bit graphic characters.
New programs should accept both 7-bit and 8-bit forms of the C1 control characters.

### 4.5 Showing Control Characters

The VT520 lets you display control characters as graphic characters, when you want to debug your applications. With this mode enabled, the terminal does not perform all control functions.

To enable this mode, use the **Display** Set-Up menu and enable the check box for Show control characters; or you can use the control representation mode (CRM) control sequence. (You cannot select this mode with an escape sequence.)

#### VT level 5 mode

The terminal uses new control sequences developed for the VT500 series terminals. This level includes all other levels.

#### VT level 4 mode

The terminal uses new control sequences developed for the VT400 series terminals. This level includes all lower levels. The terminal temporarily loads a special graphic character set into C0, GL, C1, and GR. Figures 4-1 and 4-2 shows this special set, called the display controls font. The terminal uses this font to display control characters on the screen.

#### VT level 1 or VT52 mode

The terminal uses new control codes and escape sequences developed for the VT100 series terminals, include those developed for the VT52 terminal. The terminal temporarily loads the left half of the display controls font into C0 and GL. The terminal uses this half of the font to display all C0 and GL characters. (C1 and GR are meaningless in VT52 or VT100 emulations.)

#### Displaying 36 or more lines on the screen

When you display 36 or more lines on the screen (DECSNLS), the terminal uses a smaller font to display control characters. The smaller font represents each control character as a two-character symbol instead of a three-character symbol. Figures 4–1 and 4–2 show what the control characters look like when displaying 24 or 25 lines on the screen. Table 4-4 shows the abbreviation for the control characters in the smaller font.

Table 4–4 Control Character Displayed on Screen

Control Character in Large Font	Control Character in Small Font	Name
NUL	NL	Null
SOH	SH	Start of heading
STX	SX	Start of text
ETX	EX	End of text
EOT	ET	End of transmission
ENQ	EN	Enquire
ACK	AK	Acknowledge
BEL	BL	Bell
BS	BS	Backspace
HT	HT	Horizontal tab
LF	LF	Line feed
<del></del>	<del>==</del>	
VT	VT	Vertical tab

(continued on next page)

# ANSI Control Functions Summary 4.5 Showing Control Characters

Table 4-4 (Cont.) Control Character Displayed on Screen

Control Character in Large Font	Control Character in Small Font	Name
FF	FF	Form feed
CR	CR	Carriage return
SO	SO	Shift out
SI	SI	Shift in
DLE	DE	Data link escape
DC1	D1	Device control 1 (XON)
DC2	D2	Device control 2
DC3	D3	Device control 3 (XOFF)
DC4	D4	Device control 4
NAK	NK	Negative acknowledge
SYN	SY	Synchronous idle
ETB	EB	End of transmission block
CAN	CA	Cancel
EM	EM	End of medium
SUB	SB	Substitute
ESC	EC	Escape
FS	FS	Field separator
GS	GS	Group separator
RS	RS	Record separator
US	US	Unit separator
IND	IN	Index
NEL	NE	Next line
SSA	SA	Start selected area
ESA	EA	End selected area
HTS	HS	Horizontal tab set
HTJ	НЈ	Horizontal tab with justify
VTS	VS	Vertical tab set
PLD	PD	Partial line down
PLU	PU	Partial line up
RI	RI	Reverse index
SS2	S2	Single shift 2
SS3	S3	Single shift 3
DCS	DC	Device control string
PU1	P1	Private use 1
PU2	P2	Private use 2
STS	SS	Set transmit state
CCH	CC	Cancel character
MW	MW	Message waiting
SPA	SP	Start protected area
EPA	EP	End protected area
CSI	CS	Control sequence introducer
ST	ST	String terminator
OSC	OS	Operating system command
		( 1

(continued on next page)

### **ANSI Control Functions Summary** 4.5 Showing Control Characters

Table 4–4 (Cont.) Control Character Displayed on Screen

Control Character in Large Font	Control Character in Small Font	Name		
PM	PM	Private message		
APC	AP	Application program command		
NS	NS	No-break space		


#### **Exceptions**

Some control functions still work in this mode.

- LF, FF, and VT cause a carriage return and line feed (CR LF) that move the cursor to a new line. The terminal displays the LF, FF, or VT character before performing the new line function.
- XOFF (DC3) and XON (DC1) maintain flow control, if enabled in set-up. The terminal displays the DC1 or DC3 character after performing the control function.
- The terminal does not display SSU session management commands.

### ANSI Control Functions Summary 4.5 Showing Control Characters

Figure 4-1 7-bit ASCII Code Table with C0 Control Characters Font (Left Half)



GSF\_0647\_89.DG

10 8 9 11 12 13 14 15 Column Bits 4 b3 b2 b1 Row 0 Ð à 0 0 0 0 Α  $\overline{\underline{P}}_{\underline{1}}$ 341 225 E1 361 241 F1 á ñ 1 Á 0 0 N 362 242 F2 302 194 C2 262 178 B2 Α ¢ ò 2 0 0 1 0 303 195 C3 304 196 C4 243 163 A3 244 164 £ ó Ã ã 3 Ó 0 0 1 1 344 228 E4 **^** 204 132 84 264 180 B4 Ä 324 212 D4 **۸** ä Ø 1 0 0 4  $_{\mathrm{W}}^{\mathrm{M}}$ ¥ Å å õ õ 0 1 0 5 266 182 B6 206 134 86 ö ö Æ 6 æ § Ç 7 Ç 9 8 è È Ø Ø 8 (C) É é U а 0 Ê Ú ú 10 Ë 11 ë 274 188 BC Ü ü 12 o<sub>s</sub> 215 141 8D 235 157 9D 335 221 DD 1/2 13 316 206 CE 236 158 9E 276 190 BE  $_{\rm M}^{\rm P}$ Ъ  $\mathbb{R}$ 3/4 14 1 1 1 0 2727 191 BF 317 207 ï ÿ j ß 15 - C1 Codes -— GR Codes — (ISO Latin-1 Supplemental Graphic) GSF\_0648\_89.DG

Figure 4–2 8-bit ASCII Code Table with C1 Control Characters Font (Right Half)

### 4.6 Terminal Management Functions

Terminal management functions are control functions not intended for use by applications software. Rather, they are intended to allow the user, the system administrator, or the host software to configure the terminal for use in the desired application environment.

### 4.7 ANSI Control Function Tables

The tables in this section summarize the ANSI Control Functions for ANSI-compatible VT mode and VT PCTerm mode. Default conditions are in boldface type. If you need additional information on a particular function, refer the the mnemonic in Chapter 5, which describes all the ANSI control functions in alphabetical order by mnemonic.

Refer to the following sections for a brief summary of the control for a particular function.

Control Functions	Refer to	Page
Session management	Section 4.7.1	4-16
Window management	Section 4.7.2	4-17
Audible attributes	Section 4.7.3	4-18
Color selection	Section 4.7.4	4-18
Visual attributes	Section 4.7.5	4-20
Editing	Section 4.7.6	4-21
Text processing	Section 4.7.7	4-22
Graphic character sets	Section 4.7.8	4-25
Keyboard processing	Section 4.7.9	4-27
Program keys		4-30
Printer	Section 4.7.10	4-33
Terminal management	Section 4.7.11	4-34
Desktop features		4-34
Energy saver functions		4-34
Terminal communications	Section 4.7.12	4-39
Terminal synchronization	Section 4.7.13	4-41
Reports	Section 4.7.14	4-42

In these tables, the word "same" signifies the same control sequences as in the VT520 column.

### 4.7.1 Sessions Management Control Functions

	Control Function				
Sessions Management		VT520	VT420	VT100	Mnemonic
Enable Se	ession	CSI & x	n/a	n/a	DECES
Session Pa	age Memory Allocation	CSI <i>Pn1; Pn2; Pn3;</i> <i>Pn4;</i> , x	n/a	n/a	DECSPMA
Pn	Pages per session (14)				
Update Se	ession	CSI <i>Ps</i> , y	n/a	n/a	DECUS
Ps	Item	Ü			
$\frac{Ps}{1}$	Only when active				
2	When available				
3	At regular intervals				
	Ü				

### 4.7.2 Window Management Control Functions

WINDOW MANAGEMENT	Cont			
Coupling Mode	VT520	VT420	VT100	Mnemonic
Auto Resize Mode		n/a	n/a	DECARSM
Set (enable):	CSI ? 98 h			
Reset (disable):	CSI ? 98 l			
Horizontal Cursor Coupling		n/a	n/a	DECHCCM†
Set:	CSI ? 60 h			
Reset:	CSI ? 60 l			
Page Cursor Coupling		same	n/a	DECPCCM
Set:	CSI ? 64 h			
Reset:	CSI ? 64 l			
Vertical Cursor Coupling		same	n/a	DECVCCM
Set:	CSI ? 61 h			
Reset:	CSI ? 61 l			
Display Extent				
Request Displayed Extent	CSI " v	same	n/a	DECRQDE
Report Displayed Extent	CSI <i>Ph;Pw;Pml;Pmt</i> ;	<i>;Pmp;</i> " w		·
		same	n/a	DECRPDE
Select number of lines per screen	CSI Pn *	same	same	DECSNLS
Windows				
Framed Windows Mode		same	same	DECFWM
Set:	CSI ? 111 h			
Reset:	CSI ? 111 l			
Review Previous Lines		same	same	DECRPL
Set:	CSI ? 112 h			
Reset:	CSI ? 112 l			
Set ICON Name	OSC 2 DD ST	n/a	n/a	DECSIN
where $DD$ is L; <name> (up to 12 c</name>				
Set Window Title	OSC 2 DD ST	n/a	n/a	DECSWT
where $DD$ is 1 ; <name> (up to 30 cl</name>	har)			
Pan Direction				
Pan Down	CSI PlS	same	same	SU
Pan Up	CSI Pl T	same	same	SD

†Mode is always Reset and cannot be changed.

#### 4.7.3 Audible Attributes Control Functions

	Control Function				
Audible Attributes	VT520		VT420	VT100	Mnemonic
Bell	BEL	BEL		same	BEL
Set Margin Bell Volume	CSI Ps SP 1	u	same	n/a	DECSMBV
<u>Ps</u> <u>Volume</u>					
$\overline{\mathbf{none}},0,1$ Off					
2,3,4 Low					
5,6,7,8 High					
Set Warning Bell Volume	CSI Ps SP t	t	n/a	n/a	DECSWBV
Ps Volume Off					
2,3,4 Low					
none,0, High					
5,6,7,8	00T D 1 T		,		55050
Play Sound	CSI Pvol, P	duration;	n/a	n/a	DECPS
D 1	Pnote, ~				
$\frac{Pvol}{2}$	Pduration	1 (			
$\overline{07}$ (0 = silent)	$\overline{0255}$ (1/ $\overline{3}$ 2	nd of a sec			
Pnote	Selection	Pnote	Selection	Pnote	Selection
0	silent	9	G#5	18	F6
1	C5	10	A5	19	F#6
2	C#5	11	A#5	20	G6
3	D5	12	B5	21	G#6
4	D#5(Eb)	13	C6	22	A6
5	E5	14	C#6	23	A#6
6	F5	15	D6	24	B6
7	F#5	16	D#6	25	C7
8	G5	17	E6		

### 4.7.4 Color Selection Control Functions

The VT525 and VGB25 can display 16 colors from a palette of 4096. These functions allow you to define the color map and select colors for different display uses and text attributes.

	Contro	Control Function			
Color Selection	VT520	VT420	VT100	Mnemonic	
$\begin{array}{c c} Assign Color \\ \underline{Ps1} \\ \hline 1 \\ \hline \\ 1 \\ \hline \\ Normal text \\ 2 \\ \hline Window frame \\ \underline{Ps2} \\ \hline \\ \hline 0-15 \\ \hline \\ \hline \\ \hline 0-15 \\ \hline \\ $	CSI <i>Ps1 Ps2 Ps3</i> ,	n/a	n/a	DECAC	
Alternate Text Color	CSI <i>Ps1 Ps2 Ps3</i> , }	n/a	n/a	DECATC	
Ps1 Attribute	$\frac{Ps1}{s}$	Attribute			
0 Normal text	8	Reverse u			
1 Bold	9	Reverse b	link		

ion Reverse	VT520		VT420	VT100	Mnemonic
Reverse					Millelilollic
	10	)	Underline	blink	
Underline	11	1		rse underline	e
Blink	12	2	Bold reve		
Bold reverse	13			erline blink	
Bold underline	14	4			ık
	15	5	Bold reve	rse underline	e blink
color map entry					
xt Color Blink Mode			n/a	n/a	DECATCBM
	CSI ? 115 h				
			n/a	n/a	DECATCUM
	CSI ? 114 h		12.4		22011100111
` '					
	001 / 1111		n/a	n/a	DECBBSM
	CSI ? 116 h				220220
,					
roeset (1 oreana omy).	001 1 110 1				
Request/Report/Restore			n/a	n/a	DECCTR
	CSI 2 : <i>Pu</i> \$ u				
		ST			
	200 a v p 22	~ 1			
· ·	ration)				
	,				
real (rea, green, mue)					
If <i>Pu</i> =1	If <i>Pu</i> =2				
O					
Sacuration o 100,	2140 0 100				
Mode			n/a	n/a	DECECM
	CSI ? 117 h				
Reset (erase to text):	CSI ? 117 l				
Look-Up Table	CSI Ps) {		n/a	n/a	DECSTGLT
-	, ,				
Mono					
	ttributes)				
	,				
	Bold blink Foreground color map entry Background color map entry  xt Color Blink Mode Set (blink): Reset: xt Color Underline Mode Set (underline): Reset: nk Style Mode Set (ForeGnd & BkGnd): Reset (ForeGnd only):  Request/Report/Restore Request: Reply to Host: Restore format: A group of 5 parameters: Pc; Pu; Px; Py; Pz/ Color number 0-255 Color coordinate system illegal HLS (hue, lightness, satur RGB (red, green, blue)  If Pu=1 Hue 0-360 Lightness 0-100; Saturation 0-100;  Mode Set (erase to screen): Reset (erase to text):  Look-Up Table Selection Mono	Bold blink Foreground color map entry Background color map entry  xt Color Blink Mode Set (blink): Reset: CSI ? 115 h Reset: CSI ? 115 l  xt Color Underline Mode Set (underline): CSI ? 114 h Reset: CSI ? 114 l  nk Style Mode Set (ForeGnd & BkGnd): CSI ? 116 h Reset (ForeGnd only): CSI ? 116 l  Request/Report/Restore Request: Reply to Host: Restore format: A group of 5 parameters: Pc; Pu; Px; Py; Pz/ Color number 0-255 Color coordinate system illegal HLS (hue, lightness, saturation) RGB (red, green, blue)  If Pu=1 Hue 0-360 Lightness 0-100; Saturation 0-100; Blue 0-100  Mode Set (erase to screen): CSI ? 117 h Reset (erase to text): CSI ? 117 l  Look-Up Table Selection Mono Alternate color (use text attributes) Alternate color	Bold blink Foreground color map entry Background color map entry  xt Color Blink Mode Set (blink):	Bold blink Foreground color map entry Background color map entry  xt Color Blink Mode Set (blink): CSI ? 115 h Reset: CSI ? 115 l xt Color Underline Mode Set (underline): CSI ? 114 h Reset: CSI ? 114 l nk Style Mode Set (ForeGnd & BkGnd): Reset (ForeGnd only): CSI ? 116 h Reset (ForeGnd only): CSI ? 116 l  Request/Report/Restore Request: CSI 2 : Pu \$ u Reply to Host: DCS 2 \$ s DD ST A group of 5 parameters: Pc; Pu; Px; Py; Pz/ Color coordinate system illegal HLS (hue, lightness, saturation) RGB (red, green, blue)  If Pu=1 Hue 0-360 Lightness 0-100; Saturation 0-100; Blue 0-100  Mode Set (erase to screen): CSI ? 117 h Reset (erase to text): CSI ? 117 l  Look-Up Table CSI Ps) {  n/a  Selection Mono Alternate color (use text attributes) Alternate color	Bold blink Foreground color map entry Background color map entry  xt Color Blink Mode Set (blink): CSI ? 115 h  Reset: CSI ? 115 l  xt Color Underline Mode Set (underline): CSI ? 114 h  Reset: CSI ? 114 l  nk Style Mode Set (ForeGnd & BkGnd): CSI ? 116 h  Reset (ForeGnd only): CSI ? 116 l  Request/Report/Restore Request: CSI 2 ; Pu \$ u  Reply to Host: DCS 2 \$ s DD ST  Restore format: A group of 5 parameters: Pc; Pu; Px; Py; Pz/ Color number 0-255 Color coordinate system illegal HLS (hue, lightness, saturation) RGB (red, green, blue)  If Pu=1 Hue 0-360 Lightness 0-100; Saturation 0-100; Blue 0-100  Mode Set (erase to screen): CSI ? 117 h  Reset (erase to text): CSI ? 117 l  Look-Up Table CSI Ps) { n/a n/a n/a  n/a  N/a  N/a  N/a  N/a  N

### 4.7.5 Visual Attributes Control Functions

			Control Function					
Visual Attributes		VT520		VT420	VT100	Mnemonic		
Double Height Line Top Double Height Line Bottom		ESC # 3 ESC # 4		same same	same same	DECDHL DECDHL		
Single Widt	h Line	ESC # 5		same	same	DECSWL		
Double Wid	th Line	ESC # 6		same	same	DECDWL		
Screen Mode – Light/Dark				same	same	DECSCNM		
Set	(light background):	CSI ? 5 h						
Reset	(dark background):	CSI ? 5 l						
Select Grap	hic Rendition	CSI Ps; Ps	m	same	same	SGR		
<u>Ps</u>	Attribute							
0	All attributes off							
	VT Level 1 or higher		<u>Ps</u>	VT Level	2 or higher			
1	Bold		22	Normal (l	oold off)			
4	Underline		24	Underline	e off			
5	Blink		25	Blinking	off			
7	Negative (reverse) image		27	Positive i	mage (negati	ve off)		
<u>Ps</u>	Attribute (DA1 Reports -	VT525 only)	Default C	olor				
30	Foreground Color 0		Black					
31	Foreground Color 1		Red					
32	Foreground Color 2		Green					
33	Foreground Color 3		Yellow					
34	Foreground Color 4		Blue					
35	Foreground Color 5		Magenta					
36	Foreground Color 6		Cyan					
37	Foreground Color 7		White					
39	Default Foreground Colo	r	White					
40	Background Color 0		Black					
41	Background Color 1		Red					
42	Background Color 2		Green					
43	Background Color 3		Yellow					
44	Background Color 4		Blue					
45	Background Color 5		Magenta					
46	Background Color 6		Cyan					
47	Background Color 7		White					
49	Default Background Colo	or	Black					

### **4.7.6 Editing Control Functions**

		Control Function				
EDITING		VT520	VT420	VT100	Mnemonic	
Delete Char		CSI Pn P	same	same	DCH	
Pn	Number of characters to delete (default = 1).					
Delete Colu		CSI Pn'~	same	n/a	DECDC	
Pn	Number of columns to delete (default = 1).					
Delete Line		CSI Pn M	same	same	DL	
Pn	Number of lines to delete (default = 1).					
Erase Chara		CSI <i>Pn</i> X	same	n/a	ECH	
Pn	Number of characters to erase $(Pn = 0 \text{ or } 1 \text{ (default)} = 1 \text{ character}).$					
Erase in Dis		CSI Ps J	same	same	ED	
$\frac{Ps}{0}$	Erase from  Cursor to end of displa					
1	Top of display through cu					
2	Top to bottom of display					
Erase in Lir	ne	CSI <i>Ps</i> K	same	same	EL	
<u>Ps</u>	Erase from					
0	Cursor to end of line					
1	Start of line through curs	or				
2	Start to end of line	CCI D @		,	TOLL	
Insert Char		CSI Pn @	same	n/a	ICH	
Insert Colur <i>Pn</i>	Number of columns to	CSI Pn'}	same	n/a	DECIC	
	insert ( $default = 1$ ).					
Pn	Number of lines to insert (default = 1).					
Insert Line		CSI <i>Pn</i> L	same	same	IL	
Pn	Number of lines to insert (default = 1).					
Insert/Repla			same	same	IRM	
P10	Set (insert):	CSI 4 h	541110		<b>-</b>	
	Reset (replace):	CSI 4 l				
Select Chara	acter Attribute <sup>1</sup>	CSI Ps " q	same	n/a	DECSCA	
<u>Ps</u>	Meaning	-				
0	DECSED and DECSEL					
a a	can erase characters.					
1	DECSED and DECSEL					
2	cannot erase characters. Same as 0.					
	ase in Display	CSI ? Ps J	same	n/a	DECSED	
Ps	Erase from	051:133	Same	11/ A	DECSED	
<del>1</del> <del>3</del> 0	Cursor to end of displa	v				
1	Top of display through cu					
2	Top to bottom of display					
Selective Er		CSI ? Ps K	same	n/a	DECSEL	
Ps	Erase from					
0	Cursor to end of line					
1	Start of line through curs	or				
2	Start to end of line					

 $<sup>^{1}\</sup>mathrm{DECSCA}$  does not affect visual character attributes set by the select graphic rendition (SGR) function.

		Control Function				
Rectangle	Area Processing	VT520	VT420	VT100	Mnemonic	
Change Attribute in Rectangle		Attribute in Rectangle CSI <i>Pt;Pl;Pb;Pr; Ps1;Psn</i> \$ r n/a			DECCARA	
<u>Ps</u>	<u>Attribute</u>					
0	Off					
1	Bold	P	t Top line			
4	Underline	P	1 Left colu	mn		
5	Blink	P	b Bottom li	ine		
7	Negative image	P	r Right col	umn		
22	No bold		o .			
24	No underline					
25	No blink					
27	Positive image					
Copy Rectangular Area	CSI Pts;Pls;Pbs;Prs;P	ps;Ptd;Pld;Pt	od\$v			
13			same	n/a	DECCRA	
	Source		Destinati	ion		
Pts	Top line border	P	td Top line	border		
Pls	Left column border		ld Left colu			
Pbs	Bottom line border	P	pd Page nur	nber		
Prs	Right column border					
Pps	Page number					
	angular Area	CSI Pt;Pl;Pb;Pr \$ z	same	n/a	DECERA	
	gular Area	CSI Pch; Pt;Pl;Pb;Pr S				
	8		same	n/a	DECFRA	
Pch	Character					
	tribute in Rectangle	CSI Pt;Pl;Pb;Pr Ps1;	. <i>Psn</i> \$ t			
			same	n/a	DECRARA	
Ps	Reverse Attributes		541110		220111111	
0	All					
1	Bold					
4	Underline					
5	Blink					
7	Negative image					
-	ibute Change Extent	CSI Ps * x	same	n/a	DECSACE	
SCICCE FILLI	rase Rectangular Area	CSI Pt;Pl;Pb;Pr \$ {	same	n/a	DECSERA	

### **4.7.7 Text Processing Control Functions**

	Contro	I Function		
<b>Cursor Position</b>	VT520	VT420	VT100	Mnemonic
Autowrap mode		same	n/a	DECAWM
Set (enable):	CSI ? 7 h	Sume	11/4	BECHIVIN
Reset (disable):	CSI ? 7 l			
Backspace	BS	same	same	BS
Carriage Return	CR	same	same	CR
Cursor Backward	CSI $Pc$ D	same	same	CUB
Cursor Backward Tabulation	CSI Pn Z	n/a	n/a	CBT
Cursor Down	CSI <i>Pl</i> B	same	same	CUD
Cursor Forward	CSI $Pc$ C	same	same	CUF
Cursor Horizontal Absolute	CSI <i>Pn</i> G	n/a	n/a	CHA
Cursor Horizontal Forward Tab	CSI <i>Pn</i> I	n/a	n/a	CHT
Cursor Information Report	DCS 1\$u DD ST	same	n/a	DECCIR
Cursor Next Line	CSI <i>Pn</i> E	n/a	n/a	CNL

		Cont	rol Function		
Cursor Pos	sition	VT520	VT420	VT100	Mnemonic
Cursor Pre	vious Line	CSI Pn F	n/a	n/a	CPL
Cursor Pos	ition	CSI Pl ; Pc H	same	same	CUP
Cursor Pos	ition Report	CSI 6 n	same	same	CPR
(Also see	DECCIR, DECXCPR, and I	OSR.)			
	Response:	CSI <i>Pl; Pc</i> R			
Pl	No. of lines				
Pc	No. of columns				
Cursor Up		CSI <i>Pl</i> A	same	same	CUU
Extended (	Cursor Position Report	CSI ? 6 n	same	n/a	DECXCPR
	Response:	CSI Pl; Pc; Pp R			
PI	Line				
Pc	Column				
Pp	Page				
Restore Cu		ESC 8	same	same	DECRC
	ved Cursor (SCO)	CSI u	n/a	n/a	SCORC
Right-to-Le	_ = -		n/a	n/a	DECRLCM
	Set:	CSI ? 96 h			
	Reset:	CSI ? 96 l			
Right-to-Le			n/a	n/a	DECRLM
	Set:	CSI ? 34 h			
a a	Reset:	CSI ? 34 l			PEGGG
Save Curso		ESC 7	same	same	DECSC
	or Position (SCO)	CSI s	n/a	n/a	SCOSC
Set Cursor	Style	CSI <i>Ps</i> SP q	n/a	n/a	DECSCUSR
<u>Ps</u>	DI: 1: .11 1				
<b>none</b> ,0,1					
2	Steady block				
3	Blinking underline				
4 Tt C	Steady underline			/-	DECTCEM
Text Curso	r Enable Mode	CCI 2 of L	same	n/a	DECTCEM
	<b>Set (visible):</b> Reset (invisible):	<b>CSI ? 25 h</b> CSI ? 25 l			
		CSI : 23 I			
Horizontal	and Vertical Position				
Form Feed		FF	same	same	FF
Horizontal	Tab	HT	same	same	HT
Horizontal/	Vertical Position	CSI <i>Pl ; Pc</i> f	same	same	HVP
Pl	No. of lines to move to				
Pc	No. of columns to move	to			
Horizontal	Position Absolute	CSI Pn'	same	same	HPA
Horizontal	Position Relative	CSI <i>Pn</i> a	same	same	HPR
Line Feed		LF	same	same	LF
Line Feed/	New Line Mode		same	same	LNM
	Set (NL):	CSI 20 h			
	Reset (LF):	CSI 20 l			
Next Line		ESC E	same	same	NEL
Vertical Lin	ne Position Absolute	CSI Pn d	n/a	n/a	VPA
Vertical Lin	ne Position Relative	CSI <i>Pn</i> e	n/a	n/a	VPR
Vertical Ta	b	VT	same	same	VT

		Control Function					
Horizontal Ta	bs—Set/Clear	VT520	VT420	VT100	Mnemonic		
Set Horizonta	al Tah	ESC H	same	samo	HTS		
	ery 8 columns	CSI ? 5 W	n/a	same n/a	DECST8C		
Clear Tabs	cry o columns	CSI Ps g	same	same	TBC		
Ps	Clear	001108	Surre	Surre	120		
<u>no</u> ne, 0	tab at cursor						
3	all tabs						
Margins and	Scrolling						
Back Index		ESC 6	same	n/a	DECBI		
Forward Inde	ex	ESC 9	same	n/a	DECFI		
Index		ESC D	same	same	IND		
Origin Mode		2002	same	same	DECOM		
-8 1.1040	Set (in margins):	CSI ? 6 h					
	Reset (upper-left):	CSI ? 6 l					
Reverse Index		ESC M	same	same	RI		
Scrolling Mod			same	same	DECSCLM		
	Set (smooth):	CSI ? 4 h					
	Reset (jump):	CSI ? 4 l					
Set Scroll Spe		CSI Ps SP p	n/a	n/a	DECSSCL		
Ps		1					
<b>none</b> , 0, 1, 2, 3	Smooth 2						
4, 5, 6,	Smooth 4				DECSCLM		
7, 8							
9	Jump						
Left Right Ma	argin Mode		same	n/a	DECLRMN		
	Set (enable):	CSI 69 h					
	Reset (disable):	CSI 69 l					
Set Left and I	Right Margin	CSI Pl; Prs	same	same	DECSLRM		
Pl	Left column margin (default = 1)						
Pr	Right column margin (default = <b>80</b> or <b>132</b> ,						
	depending on page width)						
-	Bottom Margin	CSI <i>Pt</i> ; <i>Pb</i> r	same	same	DECSTBM		
Pt	Top margin (default = $1$ )						
Pb	Bottom margin						
Page Arrange	ement and Size <sup>1</sup>						
Column Mode			same	same	DECCOLM		
	Set (132 columns):	CSI ? 3 h					
	Reset (80 columns):	CSI ? 3 l					
No clear scre	en on column change		n/a	n/a	DECNCSN		
	Do not clear:	CSI ? 95 h					
	Clear screen:	CSI ? 95 l					
Select Colum		CSI Ps \$	same	n/a	DECSCPP		
$\frac{Ps}{r}$	Set each page to						
0 or 80	80 columns						
132	132 columns						
Set Lines Per	· Page	CSI <i>Pn</i> t	same	same	DECSLPP		

<sup>&</sup>lt;sup>1</sup>The page size can be 24, 25, 36, 42, 48, 52, and 72 lines with 80 or 132 columns.

			Contro	Function			
Page Moven	nent	VT520		VT420	VT100	Mnemonic	
Novt Dogo		CCI Dn II		como	como	ND	
Next Page <i>Pn</i>	Number of pages to move	CSI Pn U		same	same	NP	
1 11	( <b>0</b> or  1 = <b>1</b> page)						
Preceding Pa		CSI Pn V		same	same	PP	
Pn	Number of pages to move	CDI I II V		Sume	Sume	11	
1 11	(0  or  1 = 1  page)						
Page Position		CSI Pn SP P		same	same	PPA	
Page Position		CSI Pn SP R		same	same	PPB	
Page Position		CSI Pn SP Q	!	same	same	PPR	
4.7.8 Gra	phic Character Sets	Control Fu	unctions	S			
			Contro	I Function			
GRAPHIC CI	HARACTER SETS	VT520		VT420	VT100	Mnemonic	
	Preferred Supp Set	DCS Ps! u I	Oscs ST	same	n/a	DECAUPSS	
$\frac{Ps}{0}$	94-Character Set						
1	96-Character Set						
Dscs	Default 94-Character Set		Dscs	Default 9	6-Character	Set	
<del>2565</del> <b>% 5</b>	DEC Supplemental		$\frac{DSCS}{A}$	ISO Latin-1 Supplemental			
" ?	DEC Greek		В		n-2 Suppleme		
" 4	DEC Hebrew		F		k Supplemen		
% <b>0</b>	DEC Turkish		Н		ew Suppleme		
& 4	DEC Cyrillic		L	ISO Latir			
<	User-preferred		M	ISO Latin-5 Supplemental			
	supplemental		<		erred supple		
Down-line L	$pad^1$	DCS Pfn; Pcn; Pe;			Pcmh; Pcss {		
		<dscs><sixel< td=""><td>-font-patt</td><td></td><td>,</td><td></td></sixel<></dscs>	-font-patt		,		
				same	n/a	DECDLD	
	Load Allocation	CSI Ps, z		n/a	n/a	DECDLDA	
$\frac{Ps}{}$	Character sets per session						
1	One each						
2	Two each S1 and S2						
Select Chara	cter Set	ESC I Dscs		same	n/a	SCS	
I	94-Character G-set		I	96-Chara	cter G-set		
(	$\overline{\text{G0}}$		<u>I</u> -	G1	_		
)	G1			G2			
*	G2		/	G3			
+	G3						
<u>Dscs</u>	Default 94-Character Set		<u>Dscs</u>		6-Character		
& 4	Cyrillic (DEC)		A		n-1 Suppleme		
Α	British/U.K. NRCS		В	ISO Latir	n-2 Suppleme	ental	
<u>Dscs</u>	Default 94-Character Set		<u>Dscs</u>		6-Character		
5 or C	Finnish NRCS		$\overline{\mathbf{F}}$		k Supplemen		
R	French NRCS		Н	ISO Hebr	ew Suppleme	ental	
	- 10 1 17-00		M	TCO I atta	n-5 Suppleme	mtal	
9 or Q	French Canadian NRCS					entai	
	French Canadian NRCS German NRCS Greek (DEC)		L	ISO Latir			

 $<sup>^{1}</sup>$ The VT520 DRCS follows the same DECDLD sequence with the exceptions noted in reference.

		Contro	I Function		
GRAPHIC CH	HARACTER SETS	VT520	VT420	VT100	Mnemonic
" >	Greek NRCS				
Dscs	Default 94-Character Set				
" 4	Hebrew (DEC)				
% =	Hebrew NRCS				
Y	Italian NRCS				
', E, or 6	Norwegian/Danish NRCS				
% 6	Portuguese NRCS				
& 5	Russian NRCS				
% 3	SCS NRCS				
Z	Spanish NRCS				
7 or H	Swedish NRCS				
=	Swiss NRCS				
% <b>0</b>	Turkish (DEC)				
% 2	Turkish NRCS				
0	DEC Special Graphic				
% 5	DEC Supplemental				
>	DEC Technical Character	Set			
<	User-preferred Supplement	tal			
Select Zero S	Symbol	CSI Ps, {	n/a	n/a	DECSZS
Ps	Selection	, ,			
1	oval zero - 0				
2	zero with slash - Ø				
3	zero with dot				
Supplementa	al Character Set	VT520	VT420	VT100	Mnemonic
National Rep	olacement Character Set Mo	de	same	n/a	DECNRCM
•	Set (National):	CSI ? 42 h			
	(7-bit characters)				
	Reset (Multinational):	CSI ? 42 l			
	(8-bit characters)				
Request Use	r-Preferred	CSI & u	same	n/a	DECRQUPSS
Supplemer					·
	Response:	DEC Ps! u Dscs ST			See
	Parameters:				DECAUPSS

Control Ch	aracters and	C	ontrol Function		
Code Exter	nsion Functions	VT520	VT420	VT100	Mnemonic
Display CO controls as PC Characters (SCO)		ESC xx	n/a	n/a	SCODPCC
Show Cont	rol Character Mode		same	same	CRM
	Set (show):	CSI 3 h			
	Reset (interpret):	CSI 3 l			
Send Conti	rol Character to Host				
	7-bit controls	ESC SP F	n/a	n/a	S7C1T
	8-bit controls	ESC SP G	n/a	n/a	S8C1T
Single Shif	t 2	ESC N	same	same	SS
Single Shif		ESC O	same	same	SS
Locking Sh	ift				LS
LSO	Map G0 into GL	SI	same	same	
LS1	Map G1 into GL	SO	same	same	
LS1R	Map G1 into GR	ESC ~	same	n/a	
LS2	Map G2 into GL	ESC n	same	n/a	
LS2R	Map G2 into GR	ESC }	same	na/	
LS3	Map G3 into GL	ESC o	same	n/a	
LS3R	Map G3 into GR	ESC	same	n/a	
Locking Sh	aift Zero	SI	same	same	LS0
Locking Sh	ift One	SO	same	same	LS1
Locking Sh	ift Two	ESC n	same	n/a	LS2
Locking Sh	ift Three	ESC o	same	n/a	LS3
Locking Sh	ift One Right	ESC ~	same	n/a	LS1R
Locking Sh	ift Two Right	ESC }	same	n/a	LS2R
Locking Sh	ift Three Right	ESC	same	n/a	LS3R
Single Shif	t Two	ESC N	same	same	SS2
Single Shif	t Three	ESC O	same	same	SS3
Send 7-bit	C1 control character to host	ESC SP F	same	n/a	S7C1T
Send 8-bit	C1 control character to host	ESC SP G	same	n/a	S8C1T

### 4.7.9 Keyboard Processing Control Functions

		Control	Function		
Keyboard F	unction	VT520	VT420	VT100	Mnemonic
Autorepeat	Mode		same	same	DECARM
•	Set (repeat):	CSI ? 8 h			
	Reset (disabled):	CSI ? 8 l			
Auto Repea	t Rate	CSI <i>Ps</i> - p	n/a	n/a	DECARR
Ps	Rate				
0-5	$\overline{\mathrm{Off}}$				
6-15	Slow (10 cps)				
16-30	Fast (30 cps)				
Backarrow	Key Mode		same	same	DECBKM
	Set (backspace):	CSI ? 67 h			
	Reset (delete):	CSI ? 67 l			
Copy Key D	)efault	DCS " z <i>DD</i> ST	n/a	n/a†	DECCKD
DD	Key-s/Key-d;Key-s/Key	y-d;			
Key-s	Source key				
Key-d	Destination key				

†You can exchange keys in Set-Up.

		Control Function				
Keyboard Function		VT520		VT420	VT100	Mnemonic
Cursor Key	rs Mode			same	same	DECCKM
	Set (application):	CSI ? 1 h				
	Reset (cursor):	CSI ? 1 l				
Define Fun	ction Key (SCO)	ESC Q Fn string	ŗ	n/a	n/a	SCODFK
Device Stat	tus Report (keyboard status)					DSR
Request	Keyboard Report:	CSI ? 26 n		same	same	
Reply to	Keyboard Request:	CSI ? 27 ; Pn; Ps	st; Ptyp	n		
				same	same	
$\underline{Pn}$	Keyboard Language (VT/I	PC)	$\underline{Pn}$	Keyboard	ł Language	(VT or PC)
0	Unknown		15	Spanish		<u> </u>
1	North American		16	Portugue	ese	
2	British		19	Hebrew		
3	Belgian (Flemish)		22	Greek		
4	French Canadian		28	Canadiar	n English	
5	Danish		29		Q/Turkish	
6	Finnish		30		F/Turkish	
7	German/German		31	Hungaria	an	
8	Dutch		33	Slovak		
9	Italian		34	Czech		
10	Swiss French		35	Polish		
11	Swiss German		36	Romania	n	
12	Swedish		38	SCS		
13	Norwegian		39	Russian		
14	French		40	Latin An	nerican	
Pst	Keyboard Status		Ptyp	Keyboard		
0	Keyboard Ready		$\frac{JI}{4}$	LK411	<u> </u>	
3	No Keyboard		5	PCXAL		
8	Keyboard Busy		-			
	Keyboard Report	APC : ppp mm S	Т	same	n/a	DECEKBD
	al Functions	CSI Pf1;Pc1;Pf			n/a	DECELF
	ondary Keyboard	001111,1 01,1111	,	same	n/a	DECESKM
Languag				Same	11/4	DECESION
88	Set (secondary):	CSI ? 104 h				
	Reset (primary):	CSI ? 104 l				
		00211011				
Hebrew En	coding Mode <sup>1</sup>			same	n/a	DECHEM
	Set (8-bit char):	CSI ? 36 h		-		
	Reset (7-bit char):	CSI ? 36 l				
Hebrew Ke	yboard Map Mode			same	n/a	DECHEBM
	Set (Hebrew keyboard):	CSI ? 35 h				
	Reset (North	CSI ? 35 l				
	American):					
Keyboard A	Action Mode			same	same	KAM
J	Set (lock):	CSI 2 h		-	-	
	Reset (unlock):	CSI 2 l				
Keypad Ap	plication Mode	ESC =		same	same	DECKPAM
	-					
Keyboard I	anguage Selection	CSI Ps1; Ps2 SP	}	same	n/a	DECKBD
Ps1	Keyboard Type					
1,0	DEC keyboard layout					
2	Enhanced PC keyboard la	_				

 $<sup>\</sup>overline{\ }^1$  DECHEM is opposite in action to DECNRCM; that is, setting DECHEM has the same result as resetting DECNRCM.

		Control Function				
Keyboard I	Function	VT520		VT420	VT100	Mnemonic
Ps2	Keyboard Language (VT/F	PC)	Ps2	Keyboar	d Languag	e (VT or PC)
none,	North American		15	Spanish		
0 or 1			16	Portugue	ese	
2	British		19	Hebrew		
3	Belgian		22	Greek		
4	French Canadian		28	Canadia	n English	
5	Danish		29	Turkish	Q/Turkish	
6	Finnish		30	Turkish	F/Turkish	
7	German		31	Hungari	an	
8	Dutch		33	Slovak		
9	Italian		34	Czech		
10	Swiss French		35	Polish		
11	Swiss German		36	Romania	an	
12	Swedish		38	SCS		
13	Norwegian		39	Russian		
14	French		40	Latin Ar	nerican	
Keypad Nu	meric Mode	ESC >		same	same	DECKPNM
Key Position Mode				same	n/a	DECKPM
_	Set (key position):	CSI ? 81 h				
	Reset (char codes):	CSI ? 81 l				
Keyboard U	Jsage Mode			same	n/a	DECKBUM
	Set (data processing): Reset (typewriter):	CSI ? 68 h CSI ? 68 l				
Local Func	tion Key Control	CSI Pk1; Pf1; I	Pk2; Pf2	*}		
				same	n/a	DECLFKC
Pk	Function	VT Keyboard			ed PC Keyb	oard
1	Hold	F1		Scroll Lo	ock	
2	Print	F2		Print Sc	reen	
3	Set-Up	F3		Cap Loc	k/Print Scr	een
North Ame	rican/Greek Selection			same	n/a	DECNAKB
	Set (North American):	CSI ? 57 h				
	Reset (Greek keyboard):	CSI ? 57 l				
Numeric K	eypad Mode			same	n/a	DECNKM
	Set (application):	CSI ? 66 h				
	Reset (numeric):	CSI ? 66 l				

Program Keys	s	VT520				
		VT520		VT420 VT1		Mnemonic
Program Alphanumeric Key Program Function Key		DCS " y <i>DD</i> DCS " x <i>DD</i>	ST ST	n/a n/a	n/a n/a	DECPAK DECPFK
DD	Key1/Mod1/Function n/U	JDS/UDS Dir;	Key1/Mod	d1/Functio	n n/UDS/	UDS Dir;
Keyn	VT Keyboard	PC Keyboard				
11	F1	F1				
12	F2	F2				
13	F3	F3				
14	F4	F4				
15	F5	F5				
17	F6	F6				
18 19	F7 F8	F7 F8				
20	F9	F9				
21	F10	F10				
23	F11	F11				
24	F12	F12				
25	F13					
26	F14					
28	F15					
29	F16					
31	F17					
32	F18					
33	F19					
34	F20	_				
<u>Modn</u>	Modifier Key	Function n		ction numl		
0, <b>none</b>	Normal	UDS UDS		ned sequer	<u>ice</u>	
1 2	Normal Shift	<u>UDS Dir</u> 0, <b>none</b>	UDS Dire	ection		
3	Alt	0, <b>none</b> 1	Local			
4	Alt + Shift	2	Remote			
5	Control	~	remote			
6	Shift + Control					
7	Alt + Control					
8	Alt + Control + Shift					
Program Key		CSI Ps + z		n/a	n/a	DECPKA
<u>Ps1</u>	Program Key Action					
$\mathbf{none},0$	None					
1	Lock Keys and Modifiers					
2	Restore Factory Defaults					
3	Recall Key Definitions					
Program Kev	Free Memory Report <sup>2</sup>	CSI Ps1; Ps2	+ y	n/a	n/a	DECPKFMR
Ps1	Total memory (bytes)	•	•			
Ps2	Free memory					
	ram Key Free Memory DECPKFMR	CSI + x		n/a	n/a	DECRQPKFM

 $<sup>^2</sup>$ The VT520 reports this sequence upon receiving DECRQPKFM from the host. See reference for limitations.

-	Control Function					
Kev Type, C	lick, Lock, LEDs	VT520	VT420	VT100	Mnemonic	
	,,					
Request Key		CSI Ps1; Ps2, w	n/s	n/a	DECRQKD	
<u>Ps1</u>	Key station number					
Ps2	Modifier Key					
0,none	Normal					
1	Normal					
2	Shift					
3	Alt					
4	Alt + Shift					
5	Control					
6	Shift + Control					
7	Alt + Control					
8	Alt + Control + Shift					
Request Key	Type	CSI Ps , u	n/a	n/a	DECRQKT	
Report Key		CSI <i>Ps1; Ps2</i> , v	n/s	n/a	DECRPKT	
	tion Key Definition	DCS " } DD ST	n/a	n/a	DECRPFK	
	fiers/Key State	DCS " ~ DD ST	n/a	n/a	DECRPAK	
Set Key Clic		CSI <i>Ps</i> SP r	same	n/a	DECSKCV	
Ps	Volume					
1	Off					
2,3,4	Low					
none, 0,	High					
5,6,7,8.	_					
Set Leek Ve	v Ctylo	CSI <i>Ps</i> SP v	n/o	n/a	DECSLCK	
Set Lock Key		CSI PS SP V	n/a	n/a	DECSLCK	
$\frac{rs}{\text{none},0,1}$	Lock Style Caps Lock					
2	Shift Lock					
3	Reverse Lock					
Num Lock M			same	same	DECNUMLK	
rum Lock iv	Set:	CSI ? 108 h	Same	Same	DECITORER	
	Reset:	CSI ? 108 l				
Caps Lock M		CS1 : 100 1	same	same	DECCAPSLK	
Cups Lock iv	Set:	CSI ? 109 h	Sume	Sume	DECOM SER	
	Reset:	CSI ? 109 l				
Keyboard LI	EDs Host Indicator Mode		same	same	DECKLHIM	
	Set:	CSI ? 110 h				
	Reset:	CSI ? 110 l	,	,	DEGLI	
Load LEDs	** 1	CSI <i>Ps</i> q	n/a	n/a	DECLL	
$\frac{Ps}{2}$	Volume					
0	Clear all LEDs					
1	Light Num Lock					
2	Light Caps Lock					
3	Light Scroll Lock					
21	Extinguish Num Lock					
22 23	Extinguish Caps Lock					
۵3	Extinguish Scroll Lock					
Select Modif	ier Key Reporting	CSI Pm1;Pf1Pmn;P	fn + r			
(See refere			same	n/a	DECSMKR	

	Control Function						
User-Defined	Keys	VT520	VT420	VT100	Mnemonic		
User Defined	Kevs	DCS <i>Ps1; Ps2; Ps3</i>	<i>DD</i> ST				
Osci Demica	neys	DOS 151, 152, 150	same	n/a	DECUDK <sup>3</sup>		
<u>Ps1</u>	Clear						
none,0	All UDKs before loa						
1		n redefined; load new UDF	K values.				
<u>Ps2</u>	Lock						
none,0	UDKs against futur						
1		s against future redefinitio	n.				
<u>Ps3</u>	Define						
none, 0	Shifted function key						
1	Unshifted function l						
2	Shifted function key						
3	Alt unshifted functi						
4	Alt shifted function						
DD		/St2/Dir;Keyn/Stn/D	ir;				
Stn	Sequence user-defin	ed key (UDK)					
<u>Keyn</u>	VT Keyboard	PC Keyboard					
11	F1	F1					
12	F2	F2					
13	F3	F3					
14	F4	F4					
15	F5	F5					
17	F6	F6					
18	F7	F7					
19	F8	F8					
20	F9	F9					
21	F10	F10					
23	F11	F11					
24	F12	F12					
25	F13						
26	F14						
28	F15						
29	F16						
31	F17						
32	F18						
33	F19						
34	F20						
<u>Dir</u>	Direction <sup>4</sup>						
$\overline{0,\mathbf{n}}$ one	Normal						
1	Local						
2	Remote						
DSR - User-D	Defined Key Request		same	n/a	DSR-UDK		
Request U		CSI ? 25 n					
	JDK locked status:	CSI ? 20 n					
	JDK unlocked status	CSI ? 21 n					

 $<sup>\</sup>overline{\ ^3}$ CAUTION: Local Function keys may be disabled by redefining them with DECUDK.

<sup>&</sup>lt;sup>4</sup>See DECPFK for direction definitions.

#### 4.7.10 Printer Control Functions

			Control	Function				
Printer Port	t Function	VT520		VT420	VT100	Mnemonic		
DSR - Print	ter Port Report			same	same	DSR-Print		
DSR - I IIII	Request:	CSI ? 15 n		Same	Same	DSIC-1 TIIIC		
	Response:	CSI ? <i>Ps</i> n						
Ps	Printer	CDI : 13 II						
$\frac{15}{10}$	Ready							
11	Not ready							
13	Off line							
18	Busy							
19	On another session.							
13	On another session.							
	/ - Send Screen Data	CSI 2 i		n/a	n/a	-		
through Ho								
Media Copy	/ - Start/Stop Printer-to-Host	Session				MC		
	ANSI:	CSI <i>Pa</i> i		same	same			
	DEC:	CSI ? <i>Pd</i> i		same	CSI ?8i			
ANSI Mo	ode		DEC N	<b>1ode</b>				
<u>Pa</u>	Function		$\underline{Pd}$	Function	_			
$\overline{0,none}$	Print page		1	Print cu	rsor line			
4	Reset printer controller n	node	4	Reset au	itoprint mo	de		
5	Set printer controller mod		5	Set auto	Set autoprint mode			
6	Start printer to host sess:	ion	8	Stop pri	Stop printer to host session			
7	Stop printer to host session		9	Start pri	inter to hos	t session		
			10	Print con	mposed mai	in display		
			11	Print all				
			18	Assign p	rinter to ac	ctive host session		
			19			mands from sessions		
Print Exten	it Mode			same	same	DECPEX		
	Set (entire page):	CSI ? 19 h						
	Reset (scroll region):	CSI ? 19 l						
<b>Print Form</b>	Feed Mode			same	same	DECPFF		
	Set (FF):	CSI ? 18 h						
	Reset (no FF):	CSI ? 18 l						
Select Digit	al Printed Data Type <sup>1</sup>	CSI Ps) p		n/a	n/a	DECSDPT		
Ps	Printed Data Type							
$\overline{\mathbf{none}}, 0, 1$	Print National Only							
2	National and Line Drawi	ng						
3	Print Multinational							
4	Print All Characters							
Select Print	ter Type	CSI Ps \$ s		n/a	n/a	DECSPRTT		
Ps	Printer Type							
none,0,1								
2	IBM ProPrinter							
3	DEC + IBM							
Select ProP	rinter Character Set	CSI Pn * p		n/a	n/a	DECSPPCS		
Pn	Printer	•						
<b>210</b>	PC Greek							
220	PC Spanish							
437	PC International							
850	PC Multilingual							
852	PC Slavic (Latin 2)							
857	PC Turkish							
860	PC Portuguese							
550	- o z ozenguese							

<sup>&</sup>lt;sup>1</sup> This sequence takes effect only when a ProPrinter or Digital printer with ProPrinter emulation mode is attached.

862 PC Hebrew

863 PC French-Canadian865 PC Danish/Norwegian

866 PC Cyrillic

Start/stop printer; see Media Copy.

#### **DEC Printers with ProPrinter Emulation**

Enter/Return from IBM ProPrinter Emulation Mode n/a DECIPEM

Enter: CSI ? 58 h Return: CSI ? 58 l

### 4.7.11 Terminal Management Control Functions

		Contro	I Function		
Desktop Fea	ture	VT520	VT420	VT100	Mnemonic
Select Set-U <sub>l</sub>	p Language	CSI <i>Ps</i> p	n/a	n/a	DECSSL
${\mathbf{none}},0,1$	English				
2	French				
3	German				
4	Spanish				
5	Italian				
Load Time of	f Day	CSI <i>Ps1; Ps2</i> , p	n/a	n/a	DECLTOD
Ps1	Hour (decimal number between 00 and 23)	•			
Ps2	Minutes (decimal number between 00 and 59)				
CRT/Energy	Saver Functions				
CDT Cove M	ada		n/a	n/a	DECCRTSM
CRT Save Mode Set (enable CRT saver 15 min):		CSI 97 h	II/a	II/a	DECCRISM
	able CRT saver):	CSI 97 l			
CRT Saver T		CSI <i>Ps</i> - q	n/a	n/a	DECCRTST
Ps Ps	Selection	obi i baq	11/4	11/4	DECCRIST
$\frac{15}{0}$	Never				
5	5 min				
15	15 min				
30	30 min				
60	60 min				
Energy Save	r Timing	CSI <i>Ps</i> - r	n/a	n/a	DECSEST
<u>Ps</u>	Selection				
0	Never				
5	5 min				
15	15 min				
30	30 min				
Host Wake-U	Jp mode		same	same	DECHWUM
(CRT and Er					
	Set:	CSI ? 113 h			
	Reset:	CSI ? 113 l			

		Control Function				
Device Att	ributes	VT520	VT420	VT100	Mnemonic	
Device Att	ributes or	CSI c or CSI 0 c	same	same	DA1	
Primary D	evice Attributes					
· ·	Model	Response				
	<del>-</del>	CSI ? <i>Psc</i> ; <i>PS1</i> ; <i>Ps</i>	sn c			
	VT520	CSI ? 65;1;2;7;8;9;12;1	8;19;21;23;2	4;42;44;45;4	<b>16</b> с	
	VT525	CSI ? 65;1;2;7;9;12;18;	19;21;22;23;	24;42;44;45	;46 c	
Ext	Description	Ext	Descript			
1	132 columns	18	Windowi	ng capabili	ty	
2	Printer port extension	21		al scrolling		
6	Selective erase	23	Greek ex	tension		
7	DRCS	24	Turkish	extension		
8	UDK	42	ISO Lati	n-2 charact	er set	
9	NRCS	44	VT PCTe			
12	Serbo-Croatian (SCS)	45	Soft key	mapping		
15	Technical character set	46	ASCII te	rminal emi	ulation	
Secondary	Device Attributes	CSI > c  or  CSI > 0 c	same	n/a	DA2	
J	Keyboard	Response				
	VT520 VT keyboard	$\overline{\mathrm{CSI}} > 64$ ; Pv; 0 c				
	VT525 VT keyboard	CSI > 65; $Pv$ , 0 c				
	VT520 PC keyboard	CSI > 64; Pv; 1 c				
	VT525 PC keyboard	CSI > 65: <i>Pv</i> : 1 c				
Tertiary Device Attributes		CSI = c  or  CSI = 0 c	same	same	DA3	
Terminal I	D					
II uc D		FCC 7	,		DECID1	
Identify D		ESC Z DCS!   DD ST	n/a	same	DECID <sup>1</sup> DECRPTUI	
Report Ter	minal Unit ID		same	n/a	DECRPIUI	
		Pv Firmw	are version			
Select Terr	minal ID²	CSI <i>Ps</i> , q	same	same	DECTID	
<u>Ps</u>	ID Type	Response		Termina		
$\frac{15}{0}$	VT100	ESC [? 1; 2 c		VT100	<u> </u>	
1	VT101	ESC [ ? 1; 0 c		VT101		
2	VT102	ESC [ ? 6 c		VT102		
5	VT220	CSI ? 62; 1; 2; 7; 8 c			Jorth American	
~	, 1220	CSI ? 62; 1; 2; 7; 8; 9 c	•		nternational	
7	VT320	CSI ? 63; 1; 2; 7; 8 c	•		Iorth American	
•	, 1020	CSI ? 63; 1; 2; 7; 8; 9 c			nternational	
9	VT420	CSI ? 64; 1; 2; 7; 8; 9;			Jorth American	
J	V 1 120	CSI ? 64; 1; 2; 7; 8; 9;			nternational	
10	VT520/VT525	Refer to DA1 for respo		V 146U I	ncinativnai	
10	V I JAU! V I JAJ	weight to Dat for lespo	1150.			

 $<sup>^{1}\</sup>mbox{DECID}$  may not be supported; use primary device attributes (DA1) instead.

 $<sup>^2\</sup>mbox{DECTID}$  has no effect when the terminal is in VT52 mode.

			Control Function					
Terminal Mo	odes	VT520		VT420	VT100	Mnemonic		
Enter/Exit V	T PCTerm Mode or	CSI ? <i>Ps1; Ps</i>	s <i>2</i> r	same	n/a	DECPCTERM		
	II characters or scancodes	,						
Ps1	VT Emulation Mode		SCO Con	sole Mode				
$\overline{\mathbf{none}}, 0$	VT Mode		ASCII ch	aracters				
1	VT PCTerm Mode		Scancode	S				
Ps2	Character Set		Ps2	Characte	er Set			
$\overline{210}$	PC Greek		none,0	No Cha	nge			
220	PC Spanish		1	PC Mult				
437	PC International		2	PC Inter				
850	PC Multilingual		3	PC Dani	sh/Norwegi	an		
852	PC Slavic (Latin 2)		4	PC Span				
857	PC Turkish		5	PC Porti				
860	PC Portuguese		6		pplemental			
862	PC Hebrew		7	ISO Lati				
863	PC French-Canadian							
865	PC Danish							
866	PC Cyrillic							
Exit ANSI (	VT52) Mode	ESC <		same	same	DECANM		
Overscan M				n/a	n/a	DECOSCNM		
Set (enab)	le overscan):	CSI ? 106 h						
	sable overscan):	CSI ? 106 l						
	ormance (Operating) Level	CSI 6 Ps1; I	<i>Ps2 :</i> " p	same	same	DECSCL		
Ps1	Level Selected	Ps2	Data Bits					
$\frac{1}{\text{none}}$ ,0,1	1 - VT100	$\frac{1}{\text{none}}$ , 0, 2	8-bit cont	_				
2,3,4, <b>5</b>	5 - VT520/VT525	1	7-bit cor					
Ps	Cursor Style	-	. 111 001	111 013				
$\frac{15}{1}$	50 Hz							
2	60 Hz							
none	≥ <b>70 Hz</b>							
0 or 3	≥ 70 HZ							
	ol Character Mode			same	same	CRM		
Show Contro	Set (show):	CSI 3 h		Sume	Same	CIVIVI		
	Reset (interpret):	CSI 3 I						
Terminal Ma	ode Emulation	CSI Ps SP ~		n/a	n/a	DECTME		
Ps	Terminal Mode	CDITSDI		11/4	11/4	DECTME		
13	VT520/VT525 (VT Level	l 5)						
2	VT100	10)						
3	VT52							
3 4	VT PCTerm							
5	WYSE 160/60							
5 6	WYSE PCTerm							
7	WYSE 50/50+							
8	WYSE 150/120							
9	TVI 950							
9 10	TVI 925							
11	TVI 910+							
12	ADDS A2							
13	SCO Console							
14	WYSE 325							
Set Mode		CSI P1Pn	h	çame	same	SM		
Set Mode		CSI F1PII	11	same	same	SIM		

<sup>&</sup>lt;sup>3</sup>The VT525 and VGB25 models do not have overscan.

Mode Description	ANSI M	ode	DEC N	<b>I</b> ode
r	Pa	Mnemonic <sup>4</sup>	Pd	Mnemonic Mode
Guarded area transfer	1	GATM *	<del>?1</del>	DECCKM Cursor keys
Keyboard action	2	KAM	?2	DECANM ANSI
Control representation	3	CRM	?3	DECCOLMColumn
Insert/replace	4	IRM	?4	DECSCLMScrolling
Status reporting transfer	5	SRTM *	?5	DECSCNMScreen
. 0			?6	DECOM Origin
Vertical editing	7	VEM *	?7	DECAWM Autowrap
Horiz editing	10	HEM *	?8	DECARM Autorepeat
Positioning unit	11	PUM *		-
Send/receive	12	SRM		
Format effector action	13	FEAM *		
Format effector transfer	14	FETM *		
Multiple area transfer	15	MATM *		
Transfer termination	16	TTM *		
Selected area transfer	17	SATM *		
Tabulation stop	18	TSM *	?18	DECPFF Print form
Editing boundary	19	EBM *	?19	DECPEX Print extent
Linefeed/New line	20	LNM		
Text cursor enable			?25	DECTCEM
Right-to-left			?34	DECRLM
Hebrew keyboard map			?35	DECHEBM
Hebrew encoding			?36	DECHCEM
NRCS characters			?42	DECNRCM
Greek/N.A.			?57	DECNAKB
Horiz cursor coupling			?60	DECHCCM *
Vertical cursor coupling			?61	DECVCCM
Page cursor coupling			?64	DECPCCM
Numeric keypad			?66	DECNKM
Backarrow key			?67	DECBKM
Keyboard usage			?68	DECKBUM
Vertical split screen			?69	DECVSSM
Transmit rate limiting			?73	DECXRLMM
No clear screen			?95	DECNCSM
Right-to-left copy			?96	DECRLCM
CRT save			?97	DECCRTSM
Auto resize			?98	DECARSM
Modem control			?99	DECMCM
Auto answerback			?100	DECAAM
Conceal answerback			?101	DECCANSM
Null			?102	DECNULM
Half-duplex			?103	DECHDPXM
Enable secondary keyboard language			?104	DECESKM
Overscan			?106	DECOSCNM
Framed windows mode			?111	DECFWM
Review previous lines			?112	DECRPL
Host Wake-Up			?113	DECHWUM
Alternate text color underline			?114	DECATCUM
Alternate text color blink			?115	DECATCBM
Bold and blink style mode			?116	DECBBSM
Erase color mode			?117	DECECM

<sup>&</sup>lt;sup>4</sup>The \* means this mode is always Reset in the terminal and cannot be changed.

		Control I			
Terminal Mo	odes	VT520	VT420	VT100	Mnemonic
Report Mode	e (ANSI)	CSI <i>Pa; Ps</i> \$ y	same	n/a	DECRPM
or	(DEC)	CSI ? <i>Pd; Ps</i> \$ y	same	n/a	
Reset Mode		CSI <i>P1Pn</i> l	same	same	RM
Set/Reset	t Parameters	ANSI Mode		DEC 1	Mode
		$\underline{Ps}$			
Not recogn	nized	0		same	
Set		1		same	
Reset	_	2		same	
Set perma		3		same	
Reset per		4		same	
	eset Mode (See also DECRO	QM.)			SM/RM
Send/Receiv	e Mode (Local Echo)		same	same	SRM
	Set (Local echo off):	CSI 12 h			
	Reset (Local echo on):	CSI 12 l			
Tests					
Invoke Conf	idence Test <sup>5</sup>	CSI 4; <i>Ps</i> ;; <i>Ps</i> y	same	n/a	DECTST <sup>6</sup>
Ps	Test	, , , ,			
0	"All Tests" (1,2,3,6)				
1	Power-Up Self Test				
2	RS-232 Port Data Loopb	ack			
3	Printer Port Loopback				
4	Speed Select and Indicat	or			
5	Reserved - No action				
6	Modem Loopback Test				
7	EIA-423 Port Loopback				
8	Parallel Port Loopback				
9	Repeat other tests				
Messages					
Auto Answe	rhack Mode		same	same	DECAAM
. Ideo I III SWC	Set:	CSI ? 100 h	Sume	Same	
	Reset:	CSI ? 100 l			
Conceal Ans	swerback Message Mode	<del></del>	n/a	n/a	DECCANSM
	Set:	CSI ? 101 h			
	Reset:	CSI ? 101 l			
Load Answe	rback Message	DCS Ps v DD ST	n/a	n/a	DECLANS
Load Banne		DCS Ps r DD ST	n/a	n/a	DECLBAN
Ps1	Printer Port		<del>-</del>		
1	Parallel port				
2	Comm1				
3	Comm2				
Ps2	Session 1				
$\frac{1}{1}$	Comm1				
2	Comm2				

<sup>&</sup>lt;sup>5</sup>"ESC # 8" invokes the Screen Alignment test (all Es).

 $<sup>^6\</sup>mathrm{DECTST}$  causes a disconnect; therefore, it should not be used in conjunction with a modem.

	Cont	rol Function		
Reset Terminal	VT520	VT420	VT100	Mnemonic
Reset to Initial state Secure Reset Secure Reset Confirmation Soft Terminal Reset	ESC c ESC [ <i>Pr</i> + p ESC [ <i>Pr</i> * q CSI ! p	same same same	same n/a same n/a	RIS DECSR DECSRC DECSTR
Terminal Status Display				
Select Active Status Display  Ps Send data to  Main display only  Status line only	CSI Ps \$ }	same	n/a	DECSASD
$ \begin{array}{ccc} \text{Select Status Display (Line) Type} \\ \underline{Ps} & \underline{Status \ Line \ Selected} \\ \hline 0 & No \ status \ line \\ \hline \textbf{1} & \textbf{Indicator status line} \\ 2 & \text{Host-writable status line} \\ \end{array} $	CSI Ps \$ ~	n/a	n/a	DECSSDT

# 4.7.12 Terminal Management—Communications Control Functions

Terminal Ma	nagement –	Control	Function		
Communica	tion Function	VT520	VT420	VT100	Mnemonic
Select Comm	nunication Port Printer Port None	CSI <i>Ps1; Ps2</i> * u	n/a	n/a	DECSCP
1 4 <u>Ps2</u> 1 2	Centronics Comm3 Host port Comm1 Comm2				
3 Select Comm  Ps1 none,0,1 2 3 4 5	Comm3 nunication Speed Comm Line Host Transmit Host Receive Printer Modem Hi Modem Lo	CSI Ps1; Ps2 * r  Ps2 none,0  1  2  3  4  5  6  7  8  9  10  11		n/a nication Spe ult speed.	DECSCS eed
Communic Host Tran Host Rece Printer Modem H Modem Lo	ive i	Default Communic 9600 Receive=transmit 4800 Ignore Ignore	cation Speed		

Terminal Ma	nagement –		Control F	unction		
Communica	tion Function	VT520		VT420	VT100	Mnemonic
Set Port Par	rameters	CSI Ps1; Ps2,	: Ps3; Ps4 -	+ <b>w</b>		
				n/a	n/a	DECSPP
Ps1	Port		Ps3	Parity		
none,	<del></del>		$\overline{\mathbf{none}}, 0$			
0 or 1	Comm Port		or 1	No pari	ty	
2	Printer Port		2	Even		
			3	Odd		
Ps2	Data		<b>4</b> †	Even		
$\overline{1,0}$ or	8 bits		5†	Odd, und	checked	
none			6	Mark		
2	7 bits		7	Space		
Ps4	Stop Bit			•		
none,						
0 or 1	1 bit					
2	2 bits					
Set Transmi	t Rate Limit	CSI <i>Ps1;Ps2</i> '	' u	n/a	n/a	DECSTRL
Ps	Key Type					
none,						
0 or 1	All keys					
2	Graphic key					
3	Function key					
Ps	Characters Per Second					
$\overline{\mathbf{none}}, 0, 1$	150 cps					
2	50 cps					
3	30 cps					
Transmit Ra	te Limiting Mode			same	n/a	DECXRLM
	Set (limited):	CSI ? 73 h				
	Reset (unlimited):	CSI ? 73 l				

<sup>†</sup> Not available for the printer port. If specified in the sequence to configure the printer port, the Ps3 value is ignored.

# 4.7.13 Terminal Synchronization Control Functions

	Control Function					
Terminal Sy	nchronization	VT520		VT420	VT100	Mnemonic
Device Cont		DC1		same	same	
Device Cont	rol 3 (XOFF)	DC3		same	same	
Disconnect I  Ps 1 2 none,0,3	Delay Time Delay Time None 60 ms 2 s	CSI Ps \$ q		same	same	DECSDDT
Flow Contro	l	CSI Ps1; Ps2	: Ps3; Ps4	* s		
Ps1 none,0,1  2  Ps2 1,0 or none 2 3	Port Type Comm Port  Printer Port  Transmit or Receive  Transmit Receive Transmit and Receive		Ps3 none, 0 or 1 2 3 4 Ps4 none 0 or 1 2	XON/XO XPC (for DTR Both None	receive on	•
Half-Duplex	Mode Set: Reset:	CSI ? 103 h CSI ? 103 l		n/a	n/a	DECHDPXM
Modem Cont	trol Mode Set: <b>Reset:</b>	CSI ? 99 h CSI ? 99 l		n/a	n/a	DECMCM
Null Mode	Set (ignore NUL): Reset (accept NUL):	<b>CSI ? 102 h</b> CSI ? 102 l		n/a	n/a	DECNULM

### 4.7.14 Reports Control Functions

	Contr	Control Function			
Macros	VT520	VT420	VT100	Mnemonic	
Define Macro	DCS <i>Pid;Pdt;Pen</i> ! z	<i>DD</i> ST			
		same	n/a	DECDMAC	
DSR - Macro Space	CSI ? 62 n	same	n/a	DSR-MSR	
Invoke Macro	CSI <i>Pid</i> * z	same	n/a	DECINVM	
Macro Space Report	CSI Pn * {	same	n/a	DECMSR, DSR-MSR	
$Pn = \frac{number\ of\ bytes}{16}$					
Reports					
Device Status Report – ANSI:	CSI <i>Ps</i> n	same	same	DSR	
- DEC:	CSI ? Ps n	same	same	DSR	
DSR - Data Integrity Report	CSI ? 75 n	same	n/a	DSR-Data	
Response:	CSI ? Ps n				
Ps Meaning					
$\overline{70}$ Ready, no power loss of	r				
comm errors.					
71 Malfunction, comm err	ror.				
73 No reported data loss					
since last power up.					
Memory Checksum Report or DSR- Memory Checksum	CSI ? 63; <i>Pid</i> n	same	n/a	DECCKSR or DSR-Mem	
Response:	DCS <i>Pid</i> ! ~ <i>DD</i> ST	Γ		DSR-Meili	
Request Checksum of Rect Area	CSI <i>Pid;Pp;Pt;Pl;Pb;</i> i	Pr * v			
request enconsum of rect rica	001 1 Id,1 p,1 t,1 1,1 b,1	same	n/a	DECRQCRA	
Response:	DCS <i>Pid</i> ! ~ <i>DD</i> ST	Γ		·	
Presentation State Report		n/a	n/a	DECPSR	
(See DECRQPSR.)					
Report Mode (DECRPM)		same	n/a	DECRPM	
(See Report Mode (ANSI) below.)					
Request Mode (ANSI)	CSI <i>Pa</i> \$ p	same	n/a	$DECRQM^1$	
Request Mode (DEC)	CSI ? <i>Pd</i> \$ p	same	n/a	DECRQM	
Request Presentation State Report	CSI Ps \$ w	same	n/a	DECRQPSR	
Ps Report Requested					
Terror, restore ignored.					
1 Cursor information re					
2 Tab stop report (DECT	CABSR)				

 $<sup>^{1}</sup>$ A DECRQM sequence can only ask about one mode at a time. When the terminal is set to VT52 mode, DECRQM provides no report.

		Co	ntrol Function		
Reports	VT	520	VT420	VT100	Mnemonic
Report Sele	ection or Setting		same	n/a	DECRPSS
	ECRQSS.)				
Request Se	election or Setting		same	n/a	DECRQSS
		CS \$ q <i>DD</i> ST			
	Report (DECRPSS): DC	CS <i>Ps</i> \$ r <i>DD</i> S	ST		
	Setting Control Sequence	<u>Fina</u>	l Characters		Mnemonic
	Assign Color	,			DECAC
	Alternate Text Color	, }			DECATC
	Select Active Status Display	\$ }			DECSASD
	Select Attribute Change Exter	* x			DECSACE
	Set Character Attribute	" q			DECSCA
	Set Columns Per Page	\$			DECSCPP
	Select Communication Speed	* r			DECSCS
	Select Communication Port	* u			DECSCP
	Set Conformance Level	" p			DECSCL
	Set Cursor Style	SP o	İ		DECSCUSR
	Select Digital Printed Data Ty		-		DECSDPT
	Select Disconnect Delay Time	\$ q			DECSDDT
	Select Flow Control Type	* S			DECSFC
	Set Graphic Rendition	m			SGR
	Set Key Click Volume	SP r			DECSKCV
	Set Left and Right Margins	S			DECSLRM
	Set Lines Per Page	t			DECSLPP
	Set Lock Key Style	SP v	7		DECSLCK
	Set Margin Bell Volume	SP u			DECSMBV
	Set Number of Lines per Scree		•		DECSNLS
	Session Page Memory Allocation				DECSPMA
	Set Port Parameter	+ W			DECSPP
	Select Printer Type	\$ s			DECSPRTT
	Select ProPrinter Character Se				DECSPPCS
	Set Scroll Speed	SP p	,		DECSSCLS
	Select Set-Up Language	р	,		DECSSL
	Set Status Line Type	Р \$ ~			DECSSDT
	Set Top and Bottom Margins	r			DECSTBM
	Set Transmit Rate Limit	" u			DECSTRL
	Set Warning Bell Volume	SP t			DECSTRE
	Select Zero Symbol	, {			DECSWBV
Request To	rminal State Report		same	n/a	DECRQTSR
request 16		I 1 \$ u	Same	11/ Cl	DECRAISK
		CS 1 \$ s <i>DD</i> ST	r		
	Effects	.5 1	L		
DDD1	DECRLM, DECHEBM, and DECHCEM are set. <sup>2</sup>				DDD1
DDD2	DECRLM is reset.				DDD2
DDD:	ASCII is designated in G1.				DDD?
DDD3	ASCII is designated in G0.				DDD3

<sup>&</sup>lt;sup>2</sup> DDD1, DDD2, and DDD3 only work in VT100 mode when the Hebrew keyboard is selected.

		Contro	Function	Control Function			
Reports		VT520	VT420	VT100	Mnemonic		
Restore Pre	esentation State	DCS Ps \$ t DD ST	same	n/a	DECRSPS		
Ps	Data String Format						
0	Error, restore ignored.						
1	Selects the format of the cursor information report (DECCIR).						
2	Selects the format of the tab stop report (DECTABSR).						
DD	Data string of tab stops or cursor position.						
Color Table	Request/Report/Restore		n/a	n/a	DECCTR		
<i>DD</i>	Request: Reply to Host: Restore format: A group of 5 parameters:	CSI 2 ; <i>Pu</i> \$ u DCS 2 \$ s <i>DD</i> ST DCS 2 \$ p <i>DD</i> ST					
Pc	Pc; Pu; Px; Py; Pz/ Color number 0-255						
$\frac{Pu}{0}$	Color coordinate system						
0	illegal						
1	HLS (hue, lightness, satur	ration)					
2	RGB (red, green, blue)						
Px	<u>If <i>Pu</i>=1</u> <u>Hue 0-360</u>	If <i>Pu</i> =2 Red 0-100					
Py Pz	Lightness 0-100; Saturation 0-100;	Green 0-100 Blue 0-100					
PZ	Saturation 0-100;	Diue 0-100					
Restore Ter	minal State	DCS Ps \$ p DD ST	same	n/a	DECRSTS		
Ps	Data String Format						
0	Error, restore ignored.						
1	Selects the format of the						
	terminal state report (DECTSR).						
<i>DD</i>	Data string of restored information.						
Tabulation	Stop Report	DCS @ \$ u <i>DD</i> ST	same	n/a	DECTABSR		
DD	Column numbers of tab st	ops.					
Terminal S	tate Report (See DECRQTSR	.)	same	n/a	DECTSR		

# 4.8 VT52 Mode Escape Sequences

Table 4–5 shows the escape sequences that the terminal recognizes when the VT52 Emulation Mode is selected.

Table 4-5 VT52 Mode Escape Sequences

Sequence	Action
ESC A	Cursor up.
ESC B	Cursor down.
ESC C	Cursor right.
ESC D	Cursor left.
ESC F	Enter graphics mode.
ESC G	Exit graphics mode.
ESC H	Move the cursor to the home position.
ESC I	Reverse line feed.
ESC J	Erase from the cursor to the end of the screen.
ESC K	Erase from the cursor to the end of the line.
ESC =	Enter alternate keypad mode.
ESC >	Exit alternate keypad mode.
ESC <	Exit VT52 mode.
ESC ^	Enter autoprint mode.
ESC _	Exit autoprint mode.
ESC V	Print the line with the cursor.
ESC W	Enter printer controller mode.
ESC X	Exit printer controller mode.
ESC ]	Print the screen.
ESC Y Pn	Move the cursor to column <i>Pn</i> .
ESC Z	Identify (host to terminal).
ESC / Z	Report (terminal to host).

# **ANSI Control Functions**

This chapter describes the ANSI escape and control sequences in detail, whereas the previous chapter provides only a brief summary of these sequences.

Each command in this chapter is formatted in such a way that you can refer to the command by either the mnemonic, name, or control function.

#### **ANSI Conformance Levels**

This control function lets an application map certain character sets into the terminal's in-use table as default sets. The character sets are based on ANSI conformance levels.

#### **Format**

#### **Parameters**

indicates the ANSI conformance level for the subsequent data exchange.

Final	ANSI Conformance Level
L	Level 1
M	Level 2
N	Level 3

#### **Description**

ANSI conformance levels represent an agreement between the sender and receiver for compatible data exchange. The control function:

- 1. Acts as an *announcer* for the data exchange that follows between the terminal and application software.
- 2. Selects which character sets the terminal uses by default in the data exchange.

#### **ANSI Conformance Levels**

The VT520 supports three ANSI conformance levels.

#### **ANSI Levels 1 and 2**

- ASCII designated as G0.
- ISO Latin-1 supplemental designated as G1.
- G0 mapped into GL.
- G1 mapped into GR.

#### **ANSI Level 3**

- ASCII designated as G0.
- G0 mapped into GL.

#### **Notes**

- If the terminal is reset, turned off, or changed with a set conformance level (DECSCL) sequence, then the software must send another announcer sequence to the terminal. Otherwise, the terminal uses the default character sets (ASCII in GL, DEC Supplemental or ISO Latin-1 supplemental in GR).
- The announcer sequence is available in VT Level 4 or higher modes only.
- Do not confuse ANSI conformance levels with VT Levels.

### **CBT—Cursor Backward Tabulation**

Move the active position n tabs backward.

Default: 1.

#### **Format**

#### **Parameters**

#### Pn

is the number of active position tabs to move backward.

#### **Description**

The active position is moved to the character position corresponding to the n-th preceding horizontal tabulation stop. If an attempt is made to move the active position past the first character position on the line, then the active position stays at column one.

#### **CHA—Cursor Horizontal Absolute**

Move the active position to the n-th character of the active line.

Default: 1.

#### **Format**

#### **Parameters**

#### Pn

is the number of active positions to the n-th character of the active line.

#### **Description**

The active position is moved to the n-th character position of the active line.

### **CHT—Cursor Horizontal Forward Tabulation**

Move the active position n tabs forward.

Default: 1.

#### **Format**

#### **Parameters**

#### Pn

is the number of active position tabs to move forward.

#### **Description**

The active position is moved to the character position corresponding to the following n-th horizontal tabulation stop.

#### **CNL—Cursor Next Line**

Move the cursor to the next line.

Default: 1.

#### **Format**

#### **Parameters**

#### Pn

is the active position to the first character of the n-th following line.

# **Description**

The active position is moved to the first character of the n-th following line.

# **CPL—Cursor Previous Line**

Move the cursor to the preceding line.

Default: 1.

#### **Format**

#### **Parameters**

Pn

is the number of active position moved to the first character of the n-th preceding line.

### **Description**

The active position is moved to the first character of the n-th preceding line.

# **CPR—Cursor Position Report**

The host asks the terminal for a cursor position report.

#### **Format**

CSI6nRequest cursor position.9/11
$$3/6$$
 $6/14$ Request cursor position.CSIPI;PcR9/11 $3/n$  $3/11$  $3/n$  $5/2$ Report cursor position.

#### **Parameters**

indicates what line the cursor is on.

Рс

indicates what column the cursor is at.

#### CRM—Show Control Character Mode

Enable or disable control characters to be displayed.

**Default:** Interpret

#### **Format**

```
CSI
        3
               h
                      Set: show control character.
        3/3
               6/8
9/11
CSI
        3
                       Reset: interpret control character.
9/11
        3/3
```

#### **Description**

When CRM mode is set, all characters (graphic or control) are displayed in the CRM font. All control functions are displayed as graphic characters. No control functions are executed, except LF, FF, and VT, which are represented in the CRM font before a CRLF (new line) is executed. XOFF (DC3) and XON (DC1) are used for flow control (if enabled). DC1 and DC3 are displayed after execution.

This function affects data received in the data stream following the change to CRM mode. Characters already displayed are not affected. Entering Control Representation mode temporarily causes G0 and GL to be loaded with ASCII. G2 and GR are loaded with user-selected Supplemental Graphic characters if in 8-bit Multinational Character mode.

#### Notes on CRM

- CRM mode works in all terminal modes (VT52, VT100, and VT500).
- NUL is displayed and is not useful as a fill character.
- CRM mode overrides Printer Controller mode. When in CRM, Printer Controller mode is temporarily off.
- In local mode and CRM (or local echo and CRM), ESC Fe sequences may be represented as either ESC Fe sequences or as C1 controls. Conversely, C1 controls may be represented as either C1 controls or as ESC Fe sequences.
- In CRM mode, auto-wrap always occurs at the right margin. Sending a sequence or disabling auto-wrap in Set-Up is ignored.
- Terminal Device Protocol commands are not affected if Control Representation mode is entered.

#### **CUB—Cursor Backward**

This control function moves the cursor to the left by a specified number of columns. The cursor stops at the left border of the page.

#### **Format**

#### **Parameters**

#### Pn

is the number of columns to move the cursor to the left.

#### **CUD—Cursor Down**

This control function moves the cursor down a specified number of lines in the same column. The cursor stops at the bottom margin. If the cursor is already below the bottom margin, then the cursor stops at the bottom line.

#### **Format**

#### **Parameters**

#### Pn

is the number of lines to move the cursor down.

#### **CUF—Cursor Forward**

This control function moves the cursor to the right by a specified number of columns. The cursor stops at the right border of the page.

#### **Format**

#### **Parameters**

is the number of columns to move the cursor to the right.

#### **CUP—Cursor Position**

This control function moves the cursor to the specified line and column. The starting point for lines and columns depends on the setting of origin mode (DECOM). CUP applies only to the current page.

#### **Format**

#### **Parameters**

is the number of the line to move to. If Pl is 0 or 1, then the cursor moves to line 1.

Pc

is the number of the column to move to. If Pc is 0 or 1, then the cursor moves to column 1.

# **CUU—Cursor Up**

Moves the cursor up a specified number of lines in the same column. The cursor stops at the top margin. If the cursor is already above the top margin, then the cursor stops at the top line.

#### **Format**

#### **Parameters**

is the number of lines to move the cursor up.

# **DA1—Primary Device Attributes**

In this DA exchange, the host asks for the terminal's architectural class and basic attributes.

#### **Host Request**

The host uses the following sequence to send this request:

#### Terminal Response

The terminal responds by sending its architectural class and basic attributes to the host. This response depends on the terminal's current operating VT level.

#### **Response from VT520**

#### **Parameters**

Ps1; ... Psn

reports device attributes.

The value of the first parameter is encoded so a simple range check can be performed to determine the basic service class and level of the device. VT520 is a level 5 terminal so its service class code is 65. The following extensions to levels 4 and 5 are provided:

# **DA1—Primary Device Attributes**

Ps	Meaning
1	132 columns
2	Printer port
6	Selective erase
7	Soft character set (DRCS)
8	User-defined keys (UDKs)
9	National replacement character sets (NRCS)
12	Serbo-Croatian (SCS)
15	Technical character set
18	Windowing capability
19	Sessions
21	Horizontal scrolling
22	Color
23	Greek
24	Turkish
42	ISO Latin-2
44	PCTerm
45	Soft key mapping
46	ASCII terminal emulation

# **Primary DA Example**

Here is a typical primary DA exchange.

Exchange	Sequence	Meaning
Request (Host to VT520)	CSI c or CSI 0 c	The host asks for the terminal's architectural class code and supported extensions.
Response (VT520 to host)	CSI ? 65; 1; 2; 7; 9; 12; 18; 19; 21; 23; 24; 42; 44; 45; 46 c	The terminal is a level 5 device (65) and supports the Ps parameters listed above. The DA1 response above is used when the "Terminal ID to host" is set to VT520 and the conformance level is set to Level 5 (factory default). Extensions: 6 (selective erase); 8 (UDK); and 15 (technical character set) are not reported explicitly at Level 5.

# **DA2—Secondary Device Attributes**

In this DA exchange, the host requests the terminal's identification code, firmware version level, and hardware options.

#### **Host Request**

The host uses the following sequence to send this request:

#### **Terminal Response**

The terminal with a VT keyboard uses the following sequence to respond:

					DA2R for terminal with STD keyboard.
<b>&gt;</b> 3/14		•	•		DA2R for terminal with PC keyboard.

#### **Parameters**

#### 64

indicates the identification code for the terminal. The VT520 has an identification code of 64 (65 for color terminal).

#### Pv

indicates the version level of the firmware implementing the terminal management functions, as shown in the following table.

Pv	Version	
10	V1.0 (released version 1.0)	
20	V2.0 (released version 2.0)	

# **Secondary DA Example**

The following is a typical secondary DA exchange:

Exchange	Sequence	Meaning
Request (Host to VT520)	CSI > c or CSI > 0 c	The host asks for the terminal's identification, firmware version, current hardware options.
Response (VT520 to host)	CSI > 64; 20; 1 c	The terminal identifies itself as a VT520 that uses version 2.0 firmware, and has a PC keyboard option.

# **DA3—Tertiary Device Attributes**

In this DA exchange, the host asks for the terminal unit identification code. This ID code serves as a way to identify each terminal in a system. The unit ID code is preset at the factory.

#### **Host Request**

The host uses the following sequence to send this request:

#### **Terminal Response**

The terminal responds by sending a report terminal unit ID (DECRPTUI) control string to the host.

Available in: VT Level 4 or higher mode only.

#### **Parameters**

#### D....C

is the unit ID of the terminal, consisting of four hexadecimal pairs. The first pair represents the manufacturing site code. This code can be any hexadecimal value from 00 through FF.

The last three hexadecimal pairs are the terminal ID number. This number is unique for each terminal manufactured at that site.

#### Tertiary DA Example

Here is a typical tertiary DA exchange.

Exchange	Sequence	Meaning	
Request (Host to Terminal)	CSI = c or CSI = 0 c	The host asks for the terminal unit ID.	
DECRPTUI Response (Terminal to host)	DCS!   00 01 02 05 ST	The terminal was manufactured at site 00 and has a unique ID number of 010205.	

# **DCH**—Delete Character

This control function deletes one or more characters from the cursor position to the right.

#### **Format**

#### **Parameters**

#### Pn

is the number of characters to delete. If Pn is greater than the number of characters between the cursor and the right margin, then DCH only deletes the remaining characters.

Default: Pn = 1.

# **Description**

As characters are deleted, the remaining characters between the cursor and right margin move to the left. Character attributes move with the characters. The terminal adds blank spaces with no visual character attributes at the right margin. DCH has no effect outside the scrolling margins.

# DDD1, DDD2, DDD3

DDD2 and DDD3 only work in  $VT100\ mode$  when the Hebrew keyboard, DDD1, is selected.

# **Format**

# **Description**

These escape sequences have the follow effects:

Escape Sequence	Effect
DDD1	DECRLM is set. DECHEBM is set. DECHEM is set
DDD2	DECRLM is reset. ASCII is designated in G1.
DDD3	ASCII is designated in G0.

# **DECAAM—Set/Reset Auto Answerback Mode**

Selects whether the terminal automatically sends (enables) or does not send (disables) the answerback message to the host computer after a communication line connection.

**Default:** Auto answerback disabled.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>0</b> 3/0	<b>h</b> 6/8	Set: enables auto answerback.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>0</b> 3/0	I 6/12	Reset: disables auto answerback.

### **Description**

When modem control is enabled, the answerback message is sent 500 ms after the connection is made.

# **DECAC—Assign Color**

Selects the colors used for normal text.

**Default:** ANSI SGR color

#### **Format**

#### **Parameters**

Ps1 Item

Ps1	Color Item
1	Normal text
2	Window frame

#### Ps2

 $Foreground\ color\ index$ 

0...15

#### Ps3

Background color index

0...15

#### **Description**

DECAC selects the foreground and background colors used for normal text in ANSI SGR color mode and the window frame colors. The normal text colors are used in ANSI SGR color mode as the default foreground and background colors. The window frame foreground color is also used for the session icons and keyboard indicator line.

DECAC can be reported using DECRQSS and DECRPSS. Use  $\bf Ps1$  in DECRQSS to select the item to be reported.

# **DECALN—Screen Alignment Pattern**

This control function fills the complete screen area with a test pattern used for adjusting screen alignment. Normally, only manufacturing and service personnel would use DECALN.

#### **Format**

#### **Notes on DECALN**

DECALN sets the margins to the extremes of the page, and moves the cursor to the home position.

Also see the screen alignment in Chapter 2.

# **DECANM—ANSI Mode**

DECANM changes the terminal to the VT52 mode of operation. In VT52 mode, the terminal acts like a VT52 terminal. This mode lets you use applications designed for the VT52 terminal.

#### **Format**

**CSI** ? **2 I** 9/11 3/15 3/2 6/12

# **Description**

Table 5-1 VT52 Escape Sequences

Sequence	Action
ESC A	Cursor up.
ESC B	Cursor down.
ESC C	Cursor right.
ESC D	Cursor left.
ESC F	Enter graphics mode.
ESC G	Exit graphics mode.
ESC H	Cursor to home position.
ESC I	Reverse line feed.
ESC J	Erase from cursor to end of screen.
ESC K	Erase from cursor to end of line.
ESC Y Pn	Move cursor to column Pn.
ESC Z	Identify (host to terminal).
ESC /Z	Report (terminal to host).
ESC =	Enter alternate keypad mode.
ESC >	Exit alternate keypad mode.
ESC <	Exit VT52 mode. Enter VT100 mode.
ESC ^	Enter autoprint mode.
ESC _	Exit autoprint mode.
ESC W	Enter printer controller mode.
ESC X	Exit printer controller mode.
ESC ]	Print screen.
ESC V	Print the line with the cursor.

# **DECANM Exit—Exiting ANSI (VT52) Mode**

When the terminal exits VT52 mode, it returns to the previous mode before entering VT52 mode. The terminal exits VT52 mode with the following escape sequence:

#### **Format**

# **DECARM**—Autorepeat Mode

This control function determines whether or not keys automatically repeat their character when held down. If DECARM is set, then most keys you press for more than 0.5 seconds send a character repeatedly until you release the key.

**Default:** Repeat (set)

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>8</b> 3/8	<b>h</b> 6/8	Set: keys autorepeat when pressed for more than 0.5 seconds.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>8</b> 3/8	<b>I</b> 6/12	Reset: keys do not autorepeat.

#### **Notes on DECARM**

• The following keys on the VT keyboard do not repeat:

F1 (Hold)	F5 (Break)	Return
F2 (Print)	Compose Character	Lock
F3 (Set-Up)	Shift	Ctrl
F4 (Session)	Alt Function	Extend

• The following keys on the PC keyboard do not repeat:



# **DECARR—Select Auto Repeat Rate**

# **DECARR—Select Auto Repeat Rate**

Controls the keystroke auto repeat rate.

**Default:** Fast (30/sec)

#### **Format**

#### **Parameters**

#### Ps

**Auto Repeat Rate** 

Ps	Selection	
05	Off	
615	Slow (10 cps)	
1630	Fast (30 cps)	

# **Description**

DECARR controls the keystroke auto-repeat rate. Values for  $\bf Ps$  outside the defined range are ignored.

DECARR can be reported using DECRPSS.

#### **DECARSM—Set/Reset Auto Resize Mode**

Enable or disable changing the lines per screen automatically when the page arrangement changes.

**Default:** Auto resize disabled

#### **Format**

	<b>?</b> 3/15			Set: enable auto resize.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>8</b> 3/8	<b>I</b> 6/12	Reset: disable auto resize.

# **Description**

When **Auto Resize** is enabled, the number of Lines/Screen changes automatically each time the page arrangement changes.

**Auto Resize** and **Number of lines per screen** are user features that can be locked from being redefined by the host if the **User Feature Lock** in Set-Up is enabled.

The following table indicates how the lines/screen changes when the page size changes, assuming **Auto Resize** is set.

Page size	Lines/Screen					
24	26 (24 data lines, 1 status line, 1 blank line)					
25	26 (25 data lines, 1 status line)					
36	42 (36 data lines, 1 status line, 5 blank lines)					
41	42 (41 data lines, 1 status line)					
42	42 (42 data lines, no status line)					
48	53 (48 data lines, 1 status line, 4 blank lines)					
52	53 (52 data lines, 1 status line)					
53	53 (53 data lines, 0 status line)					
72	53 (53 data lines, 0 status line)					

# **DECATC**—Alternate Text Color

Selects the colors used for text attribute combinations.

#### **Format**

#### **Parameters**

**Ps1** Attribute combinations

Ps1	Attributes
0	Normal text
1	Bold
2	Reverse
3	Underline
4	Blink
5	Bold reverse
6	Bold underline
7	Bold blink
8	Reverse underline
9	Reverse blink
10	Underline blink
11	Bold reverse underline
12	Bold reverse blink
13	Bold underline blink
14	Reverse underline blink
15	Bold reverse underline blink

#### Ps2

Foreground color index 0...15

. .

#### Ps3

Background color index 0...15

# **Description**

DECATC can be reported using DECRQSS and DECRPSS. Use **Ps1** in DECRQSS to select the attribute combination to be reported.

#### **DECATCBM—Set/Reset Alternate Text Color Blink Mode**

Allows text with blink attributes to blink.

#### **Format**

#### **Description**

If **blink text** is selected, text with the blink attribute will blink, as well as displayed using the specified alternate text colors. See **Alternate Text Colors** in Set-Up for details.

DECATCBM can be reported using DECRQM and DECRPM.

#### DECATCUM—Set/Reset Alternate Text Color Underline Mode

Allows text with underline attributes to be displayed in alternate color.

#### **Format**

### Description

If **underline text** is selected, text with the underline attribute will be underlined, as well as displayed using the specified alternate text colors. See **Alternate Text Colors** in Set-Up for details.

DECATCUM can be reported using DECRQM and DECRPM.

# **DECAUPSS—Assigning User-Preferred Supplemental Sets**

You can assign the supplemental character set you use most often as a special standby set. This standby set is called the user-preferred supplemental set. This feature provides applications with an easy way to access the user's preferred supplemental set.

**Default:** DEC Supplemental Graphic

#### **Format**

DCS	Pn	!	u	Dscs	ST
9/0	3/n	2/1	7/5	3/n	9/12

#### **Parameters**

#### Pn

represents a character set designator.

Pn	Meaning
0	DEC, ISO Latin-1, ISO Latin-2
1	ISO Latin-5, ISO Latin-7, ISO Cyrillic, ISO Hebrew

#### **Dscs**

represents a character set.

Dscs	Character Set
% 5	DEC Supplemental
"?	DEC Greek
" 4	DEC Hebrew
% <b>0</b>	DEC Turkish
& 4	DEC Cyrillic
<	User-preferred Supplemental
A	ISO Latin-1 Supplemental
В	ISO Latin-2 Supplemental
F	ISO Greek Supplemental
Н	ISO Hebrew Supplemental
M	ISO Latin-5 Supplemental
L	ISO Latin-Cyrillic

#### **Description**

You can assign any supplemental or ISO Latin supplemental set as the standby set. See SCS—Select Character Set for more information.

After you assign a set:

- 1. Designate the set as G1, G2, or G3.
- 2. Map the set into GR.

# **DECAWM—Autowrap Mode**

This control function determines whether or not received characters automatically wrap to the next line when the cursor reaches the right border of a page in page memory.

**Default:** No autowrap

#### **Format**

#### **Description**

If the DECAWM function is set, then graphic characters received when the cursor is at the right border of the page appear at the beginning of the next line. Any text on the page scrolls up if the cursor is at the end of the scrolling region.

If the DECAWM function is reset, then graphic characters received when the cursor is at the right border of the page replace any previous characters there.

# **DECBBSM—Bold and Blink Style Mode**

Selects whether the bold and blink attributes affect the text foreground only or both the foreground and background.

#### **Format**

#### **Description**

This setting selects whether the bold and blink attributes affect the text foreground only, or both foreground and background. See the Set-Up chapter for details.

DECBBSM can be reported using DECRQM and DECRPM.

#### **DECBI—Back Index**

This control function moves the cursor backward one column. If the cursor is at the left margin, then all screen data within the margin moves one column to the right. The column that shifted past the right margin is lost.

Available in: VT Level 4 or higher mode only

#### **Format**

#### **Description**

DECBI adds a new column at the left margin with no visual attributes. DECBI is not affected by the margins. If the cursor is at the left border of the page when the terminal receives DECBI, then the terminal ignores DECBI.

# **DECBKM—Backarrow Key Mode**

This control function determines whether the  $\triangleleft$  key works as a backspace key or delete key.

To be compatible with some software, DECBKM should be reset (delete key setting).

**Default:** Delete key

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>7</b> 3/7	<b>h</b> 6/8	Set: backspace key.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>7</b> 3/7	I 6/12	Reset: delete key.

#### Description

If DECBKM is set,  $\leq \mathbb{X}$  works as a backspace key. When you press  $\leq \mathbb{X}$ , the terminal sends a BS character to the host.

If DECBKM is reset,  $\leq \mathbb{Z}$  works as a delete key. When you press  $\leq \mathbb{Z}$ , the terminal sends a DEL character to the host.

# **DECCANSM—Conceal Answerback Message Mode**

Conceal the answerback message.

**Default:** Answerback message is not concealed

## **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1		<b>1</b> 3/1	<b>h</b> 6/8	Conceal answerback message
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>1</b> 3/1	<b>I</b> 6/12	Answerback message is not concealed

## **Description**

Setting	Function
Not concealed	The answerback message is visible in Set-Up.
Concealed	The text "concealed" replaces the answerback message.
	The answerback message cannot be set back to "not concealed" either through a host control function or Set-Up. Only entering a new message returns this field to "not concealed."
	If the user or host requests the terminal to reset to the default setting (answerback message not concealed (CSI ? 101 l)) when the answerback message is set to "concealed," then the terminal will not reset the answerback message to "not concealed."

## **DECCAPSLK—Caps Lock Mode**

DECCAPSLK controls the CapsLock state of the keyboard as if the CapsLock key had been pressed.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>9</b> 3/9	<b>h</b> 6/8	Set: Lock on.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>9</b> 3/9	<b>I</b> 6/12	Reset: Lock off.

## **DECCARA—Change Attributes in Rectangular Area**

This control function lets you change the visual character attributes (bold, blink, reverse video, and underline) of a specified rectangular area in page memory. The select attribute change extent (DECSACE) control function determines the stream or rectangular area. DECCARA does not change the values of characters just the visual attributes of those characters.

**Available in:** VT Level 4 or higher mode only

#### **Format**

CSI	Pt; Pl; Pb; Pr;	Ps1; Psn	\$	r
9/11	area to be changed	attributes to change	2/4	7/2

### **Parameters**

#### Pt; Pl; Pb; Pr;

define the rectangular area to be changed. A semicolon (3/11) separates parameters.

#### Pt

is the top-line border. Pt must be less than or equal to Pb. Default: Pt = 1.

#### **P1**

is the left-column border. Pl must be less than or equal to Pr. Default: Pl = 1.

#### Pb

is the bottom-line border.

Default: Pb = last line of the active page.

#### Pr

is the right-column border.

Default: Pr = last column of the active page.

#### Ps1; . . . Psn

select the visual character attributes to change. These values correspond to the values used in the select graphic rendition.

## **DECCARA—Change Attributes in Rectangular Area**

Psn	Meaning			
0	Attributes off (no bold, no underline, no blink, positive image)			
(default)	•			
1	Bold			
4	Underline			
5	Blink			
7	Negative image			
22	No bold			
24	No underline			
25	No blink			
27	Positive image			

DECCARA ignores all other parameter values. When you use more than one parameter in a command, DECCARA executes them cumulatively in sequence.

## **Examples**

The following sequence changes the video attributes of the complete screen to blink and underscore:

```
CSI;;;;0;4;5;$r
```

The following sequence turns off the blinking character attribute from position line 10, column 2 to position line 14, column 45 on the current page:

```
CSI 10; 2; 14; 45; 25 $ r
```

#### **Notes on DECCARA**

- The coordinates of the rectangular area are affected by the setting of origin mode (DECOM).
- DECCARA is not affected by the page margins.
- If the value of *Pt, Pl, Pb,* or *Pr* exceeds the width or height of the active page, then the value is treated as the width or height of that page.
- DECCARA does not change the active cursor position.
- DECCARA does not change the current rendition set by the select graphic rendition (SGR) function.
- The exact character positions affected by DECCARA depend on the current setting of the select attribute change extent (DECSACE) function.

## **DECCIR—Cursor Information Report (Terminal to Host)**

## **DECCIR—Cursor Information Report (Terminal to Host)**

The terminal sends this sequence in response to a request presentation state report (DECRQPSR) sequence. DECCIR reports the status of the cursor position, including visual attributes and character protection attributes. DECCIR also reports the status of origin mode (DECOM) and the current active character sets.

### **Format**

## **Description**

DECCIR reports all the character sets if they are assigned to one of the G0, G1, G2, or G3 sets. Refer to SCS—Select Character Set for all character set designators.

## **DECCKD—Copy Key Default**

Copies the default states of a key and its key/modifier combination to another key and its key/modifier combination.

#### **Format**

```
DCS " z D...D ST 9/0 2/2 7/10 D...D 9/12
```

## **Description**

This control function copies the default states of a key and all its modifier combinations to another key and its modifier combinations. The source key may have been reprogrammed to perform a non-default function when copy operation is executed. Only the default states of the source key are copied.

The source key and the destination key can be two different keys or the same key. If they are different keys, then the copy operation occupies the memory space that is reserved for the operations of control functions, DECPFK, DECPAK, and DECUDK and their equivalent functions in Set-Up. (Refer to DECPFK—Program Function Key for details.) If they are the same key, then the function of the copy operation is to restore the key's default. In this state, the terminal does not allocate new memory space. The terminal frees up the space by deleting the non-default functions of the destination key and its modifier combinations.

A function key can copy the default state from a function key or a graphic key. When a graphic key's default is copied, the function key operates as a graphic key. Only the modifiers that are suitable for a graphic key operate with the key. This logic is used when a graphic key copies the default from a function key.

Multiple keys can be copied in one sequence.

The data string D...D format is:

```
Key-s/Key-d;Key-s/Key-d....;
```

#### Where:

- Key-s is the keystation number of the key to be copied.
- Key-d is the keystation number of the destination key.

Once programmed, the key states are not affected by the terminal mode changes. Refer to DECPFK—Program Function Key for the list of terminal mode changes.

This function works in all the VT modes except in VT52 mode.

## **DECCKM—Cursor Keys Mode**

This control function selects the sequences the arrow keys send. You can use the four arrow keys to move the cursor through the current page or to send special application commands.

**Default:** Cursor

### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>h</b> 6/8	Set: application sequences.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>I</b> 6/12	Reset: cursor sequences.

## **Description**

If the DECCKM function is set, then the arrow keys send application sequences to the host.

If the DECCKM function is reset, then the arrow keys send ANSI cursor sequences to the host.

## **DECCKSR—Memory Checksum Report**

The host asks for a memory checksum report of current text macro definitions.

### **Programming Tip**

Enter your macro definitions, then request and save a memory checksum. After this procedure, you can request another checksum to determine if the checksum has changed.

#### **Format**

#### **Parameters**

## Pid (request)

is an optional numeric parameter that provides a label to identify the particular checksum request. The checksum report returns the label. This label lets you distinguish between multiple checksum reports.

#### Pid (response)

is a label indicating which DSR request the report is for.

### D . . . D

is the data string consisting of four hexadecimal digits indicating the checksum. The digits can be in the range of 3/0 through 3/9 and 4/0 through 4/6.

## **DECCOLM—Selecting 80 or 132 Columns per Page**

There are two control functions that can set the page width to 80 or 132 columns, DECSCPP (DECSCPP—Select Columns Per Page ) and DECCOLM.

\_\_\_\_\_ NOTE \_\_\_\_\_

It is recommended that new applications use DECSCPP rather than DECCOLM. DECCOLM resets the cursor position to 1;1. DECSCPP does not clear page memory or reset the scrolling regions, as does DECCOLM. If DECNCSM is set, the page is not erased by DECCOLM. DECCOLM is provided mainly for compatibility with previous products.

**Default:** 80 columns

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	-	<b>h</b> 6/8	Set: 132-column font.
•••	<b>?</b> 3/15	•	I 6/12	Reset: 80-column font.

#### Notes on DECCOLM

- DECCOLM sets the number of columns on the page to 80 or 132 and selects the corresponding 80- or 132-column font.
- If you change the DECCOLM setting, the terminal:
  - Sets the left, right, top and bottom scrolling margins to their default positions.
  - Erases all data in page memory, unless DECNCSM is set; then, the page is not erased.
- DECCOLM resets vertical split screen mode (DECLRMM) to unavailable.
- DECCOLM clears data from the status line if the status line is set to host-writable.

## **DECCRA—Copy Rectangular Area**

This control function copies a rectangular area of characters from one section to another in page memory. The copied text retains its character values and attributes.

Available in: VT Level 4 or higher mode only

#### **Format**

```
CSI Pts; Pls; Pbs; Prs; Pps; Ptd; Pld; Ppd $ v 9/11 area to be copied destination 2/4 7/6
```

#### **Parameters**

#### Pts; Pls; Pbs; Prs; Pps;

define the rectangular area to be copied (the source). A semicolon (3/11) separates parameters.

#### Pts

is the top-line border. Pts must be less than or equal to Pbs. Default: Pts = 1.

#### PIs

is the left-column border. Pls must be less than or equal to Prs. Default: Pls = 1.

#### Pbs

is the bottom-line border.

Default: Pbs =the last line of the page.

### Prs

is the right-column border.

Default: *Prs* = the last column of the page.

#### Pps

is the number of the page where the rectangular area is located.

Default: Pps = 1.

## Ptd; Pld; Ppd;

define the destination of the copied rectangular area.

#### Ptd

is the top-line border.

Default: Ptd = 1.

#### Pld

is the left-column border.

Default: Pld = 1.

#### Ppd

is the number of the page.

Default: Ppd = 1.

## **DECCRA—Copy Rectangular Area**

### **Notes on DECCRA**

- If *Pbs* is greater than *Pts*, or *Pls* is greater than *Prs*, the terminal ignores DECCRA.
- The coordinates of the rectangular area are affected by the setting of origin mode (DECOM).
- DECCRA is not affected by the page margins.
- The copied text takes on the line attributes of the destination area.
- If the value of *Pt, Pl, Pb,* or *Pr* exceeds the width or height of the active page, then the value is treated as the width or height of that page.
- If a page value exceeds the number of pages available in the current page arrangement, then the value is treated as the last available page number.
- If the destination area is partially off the page, then DECCRA clips the off-page data.
- DECCRA does not change the active cursor position.

## **DECCRTST—CRT Saver Timing**

Controls the timing of the CRT screen saver.

**Default:** 15 minutes

#### **Format**

### **Parameters**

#### Ps

Screen saver timing

Ps	Selection	
0	Never	
5	5 minutes	
15	15 minutes	
30	30 minutes	
60	60 minutes	

## **Description**

The **CRT saver** feature causes the screen to go blank after the specified interval of no keystroke or receive character activity. Refer to Set-Up for details.

DECCRTSM remains functional (set = 15 min; reset = never).

DECCRTST can be reported using DECRPSS.

## **DECCRTSM—Set/Reset CRT Save Mode**

Enable or disable CRT saver.

**Default:** Enable CRT saver.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>9</b> 3/9	<b>7</b> 3/7	<b>h</b> 6/8	Set: enable CRT saver.
	<b>?</b> 3/15				Reset: disable CRT saver.

## Description

If CRT saver is enabled and the terminal is inactive for 15 minutes (no keyboard activity or input from a host computer), then the monitor screen goes blank to prolong the life of the CRT. No data is lost when CRT saver is active. Keyboard activity or input from the host computer re-activates the monitor.

When the monitor goes blank, the keyboard LEDs flash.

## **DECDC—Delete Column**

This control function deletes one or more columns in the scrolling region, starting with the column that has the cursor.

**Available in:** VT Level 4 or higher mode only.

#### **Format**

#### **Parameters**

#### Pn

is the number of columns to delete.

Default: Pn = 1.

### **Description**

As columns are deleted, the remaining columns between the cursor and the right margin move to the left. The terminal adds blank columns with no visual character attributes at the right margin. DECDC has no effect outside the scrolling margins.

## **DECDHL**—Double-Width, Double-Height Line

These two control functions make the line with the cursor the top or bottom half of a double-height, double-width line. You must use these sequences in pairs on adjacent lines. In other words, the same display characters must appear in the same positions on both lines to form double-height characters. If the line was single width and single height, then all characters to the right of the screen center are lost.

#### **Format**

<b>ESC</b> 1/11	# 2/3	<b>3</b> 3/3	Top Half
<b>ESC</b> 1/11	# 2/3	<b>4</b> 3/4	Bottom Half

## Description

The following sequences make the phrase "VT520 Video Terminal" a double-height, double-width line.

ESC#3 VT520 Video Terminal ESC#4 VT520 Video Terminal

This control does not operate when DECLRMM (left right margin mode) is set.

DECDLD loads your soft character set into dynamically redefinable character set (DRCS) font buffers. The terminal supports two each S1 and S2 buffers for soft character sets.

The terminal arranges the DRCS font buffers into sets. Each DRCS set has two font buffers: one for 80-column fonts and one for 132-column fonts. These buffers also allow you to load two different font heights or character sets in both 80- and 132-column widths.

Although the terminal allows you to use two different soft character sets at one time, it only allows you to use one DRCS set at one time.

#### **Format**

DCS Pfn; Pcn; Pe; Pcmw; Pss; Pt; Pcmh; Pcss { < Dscs>< sixel-font-pattern> ST

## **Description**

DCS is the DCS control string introducer. DCS is an 8-bit C1 character. You can use the equivalent 7-bit sequence, ESC P (1/11, 5/0), when coding for a 7-bit environment.

ST is the string terminator. ST is an 8-bit C1 character. You can use the equivalent 7-bit sequence, ESC  $\setminus$  (1/11, 5/12), when coding for a 7-bit environment.

#### **Parameters**

#### Pfn; Pcn; Pe; Pcmw; Pss; Pu; Pcmh; Pcss

are parameter characters, separated by semicolons (3/11). Table 5-2 describes these parameters and lists their possible values.

is the final character. It marks the end of the parameter characters and indicates that this string is a DECDLD function.

defines the name for the soft character set. You use this name in the select character set (SCS) escape sequence. You use the following format for the Dscs name:

IF

Ι is 0, 1, or 2 intermediate characters from the 2/0 to 2/15 range in the ASCII character set.

Fis a final character in the 3/0 to 7/14 range.

NOTES	

- If two downline loaded soft character sets have the same *Dscs*, then the most recently loaded set is used. The terminal looks for a matching *Dscs* in reverse load order (last loaded first).
- If the terminal receives a DRCS control string for a given font number with a different *Dscs* (designating sequence), *Pcmh* (height) or *Pcss* (character set size), then the terminal erases the previously downline loaded set (if any) in both 80- and 132-column mode.
- If there is no DRCS available that is compatible with the current number of lines per screen (font height), then the terminal displays a reverse question mark in place of any characters.

### **Examples of Dscs Names**

Namo	e		Function
<b>sp</b> 2/0	<b>@</b> 4/0		Defines the character set as an unregistered soft set. <b>This value is the recommended default for user-defined sets.</b> The value of <i>Pcss</i> defines whether this set has 94 or 96 characters.
<b>A</b> 4/2			If <i>Pcss</i> is 0, then A defines the soft character set as the U.K. national replacement character set.  If <i>Pcss</i> is 1, then A defines the soft character set as the ISO Latin-1 supplemental set.
<b>&amp;</b> 2/6	% 2/5	<b>C</b> 4/3	Defines the soft character set as % C, which is currently an unregistered set. The value of <i>Pcss</i> defines whether this set has 94 or 96 characters.

Table 5-2 DECDLD Parameter Characters

Parameter	Name	Description			
Pfn	Font number	Selects the DRCS (soft character set) to load. The previous set (if any), that you load with that font number, is erased or overwritten as specified by the control sequence.			
		You can assign a value of 0, 1, and 2 to $Pfn$ . Other values cause the terminal to ignore the entire sequence. $Pfn = 0$ defaults to the first empty font buffer, or, if none are empty, to font buffer 1.			
Pcn	Starting character	Selects where to load the first character in the DRCS font buffer. The location corresponds to a location in the ASCII code table. For example, a $Pcn$ value of 0 means that the first soft character is loaded into position $2/0$ of the character table. A $Pcn$ value of 1 means position $2/1$ in the table, and so on, up to $Pcn = 95$ (position $7/15$ ). $Pcn$ is affected by the character set size. See $Pcss$ below.			
Pe	Erase control	Selects which characters to erase from the DRCS buffer before loading the new font.			
		0 = Erases all characters in the DRCS buffer with this number, width, and rendition.			
		1 = Erases only characters in locations			
		being reloaded.  2 = Erases all renditions of the soft character set (normal, bold, 80-column, 132-column).			
		Note			
		Erased characters are undefined (not blank). The terminal displays these characters as the error character (reverse question mark).			
		(continued on next page)			

(continued on next page)

Table 5-2 (Cont.) DECDLD Parameter Characters

Parameter	Name	Desc	Description				
Pcmw	Character matrix width	Selects the maximum character cell width. When <i>Pss</i> specifies 80 columns, <i>Pu</i> specifies font usage full cell as follows:					
		0 2 3 4 5 6 7 8 9	= = = = = = = = = = = = = = = = = = = =	10 pixels wide for 80 columns, 6 pixels wide for 132 columns. (default). device default 5 × 10 pixel cell (width × height). 6 × 10 pixel cell (width × height). 7 × 10 pixel cell (width × height). 5 pixels wide. 6 pixels wide. 7 pixels wide. 8 pixels wide. 8 pixels wide. 9 pixels wide. 10 pixels wide.			
			When $Pss$ specifies 80 columns, $Pu$ specifies four usage text as follows:				
		0	=	10 pixels wide for 80 columns, 6 pixels wide for 132 columns. (default)			
		0 2 3 4 5	= = = =	device default $5 \times 10$ pixel cell (width $\times$ height). $6 \times 10$ pixel cell (width $\times$ height). $7 \times 10$ pixel cell (width $\times$ height). $5$ pixels wide.			
				9 pixels wide. ss specifies 132 columns, <i>Pu</i> specifies ge full cell as follows:			
		0	=	10 pixels wide for 80 columns, 6 pixels wide for 132 columns. (default)			
		2 3 4 5 6	= = = =	$5 \times 10$ pixel cell (width $\times$ height). $6 \times 10$ pixel cell (width $\times$ height). $7 \times 10$ pixel cell (width $\times$ height). 5 pixels wide. 6 pixels wide.			

(continued on next page)

Table 5-2 (Cont.) DECDLD Parameter Characters

Parameter	Name	Des	Description			
				ks specifies 132 columns, <i>Pu</i> specifies ge text as follows:		
		0	=	10 pixels wide for 80 columns, 6 pixels wide for 132 columns. (default)		
		2	=			
		3	=	$6 \times 10$ pixel cell (width $\times$ height).		
		4	=	$7 \times 10$ pixel cell (width $\times$ height).		
		5	=	5 pixels wide.		
		defa is 0 valu <i>Pcn</i>	ault ( ), <i>Pci</i> ue ov	mit a <i>Pcmw</i> value, the terminal uses the character width. If the <i>Pe</i> parameter <i>mw</i> must be less than 10. Any <i>Pcmw</i> rer 10 is illegal. For illegal values of the terminal ignores the rest of the load e.		
For VT200 o	compatible so	ftware:	Use	a Pcmw value of 0=device default,		
	l high matrix.					

11 =

Pss Font set size Defines the screen width and screen height for this font.

0,1 80 columns, 24 lines. (default) 80 columns, 24 lines 0 = 80 columns, 24 (25 or 26) lines 1 2 132 columns, 24 lines

132 columns, 36 lines 12 = 80 columns, 48 (50 or 52) lines 21 =

80 columns, 36 (40 or 42) lines

11 132 columns, 48 lines

For illegal values of *Pss*, the terminal ignores the rest of the load sequence.

If the number of columns or lines/screen changes, then the terminal uses the appropriate variation of the soft set. If you try to display a DRCS character when there is no soft set defined for the current number of lines and columns, then the terminal displays the error character (reverse question mark).

\_\_\_\_ Note \_\_\_\_

For VT220 compatibility, you must use a soft font of 80 or 132 columns (not both). The VT220 allows a single font to be used for 80 and 132 columns.

(continued on next page)

Table 5-2 (Cont.) DECDLD Parameter Characters

Parameter	Name	Description
		You can load a font for any of the six sizes at any time. When a new soft set is loaded, any characters from the previous soft set are lost. Characters currently displayed from the old set become reverse question marks.
Pu	Text or full cell	Defines the font as a text font or full-cell font.  0 = text. (default)  1 = text.  2 = full cell.  Full-cell fonts can individually address all pixels in a cell.  Text fonts cannot individually address all pixels. If you specify a text cell, then the terminal automatically performs spacing and centering of the characters.
Pcmh	Character matrix height	Selects the maximum character cell height. <b>0 or omitted = 16 pixels high. (default)</b> 1 = 1 pixel high.  8 = 8 pixels high.  9 = 9 pixels high.  .  .  16 = 16 pixels high.  Pcmh values over 16 are illegal. If the value of Pcmw is 2, 3, or 4, then Pcmh is ignored.

## **DECDMAC—Define Macro**

This device control string lets you define a macro consisting of a string of ANSI text and control functions. After you define the macro, you can execute it by using the invoke macro control function (DECINVM). The terminal processes the macro as normal input.

Available in: VT Level 4 or higher mode only.

#### **Programming Tip**

You can find how much memory space you have available for macros by using a device status report sequence.

### **Format**

DCS	Pid	;	Pdt	;	Pen	!	Z	D D	ST
9/0	3/?	3/11	3/?	3/11	3/?	2/1	7/10		9/12

## **Parameters**

#### Pid

is the macro ID number. Pid can be any number between 0 and 63, otherwise the terminal ignores the command. If you give a macro an ID that already exists, then DECDMAC deletes the old macro definition before using the new one.

Pdt defines how the terminal treats new macro definitions.

Pdt	Meaning
0 or omitted	DECDMAC deletes the old macro with the same ID number before defining this new macro.
1	DECDMAC deletes all current macro definitions before defining this macro.
Other	The terminal ignores the macro.

#### Pen

selects the encoding format for the text of the macro definition.

Pen	Meaning
0 or omitted	Uses standard ASCII characters in the macro.
1	Uses hex pairs in the macro. Each pair of characters in the macro is the hex value for a single ASCII character.
Other	The terminal ignores the macro.

#### D...D

is the data of the control string. This data is the string of text and control functions performed when an application invokes the macro. The data can consist of ASCII text or hex pairs.

When you use ASCII text (Pen = 0 or omitted), the macro consists of the graphic characters that appear in the device control string. Only characters from positions 2/0 through 7/14 and 10/00 through 15/15 in the code table are valid.

**When you use hex pairs (Pen = 1)**, the macro consists of pairs of hex numbers, each of which represents an ASCII character. When using hex pairs, you can also use a repeat introducer in the data string. The repeat introducer is the ! (2/1) character. The repeat introducer lets you repeat any hex pair within the definition string any number of times. You embed repeat sequences within the data string of the macro definition.

#### Notes on DECDMAC

- If ASCII text is specified as the encoding format, then you cannot use the repeat sequence.
- ! is the repeat sequence introducer. The format of the hex string with the repeat introducer is as follows:

! Pn: D...D:

Pn is a numeric parameter that specifies the number of times to repeat the sequence. If Pn is omitted, then the macro repeats the sequence once.

D...D is the sequence of hex pairs to repeat Pn times.

A semicolon; (3/11) separates the repeat count from the sequence of hex pairs. Another semicolon ends the sequence. If any characters are included before the first semicolon, then the terminal ignores the macro. If a string terminator is placed before the final semicolon, then the repeat string ends normally.

- The VT520 has 6 Kbytes of memory available for the storage of macros. The terminal ignores any macro definitions that cannot fit into this space.
- A reset to initial state (RIS) or secure reset (DECSR) operation clears all macro definitions. A soft terminal reset (DECSTR) has no effect on stored macro definitions.
- You can include characters from positions 0/8 through 0/13 to format the device control string, but these characters cannot be part of the macro definition.

## **DECDLDA—Down Line Load Allocation**

This control function controls the number of soft character sets (DECS) allowed per session.

Available for: monochrome terminals only; not available for color terminals.

#### **Format**

#### **Parameters**

#### Ps

is the number of soft character sets allowed:

Default: Ps = 2.

Ps	Description	Compatible with terminals such as
1	One each	VT420 video terminal.
2	Two each for sessions S1 and S2	VT510 video terminal.

## **Description**

For the monochrome monitor, you can use these commands to set up one or two soft character sets for sessions S1 and S2. You can also use the **Session** ⊳ **Soft character sets/session** to perform this same function. Also see 2.6.4.

The color terminal does not use this command because it has enough memory to give all four sessions **Two each**.

DECDLDA can be reported using DECRPSS.

## **DECDWL**—Double-Width, Single-Height Line

This control function makes the line with the cursor a double-width, single-height line. If the line was single width and single height, then all characters to the right of the screen's center are lost.

#### **Format**

#### Note on DECDWL

DECDWL control does not operate when DECLRMM (left right margin mode) is set.

### **DECECM—Erase Color Mode**

Controls the background color used when text is erased or new text is scrolled on to the screen.

**Default:** Erase to text background

#### **Format**

## **Description**

The **erase color** selection controls the background color used when text is erased or new text is scrolled onto the screen. Refer to Set-Up for details.

DECECM can be reported using DECRQM and DECRPM.

## **DECEKBD—Extended Keyboard Report**

This control function is a report that provides applications with more complete keystroke information. Each report consists of an ISO key position code and the current state of the eight modifier keys—pressed or released.

#### **Format**

#### **Parameters**

#### ppp

is a three-character ISO key position name, for example C01. For keys that occupy more than one position in the ISO key position map, the VT520 uses the largest lower-left position. The position for the space bar is A02; Return is C13.

#### mm

are two ASCII hexadecimal digits that represent the state of the modifier keys.

The terminal represents the state of each modifier key as a bit in an 8-bit binary number. A bit value of 1 means the key is pressed, and a bit value of 0 means the key is not pressed. *mm* is the hexadecimal equivalent of the resulting 8-bit binary number.

The following table shows the order in which keys are represented in the binary number, and their corresponding hexadecimal values when pressed. The least significant bit represents the left Shift key. The most significant bit represents the right Compose Character key.

For example,  $00000010_2$  means that the right Shift key is pressed. The hexadecimal value for  $00000010_2$  is  $02_{16}$ .

mm	Key
01	left Shift (Least significant bit)
02	right Shift
04	Lock
08	Ctrl
10	left Alt Function
20	right Alt Function
40	left Compose Character
80	right Compose Character (Most significant bit)

## **DECEKBD—Extended Keyboard Report**

## **Description**

The terminal only sends extended key position reports when key position mode (DECKPM) is set.

The terminal uses the following rules when sending extended key reports:

- A single report may contain more than one keystroke. In this case, each
  keystroke is separated by a slash (/). The terminal sends the control string
  (APC ... ST) when a modifier key changes, or to separate keystroke data from
  other terminal reports.
- The terminal only sends the modifier key state when it changes in the first keystroke after an APC character.
- The terminal sends repeated key position reports as a single repeat character, period (.).

## **Examples**

The following sequence reports an  $\boxed{a}$  key with no modifier keys, four  $\Longrightarrow$  keys, one  $\mathclap{\longleftarrow}$  key, and a  $\boxed{b}$  key:

```
APC : C01 00 / B18.../ B16 / B05 ST
```

The following sequence reports a left Shift key and an A key:

APC : B99 01 / C01 ST

## **DECELF—Enable Local Functions**

This control function lets you enable or disable the keys used to perform several local terminal functions: cutting and pasting text, panning, and resizing windows. DECELF is useful for:

- · Simplifying the keyboard for novice users
- Letting the corresponding keys send position codes to the host when key position mode (DECKPM) is set
- · Disabling features that are not compatible with the application

#### **Format**

**CSI** *Pf1* ; *Pc1* ; ··· *Pfn; Pcn* + **q** 
$$9/11$$
  $3/n$   $3/11$   $3/n$   $3/11$  ···  $3/n$   $3/11$  ···  $3/n$   $3/11$  ···

#### **Parameters**

#### Pfn

is a number that specifies the local function affected.

Pfn	Local Functions Affected	Default Setting
0 (default)	All local functions listed for 1, 2, and 3.	
1	Copy and paste keys, including F1 (Hold), Select, Remove, and Insert Here.	The keys are enabled.
2	Panning keys, including $\boxed{\text{Ctrl}}$ with $\boxed{\uparrow}$ , $\boxed{\downarrow}$ , $\boxed{\Leftarrow}$ , or $\boxed{\Rightarrow}$ .	The keys are enabled.
3	Window resizing keys, including: Control and Shift with ↑ or ↓ keys.	The keys are enabled.

### Pcn

controls the action of the local function specified by the corresponding *Pfn* value.

Pcn	Meaning				
0	Selects the default setting of the local function.				
	In VT mode, the default setting is enabled.				
	In PC Term mode, the default setting is disabled.				
1	Enables the local function. The associated keys perform the local function and cannot send position codes to the host.				
2	Disables the local function. The associated keys do not perform the local function and may send position codes to the host.				

## **Description**

DECELF can accept any number of parameter pairs. The terminal executes the parameters in the order in which it receives them.

## **DECERA—Erase Rectangular Area**

This control function erases characters from the specified rectangular area in page memory. When an area is erased, DECERA replaces all character positions with the space character (2/0). DECERA erases character values and visual attributes from the specified area. DECERA does not erase line attributes.

Available in: VT Level 4 or higher mode only.

#### **Format**

### **Parameters**

#### Pt, Pl, Pb, and Pr

define the rectangular area to be erased:

**Pt** is the top-line border. *Pt* must be less than or equal to *Pb*.

Default: Pt = 1.

**Pl** is the left-column border. Pl must be less than or equal to Pr. Default: Pl = 1.

Pb is the bottom-line border.

Default: Pb = the last line of the active page.

Pr is the right-column border.

Default: Pr = the last column of the active page.

#### **Notes on DECERA**

- The coordinates of the rectangular area are affected by the setting of origin mode (DECOM).
- DECERA is not affected by the page margins.
- If the value of *Pt, Pl, Pb,* or *Pr* exceeds the width or height of the active page, then the value is treated as the width or height of that page.
- DECERA does not change the active cursor position.

## **DECES—Enable Session**

Make the session receiving this command the active session.

#### **Format**

## **Description**

This command makes the session receiving this command the active session for keyboard input. Normally the active session for keyboard input is controlled by the user pressing the Session key.

## **DECESKM—Enable Secondary Keyboard Language Mode**

Select a secondary or primary keyboard language.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>4</b> 3/4	<b>h</b> 3/8	Secondary keyboard mapping.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>4</b> 3/4	<b>I</b> 6/12	Primary keyboard mapping.

## **Description**

When enabled, a secondary keyboard mapping (Group 2) replaces the primary keyboard mapping. To use the secondary keyboard mapping, a secondary keyboard language has to be defined for the currently selected keyboard language, such as Hebrew, Greek, or Cyrillic.

## **DECFI—Forward Index**

This control function moves the cursor forward one column. If the cursor is at the right margin, then all screen data within the margins moves one column to the left. The column shifted past the left margin is lost.

Available in: VT Level 4 or higher mode only.

### **Format**

**ESC** 9 1/11 3/6

## **Description**

DECFI adds a new column at the right margin, with no visual attributes. DECFI is not affected by the margins. If the cursor is at the right border of the page when the terminal receives DECFI, then the terminal ignores DECFI.

## **DECFRA—Fill Rectangular Area**

This control function fills a rectangular area in page memory with a specified character. DECFRA replaces the rectangular area's character positions and attributes with the specified fill character. The fill character assumes the visual character attributes set by the last select graphic rendition (SGR) command. DECFRA does not change the current line attributes.

**Available in:** VT Level 4 or higher mode only

#### **Format**

```
CSI Pch ; Pt; Pl; Pb; Pr $ x 9/11 3/n 3/11 3/n 2/4 7/8
```

#### **Parameters**

#### **Pch**

is the decimal value of the fill character. *Pch* can be any value from 32 to 126 or from 160 to 255. If *Pch* is not in this range, then the terminal ignores the DECFRA command. The decimal value refers to the character in the current GL or GR in-use table.

#### Pt: Pl: Pb: Pr

define the rectangular area to be filled:

**Pt** is the top-line border. *Pt* must be less than or equal to *Pbs*.

Default: Pt = 1.

**Pl** is the left-column border. *Pl* must be less than or equal to *Pr*.

Default: Pl = 1.

**Pb** is the bottom-line border.

Default: Pb = the last line of the active page.

Pr is the right-column border.

Default: Pr = the last column of the active page.

#### Notes on DECFRA

- The coordinates of the rectangular area are affected by the setting of origin mode (DECOM).
- DECFRA is not affected by the page margins.
- If the value of *Pt, Pl, Pb,* or *Pr* exceeds the width or height of the active page, the value is treated as the width or height of that page.
- DECFRA does not change the active cursor position.

## **DECFWM—Set/Reset Framed Windows Mode**

Selects whether or not session windows are displayed with window frames with frame borders and icons.

**Default:** Framed windows enabled

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>1</b> 3/1	<b>1</b> 3/1	<b>h</b> 6/8	Set: enables framed windows
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>1</b> 3/1	<b>1</b> 3/1	<b>I</b> 6/12	Reset: disables framed windows

## Description

When **framed windows** is selected, window frames with title bars are added to each displayed window. Refer to Set-Up chapter for details.

DECFWM can be reported using DECRQM and DECRPM.

## **DECHDPXM—Set/Reset Half-Duplex Mode**

Enables half-/full-duplex communication.

### **Format**

## Description

Full-duplex mode allows simultaneously two-way communication; half-duplex mode is limited to one-way communication at any given time. Half-duplex mode is available only in an RS232 line. Refer to Chapter 9 for details about half-duplex mode communication protocol.

## **DECHEM—Hebrew Encoding Mode**

This control function sets the terminal's character set mode to DEC (8-bit) multinational mode. On a reset, the sequence resets the terminal's character set mode to (7-bit) national mode (NRC sets).

The terminal maintains DECHEM for the main display and status line separately in the same way as it maintains National Replacement Character Set Mode (DECNRCM).

### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>3</b> 3/3	<b>6</b> 3/6	<b>h</b> 6/8	Set
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>3</b> 3/3	<b>6</b> 3/6	<b>I</b> 6/12	Reset

## **DECHEBM—Hebrew/N-A Keyboard Mapping Mode**

This control function sets the keyboard mapping to  ${\tt Hebrew/N-A}$  and resets the mapping to  ${\tt North\ American}$ .

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>3</b> 3/3	<b>5</b> 3/5	<b>h</b> 6/8	Set
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>3</b> 3/3	<b>5</b> 3/5	<b>I</b> 6/12	Reset

## **Description**

When 8-bit characters are selected, DECHEBM switches between the Group 1 and the Group 2 character set mappings. It does not affect the keyboard character set selection or the processing of received characters.

When 7-bit characters are selected or the terminal is set to VT100 mode, setting DECHEBM does the following:

- Switches keyboard map to Group 2.
- Makes DEC 7-bit Hebrew the keyboard character set.
- Causes received characters in the range of 60 to 7A (hex) to be displayed using the DEC 7-bit Hebrew when ASCII is designated or invoked and keyboard Group 2 is active.

Receiving DECHEBM does the following:

- Switches keyboard map to Group 1.
- Makes ASCII the keyboard character set.
- Causes received characters to be displayed using the graphic left (GL) table of characters in use at the time.

Note
DECHEBM is only valid when a Hebrew keyboard language is selected. Also it does not convert ASCII or Hebrew characters already on the display.

## **DECHWUM—Host Wake-Up Mode (CRT and Energy Saver)**

When the Host wake-up feature is selected, any character received from the host will also restore the display.

#### **Format**

## Description

This command allows any character received from the host to restore the display when either the CRT or Energy saver is in effect. Refer to Set-Up chapter for details.

DECHWUM can be reported using DECRPM.

## **DECIC**—Insert Column

This control function inserts one or more columns into the scrolling region, starting with the column that has the cursor.

**Available in:** VT Level 4 or higher mode only

#### **Format**

#### **Parameters**

#### Pn

is the number of columns to insert.

Default: Pn = 1.

### **Description**

As columns are inserted, the columns between the cursor and the right margin move to the right. DECIC inserts blank columns with no visual character attributes. DECIC has no effect outside the scrolling margins.

## **DECID—Identify Device**

This control function is similar to a primary device attributes (DA) request from the host.

\_ Note \_\_\_\_\_

Using DECID is not recommended. DECID may not be supported in the manufacturers terminals. You should use the primary device attributes request for this purpose. In VT400 or higher mode, the terminal ignores DECID.

### **Format**

**ESC Z** 1/11 5/10

### **Terminal Response**

The terminal uses the same response as for a primary DA request for all operating levels (1 or 4). See DA1, DA2, and DA3.

## **DECINVM—Invoke Macro**

This control function lets you execute a stored macro. You store macros with the define macro (DECDMAC) control string. The terminal substitutes the DECINVM sequence with the contents of the macro definition and executes the

Available in: VT Level 4 or higher mode only.

#### **Format**

```
CSI
       Pid
                    Z
                    7/10
9/11
       3/n
             2/10
```

### **Parameters**

#### Pid

is the macro ID number. If the *Pid* is not associated with a particular macro, the terminal ignores the command.

#### Notes on DECINVM

Any functions executed with a macro invocation remain in affect after the terminal executes the macro.

## **Examples**

Suppose you want to create a macro that clears all pages in page memory, writes the word "top" at the top of each page, and leaves the cursor on page 1.

First, you would write the string with ASCII characters as follows:

```
DCS 1 ; 0 ; 1 ! z CSI 6 sp P ! 6 ; CSI 1 ; 1 H CSI 2 J TOP
CSI 1 V ; ST
```

Then, you must convert the string into hexadecimal code because the string uses the repeat (!) character. You can only use the repeat character with hexadecimal sequences. The following example is the same string written in hex:

```
DCS 1 ; 0 ; 1 ! z 9B 36 20 50 ! 6 ; 9B 31 3B 48 9B 32 49 54
4F 50 9B 31 56 ; ST
```

To invoke the macro, use the following sequence:

```
CSI 1 * z
```

## **DECIPEM**—Enter/Return from IBM ProPrinter Emulation Mode

Exit from DEC protocol and interpret subsequent data according to the IBM ProPrinter protocol syntax. This sequence also resets IBM ProPrinter mode to its initial state.

### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>5</b> 3/5	<b>8</b> 3/8	<b>h</b> 6/8	Set: Enter ProPrinter Emulation mode.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>5</b> 3/5	<b>8</b> 3/8	I 6/12	Reset: Return from ProPrinter Emulation mode.

## **Description**

DECIPEM works the same as the IBM SOCS and ROCS control functions.

## **DECKBD—Keyboard Language Selection**

Select a national keyboard language on either a VT keyboard or an Enhanced PC keyboard.

#### **Format**

#### **Parameters**

Ps1 denotes a keyboard type (layout): VT or enhanced PC.

Ps1	Keyboard Layout
0, 1, or None	VT
2	Enhanced PC

Ps2 indicates the national keyboard language.

Ps2	Keyboard Language (VT/PC)
0, 1 or None	North American
2	British
3	Belgian (Flemish)
4	French Canadian
5	Danish
6	Finnish
7	German
8	Dutch
9	Italian
10	Swiss French
11	Swiss German
12	Swedish
13	Norwegian
14	French
15	Spanish
16	Portuguese
19	Hebrew
22	Greek
28	Canadian (English)
29	Turkish Q/Turkish
30	Turkish F

### **DECKBD—Keyboard Language Selection**

Ps2	Keyboard Language (VT/PC)
31	Hungarian
33	Slovak
34	Czech
35	Polish
36	Romanian
38	SCS
39	Russian
40	Latin American

### **Description**

The first selective parameter, Ps1, denotes a keyboard type, VT layout or Enhanced PC keyboard layout. The second parameter, Ps2, indicates the national keyboard language.

Selecting a new keyboard language automatically initializes the keyboard character set. Refer to Chapter 8 for more details.

### **DECKBUM—Typewriter or Data Processing Keys**

You can select whether the main keyboard keys act as data processing keys or typewriter keys by using the keyboard usage mode (DECKBUM) function.

**Default:** Typewriter keys

### **Keyboard Usage Mode (DECKBUM)**

<b>CSI</b>	<b>?</b>	<b>6</b>	<b>8</b>	<b>h</b>	Set: data processing keys.
9/11	3/15	3/6	3/8	6/8	
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>8</b> 3/8	<b>I</b> 6/12	Reset: typewriter keys.

### **Description**

If DECKBUM is set, then data processing keys send the characters on the right half of their keycaps.

If DECKBUM is reset, then data processing keys send the characters on the left half of their keycaps.

#### **Notes on DECKBUM**

- DECKBUM changes the characters that the main keyboard keys send. Make sure you are aware of this change if you use DECKBUM in an application.
- If you use the North American language, then DECKBUM should always be reset (typewriter). For all other languages, you can use either mode.

### **DECKLHIM**—Keyboard LED's Host Indicator Mode

DECKLHIM controls the state of the keyboard LED's host indicator mode.

Default: Reset.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>1</b> 3/1	<b>0</b> 3/0	<b>h</b> 6/8	Set: keyboard LED's host indicator mode.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>1</b> 3/1	<b>0</b> 3/0	I 6/12	Reset: The keyboard LED's act as local indicators.

### **Description**

See DECLL for the implications of using DECLL to control the keyboard LEDs independently of any keyboard state.

### **DECKPAM—Keypad Application Modes**

DECKPAM enables the numeric keypad to send application sequences to the host.

See DECKPNM—Keypad Numeric Modes , which enables the numeric keypad to send keypad characters.

DECKPAM and DECKPNM function the same as numeric keypad mode (DECNKM).

#### **Format**

```
ESC = 3/13 Sends application sequences.
```

#### Note on DECKPAM

When you turn on or reset the terminal, it automatically selects numeric keypad mode.

### **DECKPM—Key Position Mode**

This control function selects whether the keyboard sends character codes or key position reports to the host. DECKPM lets new applications take full control of the keyboard including single shifts, locking shifts, and compose character processing.

**Default:** Send character codes

#### **Format**

```
      CSI
      8
      1
      h
      Set: send key position reports.

      CSI
      8
      1
      I
      Reset: send character codes.

      9/11
      3/8
      3/1
      6/12
      Reset: send character codes.
```

#### **Description**

If the DECKPM function is set, then all keyboard keys send extended reports that include the key position and the state of modifier keys when pressed. A *modifier key* is pressed in combination with another key to modify the code sent by that key. The <code>Ctrl</code> key is a modifier key.

If the DECKPM function is reset, then the keyboard keys send character codes.

#### Note on DECKPM

DECKPM only affects keyboard input; it does not affect how the terminal interprets data from the host.

### **DECKPNM—Keypad Numeric Modes**

DECKPNM enables the numeric keypad to send keypad characters to the host.

See DECKPAM—Keypad Application Modes , which enables the keypad to send application sequences.

DECKPNM and DECKPAM function the same as numeric keypad mode (DECNKM).

**Default:** Send keypad characters.

#### **Format**

```
ESC > Send keypad characters.
```

#### **Description**

DECKPNM enables the numeric keypad to send the characters shown on each key—number, comma, period, or minus sign. Keys PF1 to PF4 send application sequences. See DECKPAM—Keypad Application Modes for more information.

#### Note on DECKPNM

When you turn on or reset the terminal, it automatically selects numeric keypad mode.

### **DECLANS—Load Answerback Message**

This sequence loads an answerback message into the terminal's memory.

#### **Format**

#### **Description**

The answerback data string may consist of from 0 to 30, 7- or 8-bit characters, which are hex pairs in the range:

```
3/0 - 3/9 (0 through 9),
4/1 - 4/6 (A through F), and
6/1 - 6/6 (a through f).
```

Once defined, the message may be stored in the non-volatile memory if **Save settings** is executed in the Set-Up.

The selective parameter denotes the encoding of the answerback message. A "1" is always used for the VT520 indicating answerback is encoded as hex pairs. The sequence is ignored if any number other than "1" is specified in the Ps field.

Pressing Ctrl/Break or receiving ENQ code causes the VT520 to transmit the answerback message. In on-line mode, the answerback message is transmitted to the appropriate host port. The answerback is not echoed in local echo and is not "sent" in local mode.

The answerback message is transmitted as keyboard data. Any speed restrictions (as set in limited transmit) apply.

### **DECLBAN—Load Banner Message**

DECLBAN loads a banner message to be displayed.

#### **Format**

#### **Parameters**

#### Ps

denotes the encoding of the message.

Ps	Description
0	Zero or omitted, default to Ps=2.
1	Interprets as ASCII hexadecimal pairs. See DECLANS.
2	Loads as text in the VT default character set.

is a 30-character string. If a matching *Ps* value is selected as an encoding method, then you can select to define the string by the characters in the default character set or by hexadecimal pairs.

### **Description**

DECLBAN loads a banner message to be displayed at terminal power-on. Once defined, the user must store the banner message in non-volatile memory by invoking **Save settings** in order for it to be available at power-on. The terminal displays the banner message in double size characters above the <code>Selftest OK</code> message.

### **DECLFKC—Local Function Key Control**

This control function lets you select the action performed by some of the local function keys on the top row of the keyboard:

Pk	Function	VT Keyboard	Enhanced PC Keyboard
1	Hold	F1	Scroll Lock
2	Print	F2	Print Screen
3	Set-Up	F3	Caps Lock/Print Screen

You can have the key perform its local function, send a function key sequence to the host, or do nothing.

This control function is useful for:

- Simplifying the keyboard for novice users
- Disabling features that are not compatible with the application, such as local printing

#### **Format**

#### **Parameters**

#### Pkn

is a number from 0 to 4 that corresponds to the local function key affected (F1) to F4. A *Pkn* value of 0 means that all four keys (F1) through F4 are affected.

#### Pfn

controls the action of the local function key specified by the corresponding *Pkn* value.

Pfn	Meaning	VT Mode	PCTerm Mode
0	Selects the default function of the key.	Local print	Scan code
1	The key performs its local function either shifted, unshifted, or with the Ctrl key.	Print	Local Print
2	The unshifted key sends its function key sequence to the host. The key sends nothing when pressed with Shift or Ctrl.	Function Key	Scan Code
3	The key is disabled.	Disabled	Does not exist

### **Description**

DECLFKC can accept any number of parameter pairs. The terminal executes the parameters in the order in which it receives them.

#### **Note on DECLFKC**

Applications cannot disable the  $\boxed{\texttt{F5}}$  (Break) key. This restriction is required for secure systems, which ensures that the operator has control of the communication line.

### **DECLL—Load LEDs**

Load the programmable LEDs on the keyboard according to its parameters.

#### **Format**

#### **Parameters**

# Ps selects the state of the Num Lock, Caps Lock, and Scroll Lock LEDs as follows:

Ps	LED	Light Condition
0	Num Lock	Off
	Caps Lock	Off
	Scroll Lock	Off
1	Num Lock	On
2	Caps Lock	On
3	Scroll Lock	On
21	Num Lock	Off
22	Caps Lock	Off
23	Scroll Lock	Off

### **DECLRMM—Left Right Margin Mode**

This control function defines whether or not the set left and right margins (DECSLRM) control function can set margins.

**Available in:** VT Level 4 or higher mode only. **Default:** DECSLRM cannot set margins.

#### **Format**

#### **Description**

When DECLRMM is set, DECSLRM can set the left and right margins. All line attributes currently in page memory for the session are set to single width, single height. The terminal ignores any sequences to change the line attributes to double width or double height (DECDWL or DECDHL).

When DECLRMM is reset, DECSLRM cannot set the left and right margins. The margins are set to the page borders for every page. The terminal can process sequences to change the line attributes to double width or double height (DECDWL or DECDHL).

### **DECLTOD—Load Time of Day**

Down-line load the time of day on the terminal. This sequence loads the time of day into the terminal's memory.

#### **Format**

#### **Parameters**

#### Ps1

specifies the hour, which is a 2-digit decimal number between 00 and 23.

The default value is 8, indicating 8:00 a.m.

#### Ps<sub>2</sub>

specifies the minutes, which is a 2-digit decimal number between 00 and 59.

The default value is 00, indicating 8:00 a.m.

#### **DECMCM—Modem Control Mode**

Enables (set) or disables (reset) modem control.

#### **Format**

#### **Description**

When enabled for the Comm2 or Comm3 connector, no data is transmitted or received unless DSR is asserted. Assertion of DSR alone is sufficient to establish a connection. Loss of DSR causes a disconnect. When DSR is not asserted, no data is transmitted, and incoming receive data is ignored. When DSR is again asserted, the communications state is re-initialized to prepare for the new connection.

When enabled for the Comm1 (25-pin EIA) connector, the terminal does not transmit unless CTS is asserted. If a connection has not been established (DSR is deasserted), RLSD is ignored. Transmission and reception may still occur if CTS is asserted. Assertion of CTS with DSR and RLSD asserted indicates a connection has been established. (CTS is checked last.)

When Modem Control is disabled, transmission and reception occur regardless of the state of the modem control signal. The terminal communicates using data leads only. DTR and RTS are always asserted except during an operator initiated disconnect sequence, or the input buffer reaches the 64-byte threshold when DTR flow control scheme is selected.

### **DECMSR—Macro Space Report**

DECMSR is the terminal's response to a DSR from the host. DECMSR indicates the number of bytes available for macro definitions.

#### **Format**

#### **Parameters**

Pn 
$$Pn = \frac{number\ of\ bytes}{16}$$
 rounded down.

### **DECNAKB—Greek/N-A Keyboard Mapping Mode**

This control function sets the keyboard mapping to North American and resets the mapping to Greek/N-A.

#### **Format**

### **DECNCSM—No Clearing Screen On Column Change Mode**

Set/reset the following condition: do not clear the screen whenever the column mode changes.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>9</b> 3/9	<b>5</b> 3/5	<b>h</b> 6/8	Set: do not clear screen when column mode changes.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>9</b> 3/9	<b>5</b> 3/5	I 6/12	Reset: clear the screen when column mode changes.

### **Description**

When enabled, a column mode change (either through Set-Up or by the escape sequence DECCOLM) does not clear the screen. When disabled, the column mode change clears the screen as a side effect.

This sequence does not affect the column mode change caused by the sequence, DECSCPP.

### **DECNKM—Numeric Keypad Mode**

This control function works like the DECKPAM and DECKPNM functions. DECNKM is provided mainly for use with the request and report mode (DECRQM/DECRPM) control functions.

**Available in:** VT Level 4 or higher mode only

**Default:** Numeric

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>6</b> 3/6	<b>h</b> 6/8	Set: application sequences.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>6</b> 3/6	<b>I</b> 6/12	Reset: keypad characters.

### **DECNRCM—National Replacement Character Set Mode**

Enable operation in 7-bit or 8-bit character mode.

#### **Format**

### Description

On the VT520, the character set mode is reset to 8-bit characters. In 8-bit mode, the terminal operates as a normal level 5 terminal allowing 8-bit controls and using the default character set, which is user-selectable for transmission and reception.

### **DECNULM—Null Mode**

Discard NUL characters upon receipt, or pass them on to the printer.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>2</b> 3/2	<b>h</b> 6/8	Set: discard NUL characters (default).
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>2</b> 3/2	<b>I</b> 6/12	Reset: pass NUL characters to printer.

### **Description**

If enabled, the NUL character is discarded upon receipt and may be used as a time fill character. If disabled, then the NUL character is accepted and stored in the input buffer so it may be passed on to the printer port.

### **DECNUMLK—Num Lock Mode**

Controls the keyboard Num Lock state as if the Num Lock key had been pressed.

#### **Format**

<b>CSI</b>	<b>?</b>	<b>1</b>	<b>0</b>	<b>8</b>	<b>h</b>	Set: Num lock ON.
9/11	3/15	3/1	3/0	3/8	6/8	
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>8</b> 3/8	<b>I</b> 6/12	Reset: Num lock OFF.

### **DECOM**—Origin Mode

This control function sets the origin for the cursor. DECOM determines if the **cursor position** is restricted to inside the page margins. When you power up or reset the terminal, you reset origin mode.

**Default:** Origin is at the upper-left of the screen, independent of margins.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>h</b> 6/8	Set: within margins.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/3	<b>I</b> 6/12	Reset: upper-left corner.

### **Description**

When DECOM is set, the home cursor position is at the upper-left corner of the screen, within the margins. The starting point for line numbers depends on the current top margin setting. The cursor *cannot* move outside of the margins.

When DECOM is reset, the home cursor position is at the upper-left corner of the screen. The starting point for line numbers is independent of the margins. The cursor *can* move outside of the margins.

### **DECOSCNM—Set/Reset Overscan Mode (VT520 only)**

Sets or resets overscan mode for monochrome terminal. (This feature is not available for color terminals.)

**Default:** Overscan disabled (reset).

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>6</b> 3/6	<b>h</b> 6/8	Set: Enable overscan
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>0</b> 3/0	<b>6</b> 3/6	<b>I</b> 6/12	Reset: Disable overscan (Default)

### **DECPAK—Program Alphanumeric Key**

Allow users to reprogram keys to transmit user-preferred alphanumeric codes or to perform user-preferred functions.

#### **Format**

```
DCS " y D...D ST 9/0 2/2 7/9 ... 9/12
```

#### Description

This sequence programs one or more keys (and their modifier combinations) Key or Alt/Key from the current state to:

- · Transmit desired alphanumeric codes
- Perform a local function or send user-defined sequence

This function works in all the VT modes except in VT52 mode.

The memory allocation and deallocation processes (program key lock and unlock process) on the DECPAK are the same as on the DECPFK. Refer to DECPFK—Program Function Key for details.

The data string D...D format is:

```
Key1/HEX Code String/Function #/UDS/UDS Direction;
Key2/HEX Code String/Function #/UDS/UDS Direction;.....;
```

Where, Keyn is the key station number and slash "/ " is a delimiter.

"HEX code string" is the hex character code to be transmitted with each of the seven modifier states. The hex code represents a valid code in the current character set (either 7-bit or 8-bit). Use a period "." as a place holder if a modifier combination is not to be defined. Use a minus "-" preceding the hex representation of a diacritical sign if a diacritical mark is to be defined.

The VT520 always allows the ISO character set to be used for specifying accent marks to DECPAK even when:

- 1. 7-bit NRCS characters are selected
- 2. The ISO character set is not the user-preferred supplemental character set

The corresponding ISO character set would be based on the keyboard language. Refer to Chapter 8 for more information on the keyboard language and character sets.

The position of the diacritical marks within the ISO Latin character sets is as follows:

#### **DECPAK—Program Alphanumeric Key**

Diacritical Sign	Position	Available ISO Character Set(s)
Circumflex	5/14	ASCII
Grave	6/0	ASCII
Tilde	7/14	ASCII
Dieresis (umlaut)	10/8	Latin 1, Latin 2, Latin Greek, Latin Turkish
Degree (ring)	11/0	Latin 1, Latin 2, Latin Greek, Latin Turkish
Acute	11/4	Latin 1, Latin 2, Latin Greek, Latin Turkish
Cedilla	11/8	Latin 1, Latin 2, Latin Turkish
Macron	10/15	Latin 1
Breve	10/2	Latin 2
Ogonek	11/2	Latin 2
Caron	11/7	Latin 2
<b>Double Acute Accent</b>	11/13	Latin 2
Dot Above	15/15	Latin 2

You should program the Hex string according in the following order of modifier states:

- 1. Group 1 unshifted
- 2. Group 1 shifted
- 3. Group 1 alternate shifted (Shift 2)
- 4. Group 2 (Group Shift or Alt Gr) unshifted
- 5. Group 2 shifted
- 6. Group 2 alternate shifted
- 7. Control (if omitted, use default)

If the control state is not redefined in this sequence, then the Key/Ctrl combination generates the control code based on the "Group 1 unshifted" state.

A graphic key transmits alphanumeric codes only when pressed with the above modifiers. When pressed with Alt key, the graphic key performs either of these two functions:

- Local terminal function
- User-defined sequence (same as UDK)

"Function #" corresponds to a local function to be performed when the key is pressed in combination with the Alt function. Example: Function number "0" is used to make the Key/Alt combination inoperative. Function number "100" indicates a user-defined sequence (UDS), and a UDS direction is defined for the Key/Alt combination following the "/" delimiter.

The UDS and UDS direction operations on DECPAK are the same as on DECPFK. Refer to DECPFK—Program Function Key for the details.

Once programmed, the key states are not affected by the terminal mode changes. Refer to DECPFK—Program Function Key for the list of terminal mode changes.

### **DECPCCM—Page Cursor-Coupling Mode**

This control function determines if a new page appears in the display when the cursor moves to a new page. DECPCCM is only useful with a multiple-page format.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>4</b> 4/4	<b>h</b> 6/8	Set: couples the cursor to the display.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>4</b> 4/4	<b>I</b> 6/12	Reset: uncouples the cursor.

### **Description**

When DECPCCM is set, the cursor is coupled to the display when the cursor moves to a new page. The new page appears in the display to keep the cursor in view.

When DECPCCM is reset, the cursor is uncoupled from the display. If the cursor moves to a new page, then the cursor disappears.

#### **DECPCTERM**—Enter/Exit PCTerm or Scancode Mode

DECPCTERM enables you to switch the terminal between VT mode and PCTerm mode, while the terminal is in VT mode. It also enables you to switch the terminal between ASCII character and scancode keycode mode, while the terminal is in SCO Console mode.

#### **Format**

CSI	?	Ps1	;	Ps2	r
9/11	3/15	3/n	3/11	3/n	7/2

#### **Parameters**

#### Ps1

selects VT mode or PCTerm mode. In SCO console mode, this parameter selects ASCII characters or scancode keycode mode. When the mode changes, some operating features are changed to reflect the characteristics of the selected emulation mode.

Ps1	VT Emulation Mode	SCO Console Mode
0 or none	VT Mode	ASCII characters
1	PCTerm Mode	Scancodes

#### Ps2

indicates the character set selection.

There are two kinds of character set values in this parameter. Values "0" through "7" are reserved for VT520 backward compatibility. Value "8" copies the VT character set as the PCTerm character set. The rest of the parameter values are enhanced in the VT520 to denote the code page numbers that are associated with the PC character sets.

All 8-bit DEC and ISO character sets are available for both VT mode and PCTerm mode. PC character sets are available only in PCTerm mode or SCO console emulation. (SCO console uses the PCTerm character set.)

If you select a DEC or ISO character set for use in PCTerm mode, then the SCS invocation sequences can be used to modify the PCTerm character set. If you select a PC character set, then the SCS invocation sequences are ignored.

### **DECPCTERM**—Enter/Exit PCTerm or Scancode Mode

Ps2	Character Set
0 or none	No Change
1	PC Multilingual
2	PC International
3	PC Danish/Norwegian
4	PC Spanish
5	PC Portuguese
6	DEC Supplemental
7	ISO Latin 1
8	VT character set
210	PC Greek
220	PC Spanish
437	PC International
850	PC Multilingual
852	PC Slavic (Latin 2)
857	PC Turkish
860	PC Portuguese
862	PC Hebrew
863	PC French Canadian
865	PC Danish
866	PC Cyrillic

### **DECPEX—Print Extent Mode**

This control function selects how much data you can print when you use the print page function.

**Default:** Scrolling region

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>9</b> 3/9	<b>h</b> 6/8	The print function prints the complete page.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>9</b> 3/9	I 6/12	The print function prints the scrolling region only (data inside the margins).

### **DECPFF—Print Form Feed Mode**

This control function selects whether or not the terminal sends a form feed (FF) character to the printer at the end of a printing function. DECPFF does not affect the print cursor line function described in the next section.

**Default:** No form feed

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>8</b> 3/8	<b>h</b> 6/8	The terminal sends a form feed (FF) to the printer at the end of a printing function.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>8</b> 3/8	<b>I</b> 6/12	The terminal sends nothing to the printer at the end of a printing function.

### **DECPFK—Program Function Key**

Allows users to program keys to perform user-preferred functions.

#### **Format**

```
DCS " x D...D ST 9/0 2/2 7/8 ... 9/12
```

#### **Description**

This sequence programs one or more keys (and their modifier combinations) from the current state to perform user-desired functions. The type of the function programmed must be either:

- a local terminal function
- a user-defined sequence (same as UDK)

This sequence is ignored when the program key function is locked through DECPKA, DECUDK, or Set-Up.

There are 768 bytes reserved for programmable key operations. This memory is shared by the following four functions:

- Program keys through DECPFK or through Set-Up
- · Program keys through DECPAK or through Set-Up
- Copy other key default through DECCKD or Set-Up
- Program user-defined keys through DECUDK

Space is supplied on a first-come, first-serve basis. Once the 768 bytes are used, no more keys may be redefined unless space is made available. Space may be made available by restoring keys back to their default states. There are four ways to do this:

- Execute a **Restore factory defaults** from the Set-Up main menu. All the terminal parameters, including the keys, return to their default states.
- Execute a "Restore factory defaults of all keys and key definitions" either through DECPKA (Program Key Action) or **Recall key definitions** in Set-Up. This action also releases the 768 bytes.
- Execute a Copy key default to copy a key's own default either through DECCKD or in Set-Up to free the space occupied by the destination key.
- Clear UDKs by issuing a clear function in DECUDK.

The free bytes left for key programming can be seen using the **Define Key Editor** in Set-Up.

The format of data string D...D is:

Key1/Mod1/Function #/UDS/UDS Direction; Key2/Mod2/Function #/UDS/UDS Direction;
.....;

Keyn is the key station number and a slash "/ " is a delimiter.

Refer to Chapter 8 for the key station number map.

*Modn* denotes the modifier key that is to be pressed at the same time as the defined key.

Modn	Modifier Key
0 or None	Normal
1	Normal
2	Shift
3	Alt
4	Alt + Shift
5	Control
6	Shift + Control
7	Alt + Control
8	Alt + Control + Shift

- "Function #" represents a number associated with a local function. For example, function number "0" is used to make the key or key/modifier inoperative. Function number "100" indicates a user-defined sequence (UDS) and UDS direction is defined following the slash "/ " delimiter. Refer to Chapter 8.
- UDS is a user-defined sequence with a maximum length of 255 bytes, which must be written in Hex format for DEC/ANSI terminals. Each hex code in this string represents a value transmitted by the defined key combined with the modifiers.
  - UDS in DECPFK is functionally equivalent to the string Stn in the DECUDK control function.
  - DECUDK is reserved in this terminal for backward compatibility with previous VT terminals. See DECUDK—User Defined Keys.
- UDS Direction indicates the direction of the UDS transmission.

Direction	UDS is sent to the
Remote	Host only.
Local	Terminal screen only.
Normal	Host and/or the terminal, depending on the setting of the COMM mode parameter.
	For full-duplex mode, the key sequence is directed to the host.  For local mode, the sequence is sent to the screen only.

UDS Direction	Direction
0 or None	Normal (Default)
1	Local
2	Remote

#### **DECPFK—Program Function Key**

Any of the following four methods may be used to define a key to transmit a user-defined sequence (either single byte or multiple bytes):

- Control function DECPFK
- Control function DECPAK
- Control function DECUDK
- In Set-Up, **Define key** . . .

Once programmed, the key state is not effected by the terminal mode changes listed below:

- Keyboard mode change, such as switching between Data Processing mode and Typewriter mode
- Character Mode change, such as switching between 7-bit character and 8-bit character
- Keyboard Layout change, such as switching between PC layout and VT layout
- Keyboard Style change, such as switching between PC-style and VT-style
- Terminal Mode change, such as switching between VT100 and VT500

#### **Redefining Keys on the Numeric Keypad**

Using **Define key...** to redefine keys on the numeric keypad will affect only the Num Lock off state of these keys. When Num Lock is on, these keys will always send their factory default ASCII numerals and characters. The Num Lock behavior of these keys cannot be reprogrammed.

Scenario: Imagine the keyboard having two numeric keypads: one for Num Lock Off, and the other for Num Lock On. Only the Num Lock Off keypad can be reprogrammed. The Num Lock On keypad retains the factory defaults.

This function works in all the ANSI VT modes except VT52 mode.

### **DECPKA—Program Key Action**

Allow changes to programmable keys, which affects all the keys on the keyboard in all the VT modes except in VT52 mode.

#### **Format**

#### **Parameters**

#### Ps

This sequence has two functions:

- 1. Lock the keys from redefinition.
- 2. Restore the definitions of the keys either from the factory default or the NVR.

If set to "1," the parameter determines whether the keys will be locked. Any attempt to program keys will be invalid.

If the keys are not locked, then the keys are available for further definition either through Set-Up or control functions DECPFK, DECPAK, DECCKD, and DECUDK. But if "Lock UDK" is enabled by DECUDK, then the attempt to program the keys does not take effect. (Refer to DECUDK—User Defined Keys for details.)

Once locked, keys can only be unlocked through Set-Up. There is no host control function that can unlock the keys.

If the parameter Ps is set to 2, then all the keys and keys/modifiers combination restore to their factory default states. Refer to DECCKD—Copy Key Default if restoring defaults for a single key and key/modifier combination.

If the parameter Ps is set to 3, all saved settings of the keys and keys/modifiers combination are recalled from the NVR.

If the keys are locked for further definition, then restore and recall operations are not valid.

Ps1	Program Key Action
0 or none	None
1	Locks keys and keys/modifiers from further definition
2	Restores factory defaults of all the keys and their keys/modifiers
3	Recalls saved keys definition

#### Note on DECPKA

The factory default  $\overline{+5}$  key is assigned as a BREAK key. It cannot be programmed from the host even if the program key is unlocked. This restriction is required for a secure system to ensure that the operator has control of the communication line.

### **DECPKFMR—Program Key Free Memory Report**

Report the free memory space for program key operations.

#### **Format**

#### **Parameters**

#### Ps<sub>1</sub>

denotes the total memory space in bytes that is reserved for the programmable keys. The total memory available is 768 bytes, hence the Ps1 value is "768."

#### Ps2

denotes the memory space that is available at the time DECRQPKFM is received, depending on the number of bytes left in decimal format. An "0" indicates that no memory is left for any key programming operation; in which case, any attempt to program the keys will fail.

#### **Description**

The VT520 reports this sequence upon receiving DECRQPKFM from the host.

#### Note on DECPKFMR

The VT520 firmware data structure uses some memory to program the key definitions; therefore, the free bytes reported by Ps2 do not represent the exact bytes available for users. A program to enter a definition that has the same byte count as reported by Ps2 may not be valid.

### **DECPS—Play Sound**

Controls the sound frequency or notes (one at a time).

#### **Format**

#### **Parameters**

#### **Pvolume**

Sound volume

0 = off

1...3 (low)

4...7 (high)

#### **Pduration**

Duration of note in 1/32 of a second

### **Pnote**

Note

Pnote	Note	~F (Hz)	Pnote	Note	~F (Hz)
1	C5		14	C#6	1047
2	C#5		15	D6	
3	D5		16	D#6	
4	D#5(Eb)	632	17	E6	
5	E5		18	F6	
6	F5		19	F#6	
7	F#5		20	G6	
8	G5		21	G#6	
9	G#5	847	22	A6	
10	A5		23	A#6	
11	A#5	944	24	B6	
12	B5		25	C7	
13	C6				

### **Description**

The terminal's sound buffer can store 16 notes of specified volume and duration. Additional sound controls are held in the communications input buffer invoking receive data flow control as needed.

There is no TSI report for sounds played.

### **DECRARA—Reverse Attributes in Rectangular Area**

This control function lets you reverse the visual character attributes (bold, blink, reverse video, and underline) of a specified rectangular area in page memory. The select attribute change extent (DECSACE) control function determines whether all or some of the character positions in the rectangle are affected.

Reversing a visual attribute means changing the attribute to its opposite setting, on or off. For example, DECRARA can change characters from bold and not underlined to characters that are underlined and not bold. DECRARA does not change the values of characters, just the visual attributes of those characters.

**Available in:** VT Level 4 or higher mode only

#### **Format**

CSI	Pt; Pl; Pb; Pr;	Ps1; Psn	\$	t
9/11	area to be reversed	attributes to reverse	2/4	7/4

#### **Parameters**

#### Pt, Pl, Pb, and Pr

define the rectangular area to be reversed.

**Pt** is the top-line border. *Pt* must be less than or equal to *Pb*.

Default: Pt = 1.

**Pl** is the left-column border. *Pl* must be less than or equal to Pr.

Default: Pr = 1.

**Pb** is the bottom-line border.

Default: Pb = last line of the active page.

Pr is the right-column border.

Default: Pr = last column of the active page.

#### Ps1; ... Psn

select the visual character attributes to reverse. These values correspond to the values used in the select graphic rendition (SGR) function.

Ps	Meaning
0	Reverse all attributes (default).
1	Reverse the bold attribute.
4	Reverse the underline attribute.
5	Reverse the blink attribute.
7	Reverse the negative-image attribute.

DECRARA ignores all other parameter values.

When you use more than one parameter in a command, DECRARA executes them cumulatively in sequence.

#### **DECRARA—Reverse Attributes in Rectangular Area**

#### **Examples**

The following sequence reverses the blink and underscore attributes of the complete screen:

```
CSI;;;;0;4;5;$t
```

The following sequence reverses all attributes except the blink attribute, from position line 10, column 2 to position line 14, column 45 on the current page:

```
CSI 10; 2; 14; 45; 1; 4; 7 $ t
```

#### Notes on DECRARA

- The coordinates of the rectangular area are affected by the setting of origin mode (DECOM).
- DECRARA is not affected by the page margins.
- If the value of *Pt, Pl, Pb,* or *Pr* exceeds the width or height of the active page, then the value is treated as the width or height of that page.
- DECRARA does not change the active cursor position.
- DECRARA does not change the current rendition set by the select graphic rendition (SGR) function.
- The exact character positions affected by DECRARA depend on the current setting of the select attribute change extent (DECSACE) function.

#### **DECRC—Restore Cursor**

Restores the terminal to the state saved by the save cursor (DECSC) function.

#### **Format**

### **Description**

If nothing was saved by DECSC, then DECRC performs the following actions:

- Moves the cursor to the home position (upper left of screen).
- Resets origin mode (DECOM).
- Turns all character attributes off (normal setting).
- Maps the ASCII character set into GL, and the DEC Supplemental Graphic set into GR.

#### Notes on DECSC and DECRC

The terminal maintains a separate DECSC buffer for the main display and the status line. This feature lets you save a separate operating state for the main display and the status line.

### **DECRLCM—Right-to-Left Copy Mode**

Perform a copy/paste from right-to-left or from left-to-right.

**Default:** Disable right-to-left-copy.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>9</b> 3/9	<b>6</b> 3/6	<b>h</b> 6/8	Enable right-to-left copy.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>9</b> 3/9	<b>6</b> 3/6	I 6/12	Disable right-to-left copy (default).

#### Description

This function is only recognized when the keyboard language is set to Hebrew. When operating in Copy/Paste, you can paste the copied text according to the direction assigned in this command sequence.

If right-to-left copy is selected, then the text is stored in the paste buffer starting from right-to-left. For example if "ABCD" is to be copied right-to-left, when a Paste key is pressed, the string is saved in the paste buffer as "DCBA." Thus, the text is displayed as "DCBA".

### **DECRLM—Right-to-Left Mode**

This control function starts/stops the right-to-left cursor direction.

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>3</b> 3/3	<b>4</b> 4/4	<b>h</b> 6/8	Set.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>3</b> 3/3	<b>4</b> 4/4	<b>I</b> 6/12	Reset.

#### **Description**

DECRLM state is common to both the main display and the status line display. The status line is effected only when you set it to Host Writable Status Display in the Display Set-Up screen. DECRLM does not affect column numbering within the line. The first line column is always at the left side of the display window. The last column is always at the right side of the display window.

The next character position is defined as the current cursor position minus 1.

If the terminal is in Replace mode (IRM is reset), then:

- The new character is inserted in the current cursor position.
- The cursor moves to the next character position.

If terminal is in Insert mode (IRM is set), then:

- All characters from the current cursor position to the left margin inclusively are shifted one position towards the left.
- The character previously displayed at the left margin disappears.
- The new character is inserted in the current cursor position.
- The cursor moves to the next character position.

The following escape sequences are affected by the DECRLM setting:

ICH - Insert Character **DECSED** - Selective Erase in Display DCH - Delete Character **DECSEL** - Selective Erase in Line ED - Erase in Display ECH - Erase Character EL - Erase in Line

The following escape sequences are not affected by the DECRLM setting:

**CUP** - Cursor Position

HVP - Horizontal and Vertical Position

**CUF** - Cursor Forward CUB - Cursor Backward

### **DECRLM—Right-to-Left Mode**

#### **Notes on DECRLM**

- The BS control character increases the current cursor position by one, thus moving the cursor on the screen one position to the right.
- When new line mode (LNM) is set and the terminal receives one of the control codes LF, VT, or FF, the cursor moves to the last right-most column of the next line.
- When control code CR is received, the cursor moves to the last right-most column of the current line.
- When control code SUB is received, a number of cancellation activities result
  within the terminal and the terminal displays an error character, according to
  the current DECRLM setting.
- When control code NEL is received, the cursor moves to the last right-most column of the next line. If the cursor is at the bottom margin, then the page scrolls up.
- If auto-wrap is enabled (DECAWM is set), then a graphic character received
  when the cursor is at column number one appears at the right margin column
  of the next line. If the cursor is at the end of the scrolling region, then any
  text already on the page scrolls up.

### **DECRPAK—Report All Modifiers/Alphanumeric Key State**

This control string is in response to a Request Key Definition (DECRQKD).

#### **Format**

#### **Description**

String D...D has a format same as DECPAK.

#### **Parameters**

D . . . D

See DECPAK for a description of parameters.

### **DECRPDE**—Report Displayed Extent

The terminal sends this control function in response to a request displayed extent (DECRQDE) sequence. DECRPDE indicates how much of the current page is displayed on the screen.

DECRPDE indicates how much of the screen has to display the current page.

#### **Format**

#### **Parameters**

#### Ph

is the number of lines of the current page displayed excluding the status line.

#### Pw

is the number of columns of the current page displayed.

#### Pml

is the column number displayed in the left-most column.

is the line number displayed in the top line.

#### **Pmp**

is the page number displayed.

### **DECRPFK - Report Function Key Definition**

The terminal reports a function key's definition when it receives a DECRQKD. DECRPFK denotes a local function number or a defined sequence, that the target key, which is combined with a specific modifier key, performs or transmits.

#### **Format**

#### **Parameters**

uses the same format as DECPFK, Key/Modifier/Function#/UDS/UDS Direction. Function# is skipped in the report, if the function key has not been redefined and is transmitting the default escape sequence as its UDS.

### **DECRPKT—Report Key Type**

DECRPKT (from the terminal) is a response to a key type inquiry (DECRQKT).

#### **Format**

#### **Parameters**

#### Ps1

indicates is the target key's station number.

#### Ps2

indicates

Ps2	Key Type
0	Alphanumeric
1	Function

### **DECRPL—Review Previous Lines Mode**

Allows user to view lines previously scrolled off the top of the page.

**Default:** Review previous lines disabled

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>1</b> 3/1	<b>1</b> 3/1	<b>2</b> 3/2	<b>h</b> 6/8	Set: enables review previous lines
<b>CSI</b> 9/11	<b>?</b> 3/15		<b>1</b> 3/1	<b>2</b> 3/2	<b>I</b> 6/12	Reset: disables review previous lines

### **Description**

This command rearranges page memory into a single page and a scroll back buffer (transcript). Refer to Set-Up chapter for details.

DECRPL can be reported using DECRQM and DECRPM.

### **DECRPM—Report Mode - Terminal To Host**

Reports the terminal mode in response to a request mode (DECRQM) function. In the response DECRPM informs the host if a certain mode is set (SM—Set Mode) or reset (RM—Reset Mode).

#### **Programming Tip**

Applications can use the information in the DECRPM report to save the current mode settings. Later, the application can restore the mode settings that were saved.

This operation is useful for applications that need to temporarily change some of the terminal's mode settings. When the application is finished, it can restore the mode settings that were in effect before the application changed them. You use the set mode (SM) and reset mode (RM) functions to restore mode settings. SM and RM are described later in this chapter.

There are two versions of DECRPM, for ANSI and DEC private modes.

### **Reporting ANSI Modes**

#### **Reporting DEC Private Modes**

CSI	?	Pd	;	Ps	\$	У
9/11	3/15	3/n	3/11	3/n	2/4	7/9

#### **Parameters**

#### Pa

Table 5-3 lists the values for Pa.

#### Pd

indicates which DEC private mode the terminal is reporting on. Table 5-3 lists the values for Pd.

#### Ps

indicates the setting of the mode. The *Ps* values are the same for the ANSI and DEC private versions.

Ps	Mode Setting
0	Mode not recognized
1	Set
2	Reset
3	Permanently set
4	Permanently reset

### **Examples**

The following sequence reports the setting of a DEC private mode:

VT520 Report	Meaning
CSI ? 57; h	(Greek) Keyboard mapping is currently set. (57 = DECNAKB, h = set)

The following sequences report the setting for some modes:

```
CSI Ps $ p (or CSI Ps $ p for DEC private) (Request Mode)
CSI Ps1; Ps2 $ y (or CSI ? Ps1; Ps2 $ y) (Report Mode)
CSI P1.....Pn l
                                           (Reset Mode)
CSI P1.....Pn h
                                           (Set Mode)
```

### **Notes on DECRPM**

The terminal can only report on one mode at a time.

# **DECRPM—Report Mode - Terminal To Host**

# **Description**

DECRQM, DECRPM, SM, and RM support all the mode settings as follows:

Table 5-3 Settings Supported by DECRQM, DECRPM, RM, and SM

Pa	NSI-Specified Mode Mnemonic	Pd .	DEC-Private Mode Mnemonic
1	GATM*	?1	DECCKM
2	KAM	?2	DECANM†
3	CRM	?3	DECOLM
4	IRM	?4	DECSCLM
5	SRTM*	?5	DECSCNM
		?6	DECOM
7	$VEM^*$	?7	DECAWM
		?8	DECARM
10	$HEM^*$	_	_
11	$PUM^*$	_	_
12	SRM		
13	$FEAM^*$	_	_
14	$\mathbf{FETM}^*$	_	_
15	$MATM^*$	_	_
16	$TTM^*$	_	_
17	SATM*	_	_
18	$TSM^*$	?18	DECPFF
19	$\mathbf{EBM}^*$	?19	DECPEX
20	LNM	_	_
_	-	?25	DECTCEM
_	-	?34	DECRLM
_	-	?35	DECHEBM
_	-	?36	DECHEM
_	-	?42	DECNRCM
_		?57	DECNAKB
_	-	?60	DECHCCM *
_	-	?61	DECVCCM
_	_	?64	DECPCCM
_	_	?66	DECNKM
_	_	?67	DECBKM
_	_	?68	DECKBUM
_	-	?69	DECLRMM (DECVSSM)
_	_	?73	DECXRLMM

<sup>\*</sup>This mode is always reset in the terminal and cannot be changed.

(continued on next page)

<sup>†</sup>When the terminal is set to VT52 mode, DECRQM provides no report.

# **DECRPM—Report Mode - Terminal To Host**

Table 5-3 (Cont.) Settings Supported by DECRQM, DECRPM, RM, and SM

-	ANSI-Specified Mode	D	EC-Private Mode	
Pa	Mnemonic	Pd	Mnemonic	
_	-	?95	DECNCSM	
_	-	?96	DECRLCM	
_	-	?97	DECCRTSM	
_	-	?98	DECARSM	
_	-	?99	DECMCM	
_	-	?100	DECAAM	
_	-	?101	DECCANSM	
_	-	?102	DECNULM	
_	-	?103	DECHDPXM	
_	-	?104	DECESKM	
_	-	?106	DECOSCNM	
_	-	?111	DECFWM	
_	-	?112	DECRPL	
_	-	?113	DECHWUM	
_	-	?114	DECATCUM	
_	-	?115	DECATCMB	
_	-	?116	DECBSM	
-	-	?117	DECECM	

# DECRPSS—Report Selection or Setting

The terminal sends the host this sequence in response to a request selection or setting (DECRQSS) sequence. The terminal sends DECRPSS to report the setting of a particular control function.

### **Programming Tip**

Applications can use the information in the DECRPSS report to save the current selections or settings of some control functions. Later, the application can restore the control functions to their saved state.

This operation is useful for applications that need to temporarily change the settings of some of the terminal's control functions. When the application is finished, it can restore the control functions to their previous state.

#### **Format**

DCS	Ps	\$	r	D D	ST
9/0	3/n	2/4	7/2		9/12

#### **Parameters**

#### Ps

indicates whether or not the request from the host is valid.

Ps	Host Request
0	Host's request is valid.
1	Host's request is invalid.

### D . . . D

indicates the current setting of a valid control function that the host asked about. D...D consists of all the characters in the control function, except the CSI (9/11) or ESC [ (1/11, 5/11) introducer characters.

### **Examples**

The host requests the setting of the select graphic rendition (SGR) function. If the current graphic rendition is underline, blinking, and reverse, then the terminal responds with the following DECRPSS sequence:

```
DCS 0 $ r 0 ; 4 ; 5 ; 7 m ST
```

**0**; **4**; **5**; **7 m** are all the characters in the SGR sequence, except CSI.

The host requests the setting of the set top and bottom margin function (DECSTBM). If the current top and bottom margins are set to include the complete screen area (24 lines/screen), then the terminal responds with the following DECRPSS sequence:

```
DCS 0 $ r 1 ; 24 r ST
```

 ${f 1}$ ;  ${f 24}$   ${f r}$  are all the characters in the DECSTBM sequence, except CSI.

The host requests the setting of a function that the terminal does not recognize. The terminal responds with the following DECRPSS sequence:

DCS 1 \$ r ST

The terminal does not send a data string (D...D) to the host when the terminal receives an invalid request.

DECRPSS (and DECRQSS) support the following settings or selections:

Setting	Mnemonic	Final Character(s)
Alternate Text Color	DECATC	, }
Assign Color	DECAC	,
CRT Saver Timing	DECCRTST	- q
Down Line Load Allocation	DECDLDA	, Z
Energy Save Timing	DECSEST	-r
Select Active Status Display	DECSASD	\$ }
Select Attribute Change Extent	DECSACE	* x
Select Auto Repeat Rate	DECARR	- p
Select Color Lookup Table	DECSTGLT	) {
<b>Select Communication Port</b>	DECSCP	* u
Select Communication Speed	DECSCS	* r
Select Digital Printed Data Type	DECSDPT	( p
Select Disconnect Delay Time	DECSDDT	\$ q
Select Flow Control Type	DECSFC	* s
Select Printer Type	DECSPRTT	\$ s
Select ProPrinter Character Set	DECSPPCS	* p
Select Set-Up Language	DECSSL	p
Select Zero Symbol	DECSZS	, {
Session Page Memory Allocation	DECSPMA	, X
Set Character Attribute	DECSCA	" q
Set Columns Per Page	DECSCPP	\$
Set Conformance Level	DECSCL	" p
Set Cursor Style	DECSCUSR	SP q
Set Graphic Rendition	SGR	m
Set Key Click Volume	DECSKCV	SP r
Set Left and Right Margins	DECSLRM	S
Set Lines Per Page	DECSLPP	t
Set Lock Key Style	DECSLCK	SP v
Set Margin Bell Volume	DECSMBV	SP u
Set Number of Lines per Screen	DECSNLS	*
Set Port Parameter	DECSPP	+ w
Set Scroll Speed	DECSSCLS	SP p
Set Status Line Type	DECSSDT	\$ ~

# **DECRPSS—Report Selection or Setting**

Setting	Mnemonic	Final Character(s)
Set Top and Bottom Margins	DECSTBM	r
Set Transmit Rate Limit	DECSTRL	" u
Set Warning Bell Volume	<b>DECSWBV</b>	SP t
Terminal Mode Emulation	DECTME	SP ~

# **DECRPTUI**—Report Terminal Unit ID

DECRPTUI is a response from the terminal to a tertiary DA (DA3) request from the host.

Available in: VT Level 4 or higher mode only. See DA3 for more information.

### **Format**

### **Parameters**

### D...D

is the unit ID of the terminal, consisting of four hexadecimal pairs. The first pair represents the manufacturing site code. This code can be any hexadecimal value from 00 through FF.

The last three pairs are the terminal ID number. This number is unique for each terminal manufactured at that site.

# DECRQCRA—Request Checksum of Rectangular Area

This control function requests a checksum of the specified rectangular area in the specified page. The terminal returns a checksum report (DECCKSR) in response to this request.

#### **Format**

```
CSI Pid ; Pp; Pt;Pl;Pb;Pr * y 9/11 3/n 3/11 3/n 3/n . . . 3/n 2/10 7/9
```

#### **Parameters**

#### Pid

is a numeric label you can provide to identify the checksum request. The checksum report returns this number. The number serves to differentiate between multiple checksum reports.

#### Pp

is the page number that has the rectangular area. If Pp is 0 or omitted, then the terminal ignores the following parameters and reports a checksum for all pages in page memory. If Pp is a higher number than the number of pages available, then the terminal reports on the last page.

### Pt;PI;Pb;Pr

are the top, left, bottom, and right borders of the rectangular area. Pt and Pb are line numbers. Pt must be less than or equal to Pb. Pl and Pr are column numbers. Pl must be less than or equal to Pr.

Defaults are Pt = 1, Pb = current page length, Pr = current page width. If these parameters are omitted, then the terminal returns a checksum of page Pp.

### Note on DECRQCRA

The coordinates of the rectangular area are affected by the setting of origin mode (DECOM).

# **DECRQDE—Request Displayed Extent**

The host sends a DECRQDE to the terminal requesting how much of the current page is displayed on the screen for the active session.

#### **Format**

# **DECRQKD—Request Key Definition**

DECRQKD allows you to inquire about the terminal's definition of:

- A function key or a function key combined with a single modifier key.
- An alphanumeric key combined with all of its available modifier keys.

The terminal reports the function key definition with DECRPFK, and the alphanumeric key definition with DECRPAK.

### **Format**

#### **Parameters**

#### Ps1

indicates is the target key's station number. When inquiring for an alphanumeric key definition, *Ps2* is ignored by the terminal. DECRPAK always reports a hexadecimal string in which each code represents a value transmitted by pressing a combination of the target key and a modifier key. See DECRPAK.

**ps** When inquiring for a function key definition, *Ps2* represents:

Ps2	Description
0, 1 or none	Normal
2	Shift
3	Alt
4	Alt + Shift
5	Control
6	Shift + Control
7	Alt + Control
8	Alt + Control + Shift

If you enter an invalid key/modifier, the entire sequence is ignored.

# **DECRQKT—Request Key Type**

The host issues a DECRQKT to the terminal for the key definition of a function or alphanumeric key. Upon receiving the request, the terminal reports using DECRPKT.

### **Format**

### **Parameters**

### Ps

is a decimal number representing the target key's station number.

# **DECRQM—Request Mode - Host To Terminal**

The host sends this control function to find out if a particular mode is set or reset. The terminal responds with a report mode function (DECRPM—Report Mode - Terminal To Host).

DECRQM functions in ANSI and DEC private modes.

### **Requesting ANSI Modes**

### **Requesting DEC Private Modes**

### **Parameters**

#### Pa

indicates the ANSI mode that the host is asking about. Table 5-4 lists the values for Pa.

#### Pd

indicates the DEC private mode the host is asking about. Table 5-5 lists the values for Pd.

### **Examples**

The following sequences request the setting of some ANSI modes:

Host	Meaning
CSI 2 \$ p	What is the current state of keyboard action mode (KAM)? (KAM = 2)
CSI 4 \$ p	What is the current state of insert/replace mode (IRM)? $(IRM = 4)$

The following sequences request the setting of some DEC private modes:

Host	Meaning
CSI ? 36 \$ p	What is the current state of Hebrew encoding mode (DECHEM)? (DECHEM = 36)
CSI ? 6 \$ p	What is the current state of origin mode (DECOM)? (DECOM = 6)

### **Notes on DECRQM**

- The terminal does not respond to a DECRQM sequence when in VT52 mode.
- A DECRQM sequence can only ask about one mode at a time.

Table 5-4 ANSI Modes for DECRQM, DECRPM, SM, and RM

Mode	Mnemonic	Pa	
Guarded area transfer	GATM*	1	
Keyboard action	KAM	2	
Control representation	CRM†	3	
Insert/replace	IRM	4	
Status reporting transfer	SRTM*	5	
Vertical editing	$VEM^*$	7	
Horizontal editing	HEM*	10	
Positioning unit	PUM*	11	
Send/receive	SRM	12	
Format effector action	FEAM*	13	
Format effector transfer	$\mathbf{FETM}^*$	14	
Multiple area transfer	$MATM^*$	15	
Transfer termination	$TTM^*$	16	
Selected area transfer	SATM*	17	
Tabulation stop	TSM*	18	
Editing boundary	$\mathbf{EBM}^*$	19	
Line feed/new line	LNM	20	

<sup>\*</sup>This control function is permanently reset.

 $<sup>\</sup>dagger$ The host cannot change the setting of CRM. You can only change CRM from Set-Up. If CRM is set, then the terminal ignores DECRQM and most other control functions.

Table 5–5 DEC Private Modes for DECRQM, DECRPM, SM, and RM

Mode	Mnemonic	Pd
Cursor keys	DECCKM	1
ANSI	DECANM	2
Column	DECCOLM	3
Scrolling	DECSCLM	4
Screen	DECSCNM	5
Origin	DECOM	6
Autowrap	DECAWM	7
Autorepeat	DECARM	8
Print form feed	DECPFF	18
Printer extent	DECPEX	19
Text cursor enable	DECTCEM	25
Cursor direction, right to left	DECRLM	34
Hebrew keyboard mapping	DECHEBM	35
Hebrew encoding mode	DECHEM	36
National replacement character set	DECNRCM	42
Greek keyboard mapping	DECNAKB	57
Horizontal cursor coupling	DECHCCM	60
Vertical cursor coupling	DECVCCM	61
Page cursor coupling	DECPCCM	64
Numeric keypad	DECNKM	66
Backarrow key	DECBKM	67
Keyboard usage	DECKBUM	68
Vertical split screen	DECVSSM /DECLRMM	69
Transmit rate limiting	DECXRLM	73
Key position mode	DECNCSM	95
Key position mode	DECRLCM	96
Key position mode	DECCRTSM	97
Key position mode	DECARSM	98
Key position mode	DECMCM	99
Key position mode	DECAAM	100
Key position mode	DECCANSM	101
Key position mode	DECNULM	102
Key position mode	DECHDPXM	103
Key position mode	DECESKM	104
Key position mode	DECOSCNM	106

# **DECRQPKFM—Request Program Key Free Memory**

Inquire as to the amount of free memory for programmable key operations.

### **Format**

# **Description**

Upon receiving of this sequence, the terminal responds with DECPKFMR.

# **DECRQPSR—Request Presentation State Report**

The host sends this sequence to request a cursor information report (DECCIR) or tabulation stop report (DECTABSR).

### **Format**

### **Parameters**

#### Ps

indicates which report the host requests.

Ps	Report Requested
0	Error. Request ignored
1	Cursor information report (DECCIR)
2	Tab stop report (DECTABSR)

# **DECRQSS—Request Selection or Setting**

The host requests the terminal setting. See DECRPSS for the terminal's response.

### **Format**

### **Parameters**

D . . . D

indicates the current setting of a valid control function that the host asked about. D... D consists of all the characters in the control function, except the CSI (9/11) or ESC [(1/11, 5/11)] introducer characters.

# **Description**

DECRQSS (and DECRPSS) support the following settings or selections:

Setting	Mnemonic	Final Characters
Alternate Text Color	DECATC	, }
Assign Color	DECAC	,
CRT Saver Timing	DECCRTST	- q
Down Line Load Allocation	DECDLDA	, Z
Energy Save Timing	DECSEST	-r
Select Active Status Display	DECSASD	\$ }
Select Attribute Change Extent	DECSACE	* x
Select Auto Repeat Rate	DECARR	- p
Select Color Lookup Table	DECSTGLT	) {
Select Communication Port	DECSCP	* u
Select Communication Speed	DECSCS	* r
Select Digital Printed Data Type	DECSDPT	( p
Select Disconnect Delay Time	DECSDDT	\$ q
Select Flow Control Type	DECSFC	* s
Select Printer Type	DECSPRTT	\$ s
Select ProPrinter Character Set	DECSPPCS	* p
Select Set-Up Language	DECSSL	p
Select Zero Symbol	DECSZS	, {
Session Page Memory Allocation	DECSPMA	, X
Set Character Attribute	DECSCA	" q
Set Columns Per Page	DECSCPP	\$
Set Conformance Level	DECSCL	" p

Setting	Mnemonic	Final Characters
Set Cursor Style	DECSCUSR	SP q
Set Graphic Rendition	SGR	m
Set Key Click Volume	DECSKCV	SP r
Set Left and Right Margins	DECSLRM	S
Set Lines Per Page	DECSLPP	t
Set Lock Key Style	DECSLCK	SP v
Set Margin Bell Volume	DECSMBV	SP u
Set Number of Lines per Screen	DECSNLS	*
Set Port Parameter	DECSPP	+ W
Set Scroll Speed	DECSSCLS	SP p
Set Status Line Type	DECSSDT	\$ ~
Set Top and Bottom Margins	DECSTBM	r
Set Transmit Rate Limit	DECSTRL	" u
Set Warning Bell Volume	DECSWBV	SP t
Terminal Mode Emulation	DECTME	SP ~

# **DECRQTSR—Request Terminal State Report**

The host requests the terminal to report its state. The terminal reports (DECTSR) by indicating the setting of many device attributes. See DECTSR.

### **Format**

### **Parameters**

### Ps

indicates the type of report the host requests from the terminal.

Ps	Report Requested	
0 or none	Ignored. No report sent.	
1	Terminal state report (DECTSR)	

# Response

### DCS 1 \$ s D ... D ST

 $D \dots D$ 

See Device Attributes (DA1, DA2, DA3).

# **DECCTR—Color Table Request**

The host requests a color table report from the terminal. The terminal responds with a DECTSR control with parameter 2 and each color table entry.

### **Format**

### **Parameters**

#### Pu

is a parameter to select the type of color coordinate system that the terminal uses to report the color map.

Pu	Report Requested
0	Illegal
1	HLS (hue 0-360, lightness 0-100, saturation 0-100)
2	RGB (red 0-100, green 0-100, blue 0-100)

# Response

 $D \dots D$ 

See (DECTSR - Terminal State Report (Color Table Report)).

# **DECRQUPSS**—Request User-Preferred Supplemental Set

Applications can ask for the current user-preferred supplemental set. The terminal responds with the user-preferred supplemental set (DECAUPSS) sequence.

#### **Host Request (DECRQUPSS)**

The host requests the current user-preferred supplemental set by sending the following sequence:

### **Format**

### **Terminal Responses**

The terminal uses the DECAUPSS device control string to report the current user-preferred supplemental set (UPSS). The terminal sends DECAUPSS in response to a DECRQUPSS sequence. As examples, the terminal can send the following reports:

Control Sequence	UPSS
DCS 0 ! u % 5 ST	The user-preferred supplemental set is DEC Supplemental Graphic.
DCS 1! u A ST	The user-preferred supplemental set is ISO Latin-1 supplemental.

For a complete listing of combinations, see DECAUPSS—Assign User-Preferred Supplemental Character Set.

### **DECRSPS—Restore Presentation State**

This control function restores the terminal to a previous state based on one of the presentation state reports. There are two presentation state reports.

Available in: VT Level 4 or higher mode only.

Cursor information report (DECCIR) Tab stop report (DECTABSR)

A DECRSPS sequence can only restore the information from one report at a time, cursor information, or tab stop.

### **Programming Tip**

Applications can use DECRSPS to restore the terminal to a previous state specified in a presentation state report. See the previous "Cursor Information Report (DECCIR)" section in this chapter.

### **Format**

DCS	Ps	\$	t	D D	ST
9/0	3/n	2/4	7/4		9/12

### **Parameters**

#### Ps

indicates the format of the data string (D  $\dots$  D). You can use one of the two following formats for the data string. These formats correspond to the formats used in the two presentation state reports (DECPSR). Make sure you use the format of the report you are restoring.

Ps	Data String Format
0	Error, restore ignored.
1	Selects the format of the cursor information report (DECCIR).
2	Selects the format of the tab stop report (DECTABSR).

#### D . . . D

is a data string that contains the restored information. This string is identical to the data string used in the report you are restoring— Cursor Information Report (DECCIR) or Tab Stop Report (DECTABSR).

### **Examples**

The following DECRSPS sequence restores tab stops according to the tab stop report (DECTABSR):

```
DCS 2 $ t 9/ 17/ 25/ 33/ 41/ 49/ 57/ 65/ 73 ST
```

Note that the data string format above is exactly the same as the format for the tab stop report (DECTABSR). If there is an invalid value in the DECRSPS sequence, then the terminal ignores the rest of the sequence. This action may leave the terminal in a partially restored state.

### **DECRSTS—Restore Terminal State**

This sequence restores the terminal to a previous state specified in a terminal state report (DECTSR).

**Available in:** VT Level 4 or higher mode only.

### **Programming Tip**

Applications can use DECRSTS to restore the terminal to a previous operating state specified in a terminal state report.

#### **Format**

### **Parameters**

#### Ps

indicates the format of the data string (D . . . D).

Ps	Data String Format
0	Error, restore ignored
1	Selects the format of the terminal state report (DECTSR)

is a data string that contains the restored information. This string is identical to the data string used by the report you are restoring.

### **Notes on DECRSTS**

- If there is an invalid value in the DECRSTS sequence, then the terminal ignores the rest of the sequence. This action may leave the terminal in a partially restored state.
- Software should not expect the format of the terminal state report (DECTSR) to be the same for all VT400 family members.

### **DECRSTS—Restore Terminal Color Table State**

A host request to restore a color table.

#### **Format**

### **Parameters**

#### D . . . D

is a data string that contains the groups of five parameters for each color map to restore as follows:

```
Pc; Pu; Px; Py; Pz / Pc; Pu; Px; Py; Pz / ...
```

#### where:

Pc is the color number 0 -255.

Pu is the color coordinate system.

- 1—HLS (hue 0-360, lightness 0-100, saturation 0-100)
- 2-RGB (red 0-100, green 0-100, blue 0-100)

Px, Py, Pz are values in the color coordinate system.

; is the semicolon (3/11).

/ is the slash character (2/15).

# Description

To load a previously reported color map, the host transmits a DECRSTS control with parameter 2 and the desired color map definitions in the data string. When loading a color map, only the index entries specified are changed. Also see DECRQTSR and DECTSR for requesting color maps and the terminal's report.

# **DECSACE—Select Attribute Change Extent**

Selects which character positions within a rectangle are affected by an attribute change.

Available in: VT Level 4 or higher mode only

### **Format**

### **Parameters**

# **Ps** selects the area of character positions affected.

Ps	Area Effected
0 (default)	DECCARA or DECRARA affect the stream of character positions that begins with the first position specified in the DECCARA or DECRARA command, and ends with the second character position specified.
1	Same as 0.
2	DECCARA and DECRARA affect all character positions in the rectangular area. The DECCARA or DECRARA command specifies the top-left and bottom-right corners.

# **DECSASD—Select Active Status Display**

DECSASD selects whether the terminal sends data to the main display or the status line.

**Available in:** VT Level 4 or higher mode only

**Default:** Main display

### **Format**

### **Parameters**

#### Ps

indicates the display to which the terminal sends data.

Ps	Action
0 (default)	Selects the main display. The terminal sends data to the main display only.
1	Selects the status line. The terminal sends data to the status line only.

# **DECSC—Save Cursor**

### **Format**

### **Description**

Saves the following items in the terminal's memory:

- Cursor position
- Character attributes set by the SGR command
- Character sets (G0, G1, G2, or G3) currently in GL and GR
- Wrap flag (autowrap or no autowrap)
- State of origin mode (DECOM)
- Selective erase attribute
- Any single shift 2 (SS2) or single shift 3 (SS3) functions sent

# **DECSCA—Select Character Protection Attribute**

DECSCA defines the characters that come after it as erasable or not erasable from the screen. The selective erase control functions (DECSED and DECSEL) can only erase characters defined as erasable.

Available in: VT Level 4 or higher mode only

### **Format**

### **Parameters**

#### Ps

defines all characters that follow the DECSCA function as erasable or not erasable.

Ps	Meaning
0 (default)	DECSED and DECSEL can erase characters.
1	DECSED and DECSEL cannot erase characters.
2	Same as 0.

### **Note on DECSCA**

DECSCA does *not* effect visual character attributes set by the select graphic rendition (SGR) function.

# **DECSCL—Select Conformance Level**

Using DECSCL, you can select the terminal's conformance level. The factory default for the VT500 family is level 5 (VT Level 5 mode, 8-bit controls).

Note	
When you change the operating level, the terminal performs a hard re(RIS).	eset

### **Format**

Sequence						Level Selected	
							Level 1
<b>CSI</b> 9/11	<b>6</b> 3/6	<b>1</b> 3/1	" 2/2	<b>p</b> 7/0			VT100 mode
							Level 5†
<b>CSI</b> 9/11	<b>6</b> 3/6	n 3/n	" 2/2	<b>p</b> 7/0			VT Level 5 mode, 8-bit controls
<b>CSI</b> 9/11	<b>6</b> 3/6	n 3/n	; 3/11	<b>0</b> 3/0	" 2/2	<b>p</b> 7/0	VT Level 5 mode, 8-bit controls
<b>CSI</b> 9/11	<b>6</b> 3/6	n 3/n	; 3/11	<b>1</b> 3/2	" 2/2	<b>p</b> 7/0	VT Level 5 mode, 7-bit controls
<b>CSI</b> 9/11	<b>6</b> 3/6	n 3/n	; 3/11	<b>2</b> 3/2	" 2/2	<b>p</b> 7/0	VT Level 5 mode, 8-bit controls

†Level 5 includes levels 2, 3, and 4. In these sequences, n can be 2, 3, 4, or 5.

# **DECSCLM—Scrolling Mode**

This control function selects the way the terminal scrolls lines. You can select one of two scroll settings, smooth or jump.

**Default:** Smooth scroll.

#### **Format**

### **Description**

When DECSLM is set, the terminal adds lines to the screen at a moderate, smooth rate. You can select a slow rate or fast rate in Display Set-Up.

When DECSLM is reset, the terminal can add lines to the screen as fast as it receives them.

# **DECSCNM—Screen Mode: Light or Dark Screen**

This control function selects a dark or light background on the screen.

**Default:** Dark background.

#### **Format**

### **Description**

When DECSCNM is set, the screen displays dark characters on a light background.

When DECSCNM is reset, the screen displays light characters on a dark background.

### Note on DECSCNM

Screen mode only effects how the data appears on the screen. DECSCNM does not change the data in page memory.

### **DECSCP—Select Communication Port**

Select the port to be used for printer or host connection.

#### **Format**

### **Parameters**

#### Ps1

indicates the port selection for a printer connection. The VT520 enables you to select from a Centronics parallel port.

Ps1	Printer Port	
0	None	
1	Centronics	
4	Comm3	

#### Ps2

indicates the port selection for a host connection. The host session can connect to the Comm1, Comm2, or Comm3 port.

Ps2	Session 1	
1	Comm1	
2	Comm2	
3	Comm3	

### **Description**

The VT520 provides three serial ports and a parallel port. Any of the serial ports can be used as a host communication port, but only Comm3 and the parallel printer port can be a printer port.

The VT520 provides up to four session virtual terminals. When a session virtual terminal is assigned to a communication port, it is said to exist. You cannot create or destroy a session virtual terminal from the host since no communication is possible with a virtual terminal that does not exist.

If you assign two or more session virtual terminals to the same communication port, the Terminal Device/Session Management Protocol (TD/SMP) is used to multiplex the sessions. The host can open or close session connections with any currently existing virtual terminal.

DECSCP can be reported using DECRPSS.

# **DECSCPP—Select Columns Per Page**

There are two control functions that can set the page width to 80 or 132 columns, DECSCPP and DECCOLM (DECCOLM—Selecting 80 or 132 Columns per Page ).

It is recommended that new applications use DECSCPP rather than

It is recommended that new applications use DECSCPP rather than DECCOLM. DECSCPP does not clear page memory or reset the scrolling regions as does DECCOLM. DECCOLM is provided mainly for compatibility with previous products.

**Default:** 80 columns

#### **Format**

Seque	nce					Sets Each Page to
<b>CSI</b> 9/11	<b>\$</b> 2/4	 7/12				80 columns.
<b>CSI</b> 9/11	<b>0</b> 3/0	<b>\$</b> 2/4	 7/12			80 columns.
<b>CSI</b> 9/11	<b>8</b> 3/8	<b>0</b> 3/0	<b>\$</b> 2/4	 7/12		80 columns.
<b>CSI</b> 9/11	<b>1</b> 3/1	<b>3</b> 3/3	<b>2</b> 3/2	<b>\$</b> 2/4	 7/12	132 columns.

### **Notes on DECSCPP**

- DECSCPP changes the font to match the current number of columns on the page.
- DECSCPP does not move the cursor. If, however, the cursor is beyond the width of the new page when DECSCPP executes, then the cursor moves to the right column of the new page.
- If you switch from 132-column to 80-column pages, then you can lose data from page memory. Columns no longer present in page memory are lost. Make sure you set page columns *before* you enter data into page memory.

# **DECSCS—Select Communication Speed**

Select a communication speed for a communication line.

### **Format**

**CSI** *Ps1* ; *Ps2* \* **r** 9/11 3/*n* 3/11 3/*n* 2/10 7/2

### **Parameters**

**Ps1** indicates the communication line.

Ps1	Comm Line Type
1, 0 or none	Host Transmit
2	Host Receive
3	Printer
4	Modem Hi
5	Modem Low

**Ps2** indicates the communication speed.

Ps2	Speed	Ps2	Speed	
0 or none	default	6	9600	
1	300	7	19200	
2	600	8	38400	
3	1200	9	57600	
4	2400	10	76800	
5	4800	11	115200	

The default value depends on the type of communication line.

Communication Line	Default Communication Speed
Host Transmit	9600
Host Receive	Receive=transmit
Printer	4800
Modem Hi	Ignore
Modem Low	Ignore

# **DECSCUSR—Set Cursor Style**

Select the style of the cursor on the screen.

### **Format**

### **Parameters**

#### Ps

indicates the style of the cursor.

Ps	Cursor Style
0, 1 or none	Blink Block (Default)
2	Steady Block
3	Blink Underline
4	Steady Underline

This sequence causes the cursor to be displayed in a different style when the cursor is enabled.

### **Note on DECSCUSR**

The escape sequence DECTCEM can enable or disable the cursor display.

# **DECSDDT—Select Disconnect Delay Time**

Select an appropriate disconnect delay time.

### **Format**

### **Parameters**

#### Ps

indicates the selection for the disconnect delay time.

Ps	Disconnect Delay Time
1	None
2	60 ms
3, 0 or none	2 seconds

### **Description**

The disconnect delay feature determines the time allowed before the terminal disconnects from the communications line when the Received Line Signal Detect (RLSD) is lost.

All countries except the United Kingdom should use the 2 seconds delay. The 60 ms delay is for use in the United Kingdom.

If the terminal detects a loss of carrier and if the user has selected "no disconnect," then the terminal ignores RLSD (CD) after the beginning of the connection.

If the user tries to disconnect and reconnect the line, then the terminal checks if RLSD is asserted before granting the connection. Once it is connected, the terminal ignores the loss of carrier. In this case, the disconnect should be done on DSR going off.

# **DECSDPT—Select Digital Printed Data Type**

Allow users to match the characters printed to the character sets the DEC ANSI conforming printer is capable of supporting.

### **Format**

### **Parameters**

#### Ps

denotes the selection for printed data type.

Ps	Printed Data Type
1, 0 or none	Print National Only (Default)
2	National and Line Drawing
3	Print Multinational
4	Print All Characters

# **DECSED—Selective Erase in Display**

This control function erases some or all of the erasable characters in the display. DECSED can only erase characters defined as erasable by the DECSCA control function. DECSED works inside or outside the scrolling margins.

Available in: VT Level 4 or higher mode only

### **Format**

### **Parameters**

#### Ps

represents the area of the display to erase, as follows:

Ps	Area Erased
0 (default)	From the cursor through the end of the display
1	From the beginning of the display through the cursor
2	The complete display

# **DECSEST—Energy Saver Timing**

# **DECSEST—Energy Saver Timing**

Selects the energy saver timing.

**Default:** 15 minutes

### **Format**

### **Parameters**

### Ps

**Energy Saver Timing** 

Ps	Selection
0	Never
5	5 minutes
15	15 minutes
30	30 minutes

# **Description**

The **Energy saver** feature switches the monitor to suspend mode after the specified interval of CRT saver active. The energy saver is disabled if the CRT saver is set to never. Refer to the Set-Up chapter for details.

DECSEST can be reported using DECRPSS.

# **DECSEL—Selective Erase in Line**

This control function erases some or all of the erasable characters in a single line of text. DECSEL erases only those characters defined as erasable by the DECSCA control function. DECSEL works inside or outside the scrolling margins.

**Available in:** VT Level 4 or higher mode only

### **Format**

### **Parameters**

### Ps

represents the section of the line to erase, as follows:

Ps	Section Erased
0 (default)	From the cursor through the end of the line
1	From the beginning of the line through the cursor
2	The complete line

# **DECSERA—Selective Erase Rectangular Area**

This control function erases all erasable characters from a specified rectangular area in page memory. The select character protection attribute (DECSCA) control function defines whether or not DECSERA can erase characters.

When an area is erased, DECSERA replaces character positions with the space character (2/0). DECSERA does not change:

- Visual attributes set by the select graphic rendition (SGR) function
- Protection attributes set by DECSCA
- Line attributes

Available in: VT Level 4 or higher mode only

#### **Format**

### **Parameters**

#### Pt, Pl, Pb, and Pr

define the rectangular area to be selectively erased:

**Pt** is the top-line border. *Pt* must be less than or equal to *Pb*.

Default: Pt = 1.

**Pl** is the left-column border. *Pl* must be less than or equal to *Pr*.

Default: Pl = 1.

**Pb** is the bottom-line border.

Default: Pb = the last line of the active page.

Pr is the right-column border.

Default: Pr = the last column of the active page.

### **Notes on DECSERA**

- The coordinates of the rectangular area are affected by the setting of origin mode (DECOM).
- DECSERA is not affected by the page margins.
- If the value of *Pt, Pl, Pb,* or *Pr* exceeds the width or height of the active page, then the value is treated as the width or height of that page.
- DECSERA does not change the active cursor position.

# **DECSFC—Select Flow Control**

Select a flow control scheme for the communication port or printer port.

### **Format**

### **Parameters**

#### Ps1

determines which port is to be assigned the flow control scheme.

Ps1	Port Type
1, 0 or none	Comm Port
2	Printer Port

#### Ps2

indicates the flow method. On the VT520, the transmit side or the receive side of the communication line can select different or the same flow control methods.

Ps2	Transmit or Receive
1, 0 or none	Transmit
2	Receive
3	Transmit and Receive

#### Ps3

is for the flow control type. When the terminal is in PCTerm mode, XPC replaces XON/XOFF on the receive side.

Ps3	Flow Control Type
1, 0 or none	XON/XOFF or XPC (XPC is for receive only)
2	DTR
3	Both
4	None

### **DECSFC—Select Flow Control**

**Ps4** sets the flow control threshold.

Ps4	Flow Control Threshold
1, 0 or none	Low (64)
2	High (768)

The terminal uses "low" and "high" to denote the flow control threshold.

- If Low is selected, then the terminal sends an XOFF (if in software flow control) or lower DTR (in hardware flow control) to notify the host of holding transmission when the input buffer reaches 64 bytes.
- If High is selected, then 768 bytes is the flow control threshold.

"High" flow control threshold is not available for the printer port, which always uses low (64 bytes) as the flow control threshold.

### **DECSIN—Set Icon Name**

Specifies a descriptive name, up to 12 characters, for this session's icon, using an OSC string.

### **Format**

Where D...D is:

# **Description**

DECSIN specifies a descriptive name, up to 12 characters, for this session's icon.

There is no TSI report for the session icon name.

## **DECSKCV—Set Key Click Volume**

Set the keyclick volume.

### **Format**

### **Parameters**

#### Ps

indicates the selection of the click volume.

Ps	Key Click Volume
1	Off
2, 3, 4	Low
5, 6, 7, 8, 0 or none	High (Default)

## **DECSLCK—Set Lock Key Style**

Allow the host to control the Caps Lock key.

### **Format**

## **Parameters**

### Ps

indicates the selection of the Caps Lock key.

Ps	Lock Style	Meaning
1, 0 or None	Caps Lock (Default)	Lock alpha keys on main keypad in uppercase.
2	Shift Lock	Lock alpha and numeric keys on main keypad in shifted setting.
3	Reverse Lock	Works the same as Caps Lock, except that pressing Shift while Reverse Lock is active will send the lowercase or unshifted character assigned to a key. Thus, the lock state is reversible.

## **DECSLPP—Set Lines Per Page**

This control function sets the number of lines for each page in page memory.

**Default:** One session—6 pages of 24 lines

#### **Format**

#### **Parameters**

#### Pn

Sets the lines per page according to the numeric parameter.

### Description

If the number of lines specified is not one of the values supported by the implementation, then the next higher supported number of lines per page is assumed. If the number of lines specified exceeds the maximum number supported, then the maximum number supported is used. The valid Pn values are 24, 25, 36, 41, 42, 48, 52, 53, and 72.

The VT520 supports three pages of off-screen memory in the following configurations:

- 3 pages × 24 lines (default)
- 2 pages  $\times$  25 lines
- 2 pages  $\times$  36 lines
- 1 pages  $\times$  41 lines
- 1 pages  $\times$  42 lines
- 1 pages × 48 lines
- 1 pages  $\times$  52 lines
- 1 pages  $\times$  53 lines
- 1 pages  $\times$  72 lines

#### Notes on DECSLPP

- If you switch to a smaller page size, then data that was on the larger page may be split across the smaller pages. To avoid confusion, make sure you set the lines/page *before* you enter data into page memory.
- DECSLPP usually does not change the top and bottom scrolling margins.
   If, however, you change the page size so that the current scrolling margins exceed the new page size, then the terminal resets the margins to the page limits.

## **DECSLRM—Set Left and Right Margins**

This control function sets the left and right margins to define the scrolling region. DECSLRM only works when vertical split screen mode (DECLRMM) is set.

Available in: VT Level 4 or higher mode only

**Default:** Margins are at the left and right page borders.

#### **Format**

#### **Parameters**

#### Ы

is the column number for the left margin.

Default: Pl = 1.

#### P

is the column number for the right margin.

Default: Pr = 80 or 132 (depending on the page width).

#### **Notes on DECSLRM**

- The value of the left margin (*Pl*) must be less than the right margin (*Pr*).
- The maximum size of the scrolling region is the page size, based on the setting of set columns per page (DECSCPP).
- The minimum size of the scrolling region is two columns.
- The terminal only recognizes this control function if vertical split screen mode (DECLRMM) is set.
- DECSLRM moves the cursor to column 1, line 1 of the page.
- If the left and right margins are set to columns other than 1 and 80 (or 132), then the terminal cannot scroll smoothly.

## **DECSMBV—Set Margin Bell Volume**

Set the margin bell volume.

### **Format**

### **Parameters**

#### Ps

indicates the selection of the bell volume.

Ps	Key Click Volume
1, 0 or none	Off (default)
2, 3, 4	Low
5, 6, 7, 8	High

## **Description**

This sequence is used to adjust the margin bell volume, which sounds as the current position nears the right margin.

## **DECSMKR—Select Modifier Key Reporting**

Program the modifier keys to send extended keyboard reports when pressed or released. DECSMKR only works when key position mode (DECKPM) is set. Applications can use DECSMKR to gain more control over the keyboard by monitoring the action of each modifier key.

#### **Format**

#### **Parameters**

#### **Pmn**

is the key number that corresponds to the modifier key affected. A *Pmn* value of 0 selects all modifier keys.

Pmn	Key	Default Function
1	left Shift	Local shift.
2	right Shift	Local shift.
3	Lock	Local lock.
4	Ctrl	Local control.
5	left Alt Function	Report up or down transitions.
6	right Alt Function	Report up or down transitions.
7	left Compose Character	Local compose.
8	right Compose Character	Local compose.

#### Pfn

controls the action of the modifier key specified by the corresponding *Pmn* value.

Pfn	Meaning
0	Selects the default function of the key.
1	The key performs its default modifier function.
2	The key sends an extended keyboard report when pressed or released. The key does not modify other keystrokes or perform its default function.
3	The key is disabled.

## Description

DECSMKR can accept any number of parameter pairs. The terminal executes the parameters in the order in which it receives them. Applications cannot change the function of the  $\boxed{\texttt{F5}}$  (Break) key. This restriction is required for secure systems to ensure that the operator has control of the communication line.

## **DECSNLS—Set Number of Lines Per Screen**

Set the maximum lines that can be displayed on the screen.

#### **Format**

## **Description**

The terminal supports three different font heights, which allows 26, 42, or 53 data lines to be displayed on the screen or 25, 41, or 52 data lines to be displayed on the screen, plus a status line. The different character fonts are:

	80/26	132/26	80/42	132/42	80/53	132/53
Cell Width	10	6	10	6	10	6
Cell Height	16	16	10	10	8	8

### **Valid Combinations**

The terminal has the following valid combinations:

Lines Per Screen	Refresh Rate	Overscan	
26	72 Hz	No	
26	72 Hz	Yes	
26	60 Hz	No	
26	60 Hz	Yes	
42	72 Hz	No	
42	60 Hz	No	
42	60 Hz	Yes	
53	72 Hz	No	
53	60 Hz	No	
53	60 Hz	Yes	

If an invalid combination is selected, the terminal automatically returns to a valid combination according to the following priority order:

- 1. Lines Per Screen
- 2. Refresh Rate
- 3. Overscan

## **Examples**

The current combination is 26 lines/72 Hz/Overscan. If you attempt to assign 42 lines per screen, then the terminal becomes 42 lines/72 Hz/No Overscan.

The current combination is 42 lines/60 Hz/Overscan. If you attempt to assign 72 Hz refresh rate, then the terminal becomes 42 lines/72 Hz/No Overscan.

The current combination is 53 lines/72 Hz/No Overscan. Any attempt to enable Overscan is invalid.

## **DECSPMA—Session Page Memory Allocation**

Allocates 25 line pages to each session according to the corresponding parameters.

#### **Format**

### **Description**

Pages are allocated for each session in order (1 through 4). An omitted parameter leaves the previous allocation unchanged. A parameter larger than the number of pages available leaves the previous allocation for that session unchanged. No actual pages are allocated to disabled sessions, but the allocation is changed the next time the session is enabled.

DECSPMA can be reported using DECRPSS.

## **DECSPP—Set Port Parameters**

Configures communication parameters for either a communication port or a printer port.

## **Format**

### **Parameters**

#### Ps1

determines which port is to be configured.

Ps1	Port Selection
1, 0 or none	Comm Port
2	Printer Port

### Ps2

determines the data bit.

Ps2	Data Bit
1, 0 or none	8 bits
2	7 bits

#### Ps3

determines the parity.

Ps3	Parity	Ps3	Parity
1, 0 or none	No Parity	5	Odd Parity, Unchecked
2	<b>Even Parity</b>	6	Mark Parity
3	<b>Odd Parity</b>	7	Space Parity
4	Even Parity, Unchecked		

Ps3 selections 4 and 5 are not available for the printer port.

### Ps4

determines the stop bit.

Ps4	Stop Bit	
1, 0 or none	1 bit	
2	2 bits	

## **DECSPPCS—Select ProPrinter Character Set**

Allow users to match the characters printed to the character sets the IBM ProPrinter is capable of supporting.

### **Format**

#### **Parameters**

**Pn** denotes the code page numbers for ProPrinter supported character sets.

Pn	Printer	
210	PC Greek	
220	PC Spanish	
437	PC International	
850	PC Multilingual	
852	PC Slavic (Latin 2)	
857	PC Turkish	
860	PC Portuguese	
862	PC Hebrew	
863	PC French-Canadian	
865	PC Danish	
866	PC Cyrillic	

## **Description**

This sequence takes affect only when the printer type (DECSPRTT) is set to "IBM ProPrinter" or "DEC + IBM."

## **DECSPRTT—Select Printer Type**

Allow users to select a printer type that matches their environment.

#### **Format**

#### **Parameters**

#### Ps

indicates the selection of the printer type.

Ps	Printer Type
1, 0 or none	DEC ANSI (default)
2	IBM ProPrinter
3	DEC + IBM

## **Description**

Printer type "DEC ANSI" indicates a printer type that is capable of recognizing Digital ANSI conforming escape sequences.

"ProPrinter" indicates an attached printer type that recognizes the IBM ProPrinter escape sequences.

If the attached printer is an ANSI-compatible printer that has the IBM ProPrinter emulation feature, then select "DEC + IBM."

### **DECSR—Secure Reset**

This control function sets the terminal to its power-up state. DECSR lets applications know the exact state of the terminal before any attempted operations. You can use DECSR to guarantee the terminal state for secure connections. DECSR is similar to RIS, but does not perform a disconnect from the host.

## **Format**

### **Parameters**

#### Pr

is a optional random number from 0 to 16383. If Pr is included, then the terminal sends a confirmation (DECSRC) with this number.

#### **DECSR Actions**

- · Clears user-defined keys.
- · Clears soft character sets.
- Clears the screen and all off-screen page memory.
- Returns the cursor to the upper-left corner of the first page.
- Resets the scrolling margins.
- · Resets origin mode (DECOM) to absolute.
- · Sets visual character attributes to normal.
- Sets the selective erase (DECSCA) attribute to not selectively erasable.
- Sets all character sets to the defaults (G0, G1, G2, G3, GL, GR).
- Erases macro memory.
- Erases the paste buffer.
- · Reinitializes the keyboard state by:
  - Clearing the keyboard input buffer
  - Canceling compose sequences
  - Resetting the keyboard to send its default codes (in NVR)
  - Unlocking the keyboard (resetting KAM)

DECSR replaces all set-up parameters to their saved settings or power-up default values. If you include the optional Pr parameter, then the terminal returns a secure reset report to the host.

#### **Notes on DECSR**

- DECSR works in all conformance levels (level 1 or higher).
- DECSR works in display controls mode (CRM) and causes the terminal to exit this mode.
- DECSR does not work in VT52 mode or printer controller mode. The host software must explicitly exit these modes. You can send DECSR to an attached printer if the terminal is in printer controller mode.
- · The terminal buffers DECSR like any other incoming data.

## **DECSRC—Secure Reset Confirmation**

The terminal returns this report to the host if the *Pr* parameter was included in the last secure reset (DECSR) control function. DECSRC report indicates that the secure reset operation was successful.

#### **Format**

#### **Parameters**

#### Pi

is the number from 0 to 16383 that was included in the corresponding secure reset sequence.

## **DECSSCLS—Set Scroll Speed**

Select how fast lines appear on the screen.

#### **Format**

### **Parameters**

### Ps

indicates the scroll speed and lines per second.

Ps	Scroll Speed	Lines per Second
0, 1, 2, 3 or none	Smooth 2 (default)	9
4, 5, 6, 7, 8	Smooth 4	18
9	Jump	As fast as received

### **Description**

This is a user preference feature. If the **User Features Locked** is enabled, then the scroll speed cannot be changed by this control function.

The escape sequence DECSCLM can change the scroll speed between Smooth 2 and Jump scroll.

## **DECSSDT—Select Status Display (Line) Type**

This control function lets the host select the type of status line displayed.

Available in: VT Level 4 or higher mode only

**Default**: Indicator status display

#### **Format**

#### **Parameters**

#### Ps

indicates which status line the host selects:

Ps	Status Line Selected
0 (default)	No status line
1	Indicator status line
2	Host-writable status line

#### **Notes on DECSSDT**

- If you select no status line (Ps = 0), then the terminal uses the line as an additional user window line to display data.
- If you change from an indicator to a host-writable status line, then the new host-writable status line is empty.
- When you select the host-writable status line, most of the control functions that affect the main display also affect the status line. The following list describes the exceptions to the rule:

Control Function	Action
Select character set (SCS)	Both the main display and status line use the same character set.
Cursor position controls	Only the column parameters in cursor- positioning commands operate in the status line.
ANSI mode (DECANM)	Ignored if received in the status line.
Set conformance level (DECSCL)	Exits the status line.
Scrolling mode (DECSCLM)	Affects the main display and the status line.
Soft terminal reset (DECSTR)	Exits the status line.

## **DECSSDT—Select Status Display (Line) Type**

Control Function	Action
Insert/replace mode (IRM)	Affects the main display and the status line.
Hard terminal reset (RIS)	Erases and exits the status line.
Tab stops	Affect the main display and status line.
Autowrap mode (DECAWM)	Affects the main display and status line.

• DECSSDT does not affect the status line type displayed in Set-Up. In Set-Up, the terminal always uses the indicator status line.

## **DECSSL—Select Set-Up Language**

Select one of several languages for Set-Up display menus.

### **Format**

### **Parameters**

#### Ps

indicates the set-up language.

Ps	Set-Up Language
0, 1 or none	English
2	French
3	German
4	Spanish
5	Italian

## **DECST8C—Set Tab at Every 8 Columns**

Set a tab stop at every eight columns starting with column 9.

#### **Format**

## Description

Any tab stop setting before this command is executed is cleared automatically. Control function TBC clears the tab stops on the display; HTS sets a horizontal tab stop at the active column.

## **DECSTBM—Set Top and Bottom Margins**

This control function sets the top and bottom margins for the current page. You cannot perform scrolling outside the margins.

**Default:** Margins are at the page limits.

### **Format**

### **Parameters**

#### Pt

is the line number for the top margin.

Default: Pt = 1.

#### Ph

is the line number for the bottom margin.

Default: Pb = current number of lines per screen.

#### **Notes on DECSTBM**

- The value of the top margin (Pt) must be less than the bottom margin (Pb).
- The maximum size of the scrolling region is the page size.
- DECSTBM moves the cursor to column 1, line 1 of the page.

## **DECSTR—Soft Terminal Reset**

Perform a soft reset to the default values listed in Table 5-6.

## **Format**

**CSI** ! **p** 9/11 2/1 7/0

## **Description**

Table 5–6 lists the terminal's default settings:

Table 5-6 Terminal's Default Settings

Mode	Mnemonic	State after DECSTR
Text cursor enable	DECTCEM	Cursor enabled.
Insert/replace	IRM	Replace mode.
Origin	DECOM	Absolute (cursor origin at upper-left of screen. )
Autowrap	DECAWM	No autowrap.
National replacement character set	DECNRCM	Multinational set.
Keyboard action	AM	Unlocked.
Numeric keypad	DECNKM	Numeric characters.
Cursor keys	DECCKM	Normal (arrow keys).
Set top and bottom margins	DECSTBM	Top margin = 1; bottom margin = page length.
All character sets	G0, G1, G2, G3, GL, GR	Default settings.
Select graphic rendition	SGR	Normal rendition.
Select character attribute	DECSCA	Normal (erasable by DECSEL and DECSED).
Save cursor state	DECSC	Home position.
Assign user preference supplemental set	DECAUPSS	Set selected in Set-Up.
Select active status display	DECSASD	Main display.
Keyboard position mode	DECKPM	Character codes.
Cursor direction	DECRLM	Reset (Left-to-right), regardless of NVR setting.
PC Term mode	DECPCTERM	Always reset.

## **DECSTGLT—Select Color Look-Up Table**

Selects the color mode or mapping.

**Default:** ANSI SGR color

#### **Format**

### **Parameters**

### Ps

Look-Up Table

Ps	Selection	To select colors, the terminal uses
0	Mono	Monochrome or gray level color map
1	Alternate color	Text attributes (bold, blink, underline, reverse)
2	Alternate color	-
3	ANSI SGR color	ANSI SGR color parameters

## **Description**

DECSTGLT selects the color mode or mapping used to display text colors and attributes. Refer to **Color** > **Select color mode** in Set-Up chapter for details.

DECSTGLT can be reported using DECRPSS.

## **DECSTRL—Set Transmit Rate Limit**

Limit the rate of character transmission according to the selected rate.

#### **Format**

#### **Parameters**

# **Ps1** indicates the key type.

Ps1	Кеу Туре
1, 0 or none	All Keys
2	Graphic Key
3	Function Key

**Ps2** indicates the characters per second.

Ps2	Characters Per Second
1, 0 or none	150 CPS
2	50 CPS
3	30 CPS

## **Description**

When enabled, the terminal limits the rate at which it transmits the answerback, CPR, DA, TSI, and DSR messages, as well as the keyboard keys, and any other characters transmitted from the terminal. All messages and keystrokes are transmitted according to the selected "character per second" rate.

You can select different transmit rates for graphic keys and function keys, which usually transmit more than one byte at a time.

The transmit rate limit function can be enabled and disabled through the DECXRLM control function. When disabled, all messages and keystrokes are transmitted as fast as possible without any delay between characters.

## **DECSTUI—Setting Terminal Unit ID**

DECSTUI writes the terminal unit ID into the terminal's NVR. The host can read the ID with the tertiary device attribute (DA3).

#### **Format**

#### **Parameters**

#### D...D

is the terminal's unit ID, consisting of four hexadecimal pairs. The first pair represents the manufacturing site code. The last three pairs represent an ID, which is unique for all terminals manufactured at a specific site. See tertiary DA (DA3) for more information.

### **Description**

DECSTUI writes the terminal unit ID into the terminal's nonvolatile random access memory (NVR).

Available in: VT Level 4 or higher mode only.

#### Note on DECSTUI

Under normal operations the terminal ignores DECSTUI. DECSTUI works only when the non-volatile memory checksum is invalid or a small jumper inside the terminal is activated, and the terminal is set to VT Level 4 mode.

## **DECSWBV—Set Warning Bell Volume**

Set the warning bell volume.

#### **Format**

#### **Parameters**

#### Ps

indicates the selection of the click volume.

Ps	Bell Volume
1	Off
2, 3, 4	Low
5, 5, 7, 8, 0 or none	High (default)

## **Description**

This sequence is used to adjust the warning bell volume (for errors and receipt of Ctrl G).

## **DECSWL—Single-Width, Single-Height Line**

DECSWL makes the line with the cursor a single-width, single-height line. This line attribute is the standard for all new lines on the screen.

#### **Format**

## **DECSZS—Select Zero Symbol**

Selects the style of the zero displayed in text.

**Default:** 0

## **Format**

## **Parameters**

Ps

Zero Font

Ps	Selection	
1	oval zero - default 0	
2	zero with slash - Ø	
3	zero with dot	

## **Description**

DECSZS can be reported using DECRPSS.

## **DECSWT—Set Window Title**

Specifies a descriptive name, up to 30 characters, for this session.

#### **Format**

Where D...D is:

## **Description**

The session name is used in three places:

- 1. As the window title when framed windows mode is enabled.
- 2. As the icon name, using the first 12 characters of the session name, when a session icon name is not otherwise specified. Session icons are displayed when framed windows mode is enabled.
- 3. As the application parameter of the TD/SMP enable session command, the session name is transmitted to the host, where it can be used to select a desired service.

There is no TSI report for the window title.

## **DECTABSR—Tab Stop Report**

The terminal sends this sequence to the host in response to a request presentation state report (DECRQPSR) sequence. DECTABSR informs the host of the terminal's current tab settings.

#### **Programming Tip**

Applications can use information in the tab stop report to save the current tab stops. Later, the application can restore the saved tab stops.

This operation is useful for applications that need to temporarily change the terminal's tab stops. When the application is finished, it can restore the tab stops that were in effect before the application changed them. You use the restore presentation state (DECRSPS) function to restore tab stops. Refer to DECRSPS—Restore Presentation State for additional information.

#### **Format**

DCS	2	\$	u	D D	ST
9/0	3/2	2/4	7/5		9/12

#### **Parameters**

D...D

is a data string indicating the column number location of each tab stop.

## **Example**

The following is an example of a DECTABSR sequence:

DCS 2 \$ u 9/ 17/ 25/ 33/ 41/ 49/ 57/ 65/ 73 ST

9, 17, 25, 33, 41, 49, 57, 65, and 73 are the column numbers for tab stops.

### **DECTCEM—Text Cursor Enable Mode**

This control function makes the cursor visible or invisible.

**Default:** Visible

## **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>2</b> 3/2	<b>5</b> 3/5	<b>h</b> 6/8	Set: makes the cursor visible.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>2</b> 3/2	<b>5</b> 3/5	<b>I</b> 6/12	Reset: makes the cursor invisible.

## **DECTID—Select Terminal ID**

Select a terminal ID.

### **Format**

#### **Parameters**

#### Ps

denotes the ID type.

Ps	ID Type	
0	VT100	
1	VT101	
2	VT102	
5	VT220	
7	VT320	
9	VT420	
10	VT520	

## **Description**

This sequence selects the Primary DA Response ("Terminal ID") transmitted by the terminal in either VT100 or VT500 mode. DECTID has no effect when the terminal is in VT52 mode.

The VT520 supports the following DA1 responses:

VT100 ID	ESC [? 1; 2 c
VT101 ID	ESC [? 1; 0 c
VT102 ID	ESC [ ? 6 c
VT220 ID (N.A.)	CSI ? 62; 1; 2; 7; 8 c
VT220 ID (Intnl)	CSI ? 62; 1; 2; 7; 8; 9 c
VT320 ID (N.A.)	CSI ? 63; 1; 2; 7; 8 c
VT320 ID (Intnl)	CSI ? 63; 1; 2; 7; 8; 9 c
VT420 ID (N.A.)	CSI ? 64; 1; 2; 7; 8; 9; 15; 18; 21 c
VT420 ID (Intnl)	CSI ? 64; 1; 2; 7; 8; 9; 15; 18; 21 c
VT520 ID	Reference function DA1

The default ID is "VT520."

## **DECTME—Terminal Mode Emulation**

Select a terminal emulation mode.

#### **Format**

#### **Parameters**

#### Ps

The Ps parameter selects the terminal emulation mode as follows:

Table 5-7 Terminal Emulation Modes

Ps	Terminal Mode
1	VT520 (VT Level 5)
2	VT100
3	VT52
4	VT PCTerm
5	WYSE 60/160
6	WYSE PCTerm
7	WYSE 50/50+
8	WYSE 150/120
9	TVI 950
10	TVI 925
11	TVI 910+
12	ADDS A2
13	SCO Console
14	WYSE 325

## **Description**

This sequence allows you to select the terminal emulation mode. After any mode change is made, a soft reset is performed.

The VT520 is functionally equivalent to the architectural level 5 terminal. VT Level 5 provides level 2, 3, 4, and 5 compatibility. compatibility.

#### **DECTME—Terminal Mode Emulation**

#### **Notes on DECTME**

- Printer operations are not affected or halted by a change in mode.
- A soft reset is always performed as a result of a mode change between VT modes.

Exception: Entering VT52 mode using DECANM does not cause a soft reset from VT100 mode, but does cause a soft reset from VT500 Mode.

DECANM and DECSCL can also change the VT operating modes.

DECTME can be reported using DECRPSS from the VT modes. All WYSE emulations report like the WYSE 325.

## **DECTSR—Terminal State Report—Terminal to Host**

Requests and reports the state of the terminal.

#### **Format**

#### **Parameters**

#### Ps

indicates the type of report the host requests from the terminal.

Ps	Report Requested
0 or	Ignored. No report sent.
none	
1	Terminal state report (DECTSR)

#### Response

DCS 1 \$ s D ... D ST

D . . . D

See Device Attributes (DA1, DA2, DA3).

### **Description**

DECRQTSR and DECTSR requests and reports the state of the terminal.

## **DECTSR—Terminal State Report (Color Table Report)**

A response to a host request (DECRQTSR) for a color table report. The terminal responds with each color table entry given as a group of five parameters in the data string.

## **Format**

#### **Parameters**

 $D \dots D$ 

is a data string that contains the groups of five parameters as follows:

```
Pc; Pu; Px; Py; Pz / Pc; Pu; Px; Py; Pz / ...
```

where:

Pc is the color number 0 -255.

Pu is the color coordinate system.

1—HLS (hue 0-360, lightness 0-100, saturation 0-100)

2—RGB (red 0-100, green 0-100, blue 0-100)

Px, Py, Pz are values in the color coordinate system.

; is the semicolon (3/11).

/ is the slash character (2/15).

## **Description**

The DECRQTSR control with parameter 2 request the terminal color map. The terminal responds with the DECTSR control with parameter 2. To load a previously reported color map, the host transmits a DECRSTS control with parameter 2 and the desired color map definitions in the data string. When loading a color map, only the index entries specified are changed.

## **DECTST—Invoke Confidence Test**

Select tests to be performed.

#### **Format**

```
CSI 4 ; Ps ··· ; Ps y 9/11 3/4 3/11 3/n ··· 3/11 3/n 7/9
```

#### **Parameters**

#### Ps

is the parameter indicating a test to be done.

Ps	Test
0	"All Tests" (1,2,3,6)
1	Power-Up Self Test
2	RS-232 Port Data Loopback Test
3	Printer Port Loopback Test
4	Speed Select and Speed Indicator Test
5	Reserved - No action
6	RS-232 Port Modem Control Line Loopback Test
7	DEC-423 Port Loopback Test
8	Parallel Port Loopback Test
9	Repeat (Loop On) Other Tests In Parameter String

## **Description**

After the first parameter, "4", the parameters each select one test. Several tests may be invoked at once by chaining the parameters together separated by semicolons. The tests are not necessarily executed in the order in which they are entered in the parameter string.

"ESC 8" invokes the Screen Alignment test for the VT520. Additionally, after executing the power-up selftest, the terminal displays either the diagnostic messages in the upper left corner of the screen or the "VT520 OK" message in the center of the screen and within a box. Upon receipt of any character except XON or if the user types a keystroke, the screen is cleared. If the terminal is in local mode, then characters from the host are ignored and the message remains visible even if characters are received from the host. DECTST causes a disconnect; therefore, it should not be used in conjunction with a modem.

## **DECUDK—User Defined Keys**

DECUDK downloads definitions for user-defined keys.

#### **Format**

DCS	Ps1; Ps2; Ps3	1	D D	ST
9/0 Device Control String Introducer	Clear, Lock, and Modifier Parameters	7/12 Final Character	Key Definition String	9/12 String Terminator

#### **Parameters**

**Ps1** is the *clear parameter*. *Pc* selects how to clear key definitions.

Ps1	Meaning
0 (default) or none	Clear all keys before loading new values.
1	Load new UDK values; clear old values only when redefined.

When *Ps1* is 1, the terminal only clears the keys you are loading. By using a *Ps1* value of 1, you can redefine some keys without redefining them all.

There are 768 bytes of memory for all user-defined keys. A key definition can only use the number of bytes available when that key is loaded.

#### **Programming Tip**

If *Ps1* is 1, a key load may fail because no memory space is available. The reason for this is as follows:

With *Ps1* set to 1, keys are cleared and loaded sequentially. If the new definition for a key is larger than the old one, then you may exceed the 768 byte limit.

For example, suppose  $\boxed{\texttt{F6}}$  contains 412 bytes,  $\boxed{\texttt{F7}}$  contains 330 bytes, and  $\boxed{\texttt{F8}}$  contains 20 bytes. You try to load  $\boxed{\texttt{F8}}$  with 40 bytes,  $\boxed{\texttt{F6}}$  with one byte, and  $\boxed{\texttt{F7}}$  with one byte, in that order. This works if all keys are cleared first (Ps1 is 0), but not if keys are cleared one at a time (Ps1 is 1). When you try to load  $\boxed{\texttt{F8}}$  with 40 bytes, the load fails because only 26 bytes are free at that time.

768 (maximum) 
$$-412 ( [6] ) -330 ( [7] ) = 26$$

#### Ps2

is the *lock parameter*. *Pl* determines whether the key definitions are locked or unlocked after you load them.

### **DECUDK—User Defined Keys**

Ps2	Action
0 or none	Lock the keys. If you want to load new values into the keys, then you must unlock the keys by using Set-Up.
1	Do not lock the keys against future redefinition.

If *Ps2* is 1 and the keys are already locked, then nothing happens.

The terminal uses a special lock to prevent or allow the programming of user-defined keys. You can turn on this lock from Set-Up or from the host (with a DECUDK device control string). The lock affects all programmable keys. When you use the lock, you should follow these guidelines:

#### · Unlock the keys to define them.

The keys must be unlocked before you can define them. You can only unlock the keys from set-up. If a key is locked and an application tries to redefine the key with a DECUDK sequence, then the terminal ignores the sequence.

#### Lock the keys to prevent redefinition.

You can lock the keys from Set-Up or from the host by sending a DECUDK sequence. New key definitions are locked by default.

**Ps3** is the *modifier parameter*. *Ps3* designates whether the key is shifted or unshifted.

Ps3	Action
0, 2, or none	Defines the shifted function key.
1	Defines the unshifted function key.
3	Defines the alternate unshifted function key.
4	Defines the alternate shifted function key.

DECUL

is the *final character*. The vertical bar (7/12) identifies this control string as a DECUDK.

#### D . . . D

are the *key definition strings*. You include these strings between the final character (|) and the string terminator (ST). Each string consists of a key selector number (*Kyn*) and a string parameter (*Stn*), separated by a slash (/) (2/15). A semicolon (;) (3/11) separates different strings.

The key selector number (Kyn) indicates which key you are defining. Tables 5–8 and 5–9 list the definable keys and their identifying values. Table 5–10 compares the function keys on the VT keyboard to equivalent keys on the PC keyboard.

## **Description**

Table 5–8 VT Keyboards

	Pm = 1	Pm = none, 0, or 2
Kyn	Key	Кеу
11	F1	Shift/F1
12	F2	Shift/F2
13	F3	Shift/F3
14	F4	Shift/F4
15	F5	Shift/F5
17	F6	Shift/F6
18	F7	Shift/F7
19	F8	Shift/F8
20	F9	Shift/F9
21	F10	Shift/F10
23	F11	Shift/F11
24	F12	Shift/F12
25	F13	Shift/F13
26	F14	Shift/F14
28	F15	Shift/F15
29	F16	Shift/F16
31	F17	Shift/F17
32	F18	Shift/F18
33	F19	Shift/F19
34	F20	Shift/F20
		Note
		Pm values of 3 and 4 are specific to the PC keyboard. They are ignored when you use a VT keyboard.

# **DECUDK—User Defined Keys**

Table 5–9 PC Keyboards

	Pm Value					
Kyn	1	None, 0, or 2	3	4		
11	F1	Shift/F1	Alt/F1	Alt/Shift/F1		
12	F2	Shift/F2	Alt/F2	Alt/Shift/F2		
13	F3	Shift/F3	Alt/F3	Alt/Shift/F3		
14	F4	Shift/F4	Alt/F4	Alt/Shift/F4		
15	F5	Shift/F5	Alt/F5	Alt/Shift/F5		
17	F6	Shift/F6	Alt/F6	Alt/Shift/F6		
18	F7	Shift/F7	Alt/F7	Alt/Shift/F7		
19	F8	Shift/F8	Alt/F8	Alt/Shift/F8		
20	F9	Shift/F9	Alt/F9	Alt/Shift/F9		
21	F10	Shift/F10	Alt/F10	Alt/Shift/F10		
23	F11	Shift/F11	Alt/F11	Alt/Shift/F11		
24	F12	Shift/F12	Alt/F12	Alt/Shift/F12		
25	Alt/F3	Alt/Shift/F3	_	_		
26	Alt/F4	Alt/Shift/F4	_	_		
28	Alt/F5	Alt/Shift/F5	_	_		
29	Alt/F6	Alt/Shift/F6	_	_		
31	Alt/F7	Alt/Shift/F7	_	_		
32	Alt/F8	Alt/Shift/F8	_	_		
33	Alt/F9	Alt/Shift/F9	_	_		
34	Alt/F10	Alt/Shift/F10	_	_		
35	Alt/F11	Alt/Shift/F11	_	_		
36	Alt/F12	Alt/Shift/F12	_	_		

Table 5-10 VT and PC Keyboard Function Keys Compared

Keyboard			
Kyn	VT	PC	
11	F1	F1	
12	F2	F2	
13	F3	F3	
14	F4	F4	
15	F5	F5	
17	F6	F6	
18	F7	F7	
19	F8	F8	
20	F9	F9	
21	F10	F10	
23	F11	F11	
24	F12	F12	
25	F13	_	
26	F14	_	
28	F15	_	
29	F16	_	
31	F17	_	
32	F18	_	
33	F19	_	
34	F20	-	

• The string parameters (**Stn**) are the encoded definition of the keys. String parameters consist of hex pairs in the following ranges:

3/0 through 3/9 (0 through 9)

4/1 through 4/6 (A through F)

6/1 through 6/6 (a through f)

When you combine these hex values, they represent an 8-bit quantity.

This method lets you use any of the 256 character codes in the key string. You can enter key definition strings in any order.

Default: Empty. The key is undefined.

## Description

DCS (9/0) indicates the beginning of a device control string. DCS is an 8-bit C1 character. You can use ESC P ( $1/11\ 5/0$ ) for a 7-bit environment.

ST is the *string terminator*. ST (9/12) is a C1 8-bit character. You can use ESC (1/11, 5/12) for a 7-bit environment.

## **General Guidelines When Loading UDKs**

- Clear UDK memory space before loading new definitions.
  - Use a DECUDK string to clear keys without locking them. Then you can use another DECUDK string to redefine the keys and lock them.
- If you redefine a key, then the old definition is lost. This clears space if the new definition uses less bytes than the old one.
- There is only one way to unlock UDKs.
   To unlock a UDK, use Set-Up.
- When you clear a UDK, the key definition is empty.
- An invalid hex pair in a DECUDK string stops a UDK sequence.
   When a load sequence stops (error or other cause), the terminal saves keys already loaded and sends the rest of DECUDK to the screen.
- You can disable the local function keys by redefining them with DECUDK.
- DECUDK works in all VT modes except VT52 mode.

## **Examples of DECUDK Device Control Strings**

The following sequence clears unshifted UDKs:

```
DCS 0 ; 1 ; 1 | ST
```

The following sequence locks unshifted UDKs:

```
DCS 1 ; 0 ; 1 | ST
```

Suppose you want to define the unshifted F20 key to be "PRINT", without clearing or locking any other keys. The first part of your sequence would look like this:

```
DCS 1 ; 1 ; 1 | 3 4 /
```

**34** is the code for the F20 key.

After the slash character (/) (2/15), you include the definition. The rest of the sequence after the slash character would look like this:

```
5 0 5 2 4 9 4 E 5 4 ST
```

The hex encoding for "PRINT" is as follows:

```
50 = P

52 = R

49 = I

4E = N

54 = T
```

The ST character (9/12) marks the end of the control string:

```
DCS 1 ; 1 ; 1 | 34 / 50 52 49 4E 54 ST
```

## **DECUS—Update Session**

Controls how display memory is updated for this session when it is not active.

**Default:** Update when available

## **Format**

## **Description**

Update session according to the parameter Ps as follows:

Ps	Update Session	Description
1	Only when active	Prevents the session from being updated until it is explicitly made active by the user or the host.
2	When available	Allows the session to be updated when the terminal is not otherwise busy with the active session.
3	At regular intervals	Ensures session will continue to be updated even when not active.

DECUS can be reported using DECRPSS.

## **DECVCCM—Vertical Cursor-Coupling Mode**

This control function determines whether the user window pans with the cursor when the cursor moves past the top or bottom border of the user window. DECVCCM is only useful when the height of the current user window is smaller than the page. The cursor must stay on the current page.

**Default:** Coupled

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>1</b> 3/1	<b>h</b> 6/8	Set: couples the cursor to the display.
<b>CSI</b> 9/11	<b>?</b> 3/15	<b>6</b> 3/6	<b>1</b> 3/1	<b>I</b> 6/12	Reset: uncouples the cursor.

## **Description**

When DECVCCM is set, the cursor is coupled to the display for vertical movement. When the cursor moves past the top or bottom border of the user window, the window pans to keep the cursor in view.

If the cursor moves past the top of the display, the user window pans up. New lines appear at the top of the screen, while lines at the bottom move out of view.

When DECVCCM is reset, the cursor is uncoupled from the display. If the cursor moves past the top or bottom border of the user window, the cursor disappears.

## **DECXCPR**—Extended Cursor Position Report

The host asks the terminal for the current cursor position, including the current page number.

#### **Format**

### Response

#### **Parameters**

PI; Pc; Pp

The terminal indicates that the cursor is currently at line Pl, column Pc, on page Pp.

## **DECXRLM—Transmit Rate Limiting**

Applications can control the transmit rate limiting feature through the DECXRLM control function.

**Default:** Unlimited

#### **Format**

<b>CSI</b> 9/11	<b>?</b> 3/15	<b>7</b> 3/7	<b>3</b> 3/3	<b>h</b> 6/8	Set: limited transmit rate.
	<b>?</b> 3/15			I 6/12	Reset: unlimited transmit rate.

### **Modem Connection and Disconnections**

When the terminal makes a connection to the host system through a modem, the terminal performs the following operations to ensure it is ready to send and receive.

- Unlocks the keyboard (if it was locked).
- · Clears any transmission in progress.
- Clears the keyboard buffer and all message buffers.
- · Clears the input buffer.
- · Clears XOFF sent and XOFF received.

Any of the following conditions will disconnect the connection to the host system in VT mode:

- You press Shift F5 (Shift Break).
- You use the Recall or Default fields in the Set-Up Directory.
- You change the host port you are using (from the RS-232 port to the DEC-423 port, or from the DEC-423 port to the RS-232 port).
- The terminal loses the data set read (DSR) signal.
- The terminal loses the received line signal detect (RLSD) signal for a period
  of time you defined in set-up. See the **disconnect delay** feature in the
  Communications Set-Up screen.
- The terminal does not receive an RLSD signal within 30 seconds after DSR.
- The terminal receives a self-test command from the host system.

The usual way to disconnect communications is to type Shift F5 (Shift Break). The host system's response to the disconnect signal depends on the system and the software.

#### Terminal-to-Printer Data Flow Control

The terminal sends only data characters to the printer. The terminal does not send XON and XOFF characters. The terminal recognizes only XON and XOFF characters from the printer. Any other characters from the printer are ignored.

When the terminal receives XOFF from the printer, the terminal stops sending data. The terminal starts sending data again when it receives an XON, or when a clear comm operation is performed.

### **DECXRLM—Transmit Rate Limiting**

### **Using C1 Control Characters**

Using an 8-bit setting for the printer port implies the use of 8-bit C1 control characters. Using a 7-bit setting implies the use of the 7-bit ESC form of C1 control characters. You select the setting by using the **data bits/parity** feature in the Printer Set-Up screen.

### Note on DECXRLM

Older printers may not recognize the 8-bit form of C1 control characters. With these printers, you must set the printer port to 7-bits for correct operation.

### **DL—Delete Line**

This control function deletes one or more lines in the scrolling region, starting with the line that has the cursor.

### **Format**

### **Parameters**

### Pn

is the number of lines to delete.

Default: Pn = 1.

### **Description**

As lines are deleted, lines below the cursor and in the scrolling region move up. The terminal adds blank lines with no visual character attributes at the bottom of the scrolling region. If Pn is greater than the number of lines remaining on the page, DL deletes only the remaining lines. DL has no effect outside the scrolling margins.

## **DSR—Device Status Reports**

The host computer and terminal exchange DSR sequences to provide the host with the operating status of the following features:

Operating status

Keyboard status - language
Cursor position report
Cursor position with page
Printer port

User-defined keys
Macro space report
Memory checksum
Data integrity report

DSR requests and reports follow one of two formats, ANSI standard or DEC private. The format for each is as follows:

### **Format**

<b>CSI</b> 9/11	Ps 3/?	<b>n</b> 6/14	ANSI s	tandard
<b>CSI</b> 9/11	<b>?</b> 3/15	Ps 3/?	<b>n</b> 6/14	DEC private

#### **Parameters**

#### Ps

indicates the type of DSR requested. See the following individual DSR reports for specific parameters within each report.

### **Description**

There is a different DSR request for each feature. The following sections describe the possible DSR reports. If the terminal is in printer controller mode, then the printer receives the DSR request. The printer can respond through the bidirectional printer port.

## **DSR—Cursor Position Report (CPR)**

The host asks the terminal for a cursor position report.

### **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI 6 n	The host asks for a cursor position report (CPR).
CPR response (Terminal to host)	CSI PI; Pc R	The terminal indicates that the cursor is currently at line <i>Pl</i> , column <i>Pc</i> .

## **DSR—Data Integrity Report**

The host asks for the status of the data integrity flag. The data integrity flag indicates the integrity of the data flow between the terminal and host. This flag is reset each time the terminal sends a data integrity report.

### **Programming Tip**

Applications using the flag should always reset the flag before sending data to the terminal. You can reset the flag with a DSR request (**CSI** ? **75** n) sequence. After the application sends data, the application should send another request to find out if a parity error has occurred.

### **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI ? 75 n	The host asks for the status of the data integrity flag.
Possible responses (Terminal to host)	CSI ? 70 n	Ready, no communication errors or power-ups have occurred since last report.
	CSI ? 71 n	Malfunction, a communication error has occurred since the last report.
	CSI ? 73 n	The terminal has not reported data integrity since the last power-up or hard reset (RIS).

## **DSR**—Extended Cursor Position Report (DECXCPR response)

The host asks the terminal for the current cursor position, including the current page number.

### **Format**

Exchange	Sequence	Meaning
Request (Host to Terminal)	CSI ? 6 n	The host asks for an extended cursor position report (DECXCPR).
DECXCPR response (Terminal to host)	CSI Pl; Pc; Pp R	The terminal indicates that the cursor is currently at line <i>PI</i> , column <i>Pc</i> , on page <i>Pp</i> .

## **DSR**—Keyboard Report

The host asks for the current keyboard language, operating status, and type.

## **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI ? 26 n	The host asks for the keyboard status.
Response (Terminal to host)	<b>CSI ? 27</b> ; <i>Pn</i> ; <i>Pst</i> ; <i>Ptyp</i> <b>n</b>	The keyboard language is <i>Pn</i> , the keyboard status is <i>Pst</i> , and the keyboard type is <i>Ptyp</i> .

## **Parameters**

### Pn

Table 5-11 is a complete list of keyboards and keyboard languages.

Table 5-11 Keyboard Languages

Pn	VT/PC Language
0	Keyboard language cannot be determined.
1	North American
2	British
3	Belgian (Flemish)
4	French Canadian
5	Danish
6	Finnish
7	German
8	Dutch
9	Italian
10	Swiss French
11	Swiss German
12	Swedish
13	Norwegian
14	French
15	Spanish
16	Portuguese
19	Hebrew
22	Greek
28	Canadian (English)
29	Turkish-Q/Turkish
30	Turkish-F/Turkish
31	Hungarian
33	Slovak
35	Polish
36	Romanian
38	SCS
39	Russian
40	Latin American

## **DSR**—Keyboard Report

#### Pst

indicates the keyboard status.

Pst	Keyboard Status‡	
0	Keyboard Ready	The terminal sends typed characters to the current session.
3	No Keyboard	The terminal does not detect the keyboard.
8	Keyboard Busy	The other session is currently using the keyboard.

 $\ddagger$ The terminal only sends Pst in VT level 4 or 5 mode.

### Ptyp

indicates the keyboard type.

Ptyp	Keyboard Type
4	LK411
5	PCXAL

## **DSR**—Macro Space Report

The host asks for the available macro space in the form of a macro space report (DECMSR).

## **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI ? 62 n	The host asks for a macro space report (DECMSR).
DECMSR response (Terminal to host)	CSI Pn * {	The terminal indicates the number of bytes available for macro definitions.

### **Parameters**

#### Pn

$$Pn = \frac{number\ of\ bytes}{16} \text{ rounded down.}$$

## **DSR—Memory Checksum Report (DECCKSR)**

The host asks for a memory checksum report of current text macro definitions.

### **Programming Tip**

Enter your macro definitions, then request and save a memory checksum. Later, you can request another checksum and see if it has changed.

### **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI ? 63; <i>Pid</i> n	The host asks for a memory checksum report of current text macro definitions (DECCKSR).
		Pid is an optional numeric parameter that provides a label to identify the particular checksum request. The checksum report returns the label. This label lets you differentiate between multiple checksum reports.
DECCKSR response (Terminal to host)	DCS Pid! ~ DD ST	Pid is a label indicating which DSR request the report is for.
		DD is the data string consisting of four hexadecimal digits indicating the checksum. The digits can be in the range of 3/0 through 3/9 and 4/0 through 4/6.

## **DSR—Operating Status Report**

The host requests the terminal's operating status.

### **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI 5 n	The host requests the terminal's operating status. The host asks if the terminal is in good operating condition.
Responses (Terminal to host)	CSI 0 n	The terminal indicates that it is in good operating condition.
	or	
	CSI 3 n	The terminal indicates that it has a malfunction.

# **DSR—Printer Port Report**

The	host	asks	for	the	status	of	the	terminal's	printer.

Note
Host software should check the printer status before entering any print mode or starting any printing function.

## **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI ? 15 n	The host asks for the current printer status.
Possible responses (Terminal to host)	CSI ? 13 n	No printer. The data terminal ready (DTR) signal has not been asserted on the printer port since the last power-up or reset.
	CSI ? 10 n	Printer ready. DTR is asserted on the printer port.
	CSI ? 11 n	Printer not ready. DTR is not currently asserted on the printer port.
	CSI ? 18 n	Printer busy. DTR is asserted on the printer port, but the other session is using the printer.
		In VT Level 1, the terminal sends the <i>printer not ready</i> sequence above.
	CSI ? 19 n	Printer assigned to other session. DTR is asserted on the printer port, but the printer is assigned to the other session. The printer is not available to this session.
		In VT100 mode, the terminal sends the <i>no printer</i> sequence above.

## **DSR—User-Defined Keys Report (VT Level 4 or higher)**

The host asks if the user-defined keys (UDKs) are locked or unlocked.

### **Format**

Exchange	Sequence	Meaning
Request (Host to terminal)	CSI ? 25 n	The host asks if UDKs are locked or unlocked.
Possible responses	CSI ? 20 n	UDKs are unlocked.
(Terminal to host)	CSI ? 21 n	UDKs are locked.

## **ECH**—Erase Character

This control function erases one or more characters, from the cursor position to the right. ECH clears character attributes from erased character positions. ECH works inside or outside the scrolling margins.

Available in: VT Level 4 or higher mode only

### **Format**

### **Parameters**

#### Pn

is the number of characters to erase. A *Pn* value of 0 or 1 erases one character.

Default: Pn = 1.

## **ED**—Erase in Display

This control function erases characters from part or all of the display. When you erase complete lines, they become single-height, single-width lines, with all visual character attributes cleared. ED works inside or outside the scrolling margins.

### **Format**

### **Parameters**

#### Ps

represents the amount of the display to erase.

Ps	Area Erased	
0 (default)	From the cursor through the end of the display	
1	From the beginning of the display through the cursor	
2	The complete display	

### **Programming Tip**

Use a Ps value of 2 to erase the complete display in a fast, efficient manner.

## **EL—Erase in Line**

This control function erases characters on the line that has the cursor. EL clears all character attributes from erased character positions. EL works inside or outside the scrolling margins.

### **Format**

### **Parameters**

#### Ps

represents the section of the line to erase.

Ps	Section Erased	
0 (default)	From the cursor through the end of the line	
1	From the beginning of the line through the cursor	
2	The complete line	

## **HPA—Horizontal Position Absolute**

Move the active position to the n-th horizontal position of the active line.

### **Format**

### **Parameters**

#### Pn

indicates horizontal position.

## Description

HPA causes the active position to be moved to the n-th horizontal position of the active line. If an attempt is made to move the active position past the last position on the line, then the active position stops at the last position on the line.

## **HPR—Horizontal Position Relative**

Move the active position to the n-th column following the current horizontal position of the active line.

### **Format**

### **Parameters**

### Pn

indicates horizontal position.

## **Description**

HPR causes the active position to be moved to the n-th following horizontal position of the active line. If an attempt is made to move the active position past the last position on the line, then the active position stops at the last position on the line.

## **HT—Horizontal Tab**

HT moves the active position forward in the display to the next horizontal tab stop in the active line.

### **Format**

**HT** 0/9

## **Description**

- If the active position does not reach a tab stop before reaching the right margin of the active line within the scroll area, then the terminal will set the active position to the right margin of the active line.
- If the active column is beyond the right margin or the active line is outside the scroll area because of absolute cursor positioning, then the active position will move to the next tab stop or the last column of the active line, whichever comes first.

## **HTS—Horizontal Tab Set**

HTS sets a horizontal tab stop at the column position indicated by the value of the active column when the terminal receives an HTS.

You can use either one of the following formats:

### **Format**

## **Description**

Executing an HTS does not effect the other horizontal tab stop settings.

## **HVP—Horizontal and Vertical Position**

This control function works the same as the cursor position (CUP) function. New applications should use CUP instead of HVP. HVP is provided for compatibility with earlier VT products.

### **Format**

CSI 
$$9/11$$
  $6/6$  Cursor moves to home position selected by DECOM

CSI  $PI$  ;  $Pc$   $f$  Moves cursor to line PI, column Pc  $9/11$   $3/n$   $3/11$   $3/n$   $6/6$ 

### **Parameters**

### PI: PC

If PI or Pc is not selected or selected as 0, then the cursor moves to the first line or column, respectively. Origin mode (DECOM) selects line numbering and the ability to move the cursor into margins.

## **ICH—Insert Character**

This control function inserts one or more space (SP) characters starting at the cursor position.

**Available in:** VT Level 4 or higher mode only

### **Format**

### **Parameters**

#### Pn

is the number of characters to insert.

Default: Pn = 1.

## Description

The ICH sequence inserts Pn blank characters with the normal character attribute. The cursor remains at the beginning of the blank characters. Text between the cursor and right margin moves to the right. Characters scrolled past the right margin are lost. ICH has no effect outside the scrolling margins.

## **IL—Insert Line**

This control function inserts one or more blank lines, starting at the cursor.

### **Format**

### **Parameters**

#### Pn

is the number of lines to insert.

Default: Pn = 1.

## **Description**

As lines are inserted, lines below the cursor and in the scrolling region move down. Lines scrolled off the page are lost. IL has no effect outside the page margins.

## **IND**—Index

IND moves the cursor down one line in the same column. If the cursor is at the bottom margin, then the screen performs a scroll-up.

## **Format**

## IRM—Insert/Replace Mode

This control function selects how the terminal adds characters to page memory. The terminal always adds new characters at the cursor position.

**Default:** Replace.

### **Format**

```
        CSI
        4
        h
        Set: insert mode.

        9/11
        3/4
        6/8
        Set: insert mode.

        CSI
        4
        I
        Reset: replace mode.
```

## Description

If IRM mode is set, then new characters move characters in page memory to the right. Characters moved past the page's right border are lost.

If IRM mode is reset, then new characters replace the character at the cursor position.

## **KAM**—Keyboard Action Mode

This control function locks or unlocks the keyboard.

**Default:** Unlocked

### **Format**

## **Description**

If KAM is set, then the keyboard cannot send characters to the host. The Wait indicator appears on the keyboard indicator line at the bottom of the screen. The terminal ignores all keystrokes that send characters to the host. KAM does not affect the  $\boxed{\texttt{F3}}$  (Set-Up) or  $\boxed{\texttt{F4}}$  (Session) keys.

If KAM is reset, then the terminal unlocks the keyboard. The keyboard can send characters to the host.

## **LNM—Line Feed/New Line Mode**

This control function selects the characters sent to the host when you press the Return key. LNM also controls how the terminal interprets line feed (LF), form feed (FF), and vertical tab (VT) characters.

\_\_\_\_\_ Note \_\_\_\_\_

For compatibility with Digital's software, you should keep LNM reset (line feed).

**Default:** Line feed

### **Format**

<b>CSI</b>	<b>2</b>	<b>0</b>	<b>h</b>	Set: new line.
9/11	3/2	3/0	6/8	
<b>CSI</b> 9/11	<b>2</b> 3/2	<b>0</b> 3/0	I 6/12	Reset: line feed

## Description

If LNM is set, then the cursor moves to the first column on the next line when the terminal receives an LF, FF, or VT character. When you press Return, the terminal sends both a carriage return (CR) and line feed (LF).

If LNM is reset, then the cursor moves to the current column on the next line when the terminal receives an LF, FF, or VT character. When you press Return, the terminal sends only a carriage return (CR) character.

### Note on LNM

When the auxiliary keypad is in keypad numeric mode (DECKPNM), the Enter key sends the same characters as the Return key.

## **LS—Locking Shift**

When you use a locking shift, the character set remains in GL or GR until you use another locking shift. Table 5–12 lists all locking shifts available.

### **Format**

Table 5-12 Mapping Character Sets with Locking Shifts

Locking Shift	Code		Function
LS0 (locking shift 0)	<b>SI</b> 0/15	(Ctrl/o)	Map G0 into GL.(default)
LS1 (locking shift 1)	<b>SO</b> 0/14	(Ctrl/n)	Map G1 into GL.
The following locking shift functions are	e availabl	e only in VT	Level 4 mode.
LS1R (locking shift 1, right)	<b>ESC</b> 1/11	~ 7/14	Map G1 into GR.
LS2 (locking shift 2)	<b>ESC</b> 1/11	<b>n</b> 6/14	Map G2 into GL.
LS2R (locking shift 2, right)	<b>ESC</b> 1/11	} 7/13	Map G2 into GR.
LS3 (locking shift 3)	<b>ESC</b> 1/11	<b>o</b> 6/15	Map G3 into GL.
LS3R (locking shift 3, right)	<b>ESC</b> 1/11	 7/12	Map G3 into GR.

## **Examples**

The following sequence designates the DEC Technical character set as G1, then maps G1 into GL:

The following sequences designate the ISO Latin-1 supplemental character set as G2, then map G2 into GR:

## MC—Media Copy

MC is the control sequence that enables the terminal to control all print functions.

### **Format**

### **Parameters**

### Pn (ANSI standard)

indicates the following ANSI standard print functions:

Pn	Action	Notes on Print Page
0	Prints the page that has the cursor.	<ul> <li>The terminal stores data from the keyboard until printing is complete.</li> </ul>
		<ul> <li>If printer extent mode (DECPEX) is currently reset, then the print page function only prints the scrolling region.</li> </ul>
2	Sends screen data through host port.	
4	Turns off printer controller mode.	<ul> <li>Printer controller mode lets the host control printer operation. The terminal sends characters and control sequences directly to the printer, without displaying them on the screen.</li> </ul>
		<ul> <li>The terminal sends all characters and control sequences except NUL, XON, XOFF, and the printer controller mode sequences.</li> </ul>
		<ul> <li>Printer controller mode cancels autoprint mode. When the terminal leaves printer controller mode, it returns to the normal method for printing operations.</li> </ul>
		<ul> <li>The printer's active column position should always be on the left margin before the terminal leaves printer controller mode.</li> </ul>

Pn	Action	Notes on Printer Controller Mode
5	Turns on printer controller mode.	
6	Start a printer-to-host session.	
7	Stop a printer-to-host session.	

**Pn (DEC private)** indicates the following DEC private print functions:

Pn	Action	Note on Print Cursor Line
1	Prints the line that has the cursor.	The cursor does not move.
Pn	Action	Notes on Autoprint Mode
4	Turns off autoprint mode.	
5	Turns on autoprint mode.	The printer prints a line from the screen when you move the cursor off that line with an LF, FF, or VT character, or an autowrap occurs.
		<ul> <li>The printed line ends with a CR and the character (LF, FF, or VT) that moved the cursor off the previous line.</li> </ul>
8	Disables communication from the printer port to the host.	
9	Enables communication from the printer port to the host.	
Pn	Action	Note on Print Composed Main Display
10	Prints the data on the screen.	Printer extent mode (DECPEX) does not affect this function.

## MC—Media Copy

Pn	Action	Notes on Print All Pages
11	Prints all pages in page memory.	• If the current page format is 3 pages of 24 lines each, the printer prints 3 pages of 24 lines.
		<ul> <li>The terminal stores new data from the keyboard until printing is complete.</li> </ul>
		• If print form feed mode (DECPFF) is set, then the terminal sends a form feed (FF) to the printer after each page.
18	Lets the terminal accept printer commands.	

## **Description**

Escape Sequence **CSI 6 i** and **CSI 7 i** are functionally equivalent to **CSI ? 9 i** and **CSI ? 8 i**. Also, **CSI ? 9 i** and **CSI ? 8 i** are media copy commands used in VT terminals to set/reset printer to host mode.

## **NEL—Next Line**

Moves cursor to first position on next line. If cursor is at bottom margin, then screen performs a scroll-up.

### **Format**

**ESC E** 033 105

## **NP—Next Page**

This control function moves the cursor forward to the home position on one of the following pages in page memory. If there is only one page, then the terminal ignores NP.

**Default:** Move to the next page.

### **Format**

**CSI** *Pn* **U** 9/11 3/*n* 5/5

### **Parameters**

#### Pn

indicates how many pages to move the cursor forward.

Default: Pn = 0.

If Pn is 0 or 1, then the cursor moves to the next page in page memory. If Pn tries to move the cursor past the last page in memory, then the cursor stops at the last page.

## **PP—Preceding Page**

This control function moves the cursor backward to the home position on one of the preceding pages in page memory. If there is only one page, then the terminal ignores PP.

**Default:** Move to the preceding page.

### **Format**

### **Parameters**

### Pn

indicates how many pages to move the cursor backward.

Default: Pn = 0.

If Pn is 0 or 1, then the cursor moves to the preceding page. If Pn tries to move the cursor back farther than the first page in memory, then the cursor stops at the first page.

## **PPA—Page Position Absolute**

This control function can move the cursor to the corresponding row and column on any page in page memory. You select the page by its number. If there is only one page, then the terminal ignores PPA.

**Default:** Move to page 1.

### **Format**

#### **Parameters**

#### Pn

is the number of the page to move the cursor to. If Pn is greater than the number of the last page in memory, then the cursor stops at the last page. If Pn is less than the number of the first page, then the cursor stops at the first page.

## **PPB—Page Position Backward**

This control function moves the cursor backward to the corresponding row and column on one of the preceding pages in page memory. If there is only one page, then the terminal ignores PPB.

**Default:** Move backward one page.

### **Format**

### **Parameters**

#### Pr

indicates the number of pages to move the cursor backward. If Pn tries to move the cursor back farther than the first page in memory, then the cursor stops at the first page.

## **PPR—Page Position Relative**

This control function moves the cursor forward to the corresponding row and column on one of the following pages in page memory. If there is only one page, then the terminal ignores PPR.

**Default:** Move to the next page.

### **Format**

### **Parameters**

#### Pn

indicates how many pages to move the cursor forward. If Pn tries to move the cursor beyond the last page in memory, then the cursor stops at the last page.

### **RIS—Reset to Initial State**

This control function causes a nonvolatile memory (NVR) recall to occur. RIS replaces all set-up features with their saved settings.

The terminal stores these saved settings in NVR memory. The saved setting for a feature is the same as the factory-default setting, unless you saved a new setting.

\_\_\_\_ Note \_\_

It is recommended that you not use RIS to reset the terminal. You should use a soft terminal reset (DECSTR) instead. RIS usually causes a communication line disconnect and may change the current baud rate settings. When performing a RIS, the terminal sends XOFF to the host to stop communication. When the RIS is complete, the terminal sends XON to resume communication.

### **Format**

**ESC c** 1/11 6/3

### **RIS Actions**

- Sets all features listed on set-up screens to their saved settings.
- Causes a communication line disconnect.
- · Clears user-defined keys.
- Clears the screen and all off-screen page memory.
- Clears the soft character set.
- Clears page memory. All data stored in page memory is lost.
- Clears the screen.
- Returns the cursor to the upper-left corner of the screen.
- Sets the select graphic rendition (SGR) function to normal rendition.
- Selects the default character sets (ASCII in GL, and DEC Supplemental Graphic in GR).
- · Clears all macro definitions.
- Erases the paste buffer.

## **RM—Reset Mode**

There are two versions of this control function. You use the ANSI version to reset one or more ANSI modes. You use the DEC private version to reset one or more DEC private modes. You cannot reset ANSI and DEC private modes with the same RM sequence.

## **Resetting DEC Private Modes**

CSI	?	Pd	;	 ;	Pd	I
9/11	3/15	3/n	3/11	 3/11	3/n	6/12

### **Parameters**

#### Pd

indicates a DEC private mode to reset. Table 5-5 lists the Pd values for DEC private modes. You can use more than one *Pd* value in a sequence.

## **Examples**

#### **DEC Private Modes**

The following sequence resets (Hebrew) keyboard mapping (DECHEBM) and Hebrew encoding mode (DECHEM):

```
CSI ? 34; 36 l
```

**34** indicates (Hebrew) keyboard mapping.

**36** indicates Hebrew encoding mode.

### **Programming Tip**

Applications can use the SM and RM functions to restore any number of VT520 modes to a desired state. See the Report Mode (DECRPM) section in this chapter for details.

## S7C1T—Send C1 Control Character to the Host

The VT520 can send C1 control characters to the host as single 8-bit characters or as 7-bit escape sequences. You should select the format that matches the operating level you are using.

The following sequence causes the terminal to send all C1 control characters as 7-bit escape sequences or single 8-bit characters:

### **Format**

## **Description**

This sequence changes the terminal mode as follows:

Mode Before	Mode After
VT Level 4 mode, 8-bit controls	VT Level 4 mode, 7-bit controls.
VT Level 4 mode, 7-bit controls	Same. Terminal ignores sequence.
VT Level 1 or VT52 mode, 7-bit controls	Same. Terminal ignores sequence.

## S8C1T—Send C1 Control Character to the Host

The following sequence causes the terminal to send C1 control characters to the host as single 8-bit characters:

### **Format**

## **Description**

This sequence changes the terminal mode as follows:

Mode Before	Mode After
VT Level 4 mode, 8-bit controls	Same. Terminal ignores sequence.
VT Level 4 mode, 7-bit controls	VT Level 4 mode, 8-bit controls.
VT Level 1 mode	Same. Terminal ignores sequence.

## SCS—Select Character Set

Designate character sets to G-sets.

To understand how to select character sets, you must first understand the function of the terminal's *in-use table*. The in-use table contains the character sets the terminal can currently access. You can place any two character sets in the terminal's in-use table. The in-use table consists of the *graphic left* (GL) and *graphic right* (GR) logical tables.

Each time you turn on the terminal, the terminal places the following default character sets in the in-use table:

ASCII in GL

Supplemental Graphic (or ISO Latin-1 supplemental) in GR

Together, the ASCII and Supplemental Graphic sets make up the Multinational set. The ASCII and ISO Latin-1 supplemental sets make up the ISO Latin-1 set, which is the worldwide standard.

You can select a different character set by following these two steps:

### 1. Designate the set as G0, G1, G2, or G3.

G0 through G3 are logical sets that the terminal uses to access character sets. You can designate up to four character sets and have them ready for use in the in-use table.

### 2. Map the designated set into the in-use table.

After you map the set into the in-use table, you can display or send any character from that set by using 8-bit codes.

## **Designating Character Sets (SCS Sequences)**

You designate a hard character set as G0 through G3 by using a select character set (SCS) escape sequence. You cannot designate a 96-character set as G0.

SCS sequences use the following format. Table 5–14 lists the code used to select each available character set.

#### **Format**

**ESC** 
$$I_1$$
  $I_2$  ...  $I_n$   $F$   $1/11$  \*\*\* \*\*\* ... \*\*\*

#### **Parameters**

### I<sub>1</sub>, intermediate character

Designates the character set as G0, G1, G2, or G3.

## **Designating Character Sets (SCS Sequences)**

Table 5-13 Designating a Character Set

I <sub>1</sub> Character		Code Set Selection			
94	94-Character Sets				
(	left parenthesis	2/8	G0 (initial setting for GL)		
)	right parenthesis	2/9	G1		
*	asterisk	2/10	G2 (initial setting for GR)		
+	plus sign	2/11	G3		
96	-Character Sets*				
-	hyphen	2/13	G1		
	period	2/14	G2		
/	slash	2/15	G3		

 $<sup>{}^{*}</sup>$ You cannot designate a 96-character set into G0.

## $I_2...I_n$ F, intermediate and final characters

Selects one of the standard character sets. The following table lists the characters used to select standard sets.

Table 5-14 Character Set Codes

Character Set	I <sub>2</sub> I <sub>n</sub> F Characters	Code				
94-Character Sets	94-Character Sets					
ASCII (initial setting for G1 and G0)	В	4/2				
DEC Supplemental Graphic (initial setting for G2 and G3)	%5	2/5, 3/5				
DEC Special Graphic Set	0	3/0				
DEC Technical Character Set	>	3/14				
User-preferred Supplemental Set	<	3/12				
NRC Sets						
DEC Supplemental	% 5	2/5, 3/5				
DEC Greek	" ?	2/2, 3/15				
DEC Hebrew	" 4	2/2, 3/4				
DEC Turkish	% <b>0</b>	2/5, 3/0				
DEC Cyrillic	& 4	2/6, 3/4				
U.K. NRCS	A	4/1				
French NRCS	R	5/2				
French Canadian NRCS†	9 or Q	3/9 or 5/1				
Norwegian/Danish NRCS†	', E, or 6	6/0, 4/5, or 3/6				
Finnish NRCS†	5 or C	3/5 or 4/3				
German NRCS	K	4/11				

 $<sup>\</sup>dagger W\!e$  recommend using the first code shown.

(continued on next page)

Table 5-14 (Cont.) Character Set Codes

Character Set	I <sub>2</sub> I <sub>n</sub> F Characters	Code	
Italian NRCS	Y	5/9	
Swiss NRCS	=	3/13	
Swedish NRCS†	7 or H	3/7 or 4/8	
Spanish NRCS	Z	5/10	
Portuguese NRCS	% 6	2/5, 3/6	
Greek NRCS	" >	2/2, 3/14	
Hebrew NRCS	% =	2/5, 3/13	
Turkish NRCS	% <b>2</b>	2/5, 3/2	
SCS NRCS	% 3	2/5, 3/3	
Russian NRCS	& 5	3/6, 3/5	
96-Character Sets			
ISO Latin-1 Supplemental	Α	4/1	
ISO Latin-2 Supplemental	В	4/2	
ISO Greek Supplemental	F	4/6	
ISO Hebrew Supplemental	Н	4/8	
ISO Latin-Cyrillic	L	4/12	
ISO Latin-5 Supplemental	M	4/13	
User-preferred Supplemental	<	3/12	
+W			

†We recommend using the first code shown.

## **Examples**

The following sequence designates the Special Graphic character set as the G1 logical set:

ESC ) 0

The following sequence designates the ISO Latin-1 supplemental character set as the G3 logical set:

ESC / A

\_\_\_\_\_ Mapping Character Sets \_\_\_\_\_

After you designate a character set as G0, G1, G2, or G3, you must map the set into the in-use table as GL or GR. To map a set, you use *locking-shift* or *single-shift* control functions. See **LS-Locking Shift** or **SS-Single Shift**. commands.

## SD—Pan Up

This control function moves the user window up a specified number of lines in page memory.

## **Format**

## **Parameters**

### Pn

is the number of lines to move the user window up in page memory. Pn new lines appear at the top of the display. Pn old lines disappear at the bottom of the display. You cannot pan past the top margin of the current page.

## **SGR—Select Graphic Rendition**

This control function selects one or more character attributes at the same time.

**Default:** Clear all attributes.

### **Format**

```
CSI
      Ps
                   Ps
                                m
9/11
            3/11
                                6/13
```

### **Parameters**

### Ps

is a number representing a certain visual attribute. You can use more than one Ps value to select different character attributes. Table 5-15 lists Ps values and the attributes they select.

Default: Ps = 0 (clears all attributes).

Table 5-15 Visual Character Attribute Values

Ps	Attribute (VT Level 1 or higher)
0	All attributes off
1	Bold
4	Underline
5	Blinking
7	Negative image
8	Invisible image
Ps	Attribute (VT Level 2 or higher)
10	The ASCII character set is
	the current 7-bit display
	character set (default).
11	Hex 00-7F of the PC
	character set codes are
	mapped to the current 7-bit
	display character set.
12	Hex 80-FF of the current
	character set are mapped
	to the current 7-bit display
	character set.
22	Bold off
24	Underline off
25	Blinking off
27	Negative image off
28	Invisible image off

(continued on next page)

Ps	Attribute (VT Level 5, VT525 only) <sup>1</sup>	Default Color	
30	Foreground Color 0	Black	
31	Foreground Color 1	Red	
32	Foreground Color 2	Green	
33	Foreground Color 3	Yellow	
34	Foreground Color 4	Blue	
35	Foreground Color 5	Magenta	
36	Foreground Color 6	Cyan	
37	Foreground Color 7	White	
39	Default Foreground Color	White	
40	Background Color 0	Black	
41	Background Color 1	Red	
42	Background Color 2	Green	
43	Background Color 3	Yellow	
44	Background Color 4	Blue	
45	Background Color 5	Magenta	
46	Background Color 6	Cyan	
47	Background Color 7	White	
49	Default Background Color	Black	

<sup>&</sup>lt;sup>1</sup>ANSI color text extension (DA1 reports 22 for VT525 and VGB25 only).

## **Examples**

When you select more than one attribute in an SGR sequence, then they are executed in order. For example, you can use the following sequence to display text that is bold, blinking, and underlined:

```
CSI 0 ; 1 ; 5 ; 4 m
```

The following sequence displays the negative image of text:

CSI 7 m

### **Notes on SGR**

- After you select an attribute, the terminal applies that attribute to all new characters received. If you move characters by scrolling, then the attributes move with the characters.
- If you display control characters, then the terminal ignores the bold attribute for displayed control characters.
- Color renditions may be selected in any combination. Selecting additional renditions do not affect the setting of previously selected renditions or characters already on the display unless all renditions are turned off (parameter value 0).

When a PC character set is selected:

Command	(Hexadecimal) Display Character
Executing "CSI 10 m"	00-1F: control codes
	20-7F: ASCII characters
	80-FF: 8 bit PC characters
Executing "CSI 11 m"	00-1F: PC characters, except the following codes when XON/XOFF is enabled:
	1B (ESC)
	11 (DC1)
	13 (DC3)
	20-7F: ASCII characters (or PC 7 bit character)
	80-FF: 8 bit PC characters
Executing "CSI 12 m"	00-1F: PC characters that are located in 80 - 9F in PC character set, except the following codes when XON/XOFF is enabled:
	9B (ESC)
	91 (DC1)
	93 (DC3)
	20-7F: PC characters located in A0-FF
	80-FF: 8 bit PC characters.

### For ISO/ANSI character set:

Command	(Hexadecimal) Display Character		
Executing "CSI 10 m"	00-1F: control codes		
	20-7F: ASCII characters		
	80-9F: control code		
	A0-FF: GR characters		
Executing "CSI 12 m"	00-1F: control codes		
	20-7F: ISO/ANSI characters located in A0-FF		
	80-9F: control code		
	A0-FF: GR characters		

Commands "CSI 10-12 m" affect only the Hex 00-7F portion of the display character set. The hex 80-FF region of the display character set is left intact.

The ASCII character set with control codes residing in Hex 00 to 1F region is the default 7-bit display character set. This is true regardless of the ISO/ANSI or PC character set. When in an ISO/ANSI character set, issuing "CSI 10 m" is equivalent to "designating and invoking ASCII to G0 and GL."

### **SGR—Select Graphic Rendition**

When "ESC 11 m" is executed, the display character set is loaded with codes in the Hex 00 to 7F region of a PC character set. PC characters whose code values are less than 1F can be displayed through this sequence except 1B (ESC) and 11(DC1), 13(DC3) when XON/XOFF is enabled. 1B is always executed as an ESC to allow the application to execute the command to go back to the default character set. Hex 11 and 13 can be displayed only when XON/XOFF is disabled. This command does not work when the ISO/ANSI character set is selected.

Command "ESC 12 m" toggles the high bit of the current 8-bit character set. All the characters in Hex 80-FF region can be displayed as 7-bit codes except 9B (ESC) and 91(DC1), 93(DC3) when XON/XOFF is enabled. After the command is executed, 1B is executed as an ESC. Hex 11 and 13 can be displayed only when XON/XOFF is disabled.

When in an ISO/ANSI character set, issuing "CSI 12 m" is equivalent to "designating and invoking current 8 bit char set to G2 and GL."

### SRM—Local Echo: Send/Receive Mode

This control function turns local echo on or off. When local echo is on, the terminal sends keyboard characters to the screen. The host does not have to send (echo) the characters back to the terminal display. When local echo is off, the terminal only sends characters to the host. It is up to the host to echo characters back to the screen.

**Default:** No local echo

### **Format**

<b>CSI</b> 9/11	<b>1</b> 3/1	<b>2</b> 3/2	<b>h</b> 6/8	Set: local echo off.
<b>CSI</b> 9/11	-	<b>2</b> 3/2	-	Reset: local echo on.

### **Description**

When the SRM function is set, the terminal sends keyboard characters to the host only. The host can echo the characters back to the screen.

When the SRM function is reset, the terminal sends keyboard characters to the host and to the screen. The host does have to echo characters back to the terminal.

## SS—Single Shifts

You use a single shift when you want to display the next character from a different character set. A single shift maps the G2 or G3 set into GL. The character set is active for only one character, then the terminal returns to the previous character set in GL.

The terminal has two single-shift control functions available.

### **Format**

Single-Shift Control	8-Bit Character	7-Bit Equivalent Sequence		Function	
Single shift 2	<b>SS2</b> 8/14	<b>ESC</b> 1/11	<b>N</b> 4/14	Maps G2 into GL for the next character.	
Single shift 3	<b>SS3</b> 8/15	<b>ESC</b> 1/11	<b>O</b> 4/15	Maps G3 into GL for the next character.	

## **Example**

Suppose the ASCII character set is in GL. You want to display the alpha character from the DEC Technical character set, already designated as G3. You do not want to replace the ASCII set just to display one character. Instead, you can use single shift 3 to temporarily map the DEC Technical set (G3) into GL.

**SS3**single shift 3 alpha character

After displaying the alpha character, the terminal maps the ASCII set (G1) back into GL, replacing the DEC Technical set (G3).

## SM—Set Mode

This control function has two versions. You use the ANSI version to set one or more ANSI modes. You use the DEC private version to set one or more DEC private modes. You *cannot* set ANSI and DEC private modes with the same SM sequence.

## **Setting DEC Private Modes**

CSI	?	Pd	;	 Pd	h
9/11	3/15	3/n	3/11	 3/n	6/8

### **Parameters**

### Pd

indicates a DEC private mode to set. Table 5–5 lists the Pd values for DEC private modes. You can use more than one Pd value in a sequence.

### **Examples**

#### **DEC Private Modes**

The following sequence sets (Hebrew) keyboard mapping (DECHEBM) and Hebrew encoding mode (DECHEM):

```
CSI ? 34; 36 h
```

34 indicates (Hebrew) keyboard mapping.

36 indicates Hebrew encoding mode.

### **Programming Tip**

Applications can use the SM and RM functions to restore any number of VT520 modes to a desired state. See the Report Mode (DECRPM) section in this chapter for details.

## SU—Pan Down

This control function moves the user window down a specified number of lines in page memory.

### **Format**

### **Parameters**

### Pn

is the number of lines to move the user window down in page memory. Pn new lines appear at the bottom of the display. Pn old lines disappear at the top of the display. You cannot pan past the bottom margin of the current page.

## **TBC—Tab Clear**

This control function clears tab stops.

### **Format**

## **Parameters**

### Ps

indicates the tab stops to clear. There are only two values for Ps, 0 and 3.

 $\boldsymbol{0}$  or none  $\boldsymbol{\phantom{0}}$  The terminal only clears the tab stop at the cursor. (default)

3 The terminal clears all tab stops.

## **VPA—Vertical Line Position Absolute**

Move to the corresponding vertical position (line Pn) of the current column.

The default value is 1.

### **Format**

### **Parameters**

Pn

is line number.

### **Description**

Move cursor to line Pn. VPA causes the active position to be moved to the corresponding vertical position on line Pn. If an attempt is made to move the active position beyond the last line, then the active position stops at the last line.

## **VPR—Vertical Position Relative**

Move vertically Pn lines in the current column.

The default value is 1.

### **Format**

#### **Parameters**

Pn

is number of lines to move.

## Description

VPR causes the active position to be moved to vertically corresponding Pn lines following the current position of the active line. If an attempt is made to move the active position beyond the last line, the active position stops at the last line.

## **SCO Console Emulation**

This chapter describes the SCO Console mode.

## 6.1 SCO Console Emulation Mode

SCO Console mode is a terminal emulation mode. It uses ANSI sequences with minor modifications to act like a SCO UNIX operating system console on a PC.

Depending on the terminal status, SCO Console mode for the VT520 transmits ASCII characters (default) or scancode to the host when keys are pressed. Users can specify a keycode mode by issuing an escape sequence (DECPCTERM) or by keyboard encoding of Set-Up. When in SCO Console mode with the ASCII keycode selected, the terminal behavior is similar to VT mode. When in SCO Console mode with scancode selected, the terminal behavior is similar to VT PCTerm mode. Table 6–1 shows the similarities and differences.

Table 6-1 SCO Console Mode with ASCII Keycodes and Scancodes

	SCO Console			
Default	ASCII Keycodes	Scancodes	VT Mode	VT PCTerm
Screen display	25×80	25×80	24×80	25×80
Autowrap	On	On	Off	On
Autowrap behavior	Like WYSE	Like WYSE	Like VT	Like VT
Status line	None	None	Local	None
Cursor position while switching pages	Saved	Saved	Not saved	Not saved
Character set	PCTerm (including PC, ISO/ANSI character sets)		VT character set (ISO/ANSI)	PCTerm character set
CSI 10-12 m	Supported	Supported	Not supported	Not supported
SU SD	Acts like IND Acts like RI	Acts like IND Acts like RI	Acts like SU Acts like SD	Acts like SU Acts like SD
CSI s and CSI u DECSC and DECRC	Supported Supported	Supported Supported	Only DECSC and DECRC are supported	
CSI <i>Pn</i> z (switch pages)	Supported	Supported	Not supported	Not supported
ESC Q Fn String (Define Function)	Supported	Supported	Not supported	Not supported
Transmit flow control	None	None	XON/XOFF	None

## **SCO Console Emulation** 6.1 SCO Console Emulation Mode

## 6.1.1 Keyboard

SCO Console mode works with either a PC keyboard or a VT keyboard attached.

### 6.1.1.1 Local Function Keys in SCO Console Mode

The keys used to perform local functions in SCO Console mode are similar to those used for VT mode (see Chapter 8, Keyboard Processing. Table 6-2 shows the exceptions).

Table 6–2 Local Functions on VT and Enhanced PC Layouts

Fn#	Function	VT Layout	EPC Layout
1	Hold	CapsLock/F1	Scroll CapsLock
2	Print	CapsLock/F2	Print Screen
3	Set-Up	CapsLock/F3	CapsLock/Print Screen , Alt/Print Screen
5	Break	CapsLock/F5	CapsLock/Pause
7	Hard Reset	CapsLock/Ctrl/F3	Ctrl/CapsLock/Print Screen
8	Toggle Autoprint	CapsLock/Ctrl/F2	Ctrl/Print Screen
9	Disconnect	CapsLock/Shift/F5	Shift/CapsLock/Pause
10	Send Answerback	CapsLock/Ctrl/F5	Ctrl/CapsLock/Pause
11	Print Composed Main Display	Not supported	
20	Pan Up	Not supported	
21	Pan Down	Not supported	
24	Pan Prev Page	Not supported	
25	Pan Next Page	Not supported	
30	Copy and Paste	CapsLock/F1	Scroll Lock
47	Primary KB language	CapsLock/Ctrl/Alt/F1	CapsLock/Ctrl/Alt/F1
48	Secondary KB language	CapsLock/Ctrl/Alt/F2	CapsLock/Ctrl/Alt/F2
53	±DEC/IBM PC Style	Not supported	

### 6.1.1.2 PC Keyboard

Tables 6-3 through 6-6 list the default codes sent by keys in ASCII character

The keys that can be affected by Caps Lock or Num Lock send a shifted value when in Lock state. If Shift is pressed when Caps Lock or Num Lock is in effect, the key sends its unshifted value. This "Reverse Lock" is the default for a Caps Lock function.

Alt has no effect on the key pressed unless otherwise indicated. A blank in any column means the keystroke is not defined.

Table 6-3 SCO Console Mode Function Key Default Codes

Key	Unmodified	Shift	Ctrl	Ctrl/Shift
F1	ESC[M	ESC[Y	ESC[k	ESC[w
F2	ESC[N	ESC[Z	ESC[l	ESC[x
F3	ESC[O	ESC[a	ESC[m	ESC[y
F4	ESC[P	ESC[b	ESC[n	ESC[z
F5	ESC[Q	ESC[c	ESC[o	ESC[@
F6	ESC[R	ESC[d	ESC[p	ESC[[
F7	ESC[S	ESC[e	ESC[q	ESC[<
F8	ESC[T	ESC[f	ESC[r	ESC[]
F9	ESC[U	ESC[g	ESC[s	ESC[^
F10	ESC[V	ESC[h	ESC[t	ESC[_
F11	ESC[W	ESC[i	ESC[u	ESC['
F12	ESC[X	ESC[j	ESC[v	ESC[{
Print Screen	Print Screen	ESC[0i		
Scroll Lock	Scroll Lock	Scroll Lock	N/A	N/A
Pause	Break	Break	N/A	N/A

Table 6-4 SCO Console Mode Main Keypad Default Codes

Key	Unmodified	Shift	Ctrl	Ctrl/Shift
ESC	ESC	ESC	ESC	ESC
1	1	!	1	!
2	2	@	Nul	Nul
3	3	#	ESC	ESC
4	4	\$	FS	FS
5	5	%	GS	GS
6	6	^	RS	RS
7	7	&	US	US
8	8	*	DEL	DEL
9	9	(		
0	0	)		
-	-	_	US	US
=	=	+		
Backspace	BS	BS	DEL	DEL
Tab	HT	ESC[Z		
q	q	Q	DC1	DC1
W	w	W	ETB	ETB
е	e	E	ENQ	ENQ
r	r	R	DC2	DC2

(continued on next page)

## **SCO Console Emulation 6.1 SCO Console Emulation Mode**

Table 6-4 (Cont.) SCO Console Mode Main Keypad Default Codes

Key	Unmodified	Shift	Ctrl	Ctrl/Shift
t	t	Т	DC4	DC4
У	y	Y	EM	EM
u	u	U	NAK	NAK
i	i	I	HT	HT
0	0	0	SI	SI
р	p	P	DLE	DLE
1	[	{	ESC	ESC
1	]	}	GS	GS
\	\		FS	FS
Return	CR	CR	LF	LF
Ctrl	Ctrl	Ctrl	Ctrl	Ctrl
а	a	Α	SOH	SOH
S	S	S	DC3	DC3
d	d	D	EOT	EOT
f	f	F	ACK	ACK
g	g	G	BEL	BEL
h	h	Н	BS	BS
j	j	J	LF	LF
k	k	K	VT	VT
	1	L	FF	FF
,	;	:		
,	,	"		
Z	z	Z	SUB	SUB
х	X	X	CAN	CAN
С	c	С	ETX	ETX
V	v	V	SYN	SYN
b	b	В	STX	STX
n	n	N	SO	SO
m	m	M	CR	CR
,	,	<		
	•	>		
/	1	?	US	US

Table 6-5 SCO Console Mode Numeric Keypad Default Codes, Num Lock Off

Keypad Key	Unmodified	Shift	Ctrl	Ctrl/Shift
Num Lock	Num Lock	Num Lock	DC3	DC3
/	/	/		
*	*	*		
7	ESC[H	7	ESC[H	7
8	ESC[A	8	ESC[A	8
9	ESC[I	9	ESC[I	9
-	-	-	-	-
4	ESC[D	4	ESC[D	4
5	ESC[E	5	ESC[E	5
6	ESC[C	6	ESC[C	6
+	+	+	+	+
1	ESC[F	1	ESC[F	1
2	ESC[B	2	ESC[B	2
3	ESC[G	3	ESC[G	3
0	ESC[L	0	ESC[L	0
	DEL		DEL	DEL
Enter	CR	CR	LF	LF

Table 6-6 SCO Console Mode Numeric Keypad Default Codes, Num Lock On

Keypad Key	Unmodified	Shift	Ctrl	Ctrl/Shift
Numlock	Numlock	Numlock	DC3	DC3
/	/	/		
*	*	*		
7	7	ESC[H		
8	8	ESC[A		
9	9	ESC[I		
-	-	-	-	-
4	4	ESC[D		
5	5	ESC[E		
6	6	ESC[C		
+	+	+		
1	1	ESC[F		
2	2	ESC[B		
3	3	ESC[G		
0	0	ESC[L		
		DEL		
Enter	CR	CR		




Table 6-7 SCO Console Mode Editing Keypad Default Codes

Key	Unmodified, Shift, Ctrl, or Ctrl/Shift
Insert	ESC[L
Home	ESC[H
Page Up	ESC[I
Delete	DEL
End	ESC[F
Page Down	ESC[G

Table 6–8 SCO Console Mode Cursor Keypad Default Codes

Key	Unmodified, Shift, Ctrl, or Ctrl/Shift
<b>↑</b>	ESC[A
$\downarrow$	ESC[B
$\Rightarrow$	ESC[C
<b>⇐</b>	ESC[D

## 6.1.1.3 VT Keyboard Key Mapping

More key mapping information is provided in Chapter 8, Keyboard Processing.

- On the main keypad, 8-bit codes are allowed for keyboard input.
- Function keys F1 through F12 send the same codes as F1 through F12 on a PC keyboard. Function keys F13 through F20 send the same codes as F13 through F20 in VT mode, except Do sends an ESC code.
- For Autowrap, On is the default.
- On the editing keypad, VT keyboard keys send the same sequences as the corresponding PC keyboard keys:

PC Keyboard	VT Keyboard	
Insert	Insert Here	
Home	Find	
PageUp	Prev	
Delete	Remove	
End	Select	
PageDown	Next	

## 6.2 VT520 SCO Console Control Sequences

## **SCODFK—Define Function Key**

Programs function key to send a defined string in SCO Console mode.

### **Format**

### **Parameters**

is an ASCII code representing the function key being defined. F1, the first key, is represented by "0"; each following key has an ASCII value that increments 1 from the previous key's ASCII value as follows:

Key	Function Key	Fn ASCII Character
1 - 12	F1 through F12	0 - ;
13 - 24	Shift/F1 through Shift/F12	< - G
25 - 36	Ctrl/F1 through Ctrl/F12	H - S
37 - 48	Ctrl/Shift/F1 through Ctrl/Shift/F12	T
49	Kpd 7	•
50	Kpd 8	a
51	Kpd 9	b
52	Kpd [-]	c
53	Kpd 4	d
54	Kpd 5	e
55	Kpd 6	f
56	Kpd +	g
57	Kpd 1	h
58	Kpd 2	i
59	Kpd 3	j
60	Kpd 0	k

#### String

is the programmed key definition which is enveloped by two characters as the delimiters.

## SCODFK—Define Function Key

## Description

The first character after the ASCII character representing a function key becomes the delimiter. It looks for an identical character as the second and final delimiter. If string is too long and no memory is available, then the command string is aborted and remaining characters are displayed on screen. The character becomes the final character. All the following characters are displayed on the screen.

### **Example:**

Executing "ESC Q 0 'abcdefghij'klmnopq" when 100 bytes of memory is available defines the string "abcdefghij" into F1 function key and displays "klmnopq" on the screen.

If you execute the same sequence when only a 4 byte string is allowed, then the whole sequence is aborted.

A "^" character causes any following character to subtract 32 from its ASCII value. For example, "^e" in the string sends "E" when the key is pressed.

Any code in the 00-7F region can be defined. An 8-bit code entered is stripped of its eighth bit and defined as a corresponding 7-bit code.

For example, executing ESCQ0'F1KEY' defines string F1KEY for function key F1; ESC1aF2KEYa defines string F2key for F2.

The maximum string length for a defined key is 255 characters.

## SCODPCC—Display PC Characters

Displays C0 controls (lower 32 bytes) as PC characters for SCO Console mode.

### **Format**

**ESC** XX 1/11 hex value

### Description

SCO Console allows "ESC xx" to work when the PC character set is selected and displayable characters are mapped in the 00-1F region (when either "CSI 11 m" or "CSI 12 m" is executed). The command allows the character in 1B location to be displayed; 1B is always executed as an ESC control code under "CSI 11 or 12 m" (See SGR).

## SCORC—Restore Saved Cursor Position

Moves cursor to the position saved by save cursor command in SCO console mode.

### **Format**

## **Description**

This command acts the same as the DECRC command, except that the cursor stays at the same page instead of moving to a page where the cursor was saved.

## SCOSC—Save Current Cursor Position

Saves current cursor position for SCO console mode.

### **Format**

## **Description**

This command acts the same as the DECSC command, except that the page number where the cursor is located is not saved as a result of executing the command.

## **Character Sets**

This chapter describes the character sets supported by the VT520 video terminal.

### 7.1 Overview

The VT520 video terminal supports most character sets for Eastern Europe, Cyrillic, Greek, Hebrew, and Turkish character sets. In addition to traditional DEC and ISO character sets the VT520 supports a number of IBM PC *code pages* (which refer to page numbers in IBM's standard character set manual) in PCTerm mode to emulate the console terminal of industry-standard PCs.

Each code page defines both the exact repertoire (set of characters) and the assignment of code positions in the 0 - 255 range. Once configured, the code page is not usually changed within a single application.

## 7.2 Character Sets Supported

The following sections list the characters sets supported by the VT520 terminal.

## 7.2.1 VT Graphic Character Sets

The VT520 supports the following VT 8-bit multinational character sets:

- ISO Latin-1
- ISO Latin-2
- ISO Latin-Cyrillic
- ISO Latin-Greek
- ISO Latin-Hebrew
- ISO Latin-5
- KOI-8 Cyrillic
- DEC Multinational
- DEC Greek
- DEC Hebrew
- DEC Turkish

The VT520 also supports the following character sets:

- DEC Special Graphics (VT100 Line Drawing set)
- DEC Technical Character set

## Character Sets 7.2 Character Sets Supported

When **7-bit NRCS Characters** is selected, a corresponding 7-bit or NRC set is used depending on the keyboard language selected. (See Chapter 8 for details.)

- U.K. NRC (ISO)
- French NRC (ISO)
- DEC French Canadian NRC
- Norwegian/Danish NRC (ISO)
- DEC Finnish NRC
- German NRC (ISO)
- Italian NRC (ISO)
- DEC Swiss NRC
- Swedish NRC (ISO)
- Spanish NRC (ISO)
- DEC Portuguese NRC
- SCS NRC
- Russian 7-bit (KOI-7)
- DEC 7-bit Greek
- DEC 7-bit Hebrew
- DEC 7-bit Turkish

## 7.2.2 PCTerm Graphic Character Sets

When **PCTerm mode** is selected, the terminal can still use all the VT 8-bit character sets listed in Section 7.2.1. Additionally, the following PC code pages are supported:

- PC International (437)
- PC Multilingual (850)
- PC Slavic (852)
- PC Greek (210)
- PC Spanish (220)
- PC Turkish (857)
- PC Portuguese (860)
- PC Hebrew (862)
- PC French/Canadian (863)
- PC Danish/Norwegian (865)

<ul> <li>PC Cyri</li> </ul>	llic	(866)
-----------------------------	------	-------

Note
7-bit NRC sets are not available in PCTerm mode.

### 7.2.3 Control Character Sets

The following control character sets are defined in the terminal. ASCII C0 and C1 control sets have corresponding fonts for graphic representation in control representation mode.

- ASCII C0 Control Set (32 characters)
- 8-bit ASCII C1 Control Set (32 characters)

The control representation mode font includes C0 and C1 control character set graphic representations plus DELETE (7/15), non-breaking space - NBSP (10/0), and 15/15 (total of 67 characters).

### 7.2.4 Character Set Structure

The VT 8-bit multinational character sets are formed from two 7-bit character set "halves." ASCII is used as the left half (GL), and the corresponding named supplemental set is used as the right half (GR). Although the character set "halves" can be designated and invoked independently, in practice, they are almost always used together. It is simpler and more convenient to think of them as a single 8-bit multinational set, although technically they are also separate 7-bit sets.

Many characters appear in more than one of the mentioned sets, so the total number of characters is far less than the sum of the individual totals. There is also a down-line loadable portion of character RAM provided for a custom *soft font*, a Dynamically Redefinable Character Set (DRCS). This character RAM can contain up to  $2 \times 96$  characters.

#### 7.2.5 Characters Not in a Character Set.

The following characters are not technically part of any of character set. They are like "control characters," but they are not in the C0 or C1 control sets.

Name	Description	Code	Keystroke	Action on Receipt
SP	SPACE	32	Space Bar	Treated as space
DEL	DELETE	127	Delete Ctrl-8	Ignored (unless in CRM)
	Reserved	160	None	Error character generated
	Reserved	255	None	Ignored (unless in CRM)

Notes

NULL is the only fill character. (DEL and 255 are not usable as fill characters.)

If a 96-character character set is invoked into GL, then the receipt of codes 32 and 127 are part of that character set, and their graphic characters are displayed from the 96-character set. In this case, the codes 32 and 127 are not treated as SP or DEL.

If a 96-character character set is invoked into GR, the receipt of codes 160 and 255 are part of that character set, and their graphic characters are displayed from the 96-character character set. In this case, the codes 160 and 255 are not treated as an error condition or ignored, respectively.

### 7.3 VT Mode

All DEC character sets are supported in VT500 mode with either a VT keyboard or an attached Enhanced PC keyboard.

In VT100 mode, VT52 mode, or when **7-bit NRCS characters** is selected (through Set-Up or DECNRCM), only ASCII, NRC sets, and DEC Special Graphic characters are available.

## 7.3.1 Selecting Character Sets

Character sets are designated with the select character set (SCS) control function. Refer to Chapter 5 for more details.

## 7.3.2 Character Set Mappings

The following table lists the character set mappings.

Character Set	Mapped onto decimal
C0 controls	0 to 31
Space	32
ASCII, all other NRC sets, Line Drawing, DEC Technical set, DEC 7-Bit Greek, DEC 7-Bit Hebrew, or DEC 7-Bit Turkish	33 to 126
DEL	127
C1 controls	128 to 159
10/0	160
DEC Multinational Graphic,	161 to 254
15/15	255
ISO Latin-1 Supplemental Graphic, ISO Latin-2 Supplemental Graphic, ISO Latin-Cyrillic, ISO Latin-Greek, ISO Latin-Hebrew, or ISO Latin-5.	160 to 255

These are typical assignments. By appropriate designating and invoking sequences, other mappings are possible for the graphic character sets.

### 7.4 PCTerm Mode

This section describes how to select character sets in PCTerm mode.

### 7.4.1 Selecting Character Sets

If a **PC** character set is selected, then all the SCS sequences used to designate and invoke character sets into G0, G1, G2, G3, GL, and GR (including single and locking shifts) are ignored. You select the character set through a Set-Up field or an escape sequence, DECPCTERM. You can use only one code page containing 256 characters at a time.

If you use a DEC character set, all the SCS and invocation sequences continue to work normally.

## 7.4.2 Character Set Mappings

If DEC character sets are in use, all the character set mappings follow the VT mode convention. C0 and C1 regions are all control codes.

In PC character sets, the conventional ISO C1 region, (80 hex through 9F hex) are all displayable character codes. The VT520 does not recognize control sequences that have 8-bit control codes; therefore, the 8-bit control mode becomes invalid.

The C0 region (00 hex through 1F hex) in a PC character set is mixed with control characters and graphic characters. Among them, 11 locations can have both *control characters* and *displayable characters* in the same locations; other locations are occupied by displayable characters only. The 11 C0 locations include 0/5, 0/7, 0/8, 0/9, 0/A, 0/B, 0/C, 0/D, 1/1, 1/3, and 1/B.

Control codes are used for ENQ, BEL, BS, HT, LF, VT, FF, CR, DC1, DC3, and ESC operations.

You access the *displayable characters* by preceding the C0 control code with ESC to form a 2-byte pair (1Bh XXh). These 2-byte pairs, such as ESC C0, are only recognized in PCTerm mode.

### 7.5 SCO Console Mode

SCO console mode can use both VT character sets and PC character sets. You select a **VT character set** through the **PCTerm character set** field in Set-Up, or you can use an SCS invocation sequence. You can select a PC character set through the same Set-Up field, or you can use the DECPCTERM escape sequence.

Note
All the character sets can be displayed on the screen.

### 7.6 Soft Character Sets


You can download soft character set from the host system into the terminal. This feature lets you design your own soft character sets for use with the terminal. You can only load soft character sets in VT Level 4 or higher.


The control string command to down-line load the soft character sets is DECDLD. The DECDLD command down-line loads one or more characters of a specified 94-or 96-character dynamically redefinable character set (DRCS) with a specified logical pixel pattern. The affected characters in the DRCS set also change the presentation of characters from the set currently being displayed on the screen. The DECDLD control does not clear the screen.

See Chapter 5 for a description of the DECDLD—Dynamically Redefinable Character Sets Extension command.

	Note
the character cell sizes are d	appear different on a VT520 terminal, because lifferent from those terminals. See the D—Dynamically Redefinable Character Sets

## Character Sets 7.6 Soft Character Sets





The next section describes the guidelines for designing a soft set. The sections that follow describe how to code, load, designate, and clear a soft set.

### 7.6.1 Designing a Soft Character Set

Your terminal displays each character by turning on a series of pixels. A **pixel** (picture element) is the smallest displayable unit on the screen. Each character must fit in a limited area, called the character cell. The size of the character cell depends on the number of lines and columns on the screen. The screen can display 24, 36, or 48 lines in 80 or 132 columns. With 24 lines on the screen, the terminal uses a default character cell size of 10 by 16 pixels for 80 columns and 6 by 16 pixels for 132 columns (Figure 7–1).

Figure 7-1 Character Cell Sizes for 24-Line by 80- and 132-Column Fonts




Table 7–1 shows the default character cell widths and heights based on the number of lines and columns on the screen.

Table 7-1 Character Cell Sizes

Cell Size	80 Columns	132 Columns	
24 Lines/Screen			
Width	10 pixels	6 pixels	
Height	16	16	
36 Lines/Screen			
Width	10	6	
Height	10	10	
48 Lines/Screen			
Width	10	6	
Height	8	8	

When you design a character, you should lay out a character cell on grid paper. The little boxes on the grid paper represent pixels. You fill in the pixels that make up the character. The next section shows an example of a character design.

You should design six versions of your character set to fit six different character cell sizes. This means that there will be a version of your soft character set to fit any combination of lines and columns available on the terminal:

24 lines × 80 columns

24 lines × 132 columns

36 lines × 80 columns

 $36 lines \times 132 columns$ 

48 lines × 80 columns

48 lines × 132 columns

Design your character set, then load six versions of the set, one for each possible line/column combination. The terminal automatically selects which version of the set to use, based on the current number of lines and columns on the screen.

The terminal's built-in fonts follow the guidelines in Table 7–2, which lists the different guidelines for characters displayed with 24 lines, 36 lines, or 48 lines on the screen. In all cases, the screen resolution is 800 by 400 pixels for 80 columns, 792 by 400 pixels for 132 columns. The pixel aspect ratio is 1:1.4.

You must design your characters to fit the cell. The terminal ignores any pixels that are defined outside the cell. Also, you should include empty pixels on the left or right side of the character cell to allow for space between characters. Figure 7–2 shows an example of spacing for an uppercase D character with 24 lines on the screen. In this example, the character for the 80-column font has two pixel columns reserved for spacing.

Character Body Width 7 Spacing Spacing Spacing Width Spacing Character Height 10 Body Height 10

Figure 7–2 Character Body Sizes for 24-Line by 80- and 132-Column Fonts

All values are in pixels.

GSF\_0599\_89\_R.DG

Table 7-2 Guidelines for Designing Soft Characters

Character Dimension	80-Column Font	132-Column Font			
24 Lines/Screen					
Cell width	10 pixels	6 pixels			
Cell height	16	16			
Body width	8	4			
Body height	10	9			
Ascender height	3	3			
Descender height	3	3			
Spacing before character	1	1			
Spacing after character	1	1			

(continued on next page)

Table 7-2 (Cont.) Guidelines for Designing Soft Characters

Character Dimension	80-0	Column Font	132	-Column Font
36 Lines/Screen				
Cell width	10	pixels	6	pixels
Cell height	10	•	10	•
Body width	7		5	
Body height	7		7	
Ascender height	2		1	
Descender height	1		2	
Spacing before character	2		1	
Spacing after character	1		0	
48 Lines/Screen				
Cell width	10	pixels	6	pixels
Cell height	8		8	
Body width	7		4	
Body height	6		7	
Ascender height	1		1	
Descender height	1		1	
Spacing before character	2		1	
Spacing after character	1		1	

### 7.6.2 Coding the Soft Character Set

After you design your characters, you must code them for the terminal. This section describes how to code soft characters. The next section describes how to load the character codes into the terminal.

Each pixel of a soft character cell receives a binary value of 0 or 1. A 1 bit indicates the pixel is on, and a 0 bit indicates the pixel is off.

The terminal receives the code for a soft character in sections, called **sixels**. A sixel is a 6-bit binary code that represents a vertical column of 6 pixels on the screen. Each bit in a sixel corresponds to a pixel on the screen. The following example describes how to design and code a soft character.

### **Example**

Suppose you want to design an uppercase D for a 24-line by 80-column font.

### 1. Draw your design on a grid.

Use the grid for an 80-column character cell to draw your design. Mark which pixels will be on and which pixels will be off. Your design may look like Figure 7–2.

### 2. Divide the character cell into columns of 6 bits each.

## **Character Sets 7.6 Soft Character Sets**

Use the format shown in Figure 7–3. Each 6-bit pattern represents 6 pixels, or a sixel. The least significant bit is at the top, and the most significant bit is at the bottom. The terminal would receive the sixel columns in order (1 to 10), starting with Group A.

7 b0 b1 Group A b2 b3 b4 b5 b0 b1 Group B b2 b3 b4 b5 b0 b1 Group C b2 b3

Figure 7-3 Example of an Uppercase D (24-Line by 80-Column Font)

GSF\_0600\_89.DG

Because the character cell height (16 pixels) is not a multiple of 6, the columns on the bottom of the character cell (Group D) have only 4 bits each, b0 through b3. Bits b4 and b5 in the bottom cell do not affect the character's appearance, so they have been excluded from Figure 7–3.

### 3. Convert the binary value of each sixel to its hexadecimal value.

Sixels codes are restricted to characters in the range of ?  $(3F_{16})$  to  $\sim$   $(7E_{16})$ , so you must add an offset of  $3F_{16}$  to the hexadecimal value of each column. For example:

## 4. Use Table 7-3 to convert each binary number to the equivalent ASCII character.

Table 7–3 lists the results of steps 3 and 4 for each possible binary value. All you have to do is find the 6-digit binary number for each sixel bit pattern in your character design.

Figure 7–4 shows this conversion for the uppercase D in this example.

You use this procedure to convert each character of your soft character set into a string of sixel bit patterns. Then you can download your DRCS characters into the terminal, using the DECDLD device control string described in Chapter 5.

Table 7–3 Converting Binary Code to an ASCII Character

Binary Value	Hex. Value	Hex. Value + 3F Offset	Character Equivalent
000000	00	3F	?
000001	01	40	@
000010	02	41	A
000011	03	42	В
000100	04	43	С
000101	05	44	D
000110	06	45	E
000111	07	46	F
001000	08	47	G
001001	09	48	Н
001010	A	49	I
001011	В	4A	J
001100	C	4B	K
001101	D	4C	L
001110	E	4D	M
001111	F	4E	N
010000	10	4F	0
010001	11	50	P
010010	12	51	Q
010011	13	52	R
010100	14	53	S
010101	15	54	T
010110	16	55	U
010111	17	56	V
011000	18	57	W
011001	19	58	X
011010	1A	59	Y
011011	1B	5A	Z
011100	1C	5B	[
011101	1D	5C	\
011110	1E	5D	1
011111	1F	5E	٨
100000	20	5F	_

(continued on next page)

# **Character Sets** 7.6 Soft Character Sets

Table 7–3 (Cont.) Converting Binary Code to an ASCII Character

Binary Value	Hex. Value	Hex. Value + 3F Offset	Character Equivalent
100001	21	60	•
100010	22	61	a
100011	23	62	b
100100	24	63	c
100101	25	64	d
100110	26	65	e
100111	27	66	f
101000	28	67	g
101001	29	68	g h
101010	2A	69	i
101011	2B	6A	j
101100	2C	6B	k
101101	2D	6C	1
101110	2E	6D	m
101111	2F	6E	n
110000	30	6F	0
110001	31	70	p
110010	32	71	q
110011	33	72	r
100100	34	73	S
110101	35	74	t
110110	36	75	u
110111	37	76	v
111000	38	77	W
111001	39	78	X
111010	3A	79	y
111011	3B	7A	z
111100	3C	7B	{
111101	3D	7C	
111110	3E	7D	}
111111	3F	7E	~




Figure 7-4 Sixel-to-ASCII Conversion

## 7.6.3 Downloading Soft Characters

The terminal lets you load up to six variations of the same soft character set for each session. These six variations correspond to the six different combinations of character width and character height available.

### **Character Width**

For 80 columns:	10 pixels
For 132 columns:	6 pixels
Character Height	
For 24 lines/screen:	16 pixels
For 36 lines/screen:	10 pixels
For 48 lines/screen:	8 pixels

## Character Sets 7.6 Soft Character Sets

You can adjust the screen size by using the select number of lines/screen (DECSNLS) control function. The terminal automatically selects the appropriate soft set for the screen size.

When loading a soft set, you specify which of the six width/height variations the set is intended for. Your set replaces any soft set already loaded for that width/height variation.

You should load six variations of your set to correspond to the six variations of character width and height available in the terminal (80 or 132 columns by 24, 36, or 48 lines). Do not confuse the font rendition with the actual character set. You cannot load six different soft sets. However, you can load six different renditions of the same soft set.

### 7.6.4 Designating the Soft Character Set

You designate your soft character set the same way you designate the hard character sets—using a select character set (SCS) sequence. You also use the same format for the SCS sequence.

ESC	Intermediate(s)	Final	
1/11	*****	****	

#### Intermediate(s)

are one or more characters that designate the soft character set as one of the logical sets, G0 through G3. You use the same intermediate characters that you use for SCS select character set function (Table 5–13).

The intermediate character(s) also indicates whether the soft character set is a 94- or 96-character set. Make sure you use an intermediate character that matches the setting of the character set size parameter (*Pcss*) in the DECDLD string (Table 5–2).

### **Final**

is the *Dscs* name you used for the soft character set in the DECDLD string.

### **Notes on Designating Soft Character Sets**

#### · Replacing a soft set with a new soft set

If you use a new *Dscs* name when you replace the current soft set with another soft set, then the following occurs:

- Characters from the old soft set are undefined. If you redefine the soft set, characters currently on the screen may change.
- Any logical sets (G0, G1, G2, G3) used to designate the old soft set are undefined. The in-use table is also undefined.

After you load a new soft set, use a select character set (SCS) sequence to designate the soft set. Using SCS eliminates the confusion involved with undefined characters.

### Replacing a hard set with a soft set

You can define a soft set that replaces one of the hard sets (such as ASCII or DEC Special Graphic).


A soft set that replaces a hard set remains in effect until you perform one of the following actions:

- Clear the soft set by:
  - Recalling saved settings or factory-default settings with the Save or Default fields in the Set-Up Directory.
  - Running the power-up self-test.
- Redefine the soft set (using another DECDLD string).

### 7.6.5 Soft Character Set Example

Suppose you want to create a soft character set containing a solid rectangle, a blank, a rectangular box, and a striped rectangle. You decide to use a font that is 24 lines by 80 columns with a character cell size of 8 by 16 pixels. This example shows how you would

- 1. Download the set.
- 2. Designate the set as G1.
- 3. Map the G1 set into GL.



1. You could use the following DECDLD string to load your character set. The string is shown divided into sections for clarity.

### **DCS** (9/0)

introduces the device control string.

### 1;1;0;12;1;1;12;0

is the parameter string specifying the following functions. See Table 5-2 for parameter definitions.

Parameter	Function
Pfn = 1	Loads this soft set into the DRCS font buffer.
<i>Pcn</i> = 1	Selects the character at row $2$ / column 1 in the ASCII table (Figure 4–1) as the first character to load.
Pe = 0	Erases all characters in the font buffer for that rendition.
Pcmw = 12	Selects a maximum character width of 12 pixels.
Pss = 1	Selects a font set size of 80 columns, 24 lines.
Pt = 1	Defines the set as a text font.
Pcmh = 12	Selects a maximum character height of 12 pixels.
Pcss = 0	Defines the set as a 94-character set.

## Character Sets 7.6 Soft Character Sets

**{** (7/11)

indicates the end of the parameter characters and specifies that this sequence is a DECDLD string.

sp@

defines the character set as an unregistered soft set. This value is the recommended default value for user-defined sets. The sp represents one space. You can use other values to define other specific character sets.

\_\_\_/\_\_\_\_

represents the first character (a solid rectangle).

; separates the soft characters.

represents the second character (a blank).

~@@@@@@~/~??????~/~GGGGGG~

represents the third character (a hollow rectangle).

### TTTTTTTTTTTTTTTTTTTTTTTTTTT

represents the fourth character (a set of horizontal stripes).

ST (9/12) indicates the end of the DECDLD string.

2. Now you are ready to designate the character set as G1. You can use the following SCS escape sequence:

ESC ) sp @

**ESC** (1/11) introduces the SCS sequence.

(2/9)

designates the character set as G1.

sp @ (2/0, 4/0)

selects the soft set as the set to designate as G1. Remember, sp @ was the name used for the soft set in the DECDLD string.

3. Finally, you want to map the G1 set into the in-use table as GL. You can map the set by sending a shift out (SO) control character. To send (load) the SO character, you hold down the  $\boxed{\text{Ctrl}}$  key and press the  $\boxed{\mathbb{N}}$  key.

Note	

For information on using shift characters, see **LS-Locking Shift** or **SS-Single Shift** commands.

## 7.6.6 Clearing a Soft Character Set

You can clear a soft character set that you loaded into the terminal by using the following DECDLD control string:

```
DCS 1;1;2 { sp @ ST
```

Any of the following actions also clear the soft character set:

- Performing the power-up self-test.
- Selecting the Recall or Default set-up fields from the Set-Up Directory.
- Using a reset to initial state (RIS) sequence.

## **Keyboard Processing**

This chapter describes the physical keyboards and keyboard-to-host interface supported by the VT520 video terminal.

## 8.1 Overview—Keyboard Layout

The term keyboard layout describes the physical layout of a keyboard, specifically, the number of keys and their positions on the keyboard. The VT520 supports two keyboard layouts: VT layout and PC layout.

Figure 8-1 VT Keyboard Layout





Figure 8-2 PC Keyboard Layout



LJ-00226a-TI0.PS

## 8.2 DEC VT Layout

When a DEC VT Layout keyboard is used, only characters from the currently selected keyboard character set may be generated. All other graphic character keystrokes are ignored. See Chapter 8 for a list of the character sets supported.

The numeric keypad compose feature works as follows. Pressing and holding the Compose (Alt-Gr on EPC keyboards) while typing a number on the numeric keypad sends the corresponding decimal character code. The character code will be sent when the Compose key is release. If the keypad period is typed while entering the number, the previously entered value is multiplied by 16 and added to the value entered subsequently. This feature supports the column/row entry used commonly in character coding tables.

## 8.3 VT Layout - PC Term Mode

PCTerm mode using a VT layout keyboard is the same as PCTerm mode with an Enhanced PC layout keyboard with the following exceptions:

- All keystrokes send scan codes, except:
  - CapsLock F1 performs Hold,
  - CapsLock F2 forms Print,
  - CapsLock F3 enters Set-Up, and
  - CapsLock F5 send Break.
- Keystations 107, 124 126, and 130 send the corresponding scan codes generated by the LK411 VT layout. Keystations 131 - 133 act as Print Screen, Scroll Lock, and Pause.
- Keystations 42, (VT \| \| \| \), sends the scan code of keystation 29 of Enhanced PC layout (EPC \| \| \| ).
- Keystations 127 (VT Do), sends the scan code of keystation 110 (EPC Esc).

Table 8–1 shows the make/break scan codes for the VT layout in PCTerm mode.

Table 8–1 Scan Codes for VT Layout in PCTerm Mode

Key No.	VT Legend (U.S.)	Scan Code (Make / Break)
42	\	2B/AB
107	KP,	7E / FE
124	F13	E0 3D / E0 BD
125	F14	E0 3E / E0 BE
126	Help	E0 3F / E0 BF
127	Do	01 / 81
130	F17	E0 41 / E0 C1
131	PrtSc	E0 2A E0 37 / E0 B7 E0 AA Ctrl or Shift 37 / E0 B7 E0 AA
131	SysReq	Alt 54 / D4
132	Scroll Lock	46 / C6
133	Pause	E1 1D 45 E1 9D C5
	Break	Ctrl E0 46 E0 C6

## 8.4 Enhanced PC Layout - PCTerm Mode

In PCTerm mode, each press or release keystroke causes a unique scan code or sequence of scan codes to be sent to the host, corresponding to the keystation that was pressed or released. There is no keyboard character set. It is left to the host to translate scan codes into the desired display character set.

The one exception to the rule above is that Caps Lock combinations that involve local functions still work.

- CapsLock Print Screen enters Set-Up,
- CapsLock Pause send Break,
- CapsLock F1 performs Hold,
- CapsLock F2 forms Print,
- CapsLock F3 enters Set-Up, and
- CapsLock F5 send Break.

The make code for Caps Lock is sent when the Caps Lock key is released, before another key is pressed, or when another key is pressed that is not defined as a local function above.

All keys, including Shift, Alt, and Ctrl send make codes immediately upon being depressed, EXCEPT Caps Lock, whose make code is deferred as described above. If a modifier combination other than CapsLock is defined to invoke a local function (such as Alt/F3), a make code is sent for the modifier before the local function is invoked. When the local function is recognized, the corresponding break code is sent to cancel the modifier.

DEC and ISO multinational character sets are available in PCTerm mode. The 7-bit NRC sets are not included.

## 8.5 Enhanced PC Layout - VT Mode

The Enhanced PC layout can be used as an alternate to the VT Layout in VT mode. In this mode, the VT520 still operates as a traditional video terminal to communicate with conventional terminal applications. Since the Enhanced PC Layout does not correspond key-for-key to the VT Layout, some adaptation is necessary. Two styles are provided to support different users:

- DEC VT Style for traditional DEC VT users.
- IBM PC Style for IBM PC or ASCII terminal users

Pressing Caps Lock Num Lock toggles between these two styles. When DEC VT Style is selected, "VT" is displayed on the keyboard indicator line. Either style can be saved in NVM.

## 8.5.1 DEC VT Style

In this style, all keys send the same function sequences as the similarly named key on the VT Layout. The missing keys from the VT Layout are accessed by Caps Lock key combinations, where you press and hold Caps Lock while you type another key.

- Local terminal functions, "Print Screen," "Scroll Lock," and "Pause," are top row F keys.
- Left Alt/Space functions as compose key.

## Keyboard Processing 8.5 Enhanced PC Layout - VT Mode

### 8.5.2 IBM PC Style

In this style (the default style), the keys are mapped to behave as they would on an IBM PC. The differences in the IBM PC Style are:

- Editing keypad keys, Home and Delete, send sequences corresponding to these functions.
- Numeric keypad keys send different sequences when the keypad is in numeric mode to accommodate the "Num Lock" feature. With Num Lock off, the numeric keypad sends editing key sequences.
- F1 through F5 send function key sequences in PC style. Local terminal functions, "Print Screen," "Scroll Lock," and "Pause," are located as they would be on an Enhanced PC layout.
- Keys to operate copy and paste are different. See 3.7.
- Left Alt/Space does not work as compose key.

## 8.6 Main Key Array

This section describes the main keys on the keyboard.

### 8.6.1 Character Sets

Only characters from the currently selected keyboard character set may be generated. All other graphic character keystrokes are ignored. The following keyboard character sets are supported: ISO Latin 1, ISO Latin 2, ISO Latin Cyrillic, ISO Latin Greek, ISO Latin Hebrew, ISO Latin 5 (Turkish), DEC Multinational, DEC Cyrillic, DEC Greek, DEC Hebrew and DEC Turkish. When 7-bit NRCS characters is selected, a corresponding 7-bit NRC set is supported based on the Keyboard Dialect.

PC character sets are not supported in VT modes since the terminal is being used as a conventional video terminal that happens to have a PC keyboard attached. New applications should be written to use ISO character sets. (PC character sets are available in PCTerm and SCO console mode.)

Characters corresponding to the right side of the key top are typed by pressing the key in combination with Alt Gr, the right Alt key.

### 8.6.2 Tab Key

With an Enhanced PC Layout keyboard, pressing Shift/Tab causes a CBT sequence, CSI Z, to be transmitted. A horizontal tabulation code (HT, 0/9) is transmitted when a VT Layout keyboard is used.

### 8.6.3 Modifier Keys

Table 8–2 shows the corresponding modifier keys for the VT and the Enhanced PC layouts.

Table 8-2 VT Style Layout vs. Enhanced PC Style Layout Modifier Keys

VT Style Keyboard	PC Style Keyboard
Left Shift	Left Shift
Right Shift	Right Shift
Caps Lock	Caps Lock
Ctrl	Left Ctrl
none	Right Ctrl
Left Compose character	Alt Gr
Right Compose character	none
Left Alt	Left Alt
Right Alt	none or Right Alt

There is no Ctrl key on the right side of the VT keyboard. Left and right Ctrl keys on the Enhanced PC layout generates the single control function the same as on the VT Layout.

There is no key labeled "compose" on the Enhanced PC layout. [Alt Gr] (Right Alt) accesses the supplemental characters on the top right half of the key tops on some Enhanced PC layout keyboards. Alt Gr can be used with the numeric keypad to enter character codes directly. Left Alt Space can be used to initiate compose sequences when VT Style is selected.

### 8.6.4 Caps Lock

The Lock function may operate in three ways:

Caps Lock Alphabetic keys send their shifted character. Shift Lock All keys on the main key array send their shifted character. Pressing Shift temporarily reverses the effect of Caps Lock; that is, Reverse Lock unshifted or lowercase alphabetic characters are transmitted.

Pressing and releasing the Caps Lock key toggles the lock state on or off.

The Caps Lock key is also used to generate keystrokes for keys that are not present on the keyboard. Known as keyboard extension, this is done by pressing and holding the Caps Lock key and then pressing the extension key. The lock state is not toggled when an extension keystroke is pressed. The following Extension keystrokes are defined:

- Caps Lock | Print Screen | acts as the Set-Up key.
- Caps Lock Pause acts as the Break key.
- Caps Lock F1—Caps Lock F10 on the Enhanced PC Layout generates F11—F20. Caps Lock KP+ acts as KP- (DEC keypad minus) in application mode.

#### 8.6.5 Left Alt

Left Alt on the PC layout corresponds to the Alt function on the VT layout. Depressing the left key performs the following functions (unless reprogrammed):

Left Alt Space acts as the compose key in VT Style.

## **Keyboard Processing** 8.6 Main Key Array

On the United States Enhanced PC layout, the left Alt acts the same as Alt Gr when pressed and held in combination with keys from the numeric keypad. This feature keeps the two Alt keys equivalent to each other.

## 8.6.6 Right Alt

The right | All key appears on the United States Enhanced PC layout. On other country layouts, the right Alt key appears as Alt Gr. Depressing the right key performs the following functions (unless re-programmed):

- Right Alt Space acts as the compose key in VT Style. This feature keeps the two Alt keys equivalent.
- Right Alt key acts the same as the Alt Gr key when pressed and held in combination with keys from the numeric keypad.
- The right Alt key is the same as the Right Alt function on the VT layout with the exceptions listed previously.

### 8.6.7 Alt Gr

The right Att key is marked as Att Gr on all but the United States Enhanced PC layout. The words Alt Gr are short for alternate graphic and corresponds roughly to the function of the compose key.

- Alt Gr in combination with graphic character keys generate the character corresponding to the right side of the key tops.
- Alt Gr is used for numeric keypad compose.

## 8.7 Top Row Function Keys


There are 20 top row function keys on the VT layout and 12 on the Enhanced PC layout. Caps Lock/F1 through Caps Lock/F10 keys on the Enhanced PC layout transmit the same sequences as F11 through F20 in the VT layout. Additional unique function sequences are transmitted by pressing function keys in combination with Shift, Alt, or Ctrl keys. See DECFNK and DECPAK for details.


In VT Style, the F1 through F5 keys operate the same as on the VT layout and can be used for local functions to send function sequences or to be ignored. In VT Style, F13 (Print Screen), F14 (Scroll Lock), and F15 (Pause) send their corresponding function key sequences. In PC Style, the F1 through F5 keys send function sequences (unless re-programmed) while Print Screen, Scroll Lock, and Pause default to local functions.

## 8.8 Editing Keypad Keys

Figure 8–3 shows the layout for the DEC VT and Enhanced PC editing keypads.

Figure 8-3 Editing Keypad Legends on DEC and PC Layouts





MA-0028-93.GRA

When DEC VT Style is selected, the Enhanced PC layout editing keys transmit the same function sequences as the similarly legend editing keys in the VT layout. In IBM PC Style, the Home key sends a Cursor Up (CUP) sequence to move the cursor home and the Delete key transmits a DEL (7/15).

Table 8–3 lists the key sequences for Enhanced PC editing keypads.

Table 8-3 Editing Keypad Sequences for Enhanced PC Layout

Enhanced PC Legend	VT Legend	VT Style Sequence	PC Style Sequence
Insert	Insert Here	CSI 2 ~	CSI 2 ~
Delete	Remove	CSI 3 ~	DEL
Home	Find	CSI 1 ~	CSI H
End	Select	CSI 4 ~	CSI 4 ~
Page Up	Prev Screen	CSI 5 ~	CSI 5 ~
Page Down	Next Screen	CSI 6 ~	CSI 6 ~

In addition to these unshifted sequences, the editing keys can send unique sequences when pressed in combination with Shift, Alt, or Ctrl. See DECFNK for details.

## 8.9 Cursor Keypad Keys

The cursor keypad keys send the same sequences as the VT layout. Additional unique sequences can be sent when pressed in combination with Shift, Alt, or Ctrl. See DECFNK for details.

## 8.10 Numeric Keypad Keys

The Enhanced PC layout numeric keypad has three differences from the VT layout:

- 1. The four keys at the top of the keyboard are labeled Num Lock, /, \*, and instead of PF1 through PF4.
- 2. The Num Lock key toggles the keypad keys, sending either numerals or function sequences.
- 3. A two unit + key occupies the and , positions so there is no keypad comma.

## **Keyboard Processing** 8.10 Numeric Keypad Keys

In VT Style, with **Application Mode** enabled, the numeric keypad keys send the same sequences as the corresponding keys on a VT layout. When the numeric keypad is in numeric mode, the four keys at the top of the keyboard still operates as PF1 through PF4, and the + key sends an ASCII "+" character.

Table 8–4 shows the numeric keypad sequences in VT Style.

Table 8-4 PC Layout Numeric Keypad Sequences - VT Style

PC Key	DEC Key	Numeric Mode	Application Mode
Num Lock	PF1	SS3 P	SS3 P
/	PF2	SS3 Q	SS3 Q
*	PF3	SS3 R	SS3 R
-	PF4	SS3 S	SS3 S
Caps Lock/+	-		SS3 m
+	,	"+"	SS3 1
		"."	SS3 n
Enter	Enter	CR	SS3 M
0	0	"0"	SS3 p
1	1	"1"	SS3 q
2	2	"2"	SS3 r
3	3	"3"	SS3 s
4	4	"4"	SS3 t
5	5	"5"	SS3 u
6	6	"6"	SS3 v
7	7	"7"	SS3 w
8	8	"8"	SS3 x
9	9	"9"	SS3 y

In IBM PC Style, when the numeric keypad is in Application Mode, the numeric keypad keys send the same sequences as the corresponding keys on the VT layout as shown in Table 8-4.

In IBM PC Style, when the numeric keypad is in Numeric Mode, the keypad keys send either editing keypad sequences corresponding to the gray legend in the lower part of the key tops, or the numerals corresponding to the black legend in the upper part of the key tops. The numerals are sent when Shift or the Num Lock has been depressed. The Num Lock state can be toggled on or off by pressing the Num Lock key. "Num Lock" appears on the keyboard indicator line when this feature is activated. If Num Lock is on and "Reverse Lock" is activated, pressing Shift temporarily reverses the effect of Num Lock.

### Redefining Num Lock Key

Using **Define key...** to redefine keys on the numeric keypad will affect only the Num Lock off state of these keys. When Num Lock is on, these keys will always send their factory default ASCII numerals and characters. The Num Lock behavior of these keys cannot be reprogrammed.

Scenario: Imagine the keyboard having two numeric keypads: one for Num Lock Off, and the other for Num Lock On. Only the Num Lock Off keypad can be reprogrammed. The Num Lock On keypad retains the factory defaults.

Table 8-5 lists the numeric keypad sequences in PC Style Numeric mode.

Table 8-5 PC Layout Numeric Keypad Sequences - PC Style, Numeric Mode

Keys	Num Lock Off unshifted, or Num Lock On with Shift	Num Lock On unshifted, or Num Lock Off with Shift
Num Lock		
/	/	1
*	*	*
-	-	-
+	+	+
Del	DEL	
Enter	CR	CR
$0 \\ Ins$	CSI 2 ~	0
$\frac{1}{End}$	CSI 4 ~	1
2   <del>1</del>	CSI B	2
$\begin{vmatrix} 3 \\ PgDn \end{vmatrix}$	CSI 6 ~	3
4 ←	CSI D	4
5		5
6 ⇒	CSI C	6
7 Home	CSI H	7
8	CSI A	8
$\frac{9}{PgUp}$	CSI 5 ~	9

Several of the Enhanced PC layout keyboards use a comma instead of a period on key 104, sending the corresponding code for a comma instead of a period shown in Table 8-5.

## 8.11 Local Function Key Defaults

The keys used to perform local terminal functions differ between the VT keyboard, PC keyboard, and the mode selection. Table 8-6 shows the corresponding keys for the default local functions. The function number in Table 8-6 is used in the DECPFK host sequence or DECPAK's alternate function to specify a change to that local function key.

Table 8-6 Local Functions

Function Number	n Function	VT Keyboard	SCO Console	PC Keyboard VT-Style	PC Keyboard PC-Style	PC Keyboard SCO
0	no function					
1	Hold	F1	CapsLk/F1	F1	Scroll Lock	

 $<sup>\</sup>pm$  means the function switches alternately between on and off.

C&P means Copy and Paste.

CapsLk means the Lock key, Caps Lock key, or key with lock icon.

Table 8-6 (Cont.) Local Functions

Functior Number	n Function	VT Keyboard	SCO Console	PC Keyboard VT-Style	PC Keyboard PC-Style	PC Keyboard SCO
2	Print	F2	CapsLk/F2	F2	Print Screen	
3	Set-Up	F3	CapsLk/F3	F3	CapsLk/Print So	creen
					CapsLk/Sys Rq or Alt/Print Screen	]
4	Session Forward	F4, CapsLk KF	_	F4, CapsLk KP0	F4, CapsLk KP0	
5	Break	F5	CapsLk/F5	F5	CapsLk/Pause	
7	Hard Reset	Ctrl/F3	CapsLk/Ctrl/F3	Ctrl/F3	Ctrl/CapsLk/Pri	nt Screen
8	Toggle Autoprint	Ctrl/F2	CapsLk/Ctrl/F2	Ctrl/F2	Ctrl/Print Screen	
9	Disconnect	Shift/F5	CapsLk/Shift/F5	Shift/F5	Shift/CapsLk/Pa	iuse
10	Send Answerback	Ctrl/F5	CapsLk/Ctrl/F5	Ctrl/F5	Ctrl/CapsLk/Pau	ise
11	Print Composed Main Display	Shift/F2	n/a <sup>4</sup>	Shift/F2	Shift/Print Scree	en n/a
12	Session Backward	Shift F4, Shift CapsLk	(P0	Shift F4, Shift CapsLk KP0	Shift F4, Shift CapsLk KP	0
20	Pan Up	Ctrl/ ↑	n/a	Ctrl/ ↑	Ctrl/ ↑	n/a
21	Pan Down	Ctrl/ ↓	n/a	Ctrl/ ↓	Ctrl/ ↓	
24	Pan Prev Page	Ctrl/Prev	n/a	Ctrl/Page Up	Ctrl/Page Up	
25	Pan Next Page	Ctrl/Next	n/a	Ctrl Page Down	Ctrl/Page Down	
30	Copy & Paste Mode	F1 (hold down)	CapsLk/F1	F1	Scroll Lock	
31	C&P Cursor Left	<b>(</b>		<b>(</b>	<b>(</b>	
32	C&P Cursor Down	<b></b>		<b>\</b>	<b>#</b>	
33	C&P Cursor Up	$\uparrow$		$\uparrow$	$\uparrow$	
34	C&P Cursor Right	$\Rightarrow$		$\Rightarrow$	$\Rightarrow$	
35	C&P Start Selection	Select		Home	Home	
36	C&P Copy	Remove		End	End	
37	C&P Paste	Insert Here		Insert	Insert	
38	C&P ± Left-to-Right	Select		Home	Home	
41	Shift Modifier	Left or right Shift		Left or right Shift	Left or right Shift	

<sup>&</sup>lt;sup>4</sup> n/a means the function is not available in the default SCO state. If there is no "n/a" in the **SCO Console** column, then this means that the key sequence is the same as the **VT Keyboard** column. If there is no "n/a" in the **PC Keyboard SCO** column, then this means that the key sequence is the same as the **PC Keyboard PC-Style** column.

CapsLk means the Lock key, Caps Lock key, or key with lock icon.

 $<sup>\</sup>pm$  means the function switches alternately between on and off. C&P means Copy and Paste.

Table 8-6 (Cont.) Local Functions

Function Number	Function	VT Keyboard	SCO Console	PC Keyboard VT-Style	PC Keyboard PC-Style	PC Keyboard SCO
42	Control Modifier	Ctrl		Left or right Ctrl	Left or right	
43	Alt Function Modifier	Left or right Alt		Left or right	Left or right	
44	Start Compose	Left or right Compose		Left Alt/Space	Left Alt/Space	
45 <sup>1</sup>	Group Shift Modifier	Group Shift		Alt/Gr	Alt/Gr	
$46^{2}$	Shift2 Modifier	Alt/Shift				
47	Primary KB language	Ctrl/Alt/F1	CapsLk/Alt/Ctrl/	FICtrl/Alt/F1	Ctrl/Alt/F1	See SCO Console
48	Secondary KB language	Ctrl/Alt/F2	CapsLk/Alt/Ctrl/	F2Ctrl/Alt/F2	Ctrl/Alt/F2	See SCO Console
$49^{3}$	± KB language					
51	± Caps Lock State	CapsLk		CapsLk	CapsLk	
52	± Num Lock State			Num Lock	Num Lock	
53	± VT/IBM Style		n/a	CapsLk Num Lock	CapsLk Num Lock	n/a
54	Extend Kbd Modifier			CapsLk	CapsLk	
61	Screen saver					
62	± Calculator	CapsLk/Alt/F1	2	CapsLk/Alt/F12	CapsLk/Alt/F12	
63	± Clock	CapsLk/Alt/F1 or CapsLk/Enter	<u>1</u> ]	CapsLk/Alt/F11	CapsLk/Alt/F11	]
64	± Show character sets	CapsLk/Alt/F1	0	CapsLk/Alt/F10	CapsLk/Alt/F10	
65	Transfer result	Shift/Enter		Shift/Enter	Shift/Enter	
91	BS					
92	CAN					
93	ESC					
94	DEL					
100	UDK sequence					

<sup>&</sup>lt;sup>1</sup>The Group Shift Modifier is assigned to the Group Shift key (German "Left Compose") when it appears on the corresponding keyboard (German, Czech, Hungarian, Polish, and Slovak).

CapsLk means the Lock key, Caps Lock key, or key with lock icon.

<sup>&</sup>lt;sup>2</sup>The Shift2 Modifier is assigned to the Alt Shift key (German "right Compose") when it appears on the corresponding keyboard (German).

 $<sup>^3</sup>$ Toggle KB language is assigned to the named language key when it appears on the corresponding keyboard (Greek, Hebrew, and Russian).

 $<sup>\</sup>pm$  means the function switches alternately between on and off. C&P means Copy and Paste.

Table 8–6 (Cont.) Local Functions

Function Number	n Function	VT Keyboard	SCO Console	PC Keyboard VT-Style	PC Keyboard PC-Style	PC Keyboard SCO
105	Soft reset (WY) <sup>5</sup>	Shift F3		Shift F3	Shift F3	
106	±Show controls	Shift Ctrl KP1		Shift Ctrl KP1	Shift Ctrl KP1	
111	±Status display (WY)	Ctrl ←		Ctrl ←	Ctrl ←	
112	±Split screen					
113	Raise page split (WY)	Ctrl KP -		Ctrl KP -	Ctrl KP -	
114	Lower page split (WY)	Ctrl KP +		Ctrl KP +	Ctrl KP +	
115	Adjust window to show cursor (WY)	Ctrl Find		Ctrl Find	Ctrl Home	
116	±Cursor drag (WY)	Ctrl Shift KP '				
117	±Insert mode (WY)	Ctrl PF4 Ctrl Shift PF4		Ctrl PF4 Ctrl Shift Insert	Ctrl PF4 Ctrl Shift Insert	
119	Home & Clear (WY)	Ctrl Shift Prev			Ctrl Shift Home	
120	Page 0 (WY mono)	Ctrl KP0		Ctrl KP0	Ctrl KP0	
121	Page 1 (WY mono)	Ctrl KP1		Ctrl KP1	Ctrl KP1	
122	Page 2 (WY mono)	Ctrl KP2		Ctrl KP2	Ctrl KP2	
123	Page 3 (WY mono)	Ctrl KP3		Ctrl KP3	Ctrl KP3	
124	Page 4 (WY mono)	Ctrl KP4		Ctrl KP4	Ctrl KP4	
125	Page 5 (WY mono)	Ctrl KP5		Ctrl KP5	Ctrl KP5	
126	Page 6 (WY mono)	Ctrl KP6		Ctrl KP6	Ctrl KP6	
127	Page 7 (WY mono)	Ctrl KP7		Ctrl KP7	Ctrl KP7	
128	Page 8 (WY mono)	Ctrl KP8		Ctrl KP8	Ctrl KP8	
129	Page 9 (WY mono)	Ctrl KP9		Ctrl KP9	Ctrl KP9	
138	Prev Page	Ctrl Prev Ctrl Shift Prev			Ctrl PageUp Ctrl Shift PageU	р

 $<sup>^{5}</sup>$ (WY) indicates that this function is available in the ASCII emulation modes only. "WY color" indicates that this function is available only in the WYSE color emulation mode. "WY mode", only in the WYSE mono emulation mode.

CapsLk means the Lock key, Caps Lock key, or key with lock icon.

 $<sup>\</sup>pm$  means the function switches alternately between on and off. C&P means Copy and Paste.

Table 8–6 (Cont.) Local Functions

Function Number	n Function	VT Keyboard	SCO Console	PC Keyboard VT-Style	PC Keyboard PC-Style	PC Keyboard SCO
139	Next Page	Ctrl Next Ctrl Shift Next			Ctrl PageDn Ctrl Shift PageD	n
142	Slow Scroll	Ctrl Shift ↓			Ctrl Shift ↓	
143	Fast Scroll	Ctrl Shift ↑			Ctrl Shift ↑	
151	±Keyclick	Shift Enter			Shift Enter	
155	±Block mode (WY)	Shift Ctrl F5 or F4		Shift Ctrl Pause	Shift Ctrl Pause	
156	Block mode on (WY scan mode)	Alt PF1		Alt NumLock	Alt NumLock	
157	Block mode off (WY scan mode)	F4		Pause	Pause	
159	Palette soft (WY325) <sup>5</sup>	Ctrl KP .		Ctrl KP.	Ctrl KP.	
160	Palette 0 (WY color)	Ctrl KP0		Ctrl KP0	Ctrl KP0	
161	Palette 1 (WY color)	Ctrl KP1		Ctrl KP1	Ctrl KP1	
162	Palette 2 (WY color)	Ctrl KP2		Ctrl KP2	Ctrl KP2	
163	Palette 3 (WY color)	Ctrl KP3		Ctrl KP3	Ctrl KP3	
164	Palette 4 (WY color)	Ctrl KP4		Ctrl KP4	Ctrl KP4	
165	Palette 5 (WY color)	Ctrl KP5		Ctrl KP5	Ctrl KP5	
166	Palette 6 (WY color)	Ctrl KP6		Ctrl KP6	Ctrl KP6	
167	Palette 7 (WY color)	Ctrl KP7		Ctrl KP7	Ctrl KP7	
168	Palette 8 (WY color)	Ctrl KP8		Ctrl KP8	Ctrl KP8	
169	Palette 9 (WY color)	Ctrl KP9		Ctrl KP9	Ctrl KP9	
170	± Framed windows					
171	± Window configuration	Ctrl F4 Ctrl CapsLk K	P0	Ctrl F4 Ctrl CapsLk KP0	Ctrl F4 Ctrl CapsLk KP0	ס ס
172	Raise window border	Ctrl Shift 1		Ctrl Shift ↑	Ctrl Shift 介	_

 $<sup>^{5}</sup>$ (WY) indicates that this function is available in the ASCII emulation modes only. "WY color" indicates that this function is available only in the WYSE color emulation mode. "WY mode", only in the WYSE mono emulation mode.

Table 8–6 (Cont.) Local Functions

Functio Number	n Function	VT Keyboard	SCO Console	PC Keyboard VT-Style	PC Keyboard PC-Style	PC Keyboard SCO
173	Lower window border	Ctrl Shift ↓		Ctrl Shift ↓	Ctrl Shift ↓	
181	Session 1	CapsLk KP1		CapsLk KP1	CapsLk KP1	
182	Session 2	CapsLk KP2		CapsLk KP2	CapsLk KP2	
183	Session 3	CapsLk KP3		CapsLk KP3	CapsLk KP3	
184	Session 4	CapsLk KP4		CapsLk KP4	CapsLk KP4	

 $<sup>\</sup>pm$  means the function switches alternately between on and off. C&P means Copy and Paste.

CapsLk means the Lock key, Caps Lock key, or key with lock icon.

Note
See Chapter 2 to re-define keys using the Define Key Editor.

### 8.11.1 Numeric Keypad Compose

Pressing and holding Compose, Alt or Alt Gr while typing a decimal number on the numeric keypad sends the corresponding decimal character code when the compose key is released. If the . key on the keyboard is pressed while entering a number, then the value entered before pressing the ... key is multiplied by 16 and added to the value entered next. This supports column/row entry commonly used in character coding tables.

#### 8.11.2 Accessibility Aids


**Accessibility aids** allow the user with limited motor skills to use modifier key combinations in a sequential manner rather than a simultaneous manner (default). All modifier key combinations are supported.

The Accessibility aids option is enabled by depressing the Shift key five times in succession. This option can be disabled by pressing and holding a modifier key while pressing another key.

Once enabled, this option provides two levels of assistance known as Latch and Lock. The Latch state is achieved by pressing a modifier key once and affects the next key pressed. The Lock state is achieved by pressing a modifier key twice. All keys pressed are affected by the modifier until they are unlocked by either depressing the modifier key again or depressing another modifier key twice. Once any modifier is in the Locked state, pressing other modifier keys adds those modifiers to the Locked state.

A small icon appears on the Keyboard Indicator Line or Status Line to provide user feedback on the changing modifier state.

The icons for each state are as follows:



When Accessibility aid keys are disabled, no icon is displayed on the Keyboard Indicator Line or Status Line.

#### Keyboard Processing 8.12 Controlling Keyboard LEDs

## 8.12 Controlling Keyboard LEDs

The following sequences allow the host to control keyboard modifier states for <a href="Caps Lock">Caps Lock</a>, <a href="Scroll Lock">Scroll Lock</a>, and <a href="Num Lock">Num Lock</a> or keyboard LEDs to indicate program status. They are as follows:

ESC [? 108 h - Set NumLock mode (DECNUMLK)

ESC [? 108 l - Reset NumLock mode

ESC [ ? 109 h - Set CapsLock mode (DECCAPSLK)

ESC [? 109 l - Reset CapsLock mode

"Scroll Lock" or "Hold Screen" cannot be controlled from the host because it suspends transmission from the host and there is no way to release it.

DECLL controls keyboard LEDs independently of any keyboard state. The use of LEDs for this purpose conflicts with their use as keyboard state indicators. The host control selects a mode of how the keyboard LEDs are to be used: as keyboard indicators; or host indicators. If host indicators is selected, then the DECLL sequence can be used to control the keyboard LEDs.

The following control sequences are used to control keyboard LEDs.

ESC [ ? 110 h - Set Keyboard LEDs—Host Indicator Mode (DECKLHIM)

ESC [? 110 l - Reset Keyboard LEDs—Local Indicator Mode (default)

					No	ote					
~	~1	_					_	_	 		

See Chapter 2 to re-define keys using the Define Key Editor.

## 8.13 Keyboard Languages

Table 8–7 VT Keyboard Languages

Austrian/German	Greek	Russian
Belgian/French	Hebrew	SCS
British	Hungarian	Slovak
Canadian-French/English	Italian	Spanish
Czech	North American	Swedish
Danish	Norwegian	Swiss-French
Dutch	Polish	Swiss-German
Finnish	Portuguese	Turkish F
Flemish	Romanian	Turkish Q

Table 8–8 Enhanced PC Keyboard Languages

Belgian	Greek	Romanian
British	Hebrew	Russian
Czech	Hungarian	SCS
Danish	Italian	Slovak
Dutch	Latin American	Spanish
Finnish	North American	Swedish
French	Norwegian	Swiss-French
French-Canadian	Polish	Swiss-German
German	Portuguese	Turkish

### 8.14 Switching Between Keyboard Languages

The VT520 allows the user to easily switch between two different keyboard layouts for several languages (English and Hebrew, for example). This feature allows the VT520 to support both existing conventions and emerging standards for extending the graphic input repertoire and/or switching between languages in dual language environments.

The primary keyboard language corresponds to "Group 1" and generally references the legends on the left portion of the key tops.

The secondary keyboard language corresponds to "Group 2" and generally references the legends on the right portion of the key tops.

Unless otherwise overridden, Ctrl/Alt/F1 activates the primary keyboard language (locking shift), and Ctrl/Alt/F2 activates the secondary keyboard language. These factory defaults are standard on PCs.

Selecting a new Keyboard Dialect in Set-Up resets the keyboard group shift state to Group 1 and automatically initializes the keyboard character set and VT default character set as shown in table Table 8–9. The keyboard character set is initialized to match the VT default character set.

Table 8–9 8-bit Character Set Initialization when Keyboard Language is Changed

New Keyboard Language	If VT Default Character Set is not	Change to
Austrian/German, Belgian/French, British, Canadian-English, Canadian-French, Flemish, Danish, Dutch, Finnish, Italian, Portuguese, North American, Norwegian, Spanish, Swedish, Swiss-French, Swiss-German.	DEC Multinational character set or ISO Latin-1	ISO Latin-1
Czech, Hungarian, Polish, Romanian, SCS, or Slovak	ISO Latin-2	ISO Latin-1
Greek	DEC Greek or ISO Latin-Greek	ISO Latin-Greek
Hebrew	DEC Hebrew or ISO Latin-Hebrew	ISO Latin-Hebrew
Russian	KOI-8 Cyrillic or ISO Latin-Cyrillic	ISO Latin-Cyrillic
Turkish	DEC Turkish or ISO Latin-Turkish	ISO Latin-Turkish

## **Keyboard Processing** 8.14 Switching Between Keyboard Languages

If 7-bit NRCS characters is selected, then the following corresponding NRC sets are used.

Table 8-10 7-bit Character Set Initialization

	Default Character Set		
Keyboard	VT Keyboard	<b>Enhanced PC Keyboard</b>	
Austrian/German	German NRC	Austrian/German NRC	
Belgian/French	French NRC	French NRC	
British (U.K.)	U.K. NRC	U.K. NRC	
Canadian-English	French Canadian NRC	French Canadian NRC	
Canadian-French	French Canadian NRC	French Canadian NRC	
Czech	N/A	N/A	
Danish	Norwegian/Danish NRC	Norwegian/Danish NRC	
Dutch (Netherlands)	N/A <sup>1</sup>	N/A <sup>1</sup>	
$Finnish^2$	Finnish NRC	Finnish NRC	
Flemish	French NRC	N/A	
Greek	DEC Greek NRC	DEC Greek NRC	
Hebrew	DEC 7-bit Hebrew	DEC 7-bit Hebrew	
Hungarian	N/A	N/A	
Italian	Italian NRC	Italian NRC	
North American (U.S.) <sup>3</sup>	N/A	N/A	
Norwegian	Norwegian/Danish NRC	Norwegian/Danish NRC	
Polish	N/A	N/A	
Portuguese	Portuguese NRC	Portuguese NRC	
Romanian	N/A	N/A	
Russian	DEC Russian NRC	DEC Russian NRC	
SCS	SCS NRC	SCS NRC	
Slovak	N/A	N/A	
Spanish	Spanish NRC	Spanish NRC	
Swedish	Swedish NRC	Swedish NRC	
Swiss-French	Swiss NRC	Swiss NRC <sup>4</sup>	
Swiss-German	Swiss NRC	Swiss NRC	
Turkish-F	DEC 7-bit Turkish	N/A <sup>5</sup>	
Turkish-Q	DEC 7-bit Turkish	DEC Turkish NRC	

 $<sup>^1\</sup>mathrm{Same}$  as North American (U.S.) keyboard.

<sup>&</sup>lt;sup>2</sup>Same as Swedish keyboard.

 $<sup>^37</sup>$ -bit character mode is not available.

<sup>&</sup>lt;sup>4</sup>Swiss French/German is a single PC keyboard.

 $<sup>^5 \</sup>mbox{The VT}$  keyboard is available in both the Turkish-F and Turkish-Q keyboard layouts. The EPC keyboard is only available in the Turkish-Q layout.

#### 8.14.1 Keystroke Processing

Any time the terminal is operating, a keyboard encoding is being used to translate graphic character keystrokes into character codes, called the keyboard character set. The Keyboard Character set is a function of:

- 1. Keyboard language
- 2. Keyboard group (Hebrew only)
- 3. Default character set
- 4. The 7-bit or 8-bit characters setting
- 5. Any keyboard customization defined in Set-Up.

When the graphic character assigned to a keystroke (which usually corresponds to the legend appearing on the keycap) has a corresponding character in the Keyboard Character set, the terminal transmits the corresponding character code for that keystroke. The code transmitted for any given keystroke can vary depending on the Keyboard Character set. If the graphic character assigned to a keystroke does not have a corresponding character in the Keyboard Character set, then that keystroke does not transmit any code.

#### 8.14.2 Non-Spacing Accent Marks

Accented characters that do not appear directly on a keyboard can often be entered by typing a non-spacing diacritical mark followed by a base character. While most diacritical marks have stand-alone forms (not in combination with another character), the non-spacing interpretation of these marks are similar to characters but are actually a special internal keystroke representation.

Table 8-11 Non-Spacing Accent Marks

Symbol	Non-Spacing Accent Name
,	Acute accent
_	Breve
V	Hacek (caron)
	Cedilla
^	Circumflex accent
	Diaeresis (umlaut)
•	Dot above
n	Double acute accent
	Grave accent
!	Greek Tonos
-	Macron
ı	Ogonek
0	Ring above
~	Tilde

Keystrokes assigned non-spacing accent marks do not send any character code immediately, but are used instead to modify the code transmitted by the subsequent keystroke. If a keystroke that has been assigned a non-spacing accent mark is followed immediately by a graphic character, then this forms a valid

#### **Keyboard Processing** 8.14 Switching Between Keyboard Languages

character in the keyboard character set, and the corresponding character code is transmitted.

When a non-spacing diacritical key is pressed, "Compose" appears on the keyboard indicator line until the next subsequent keystroke.

If the keystroke immediately following the non-spacing diacritical keystroke does not form a valid character in the keyboard character set, then the nonspacing diacritical mark is converted to the corresponding character, if any, and transmitted from the current keyboard character set. The second keystroke is then processed normally. This "error recovery" is different from previous VT auto-compose processing; however, this process follows the emerging standard used on personal computers.

#### 8.14.3 German

For German keyboards, the Group Shift (left Compose) key functions as the keyboard repertoire extension mechanism. Group 1 and Group 2 are defined within the German keyboard dialect and are used whenever the keyboard language is set to German. Group Shift operates as a single shift prefix if pressed and released or as a modifier key if pressed and held.

#### 8.14.4 Hebrew

When Hebrew is selected as the Keyboard Dialect, the Ctrl/Hebrew key toggles between the primary and secondary keyboard language.

When switching into 7-bit Hebrew, lowercase English letters are swapped with their corresponding Hebrew characters throughout the display. The Shift/Hebrew key also performs this swapping function at any time.

## 8.15 Keystation Numbers

Figure 8-4 shows the keystation numbers for a VT keyboard.

Figure 8-4 VT Layout - Keystation Numbers




Figure 8–5shows a typical legend for a North American VT keyboard.

Figure 8-5 VT Layout - Typical North American Key Legends




Figure 8-6 Enhanced PC Layout - Map Numbers





Figure 8-7 Enhanced PC Layout - Typical North American Key Legends



## 8.16 Scan Codes Sent in PCTerm Mode for EPC Keyboards

The following keys send the corresponding scan codes, regardless of any modifiers that may be in effect.

Key #	Legend (U.S.)	Scan Code Make/Break <sup>1</sup>
1	į	29/A9
2	1	02/82
3	2	03/83
4	3	04/84
5	4	05/85
6	5	06/86
7	6	07/87
8	7	08/88
9	8	09/89
10	9	0A/8A
11	0	0B/8B
12	-	0C/8C
13	=	0D/8D
14		$7\mathrm{D}/\mathrm{FD}^2$
15	Backspace	0E/8E
16	Tab	0F/8F
17	Q	10/90
18	W	11/91
19	E	12/92
20	R	13/93
21	T	14/94
22	Υ	15/95
23	U	16/96
24		17/97
25	0	18/98
26	Р	19/99
27	Ш	1A/9A
28		1B/9B
29		2B/AB†
30	Caps Lock	3A/BA
31	A	1E/9E
32	S	1F/9F
33	D	20/A0
34	F	21/A1

 $<sup>^1\</sup>mathrm{Make}$  means when the key is pressed; Break means when the key is released.

<sup>&</sup>lt;sup>2</sup>Not used on 101/102 keyboard layout.

<sup>†101</sup> keyboard layout only

# Keyboard Processing 8.16 Scan Codes Sent in PCTerm Mode for EPC Keyboards

Kov	Logond	Scan Code
Key #	Legend (U.S.)	Scan Code Make/Break <sup>1</sup>
35	G	22/A2
36	Н	23/A3
37	J	24/A4
38	K	25/A5
39	L	26/A6
40	;	27/A7
41	,	28/A8
42		2B/AB‡
43	Return	1C/9C
44	Left Shift	2A/AA
45		56/D6‡
46	Z	2C/AC
47	X	2D/AD
48	С	2E/AE
49	V	2F/AF
50	В	30/B0
51	N	31/B1
52	M	32/B2
53	,	33/B3
54	$\Box$	34/B4
55	/	35/B5
56		73/F3 <sup>2</sup>
57	Right Shift	36/B6
58	Left Ctrl	1D/9D
60	Left Alt	38/B8
61	Space	39/B9
62	Right Alt	E0 38/E0 B8
64	Right Ctrl	E0 1D/E0 9D
90	Num Lock	45/C5
91	7 H om e	47/C7
92	4 <b>←</b>	4B/CB
93	$\begin{bmatrix} 1 \\ End \end{bmatrix}$	4F/CF
94		$7C/FC^2$
96	<mark>8</mark>	48/C8
97	KP5	4C/CC
98	$\frac{ 2 }{ \psi }$	50/D0
99	$0 \\ Ins$	52/D2

 $<sup>\</sup>overline{\,^1\text{Make}}$  means when the key is pressed; Break means when the key is released.

 $<sup>^2</sup>$ Not used on 101/102 keyboard layout.

<sup>‡102</sup> keyboard layout only

### **Keyboard Processing** 8.16 Scan Codes Sent in PCTerm Mode for EPC Keyboards

Key #	Legend (U.S.)	Scan Code Make/Break <sup>1</sup>
100	Keypad *	37/B7
101	$\begin{bmatrix} 9 \\ PgUp \end{bmatrix}$	49/C9
102	6 ⇒	4D/CD
103	$\begin{bmatrix} 3 \\ PgDn \end{bmatrix}$	51/D1
104	Del	53/D3
105	Keypad -	4A/CA
106	Keypad +	4E/CE
107		7E/FE <sup>2</sup>
108	Enter	E0 1C/E0 9C
109		$78/F8^2$
110	Esc	01/81
112	F1	3B/BB
113	F2	3C/BC
114	F3	3D/BD
115	F4	3E/BE
116	F5	3F/BF
117	F6	40/C0
118	F7	41/C1
119	F8	42/C2
120	F9	43/C3
121	F10	44/C4
122	F11	57/D7
123	F12	58/D8
125	Scroll Lock	46/C6

 $<sup>^1\</sup>mathrm{Make}$  means when the key is pressed; Break means when the key is released.

The keys in the following table send different series of scan codes depending on the modifier state in effect (Shift, Control, Alt, and/or Num Lock). Many of them have a base scan code that is identical to another key. To make each key unique, some have an extra byte hex 'E0' or hex 'E1' added to their scan code sequence.

<sup>&</sup>lt;sup>2</sup>Not used on 101/102 keyboard layout.

## **Keyboard Processing**8.16 Scan Codes Sent in PCTerm Mode for EPC Keyboards

Key #	Legend (U.S.)	Base Case Make/Break	Shift Case Make/Break	Num Lock ON Make/Break
75	Ins	E0 52/E0 D2	E0 AA E0 52/E0 D2 E0 2A*	E0 2A E0 52/E0 D2 E0 AA
76	Del	E0 53/E0 D3	E0 AA E0 53/E0 D3 E0 2A*	E0 2A E0 53/E0 D3 E0 AA
79	<b>=</b>	E0 4B/E0 CB	E0 AA E0 4B/E0 CB E0 2A*	E0 2A E0 4B/E0 CB E0 AA
80	Home	E0 47/E0 C7	E0 AA E0 47/E0 C7 E0 2A*	E0 2A E0 47/E0 C7 E0 AA
81	End	E0 4F/E0 CF	E0 AA E0 4F/E0 CF E0 2A*	E0 2A E0 4F/E0 CF E0 AA
83	$\uparrow$	E0 48/E0 C8	E0 AA E0 48/E0 C8 E0 2A*	E0 2A E0 48/E0 C8 E0 AA
84	$\downarrow$	E0 50/E0 D0	E0 AA E0 50/E0 D0 E0 2A*	E0 2A E0 50/E0 D0 E0 AA
85	Pg Up	E0 49/E0 C9	E0 AA E0 49/E0 C9 E0 2A*	E0 2A E0 49/E0 C9 E0 AA
86	Pg Dn	E0 51/E0 D1	E0 AA E0 51/E0 D1 E0 2A*	E0 2A E0 51/E0 D1 E0 AA
89	$\Rightarrow$	E0 4D/E0 CD	E0 AA E0 4D/E0 CD E0 2A*	E0 2A E0 4D/E0 CD E0 AA

<sup>\*</sup>When the left Shift key is pressed, the AA-2A shift break and make should envelope the base codes as shown in the previous table. When the right Shift key is pressed, the code B6 (right shift break) is sent in place of AA and the code 36 (right shift make) is sent in place of 2A. If both right and left Shift keys are pressed, then both B6 and AA are sent where AA is shown, and both 36 and 2A are sent where 2A is shown.

Key #	Legend (U.S.)	Scan Code Make/Break	Shift Case Make/Break
95	Keypad /	E0 35/E0 B5	E0 AA E0 35/E0 B5 E0 2A *

The marker code Hex 'E0' precedes shift codes that are artificially produced by the keyboard logic. These artificially produced shift codes are not repeated during typamatic (auto repeat) operation of the corresponding key. Only the unique base code is repeated at the auto repeat rate. The terminal must ensure that both shift states are restored when all shift-dependent keys are released.

Key #	Legend (U.S.)	Scan Code Make/Break	Ctrl Case and Shift Case Make/Break	Alt Case Make/Break
124	PrtSc	E0 2A E0 37/E0 B7 E0 AA	E0 37/E0 B7	
	SysRq			54/D4

Notice there are two base scan codes associated with keystation 124. To ensure the make/break sequence, the code associated with the break must reflect the make code regardless of the Alt state at the time of the break.

Key #	Legend (U.S.)	Scan Code Make	Ctrl down Make	
126	Pause	E1 1D 45 E1 9D C5		
	Break		E0 46 E0 C6	

The Pause/Break key is a make-only key, meaning it generates a code when pressed, not when released. All scan codes or actions associated with this key occur with the make of the key.

## 8.17 Scan Codes Sent in PCTerm Mode for VT Keyboards

All keystrokes send scan codes except:

Key	Which sends
Caps Lock F1	Hold
Caps Lock F2	Print
Caps Lock F3	Enter Set-Up
Caps Lock F5	Send Break

All keys including Shift, Alt, and Ctrl send make codes immediately upon being pressed, except the Caps Lock key. The make code for the Caps Lock key is sent after the Caps Lock key is released. The following keys send the corresponding scan codes, regardless of any modifiers that may be in effect.

Key #	Legend (U.S.)	Scan Code Make/Break
42	\	2B/AB
107	- 1	7E/FE
124	F13	E0 3D/E0 BD
125	F14	E0 3E/E0 BE
126	Help	E0 3F/E0 BF
127	Do	01/81 (Like Esc key on PC keyboard)
130	F17	E0 41/E0 C1
131	Print Screen	E0 2A E0 37/E0 B7 E0 AA Ctrl or Shift E0 37/E0 B7
	Sys Rq	Alt 54/D4
132	Scroll Lock	46/C6
133	Pause <sup>2</sup>	E1 1D 45 E1 9D C5
	Break <sup>2</sup>	Ctrl E0 46 E0 C6

<sup>&</sup>lt;sup>1</sup>On Numeric keypad.

<sup>&</sup>lt;sup>2</sup>This is a make-only key; code is sent only when key is pressed.

## 8.18 Control Codes and Keystrokes

The following codes are transmitted when the  $\boxed{\text{Ctrl}}$  key is depressed simultaneously with another key.

Table 8-12 Control Codes and Keystrokes

Legend	HEX Code Transmitted	Name
Ctrl Space	00	NUL
Ctrl 2	00	NUL
Ctrl A	01	SOH
Ctrl B	02	STX
Ctrl C	03	ETX
Ctrl D	04	EOT
Ctrl E	05	ENQ
Ctrl F	06	ACK
Ctrl G	07	BEL
Ctrl H	08	BS
Ctrl I	09	HT
Ctrl J	0A	LF
Ctrl K	0B	VT
Ctrl L	0C	FF
Ctrl M	0D	CR
Ctrl N	0E	SO
Ctrl O	0F	SI
Ctrl P	10	DLE
Ctrl Q	11	DC1†
Ctrl R	12	DC2
Ctrl S	13	DC3†
Ctrl T	14	DC4
Ctrl U	15	NAK
Ctrl V	16	SYN
Ctrl W	17	ETB
Ctrl X	18	CAN
Ctrl Y	19	EM
Ctrl Z	1A	SUB
Ctrl 3	1B	ESC
Ctrl [	1B	ESC
Ctrl 4	1C	FS
Ctrl \	1C	FS
Ctrl 5	1D	GS
Ctrl ]	1D	GS

†Code is transmitted if XON/XOFF handling is disabled.

# Keyboard Processing 8.18 Control Codes and Keystrokes

Table 8–12 (Cont.) Control Codes and Keystrokes

Legend	HEX Code Transmitted	Name
Ctrl 6	1E	RS
Ctrl ~	1E	RS
Ctrl 7	1F	US
Ctrl ?	1F	US
Ctrl 8	7F	DEL
Ctrl Tab	09	HT
Ctrl Enter	Same as Enter alone.	
Ctrl Return	Same as Return alone.	
Ctrl Delete	18	CAN

## **Communications**

This chapter describes the serial asynchronous communications through the host ports.

#### 9.1 Introduction to Communications

This chapter describes the physical layer and data link layer. The physical layer is comprised of the mechanical, electrical, and functional arrangements necessary for a physical connection, including cables and telephone lines. The physical layer applies to both ANSI and ASCII terminal emulations.

The data link layer is the electronic protocol used to convey a unit of information from the VT520 to a host computer. This layer includes flow control, character conversions, and some forms of error control.

The asynchronous character format consists of a start bit (space), the data bits (1=mark, 0=space), the parity bit (if present), and one or two stop bits (mark). The data bits represent a character with the least significant bit leading. The parity bit may be enabled as either none, odd, even, space, or mark. Received parity may be checked or ignored. When transmitting odd or even parity, the received parity must be set to the same parity as the transmitted data. These parameters can be selected through Set-Up or by using the escape sequence, DECSPP.

For further information on the asynchronous character format, refer to ANSI X3.15-1976, American National Standard for bit sequencing of the American National Standard Code for Information Interchange in Serial-By-Bit Data Transmission.

The VT520 supports the following:

Full-duplex mode Half-duplex mode

Full-duplex mode allows simultaneous two-way communication, while half-duplex mode limits communication to one way at any given time. The VT520 always supports full duplex (two wires) at the physical layer. Half-duplex mode is a simple data link layer protocol intended to support half-duplex modems. It is common to view the terminal and attached modem as a single system. Refer to Section 9.2.4 for details on half-duplex mode. This feature can be selected from Set-Up or by the control function, DECHDPXM.

The VT520 does not support synchronous communications.


## 9.2 Physical Link Layer

Communications lines may be connected to the comm ports without interaction between the two lines. You can use the Set-Up menu **Communication** - **Port select** to select the communications port. The port selection can also be programmed through the escape sequence, DECSCP.

#### 9.2.1 25-Pin Connectors

Figure 9–1 shows the typical 25-pin EIA 232 ports.<sup>1</sup> You can only use one connector at a time.

Figure 9-1 25-Pin Port Pin Numbers



Comm1, a DB-25P serial port, has full modem control, accepting a variety of modems that meet national and international standards.

Comm2 has data lead only and RS-423 drivers.

Table 9–1 shows the interface signals and functions. Interface signals are labeled with both EIA and CCITT designations.

Table 9-1 EIA Interface Signals and Functions

Pin	Signal Name	Source	Function	CCITT/EIA/DIN
1	GND	Ground		
2	TXD L	Terminal	Transmitted Data	103/BA/D1
3	RXD L	Modem	Received Data	104/BB/D2
4	RTS	Terminal	Request to Send	105/CA/S2
5	CTS	Modem	Clear to Send	106/CB/M2
6	DSR	Modem	Data Set Ready	107/CC/M1
7	SGND		Signal Ground	102/AB/E2
8	RLSD	Modem	Rec Line Signal Detector	109/CF/M5
9-11,	13-19, 21, 22, 24	, 25	No connection	

Normally grounded on the VT520. NC = no connection.

Table 9–1 (Cont.) EIA Interface Signals and Functions

Pin	Signal Name	Source	Function	CCITT/EIA/DIN
12	SPDI	Modem	Speed Mode Indication	112/CI/M4
20	DTR	Terminal	Data Term. Ready	108.2/CD/S1.2
23	SPD SEL L	Terminal	Speed Select	111/CH/S4

#### 9.2.2 DEC Corporate Modular Jacks (MMJ)

The modular jacks provide DEC-423 compatible levels with the intent of allowing greater length between terminal and host. Limited modem support is also provided. The DTR output and DSR input are supported on this connector. DEC-423 signals provide separate ground lines for TXD and RXD signals. Transmit ground for transmit data and DTR are isolated from receive ground used for receive data and DSR. Figure 9-2 shows the MMJ port signals.

Figure 9-2 MMJ Modular Jack Pin Numbers




Table 9–2 describes the function of each MMJ interface signal.

Table 9-2 MMJ Interface Signals

Pin	Signal Name	Source	Function
1	DTR	Terminal	Data Terminal Ready*
2	TXD +	Terminal	Transmitted Data
3	RXD -	Terminal	Transmit Signal Ground
4	RXD -	Modem	Receive Signal Ground
5	RXD +	Modem	Received Data
6	DSR	Modem	Data Set Ready†
6	DSR	Modem	Data Set Ready†

<sup>\*</sup>Pin 1 is a terminal output signal and uses pin 3 as a reference.

#### 9.2.3 Connector Pins Description

This section describes the function of full-duplex mode connector pins. Halfduplex mode connector pins have different functions than the full-duplex mode connector pins as mentioned in Section 9.2.4.

<sup>†</sup>Pin 6 is a terminal input signal and uses pin 4 as a reference.

## Communications 9.2 Physical Link Layer

#### 9.2.3.1 Transmitted Data-TXD L

The TXD L signal is supported on the 25-pin D-sub and the Corporate Modular Connector.

Data on this circuit represents the serially encoded characters that are transmitted from the VT520. This circuit is held at the mark state (-) during stop bits between characters and also at times when no data is being transmitted.

On the 25-pin connector when modem control is enabled, no data is transmitted unless Clear to Send is asserted from the modem. Assertion of DSR or RLSD from the modem is not required. This is specific to the 25-pin EIA connector and is intended to allow the VT520 to communicate with intelligent modems (like the DF224) before a connection has been established.

#### 9.2.3.2 Received Data-RXD L

The RXD L signal is supported on the 25-pin D-sub as well as on the Corporate Modular Connector.

Data on this circuit represents the serially encoded characters to be received by the VT520.

When modem control is not enabled, received data is processed regardless of the state of the control lines.

On a 25-pin EIA connector, when modem control is enabled and a connection has been established (DSR from the modem is asserted), the received characters are ignored if RLSD is unasserted, except when Disconnect Delay in Set-up is selected as **No disconnect**. This is an implementation in firmware of mark carrier clamping.

If a connection has not been established (DSR from the modem is not asserted), then received characters are processed even if RLSD is unasserted. This is an implementation that permits V.25 bis compatible autodial modems to be used without the user having to set "data leads only" to access the autodial functions.

#### 9.2.3.3 Request to Send-RTS

The RTS signal is supported on the 25-pin D-sub but not on the Corporate Modular Connector.

For modems with this function, asserting RTS may put the modem in the transmit mode. When the modem is in the transmit mode, it then asserts CTS.

Note
For full-duplex modems without RTS inputs, CTS is asserted by the modem whenever it is capable of transmission.

#### 9.2.3.4 Clear to Send-CTS

The CTS signal is supported on the 25-pin D-sub but not on the Corporate Modular Connector.

Assertion of CTS indicates that the modem is ready to receive data (that is, the terminal is clear to send data to the modem).

The data can be either a command to the modem if "off line" (DSR de-asserted) or transmitted data to the host if "on line" (DSR asserted).

#### 9.2.3.5 Data Terminal Ready-DTR

The DTR signal is supported on the 25-pin D-sub as well as the Corporate Modular Connector.

The VT520 asserts DTR whenever it is ready to transmit and/or receive on the port to which it is associated with.

The VT520 de-asserts DTR when:

- Recalling saved settings
- Recalling factory defaults
- Pressing Shift/Break
- Powering up self-test
- Resetting to Initial State (RIS)-hard reset
- DTR is being used for hardware flow control and the receive buffer has reached the flow control threshold

The VT520 does not de-assert DTR when:

- Resetting session
- Clearing comm

#### 9.2.3.6 Data Set Ready-DSR

The DSR signal is supported on the 25-pin D-sub as well as the Corporate Modular Connector.

When the DTR/DSR is not the selected flow control scheme, the assertion of DSR indicates the following:


- That the modem is in the data mode
- That the modem is connected to the communications channel
- The answer tone is finished
- The user is being charged by the PTT
- That the modem is ready to exchange the appropriate control signals to initiate data transmission/reception

When DTR/DSR is the selected hardware flow control scheme only, refer to Section 9.3.2.2.3.

**9.2.3.6.1 Modem Initiated Disconnect** When DSR is unasserted during the progress of a call but before DTR is unasserted, the terminal interprets this condition as a lost or aborted call and disconnects. Any subsequent assertion of DSR is considered a new call. If connected to a modem and the modem's power is turned off or if DSR becomes an open circuit, then the VT520 interprets these conditions as a de-assertion. The state of the DSR input is shown on the indicator status line display.

9.2.3.6.2 Terminal Initiated Disconnect The terminal disconnects itself from the modem by dropping DTR.

#### Communications 9.2 Physical Link Layer



If DSR is de-asserted 220 ms after DTR goes de-asserted, then do nothing, since the modem has already done a disconnect. If DSR is still asserted 220 ms after DTR goes deasserted, then DTR must remain deasserted for greater than 2 seconds to assure that the modem does a disconnect.

**9.2.3.6.3 Modem off line** When DSR is unasserted and modem control is enabled on the 25-pin EIA connector, the system is in a transitory "off line" state. In this state, the user may interact with a dial-up modem to enter numbers, change modem set-up, and so on.

When DSR is asserted and modem control is being used, the modem, terminal, and host system are ready for communication to a remote host.

#### 9.2.3.7 Receive Line Signal Detector-RLSD

This signal is supported on the 25-pin D-sub but not on the Corporate Modular Connector.

RLSD is also called Carrier Detect. The modem asserts RLSD when the received signal is of sufficient amplitude or in the case of "training modems," when both modems have adjusted and equalized to the prevailing line conditions, to ensure demodulation of Received Data. The unasserted condition of RLSD indicates that there is neither a received signal nor that it is unsuitable for demodulation.

#### 9.2.3.8 Speed Indicator-SPDI

The SPDI signal is supported on the 25-pin D-sub but not on the Corporate Modular Connector. This signal comes from the modem. When Modem Control is enabled in Set-Up, the transmit and receive speed is set as follows:

State	Transmit and Receive Speed
Unasserted	Modem Low Speed
Asserted	Modem High Speed (default)

The user should set these Set-Up fields so that the fast speed (2400 baud, for example) is exactly twice the slow (1200 baud, in the following example) if V.25 bis compatibility is desired. Otherwise, the user may set the two speeds as applicable (1200/300 baud, in the following example).

	Assert	De-assert
Bell 212	1200	300
Bell 103	300	n/a
V.22	1200	600
V.22 bis	2400	1200
V.26 ter	2400	1200
V.32	4800	2400
V.32	9600	4800

#### 9.2.3.9 Speed Select-SPDS

The SPDS signal is supported on the 25-pin D-sub but not on the Corporate Modular Connector.

If the speed is greater or equal to 1200 baud, then Speed Select will be high. If the speed is below 1200 baud, then Speed Select will be slow. This signal comes from the terminal.

#### 9.2.4 Half-Duplex Mode

Half-duplex mode works in EIA 232-E line only. It uses the pin signals to control the data traffic to one direction at any given time.

In this mode, Data Terminal Ready (DTR) is always asserted. The terminal checks the assertion of Data Set Ready (DSR) constantly. The terminal disconnects once DSR is dropped. Ready to Send (RTS) is asserted only if the terminal intends to transmit.

Before transmitting, the terminal checks for the presence of Carrier Detect (CD). If CD is still detected for five seconds, then the terminal disconnects. Otherwise, the terminal asserts the Request to Send (RTS) signal and starts detecting the Clear to Send (CTS) signal. Transmission starts if CTS is detected within five seconds. If CTS is not monitored within five seconds, then the terminal disconnects. After transmission, RTS is de-asserted from the terminal. If CTS is still detected within the next five seconds, then the terminal disconnects.

#### 9.2.5 Supported Modem Configurations

This section describes the supported modem configurations.

#### 9.2.5.1 CCITT Public Switched Telephone Network (2-wire only)

V.21 Modem (V.24/V.28) Async, FDX, up to 200/300 bit/s V.22 Modem (V.24/V.28) Async, FDX, up to 1200 bit/s V.22 bis Modem (V.24/V.28) Async, FDX, up to 2400 bit/s V.23 Modem (V.24/V.28) Async, Asymmetric FDX Receive = 600 or 1200 bit/s. Transmit = Reverse channel at 75 bit/s V.25 bis Auto Dial Protocol Modem and Hayes

#### 9.2.5.2 CCITT Dedicated Line (2-Wire / 4-Wire) Data Network

V.21 Modem (V.24/V.28, 2-W) Async, FDX, 200/300 B V.23 Modem (V.24/V.28) FDX, Async, 1200 B, 4-W V.25 bis compatible Modem Async, FDX, any standard speed from 300 baud up. X.20 bis Full-Duplex asynchronous 300 baud data service unit

#### **Communications** 9.2 Physical Link Layer

#### 9.2.5.3 European Public Circuit Switched Data Network

D1200S (Germany) VC-DCE (Nordic Network) VPC-DCE (Nordic Network)

X.20bis (V.21) Data Service Unit (V.28)

Async, FDX, up to 300 B

#### 9.2.5.4 European Public Packet Switched Data Network (PSDN)

Germany: DATEX-P

Basic Datex P10-Service (X.25): Not supported

Additional Datex-P20 Service:

Fixed Connections to PAD facility with X.28 procedure:

Service	DCE
DATEX-P20 H300	DFG300(X.20 bis), D300S (V.21)
DATEX-P20 H1200	D1200S12(V.22), D1200S (V.23,4-W)
DATEX-P20 H1200/75	D1200S (V.23 with sec. channel, 75 baud Transmit / 1200 Baud Receive)
DATEX-P20 H2400	

Access to DATEX-P PAD facility from other public switched networks with X.28 procedure:

Service	Access	DCE
DATEX-P20 L300	DATEX-L	DFG300 (X.20bis)
DATEX-P20 F300	PSTN	D300S (V.21)
DATEX-P20 F1200	PSTN	D1200S12 (V.22)
DATEX-P20 F1200/75	PSTN	D1200S (V.23 with sec channel, 75 baud Transmit, 1200 baud Receive)
DATEX-P20 F2400		

#### 9.3 Data Link Layer

This section describes the data link layer.

#### 9.3.1 7- /8-Bit VT100/VT520 Operation

The VT520 supports three broad classes of application requirements:

- Strict compatibility for existing VT100 applications:
  - No 8-bit control codes
  - No 8-bit data Function keys are not limited to the VT100 set as in previous terminals.
- A migration path that allows most applications to run without modification:
  - No 8-bit control codes
  - 8-bit graphic data allowable
  - VT400 function keys are allowable (but not immediately useful) and can be integrated into the application over time.
- Full VT520 mode (VT level 5) functionality:
  - 8-bit data allowable
  - 8-bit controls allowable
  - All VT500 function and modifier keys

The VT520 application requirements are possible through the following VT terminal modes:

- VT52 Mode (7-bit characters, 7-bit controls)
- VT100 Mode (7-bit characters, 7-bit controls)
- VT500 Mode, 8-bit characters, 7-bit controls
- VT500 Mode. 8-bit characters. 8-bit controls
- VT500 Mode, 7-bit characters (Keyboard restricted to keys that generate 7-bit codes, 7-bit graphics, 7-bit controls, for NRC sets, worldwide version only).

These modes are the only supported modes. 8-bit characters are temporarily disabled when in VT100 mode.

The following are certain limitations within these modes:

- The terminal accepts both C0 and C1 controls when 8-bit characters are selected (7-bit NRCS Characters is not selected).
- The terminal accepts both GL and GR characters when 8-bit Characters are selected.
- In VT52 mode, VT100 mode, or VT500 mode, when 7-bit characters is selected, the terminal sets the high bit of all received characters to zero. This action results in compatible character handling. The received characters, therefore, have only seven significant bits. This is applicable to both graphics characters and control characters.

## Communications 9.3 Data Link Layer

- If the user needs to restrict the controls to 7 bits, but still needs 8-bit graphic characters and new function keys, then the user can select **Transmit 7-bit controls** with an 8-bit host line. To get full efficiency out of new applications, select 8-bit controls and an 8-bit host line. The **7-bit NRCS Characters** selection is compatible with 7-bit NRC-based applications.
- C1 controls are never available directly from the default keyboard, although
  they may be available indirectly through the function keys or numeric
  compose.
- When the terminal is in printer controller mode and the 7-bit character mode, upon receiving 8-bit graphic characters, the terminal immediately retransmits them through the printer port to the printer. The highest bit is not stripped off
- In printer controller mode when the terminal is receiving 8-bit characters and immediately retransmitting them on a 7-bit line, the high bit is stripped off.
- When the screen contains 8-bit (GR) characters and is being printed on a 7-bit printer, the characters are subject to constraints, which are described in Chapter 10.
- Keyboard operation guidelines are described in Chapter 8.

#### 9.3.2 Flow Control

Flow control is a means to alternately suspend and resume the flow of characters over serial asynchronous point-to-point communication lines.

Depending on the type of flow control selected, the stop/resume transmission signal is different. Users can select a software flow control scheme, a hardware flow control scheme, or a combination software and hardware flow control scheme to meet their communication environment.

#### 9.3.2.1 Receive Buffer

The VT520 operates at a transmission speed of up to 115.2K baud. To prevent loss of data, the receive buffer is 1024 byte. The substitute (SUB) character is substituted in the input buffer for any character with detected receive parity errors or framing errors. If the input buffer overflows, a SUB character is placed in the buffer in place of the lost characters. The SUB character is displayed as a reverse question mark.

#### 9.3.2.2 Flow Control Selection

The VT520 supports bidirectional flow control. The flow control scheme can be selected independently for the transmit and receive direction. The user has the following choices for transmit data flow control:

- No Flow Control
- XON/XOFF
- DTR
- Both

The user has the following choices for receive flow control:

- No Flow Control
- XON/XOFF in VT mode or XPC in PC term mode
- DSR

#### Both

You can select flow control methods from Set-Up or through the escape sequences, DECSFC.

**9.3.2.2.1 No Flow Control** If **No Flow Control** is selected, then when the receive buffer is full, it does not send any signal; therefore, the Hold key is disabled. Ctrl/S and Ctrl/Q will be transmitted as typed. It is left to the application and user to prevent buffer overflow.

Software that does not support flow control may use all the features of the VT520 by treating NUL as a fill character. If **Ignore NUL** is selected in Set-Up, then NUL is discarded upon receipt. All other received characters are stored in the input buffer for further processing. **Ignore NUL** or **Accept NUL** can be selected from Set-Up or through the escape sequence, DECNULM.

The VT520 can be used without flow control or fill characters, when the:

- · Software never sends ESC sequences to the terminal
- · Baud rate is limited to 19200 baud or less
- Software does not use smooth scrolling

#### 9.3.2.2.2 XOFF/XON or XPC Flow Control

In the XOFF/XON flow control, two characters establish flow control. In VT mode, these two characters are DC1(11H) (XON) and DC3(13H) (XOFF). In VT mode, the VT520 sends XOFF to suspend the host transmission of data and XON to resume that transmission. Receipt of XOFF inhibits the host from transmitting any code except XOFF and XON. Once the keyboard buffer becomes full, no more keystrokes are accepted. The keyboard locks and "wait" is displayed in the keyboard indicator line. Transmission resumes when the host receives an XON.

In PC Term mode, the terminal receives from the host 11H(DC1) and 13H(DC3) for flow control; but the terminal sends 65H and 67H to the host to resume/stop the communication, known as XPC flow control.

VT520 sends XOFF to indicate halt of transmission when:

- 1. The number of characters in the input buffer reaches the first XOFF point since the last XON was sent.
- 2. The number of characters in the input buffer reaches the second XOFF point since the last XON was sent.
- 3. The input buffer is full.
- 4. Entering a hold state.

Entering a Hold state causes an XOFF to be sent by the VT520. A Hold state can be generated by pressing the  $\boxed{\text{Hold}}$  key or entering  $\boxed{\text{Ctrl/S}}$ . When exiting from the hold state either by depressing the  $\boxed{\text{Hold}}$  key or entering  $\boxed{\text{Ctrl/Q}}$ , the terminal sends XON to the host unless the input buffer is filled up to or beyond the first XOFF point (flow control threshold).

With the exception of exiting from the hold state, the VT520 sends an XON when the input buffer is emptied to the XON point and when XOFF was the last flow control sent.

Refer to the Section 9.3.2.2.5 for more information on the thresholds.

## Communications 9.3 Data Link Layer

The VT520 re-initializes the XON/XOFF(XPC) state under the following conditions:

- 1. The Clear Comm function is performed.
- 2. The completion of the NVR recall after the RECALL function is performed.
- 3. The completion of all tests in a self-test sequence is performed.
- 4. Successful completion of a connection generally, DSR assertion.
- 5. The reception of RIS.

#### 9.3.2.2.3 DSR/DTR Flow Control

When **Hardware flow control** is selected, DTR is asserted any time the terminal is not in self-test and the terminal's input buffer is below the flow control threshold; DTR is de-asserted when the input buffer is filled up to or beyond the threshold.

If the terminal is a sending device, then it polls DSR before transmitting each character. If DSR is not being asserted by the receiving device, then transmission of the character is suspended until DSR is asserted.

As in the XON/XOFF software flow control, VT520 deasserts DTR when:

- 1. The number of characters in the input buffer is greater than or equal to the flow control threshold (first XOFF point).
- 2. Entering the Hold state.

As in the XON/XOFF flow control, entering a Hold state causes a deassertion of DTR. When exiting from the hold state either by depressing the Hold key or by entering Ctrl/Q", the terminal asserts DTR unless the input buffer is filled up to or beyond the flow control threshold (first XOFF point).

With the exception of exiting from the hold state, the VT520 reasserts DTR when the input buffer is emptied to the "resume transmission" (XON) point.

DSR/DTR can be used for hardware flow control when they are not needed for modem control functions. When **Modem Control** is enabled, DST/DTR should not be selectable.

#### 9.3.2.2.4 Software and Hardware Combined Flow Control

For software and hardware flow control, both DTR/DSR and XON/XOFF(XPC) are used to control the data flow. When the receive input buffer reaches the flow control threshold, XOFF is sent and DTR is deasserted. When transmitting, the terminal must be in the XON state with DSR asserted to transmit the next character, except in the case of (XON/XOFF).

#### 9.3.2.2.5 Flow Control Threshold

Table 9-3 shows the flow control threshold points available for the VT520.

Table 9-3 Flow Control Threshold Points

1st Flow Control Threshold	Resume Transmission Point	2nd Flow Control Threshold
64	32	896
768	128	896

#### 9.3.2.3 Show Control Character Mode

While in show control character mode, all characters are temporarily stored in the input buffer and eventually displayed on the screen in the CRM font. XON and XOFF can serve both as data (to be displayed) and flow control. Note that this circumstance is unique to show control character mode.

#### 9.3.2.4 Set-Up on Flow Control Handling

Entering Set-Up leaves the received character processing in the state it was in before entering Set-Up. Characters continue to fill the silo, depending on the flow control type selected. A signal (XOFF or lower DTR) will be sent when the silo gets to the first flow control threshold.

#### 9.3.2.5 When Disconnect Occurs

If a disconnect occurs while the VT520's silo contains characters that have not been displayed or printed, then the characters may be discarded in order to prepare for the next call. XON is sent when a new connection is established.

#### 9.4 Features that Affect Communications

The following features described in Chapter 2 affect communication:

- Clear communications
- On-Line/Local
- Transmit speed
- Receive speed
- Transmit rate limiting
- Word size
- Parity
- Stop bits
- Modem control
- Modem high speed
- Modem low speed
- Disconnect delay
- Local echo

#### 9.4 Features that Affect Communications

#### 9.4.1 Clear Communications

If the terminal appears to be "locked" in Set-Up, then select **Clear communications** to clear the current session. This action:

- 1. Aborts any print operation in progress if the printer is allocated to the active session.
- 2. Aborts any escape sequence, control sequence, or device control string (DCS) processing.
- 3. Clears the keyboard buffer.
- 4. Clears the receive buffer.
- 5. Clears the transmit buffer.
- 6. Takes the terminal out of printer controller mode.
- 7. Sends XON to the host port if software flow control is in use. Asserts DTR if hardware flow control is in use.
- 8. Resets XOFF received flags on the printer and host ports if software flow control is in use.

The communications has been cleared when "Done" appears on the terminal status line.

Note
<b>Clear communications</b> does not cause a disconnect and does not clear the screen.

#### 9.4.2 Connection

If XON/XOFF flow control is enabled, then a single XON will be transmitted after the connection is made. When a connection is made, the VT520 performs the following operations to ensure that it is ready to send and receive:


- 1. Unlock the keyboard, if it is locked.
- 2. Clear any transmit in progress on this port.
- 3. Clear all buffers associated with this port.
- 4. Clear the "XOFF sent" and "XOFF received" state of this port.
- 5. At the reception of the carrier tone, the modem asserts CD, and data transmission/reception may begin.

#### 9.4.3 Line Disconnection

A disconnect sequence occurs on the following conditions:

- Operator initiates a disconnect by pressing Shift/Break (note that the BREAK can be disabled through Keyboard Set-Up).
- Doing a RECALL, or DEFAULT. (If a terminal supports more than one session, this only disconnects the active session's line.)
- · Loss of DSR.
- Switching to the EIA 232-E port from the DEC423 port or to the DEC423 port from the EIA232-E port.

- With the 25-pin connector and modem control enabled, after a connection has been established, loss of RLSD for greater than 2 seconds (or 60 ms) on host line 1.
- Receipt of a DECTST or RIS sequence (Except the keyboard test in DECTST that leaves the terminal on line).
- Turning off the terminal.



Normally DTR and RTS are asserted by the VT520 whenever power is applied except:

- During a disconnect sequence
- When hardware flow control DTR/DSR is being used and the receive buffer reaches 64 bytes threshold

#### 9.4.4 Break

The Break key operates as described in Chapter 8.

A break consists of a 275  $\pm$  25 ms space condition on the transmit data line if transmission is enabled. The break (space) condition is separated from any subsequent mark-to-space transition by at least 100 ms.

#### 9.4.4.1 Received Break

If a break is detected on the received data circuit, then it is ignored. One or more error characters (reverse question mark) may be displayed because the framing errors were generated.

## **Printer Port**

#### 10.1 Overview

The VT520 expands the traditional printer port extension to include support for IBM ProPrinter and compatible low-cost parallel interface printers. In Set-Up, you specify the type of printer attached and the terminal automatically selects the correct printing commands and character sets.

The VT520 printer port has the following features:

- Centronics parallel port (25-pin, female, D-type connector)
- IBM ProPrinter mode
- Ability to transparently pass all characters (including the NUL character) through to the printer in printer controller mode

You can connect both a serial and a parallel printer to the VT520 at the same time, and both printer ports can be active at the same time if used by different sessions.

#### 10.2 Serial Port

The VT520 uses Comm3 and the serial printer port with speeds of 300 to 115.2K baud. Comm 3 is a 6-pin MMJ connector with EIA 423 levels.

The interface signals are the same as those previously described in Chapter 9.

#### 10.2.1 Serial Port Flow Control

The VT520 serial printer port is fully bi-directional when **Printer To Host** communications is enabled in Set-Up or by a Media Copy (MC) control sequence. The printer port has two buffers: one is for output, which is 16 bytes long; and the other is for input, which is 254 bytes long.

The firmware supports bi-directional flow control on the printer port. Transmit and receive flow control protocols can be set independently to one of four choices through Set-Up or by the control sequence, DECSFC.

- None
- XON/XOFF
- DTR/DSR
- Both

**XON/XOFF:** For the 254-character receive input buffer, the XON point is 32. The first XOFF point is 64 characters, and the second is 220 characters.

**DTR/DSR:** If enabled, the terminal polls DSR before transmitting each character. The terminal asserts DTR until the buffer fills up to or beyond the first XOFF point. When the buffer empties to the XON point, the terminal again asserts DTR. When not used for hardware flow control, DTR is asserted whenever the firmware is active and not in its self-test.

When the input buffer is full and receives another character byte, it overflows. In the event of an input buffer overflow, the last byte in the buffer is replaced with the SUB character.

#### 10.3 Parallel Port

The Centronics parallel interface is considered to be industry standard and is not explained in this chapter. This port uses a 25-pin D-type connector with pin assignments shown in Figure 10–1 and listed in Table 10–1.

Figure 10-1 Parallel Printer Port




Table 10-1 Parallel Connector Signals

Pin	Signal Name	Source	Function
1	STROBE L	Terminal	Strobe
2	DATA0	Terminal	Data Bit 1
3	DATA1	Terminal	Data Bit 2
4	DATA2	Terminal	Data Bit 3
5	DATA3	Terminal	Data Bit 4
6	DATA4	Terminal	Data Bit 5
7	DATA5	Terminal	Data Bit 6
8	DATA6	Terminal	Data Bit 7
9	DATA7	Terminal	Data Bit 8
10	ACKNLG L	Printer	Acknowledge
11	BUSY	Printer	Printer cannot receive data.
12	PE	Printer	Printer is out of paper.
13	SLCT	Printer	Printer is on-line.
14	AUTO FEED XT L	Terminal	Feed 1 line automatically after printing.
			(continued on next page)

10-2 Printer Port

Table 10-1 (Cont.) Parallel Connector Signals

Pin	Signal Name	Source	Function
15	ERROR L	Printer	Paper end, printer off-line, or printer error
16	INIT L	Terminal	Resets the printer to power-on defaults
17	SLCT IN L	Terminal	The VT520 monitors SLCT to determine if a parallel printer is attached and on-line.
18	GROUND	N/A	
19	GROUND	N/A	
20	GROUND	N/A	
21	GROUND	N/A	
22	GROUND	N/A	
23	GROUND	N/A	
24	GROUND	N/A	
25	GROUND	N/A	

The VT520 uses the eight data lines along with control signals STROBE, ACKNLG, and BUSY to transfer data to the printer. All other interface signals are ignored.

#### 10.3.1 Parallel Port Flow Control

Characters are transferred to the printer in 8-bit bytes. A parallel printer port is not duplex; data can only go from the terminal to the printer.

The terminal and the printer use interface signals STROBE, ACKNLG, and BUSY to synchronize the data transfer as follows:

- 1. When the terminal is ready to send data to the printer, the terminal puts the data on the data lines and then generates a STROBE pulse to the printer.
- 2. When the printer senses the STROBE, it responds with a BUSY signal.
- 3. When printer receives the data, it pulses ACKNLG to signal the terminal that data has been read into memory.
- 4. If the printer buffer is full, the printer keeps the BUSY signal asserted.

The parallel printer port does not recognize XON/XOFF flow control.

#### 10.4 Print Modes

There are five modes that affect the control of printing operations:

- Printer Controller mode
- · Local Controller mode
- Auto Print mode
- Print Form Feed mode
- Print Extent mode

These print modes follow standard terminal transmission except for Printer Controller mode.

#### 10.4.1 Printer Controller Mode

When printer controller mode is enabled, all data received at the host port is passed through to the printer port, except for:

XON/XOFF when XON/XOFF flow control is enabled at either the host port or the printer port

NUL when **Ignore NUL characters** is selected in the communication setup.

If printer-to-host communication is enabled, then all data received at the printer port is passed through to the host port with the exceptions listed previously.

#### 10.5 Print Operation

The VT520 supports the following print operations:

- Print Line
- Print Page or Scrolling Region
- Print Screen

Print Screen prints the screen as it appears, including the status lines if enabled. Print Screen, however, does not print the keyboard indicator line.

## 10.6 Transmitting Print Data

Users have three choices for a printer type:

- DEC ANSI
- IBM ProPrinter
- DEC + IBM emulation mode

Depending on the printer type selected, the terminal transmits different control functions to the printer. You can select the printer type in Set-Up or by using the escape sequence, DECSPRTT.

#### 10.6.1 DEC ANSI

The DEC ANSI protocol supports the following printed data types:

- When in 8-bit mode:
  - ASCII only
  - ASCII + Line Drawing
- When in 7-bit mode:
  - National only
  - National + Line Drawing

You select a printed data type based on the 7- or 8-bit printer port setting and the character set capability of the attached printer. The VT520 sends initialization, transmission, and closing sequences according to the printed data type selected.

If IBM PC characters are displayed, then the terminal translates the corresponding characters in the ISO Latin-1 character set and transmits them based on the current printed data type selected. If there is no corresponding character in ISO Latin-1, then the Space character is used instead.

#### 10.6.2 IBM ProPrinter or Compatible Printer

When an IBM ProPrinter is attached, the terminal sends IBM ProPrinter sequences. You can neither designate, nor invoke the ANSI sequence or any other operating sequences in this mode.

The VT520 supports the following printer character sets for the IBM printer: PC Multilingual, PC Latin 2 (PC Slavic), PC International, PC Spanish, PC Portuguese, PC Danish, PC French Canadian, PC Hebrew, PC Greek, PC Turkish, and PC Cyrillic.

During initialization, the VT520 sends a control sequence to the printer to select the same code page as the printer character set selected in the terminal. You must select the appropriate printer character set for the correct data to be printed either in Set-Up or by the escape sequence, DECSPPCS.

In an IBM ProPrinter, each code page has the following character sets:

Character Set 1 Character Set 2 Same as receive All Characters

The character sets are identical, except for the interpretation of C0 (0/0 through 1/15) and C1 (8/0 through 9/15) characters.

In Character Set 1, the controls in C0 are identical to those in C1, except that 80 (hex) is ignored instead of being interpreted as NUL.

Character Set 2 uses the same controls as C0, except that some printable characters are added to unused character code spaces. The C1 region is all printable characters.

**Same as receive** uses IBM ProPrinter sequences with control codes or without host control codes.

The "All Characters" set only has printable characters. No control codes are allocated to this character set.

The VT520 initializes the printer to use Character Set 2 at the start of a print screen operation. When a C0 printable character is encountered, the VT520 sends the appropriate sequence to print from the "All Characters" set. See the Set-Up chapter for detailed description on selecting these character sets.

#### 10.6.2.1 Data Transmission

The printer is either an IBM personal printer or a compatible printer. It recognizes the IBM ProPrinter mode escape sequences and supports the terminal's code pages. The printer should support a software-selectable code page switching sequence. If it does not, then you need to take appropriate action to set the correct code page before a printing operation takes place.

#### Printer Port 10.6 Transmitting Print Data

Each time a print operation is requested, the VT520 sends the following escape sequences:

Escape Sequence	Meaning
ERSCS	Selects code page
ERC02	Selects Character Set 2

Characters are sent to the printer along with their display attributes. If a C0 printable character is encountered, the VT520 sends the escape sequence, ERSSACS or ERC0ACS, to print from the "All Characters" set. If a character that is not in the selected code page is encountered, then a Space character is sent instead.

The VT520 supports the following display attributes sequences:

Display Attribute Sequence	Meaning
EREDHW	Sets double-height and width
EREBD	Enables bold
ERDBD	Disables bold
EREUL	Sets underline
ERDUL	Resets underline

The VT520 supports the following character set switching sequences:

Switching Sequence	Meaning
ERSSACS	Prints a single character from "All Characters" set
ERC0ACS	Prints multiple characters from "All Characters" set

If the terminal has DEC Supplemental or ISO Latin 1 characters on the screen, then the VT520 translates the characters to corresponding characters in the code page indicated by the printer character set before the transmission takes place. If there is no corresponding character in the selected IBM code page, then the Space character is used instead.

The line and display attributes of the printer should be switched back to the default state when printing is completed.

#### 10.6.3 DEC ANSI with IBM ProPrinter Emulation

You can specify both DEC ANSI printed data types and IBM ProPrinter PC character sets in Set-Up when this type of printer is selected. If the terminal is set to display DEC or ISO character sets, then the VT520 treats the printer as a DEC ANSI printer and transmits data to the attached printer using ANSI protocols.

If the terminal is set to display PC character sets, then the VT520 transmits data to the attached printer using the IBM ProPrinter protocol. During initialization, the VT520 sends a Select Other Coding System (SOCS) sequence followed by DECIPEM sequence to the printer to force the printer into IBM ProPrinter emulation mode. The terminal sends all other sequences just as in the IBM ProPrinter mode.

#### 10.6.3.1 Data Transmission

The printer is a DEC ANSI printer with IBM ProPrinter emulation. The printer is in its default ANSI mode state. The printer recognizes IBM ProPrinter mode escape sequences and supports the IBM code pages. The printer supports the software selectable code page switching sequence. If it does not, then you must take appropriate action to set the correct code page before a printing operation takes place.

Each time a print operation is requested, the VT520 sends the following escape sequences to initialize the attached printer to a known state:

Escape Sequences	Function
SOCS	Enters IBM ProPrinter mode
DECIPEM	Enters IBM ProPrinter mode
ERSCS	Selects code page
ERC02	Selects Character Set 2

The line and display attributes of the printer return to the default state when printing is completed by sending the following sequences:

Sequence	Function
ROCS	Returns from other coding system
DECIPEM	Returns from IBM emulation mode

#### 10.7 Printer Status

The Session Management Extension is supported, so the terminal responds with "Printer Busy" and "Printer Not Assigned."

If the printer stalls, the word "Printer" flashes continuously in the Indicator Status Line.

## 10.8 Suspending Print Operations

Entering Set-Up can suspend, but not abort, printing operations. Upon exit from Set-Up, all unfinished printing operations resume unless an explicit action has been taken in Set-Up to abort the print operation, such as **Clear communications**, **Reset terminal**, or **Restore factory defaults**.

## 10.9 Aborting Print Operations

The **Clear communications** function from Set-up, aborts the current print operation, clears the output silo, and re-initializes the printer port UART. This function may be used to get out of a "hung" state.

Note		
After a <b>Clear communications</b> command, printing may not stop immediately because characters may still be in the printer's input buffer.		

# **Part III**

## **VT520 ASCII Emulation**

This part contains the following chapters:

- Chapter 11, ASCII Emulations and Control Functions
- Chapter 12, ASCII Escape Sequences
- Chapter 13, Defining and Loading ASCII Character Fonts

## **ASCII Emulations and Control Functions**

This chapter describes the ASCII emulations and control functions.

#### 11.1 Overview

The VT520 video terminal includes emulations for several popular ASCII video terminals. ASCII terminals represent the other major class of serial asynchronous video terminals in widespread use today. Like the VT100, these terminals communicate with a host computer by transmitting and receiving a data stream of 7-bit or 8-bit coded characters. To communicate successfully, the computer and the terminal use a convention for interpreting this data stream. This convention specifies how to recognize characters in the data stream as well as how to recognize control information, such as formatting or editing commands. ASCII terminals support the ASCII character set, *American Standard Code for Information Interchange, ANSI X3.4*; however, they do not follow other ANSI standards that define controls for use with the ASCII character set. The original ASCII terminal protocol pre-dates the ANSI standards. These early protocols have since been widely copied and extended to form the ASCII terminal market.

#### 11.2 ASCII Emulations

The VT520 includes a protocol emulation for the WYSE 325 color mode, WYSE 160 Native mode, WYSE 60 Native mode, and many of its popular emulations of other ASCII terminals:

- WYSE 325
- WYSE 160/60 Native mode
- WYSE PCTerm
- WYSE 50/50+
- WYSE 150/120
- Televideo 950
- Televideo 925
- Televideo 910+
- ADDS VP A2

Emulation means that virtually all host application programs designed for these terminals will function correctly.

Note that the VT520 video terminal cannot be identical to all of these terminals simultaneously, and the VT520 includes enhancements in its user interface and character handling ability. The VT520 can handle additional languages and keyboards that extend beyond the original terminals being emulated.

## ASCII Emulations and Control Functions 11.2 ASCII Emulations

The VT520 does not emulate the graphics modes of the WYSE 160, such as the TEK 4010/4014 personality.

#### 11.2.1 Enhanced Mode

WYSE 160 Native mode includes function sequences for almost all features supported by the WYSE 160 terminal, including those supported by individual sub-emulations, such as Televideo or ADDS. When one of these sub-emulations is selected, WYSE Enhanced mode (EnH) allows WYSE Native mode sequences to be used from within a sub-emulation to access features that are not normally supported by the physical terminal being emulated. This capability allows existing applications, for one of these emulated terminals, to be enhanced to take advantage of WYSE Native mode features. This enhanced mode does not apply to the VT or ANSI modes, which follow the corresponding ANSI standards.

### 11.3 Coding Notation

Since ASCII control functions do not follow a structured syntax, the notation used to describe function sequences and parameters is important to avoid confusion. Escape sequences are shown with a space between each character to make them easier to read. These spaces are not part of the Escape sequence.

**Words in all caps:** Strings of two or more capital letters, such as ESC or SPACE, are used as symbols, usually to represent a single character within an Escape sequence.

**Words in italics:** Words or abbreviations of two or more characters in *italics* represent sequence parameters that are described subsequently.

**Single characters:** Single characters, such as "E" or "8", represent the corresponding ASCII character in the sequence.

**Regular text (upper- and lowercase):** Regular text is sometimes used to describe sequences that are similar or related to other sequences.

Table 11–1 lists the symbols used in the ASCII control functions.

Table 11–1 Symbols Used in ASCII Terminal Escape Sequences

Symbol	Meaning	Symbol	Meaning
Ctrl-	Ctrl immediately followed by a single character represents a control character in the range of 0/0 to 1/15.	EnH	Enhance Mode: This is the same as the WYSE native code when Enhance Mode is on.
Same	Same as the WYSE native code (code is native to this emulation).	Wyse	Same as the WYSE native code (code is <i>not</i> native to this emulation, but is a WYSE enhancement).
n/a	Not available in this emulation.		
			(continued on next page)

Table 11–1 (Cont.) Symbols Used in ASCII Terminal Escape Sequences

Symbol	Code	Symbol	Code
NUL	0/0	DLE	1/0
SOH	0/1	DC1 (XON)	1/1
STX	0/2	DC2	1/2
ETX	0/3	DC3 (XOFF)	1/3
EOT	0/4	DC4	1/4
ENQ	0/5	NAK	1/5
ACK	0/6	SYN	1/6
BEL	0/7	ETB	1/7
BS	0/8	CAN	1/8
HT	0/9	EM	1/9
LF	0/10	SUB	1/10
VT	0/11	ESC	1/11
FF	0/12	FS	1/12
CR	0/13	GS	1/13
SO	0/14	RS	1/14
SI	0/15	US	1/15
SPACE	4/0		

#### 11.3.1 Communication Flow Control with PCTerm Mode

XON/XOFF transmit flow control is disabled while in PCTerm mode. This means XON and XOFF characters received from the host are ignored or displayed as characters from a PC character set. In PCTerm mode, the keyboard generates scan codes. There are no multi-character reports (escape sequences or paste data) sent from the terminal. The terminal can still send XPC as receive flow control.

When switching out of PCTerm mode, the XON/XOFF state of the communications link is unknown. If XON/XOFF flow control is enabled, then the terminal shall transmit a single XON and clear the XOFF received state.

#### 11.3.2 Protecting Data

Turning on Write-Protect mode does not start protecting the data. It only defines the range of data that needs to be protected. Not until Protect mode is turned on does the data become protected. Changing emulation does not change the Write-Protect mode. Characters range from 1/0 to 1/15, and embedded attributes are automatically write-protected even when Write-Protect mode is off.

To protect a certain area of data in the screen, users should:

- 1. Turn on Write-Protect mode.
- 2. Turn off Write-Protect mode, if the protected area has been defined.
- 3. Turn on Protect mode.

#### **ASCII Emulations and Control Functions** 11.3 Coding Notation

**Protect Mode On**: The protect condition usually is valid for the current page only. The exception is when Autopage mode is on, if a cursor movement command causes the cursor to move from one protected page to an unprotected page, the unprotected page becomes protected. If a cursor movement command causes the cursor to move from an unprotected page to a protected page, then the protected page becomes unprotected. Table 11–2 lists these commands.

Table 11-2 Commands that may Carry Protect Mode Features through Pages

Command	Sequence
Cursor left (backspace)	Ctrl/H
Cursor left (delete)	DEL
Cursor right	Ctrl/L
Cursor up; Scroll	ESC j
Cursor down; Scroll (linefeed)	Ctrl/J
Cursor to start of next line	Ctrl/_
Tabulate cursor	ESC i or Ctrl/I
Backtab	ESC I

- Turning on Protect mode enables Line Edit mode. The terminal ignores the command to enable Page Edit mode. Editing command activities are limited to the unprotected data. Any protected line can neither be inserted nor be deleted.
- No cursor movement commands can cause data, protected or unprotected, to scroll off the page.
- · The tabulation cursor becomes the field tab.
- Changing emulation turns off Protect mode, except when changing the terminal to a TVI emulation; in which case, the Protect mode does not change.
- Some cursor commands can move the cursor into the protected area, some cannot.

Table 11–3 lists the commands that can move the cursor to the protected area. Even if the cursor can be moved into the protected area by executing these commands, no data can be written into the area. The cursor jumps to the first unprotected position when data started writing into the screen.

Table 11–4 lists the commands that cannot move the cursor to the protected area. Any attempt to move the cursor to the protected area by executing these commands, moves the cursor up, down, left, or right into the first unprotected position.

#### **ASCII Emulations and Control Functions** 11.3 Coding Notation

Table 11-3 Commands that Can Move the Cursor to Protected Area

Move Cursor	Sequence
Up; scroll (reverse linefeed)	ESC j
Down; no scroll	Ctrl/V
To specific line	ESC [ line
To a specific column	ESC_column
In current page	ESC = line col
To a specific page	ESC h page
In specific 80-column page	ESC w @ page line col
In specific 80-column window	ESC - wnd/page line col
In 80/132-column current page	ESC a Il R ccc C

Table 11-4 Commands that Cannot Move Cursor into Protected Area

Move Cursor	Sequence	
Left (backspace)	Ctrl/H †	
Left (delete)	DEL	
Right	Ctrl/L	
Up; No scroll	Ctrl/K †‡	
Down; Scroll (linefeed)	Ctrl/J	
To start of line	Ctrl/M	
To start of next line	Ctrl/_	
Home	ESC { or Ctrl/^	

†The cursor can be moved to a protected field under certain conditions. Refer to the specific cursor command section for details.

‡Cursor can be moved to a protected field for TVI personalities.

## **ASCII Escape Sequences**

This chapter summarizes the ASCII escape and control Sequences that the VT520 recognizes when it is operating in its ASCII emulation modes.

### 12.1 ASCII Communications

Table 12-1 lists the serial port control functions for each mode. The word "same" in Table 12-1 signifies the same control sequence as the WYSE 325/160/60 column.

Table 12-1 Serial Port Control Functions

		WYS	BE			TVI			
ACK Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2	
ACK Mode On (default)	ESC e 7	n/a	same	same	EnH	EnH	EnH	EnH	
ACK Mode Off	ESC e 6	n/a	same	same	EnH	EnH	EnH	EnH	
Answerback Mode									
Answerback Off (default)	ESC e Sp	n/a		same	n/a	n/a	n/a	EnH	
Answerback On	ESC e!	n/a	same	same	n/a	n/a	n/a	n/a	
Answerback Message	ESC c; answ	<i>ver</i> Ctrl/Y							
		ESC] an.	<i>swer</i> Ctrl/M						
			same	same	n/a	n/a	n/a	EnH	
Send Answerback									
message – Format 1:	ESC c <	n/a	same	same	n/a	n/a	n/a	EnH	
Format 2:	Ctrl/E	same	same	same	same	same	same	EnH	
Conceal Answerback	ESC c =	n/a	same	same	n/a	n/a	n/a	EnH	
Assign Serial Ports									
S1=comm1 (host)	ESC e 8	n/a	same	same	EnH	EnH	EnH	EnH	
S1=comm2 (host)	ESC e 9	n/a	same	same	EnH	EnH	EnH	EnH	
Monitor Mode									
Monitor Mode Off (default)	ESC u or ESC X	same	same	same	same	same	same	EnH on or off	
Monitor Mode On	ESC U	same	same	same	same	same	same	EnH	

## ASCII Escape Sequences 12.1 ASCII Communications

Table 12–1 (Cont.) Serial Port Control Functions

Receive Null	·	WYS	SE .		-	TVI		ADDS
Character Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Ignore Null Characters from Host (default)	ESC e R	n/a	same	same	EnH	EnH	EnH	EnH
Accept Null Characters from Host	ESC e S	n/a	same	same	EnH	EnH	EnH	EnH
Set Serial Port Parameters	;							
Set Comm1 parameters	ESC c 0 Bau	ıd Stop Pari	ity Word		ESC { E	Baud Stop P	Parity Word	
		n/a	same	same		n/a	n/a	EnH
Set Comm2 parameters	ESC c 1 Baud Stop Parity		ity Word	y Word		Baud Stop P	Parity Word	
		n/a	same	same		n/a	n/a	EnH
	Baud (Comm1)		Baud (Comm2)			Descrip	tion	
	D		N/A			115200		
	В		N/A			76800		
	C		N/A		56700			
	0		@ (4/0)			38400		
	1		0 (3/0)			19200		
	2		1 (3/1)			9600		
	3		3 (3/3)			4800		
	4		5 (3/5)			2400		
	7		8 (3/8)			1200		
	8		9 (3/9)			600		
	9		: (3/10)			300		
	Stop		Descripti	on				
	0 (3/0)		1 Stop Bi	t (default)				
	1 (3/1)		2 Stop Bi	ts				
	Word		Descripti	on				
	0 (3/0)		7 bits					
	1 (3/1)		8 bits (default)					
	Parity		Description					
	0 (3/0)			(default)				
	1 (3/1)		Odd Pari	ty				
	2 (3/2)		Mark Par	9				
	3 (3/3)		Even Par	-				
	4 (3/4)		Space Pa	rity				

# **ASCII Escape Sequences** 12.1 **ASCII Communications**

Table 12-1 (Cont.) Serial Port Control Functions

	WYS	BE .			TVI		ADD
325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
ESC c 2 Hand	dshaking						
	n/a	same	same	n/a	n/a	n/a	EnH
ESC c 3 Hand	dshaking						
	n/a	same	same	n/a	n/a	n/a	EnH
ESC c 4 Hand	dshaking						
	n/a	same	same	n/a	n/a	n/a	EnH
ESC c 5 Hand	dshaking						
n/a		same	same	n/a	n/a	n/a	EnH
Handshaking		Receive F	low Contro	1	Transmit	Flow Contr	ol
0		None		_	None (def	fault)	_
1			FF/XPC (de	fault)	,	*	
2		DTR	_ (40	,	DSR		
<del></del>				d DTR		FF and DSR	2
n/a	Ctrl/N	n/a	n/a	Ctrl/N	Ctrl/N	Ctrl/N	n/a
n/a	Ctrl/O	n/a	n/a	Ctrl/O	Ctrl/O	Ctrl/O	n/a
ESC D F	ESC }	same	same	same	same	same	EnH
ESC D H	ESC {	same	same	same	same	same	EnH
ESC C	same	same	same	Wyse	Wyse	Wyse	EnH
ESC B	same	same	same	same	same or ESC c	same or ESC c	EnH
n/a	n/a	n/a	n/a	ESC c	n/a	n/a	n/a
te Limit							
ESC c 6 Max	n/a	same	same	n/a	n/a	n/a	EnH
ESC c 7 Max	n/a	same	same	n/a	n/a	n/a	EnH
Max				nd			
0		30					
1		50					
2			(default)				
3		No Limit (default) 150					
	ESC c 2 Hand ESC c 3 Hand ESC c 4 Hand ESC c 5 Hand Handshaking 0 1 2 3 n/a n/a  ESC D F ESC D H  ESC C ESC B	ESC c 2 Handshaking n/a ESC c 3 Handshaking n/a ESC c 4 Handshaking n/a ESC c 5 Handshaking n/a Handshaking 0 1 2 3 n/a Ctrl/N n/a Ctrl/O  ESC D F ESC D H ESC {  ESC D H ESC {  ESC C Same ESC B same  r/a n/a n/a n/a  te Limit  ESC c 6 Max n/a Max 0 1	ESC c 2 Handshaking n/a same ESC c 3 Handshaking n/a same ESC c 4 Handshaking n/a same ESC c 5 Handshaking n/a same  Handshaking 0 None 1 XON-XOI 2 DTR 3 XON-XOI n/a Ctrl/N n/a n/a Ctrl/O n/a  ESC D F ESC } same ESC D H ESC { same ESC D H ESC { same  ESC D H ESC } same  ESC C same same  CESC D H ESC { same  ESC C same same  ESC C same same  CESC D Same same  ESC C same same  ESC C same same  ESC C same same  ESC C same same  CESC D Same same  ESC C same same  ESC C Same same  ESC C Same same  ESC C Same same	SZS/160/60   PCTerm   150/120   50/50+	Sec   Period   Period   Solfo   Period   Perio	Sec   Sec	Secondaria

## 12.2 Terminal Management

Table 12–2 lists the terminal management control functions. The word "same" in Table 12–2 signifies the same control sequence as in the WYSE 325/160/60 column.

Table 12–2 Terminal Management Control Functions

Select Terminal		WYS	SE			ADDS			
Personality	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2	
ADDS VP A2	ESC ~ %	ESC v %	same as 325/160 /60	same	Wyse	Wyse	Wyse	Wyse	
TVI 950	ESC ~ (	ESC v (	same	same	Wyse	Wyse	Wyse	Wyse	
TVI 925	ESC ~ \$	ESC v \$	same	same	Wyse	Wyse	Wyse	Wyse	
TVI 910	ESC ~ #	ESC v #	same	same	Wyse	Wyse	Wyse	Wyse	
VT520, 7-bit	ESC ~ <	ESC v <	same	same	Wyse	Wyse	Wyse	Wyse	
VT520, 8-bit	ESC ~ =	ESC v =	same	same	Wyse	Wyse	Wyse	Wyse	
VT100	ESC ~;	ESC v;	same	same	Wyse	Wyse	Wyse	Wyse	
VT52	ESC ~ 6	ESC v 6	same	same	Wyse	Wyse	Wyse	Wyse	
WYSE 160/60	ESC ~ 4	ESC v 4	same	same	Wyse	Wyse	Wyse	Wyse	
WYSE 160/60 PCTerm	ESC ~ 5	ESC v 5	same	same	Wyse	Wyse	Wyse	Wyse	
WYSE 150/120	ESC ~ 4	ESC v 4	same	same	Wyse	Wyse	Wyse	Wyse	
WYSE 50+	ESC ~ "	ESC v "	same	same	Wyse	Wyse	Wyse	Wyse	
Send Terminal ID									
Inquire emulation ID	ESC Sp	n/a	same	same	ESC M	ESC M	ESC M	EnH	
	Emulation		Response		Respons	e in Colum	n/Row Form	at	
	WYSE 160/6	0	160			3/0 0/13)			
	WYSE 150/1	20	160		$(3/1 \ 3/6)$	3/0 0/13)			
	WYSE 50+		50		$(3/5 \ 3/0$	0/13)			
	ADDS VPA2		160		$(3/1 \ 3/6)$	3/0 0/13)			
	TVI 910+		925 REV I		(3/9 3/2 3/5 2/0 5/2 4/5 5/6 2/0 4/9 0/13				
	TVI 925		925 REV	I	(3/9 3/2 3/5 2/0 5/2 4/5 5/6 2/0 4/9 0/13				
	TVI 950		1.0		(3/1 2/14	1 3/0 2/0 0/1	3)		
Set Enhanced Mode									
Enhanced Mode On (default)	ESC ~!	ESC v!	same	same	Wyse	Wyse	Wyse	Wyse	
Enhanced Mode Off	ESC ~ Sp	ESC v Sp	same	same	Wyse	Wyse	Wyse	Wyse	
Save Set-Up Modes									
T- NV/M (	ESC c V	n/a	same	same	n/a	n/a	n/a	EnH	
To NVM (except Tabs)	LBC C V	12.00							

Table 12–2 (Cont.) Terminal Management Control Functions

		WYSE				TVI		
Select Terminal Defaults	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
PCTerm Mode Group <sup>1</sup>	n/a	ESC m	n/a	n/a	n/a	n/a	n/a	n/a
All Modes <sup>2</sup>	ESC c T	n/a	same	same	n/a	n/a	n/a	EnH
Power On Reset	ESC c X	n/a	same	same	n/a	n/a	n/a	EnH
Load/Send Time of Day								
Load Time of Day <sup>3</sup>	ESC c 8 Hr	Min						
		ESC Sp 1	a/p Hr M	in				
		•	same	same	ESC Sp	1 <i>a/p Hr M</i>	fin	EnH
Send Time of Day	n/a	ESC Sp 2	n/a	n/a	ESC Sp	ESC Sp	ESC Sp	n/a

 $<sup>^{1}\</sup>mbox{Sets}$  the following parameters for PCTerm mode:

## 12.3 Keyboard Processing

Table 12-3 lists the keyboard processing control functions. The word "same" in Table 12-3 signifies the same control sequences as in the WYSE 325/160/60 column.

Table 12-3 Keyboard Processing Control Functions

		WYSE				TVI			
Locking the Keyboard	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2	
Unlock keyboard (default)	Ctrl/N or ESC "	ESC "	same	same	ESC "	ESC "	ESC "	Ctrl/B ESC 6	
Lock keyboard	Ctrl/O or ESC #	ESC #	same	same	ESC #	ESC #	ESC #	Ctrl/D ESC 5	
Enable/Disable Key Repeat	:								
Key Repeat On (default) Key Repeat Off	ESC e - ESC e ,	n/a n/a	same same	same same	EnH EnH	EnH EnH	EnH EnH	EnH EnH	

<sup>•</sup> Autoscroll = On

<sup>•</sup> Received CR = CR

<sup>•</sup> Communication Mode = Full Duplex

<sup>•</sup> Enhanced Mode = Off

<sup>•</sup> Wrap EOL = Off

<sup>•</sup> Attribute = Char

<sup>&</sup>lt;sup>2</sup>Sets the parameters shown in Table 11-2.

 $<sup>^3</sup>$  Hour ranges from 00 to 23; Minute ranges from 00 to 59 decimal. Entering "00" in hour is displayed as 12 AM. The a/p is a single character—a = AM, p = PM.

## ASCII Escape Sequences 12.3 Keyboard Processing

Table 12–3 (Cont.) Keyboard Processing Control Functions

		WYS	SE .			TVI		ADDS
Caps Lock	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Caps Lock off	ESC e ´	ESC Sp M	same	same	EnH	EnH	EnH	EnH
Caps Lock on	ESC e &	ESC Sp L	same	same	EnH	EnH	EnH	EnH
Lock key=Caps Lock (default)	ESC e T	n/a	same	same	EnH	EnH	EnH	EnH
Lock key=Shift Lock	ESC e V	n/a	same	same	EnH	EnH	EnH	EnH
Lock key=Reverse Lock	ESC e U	n/a	same	same	EnH	EnH	EnH	EnH
Num Lock								
Num Lock off	ESC e @	ESC Sp K	same	same	EnH	EnH	EnH	EnH
Num Lock on	ESC e A	ESC Sp J	same	same	EnH	EnH	EnH	EnH
Scroll Lock								
Scroll Lock off	ESC e B	ESC Sp	same	same	EnH	EnH	EnH	EnH
Scroll Lock on	ESC e C	ESC Sp N	same	same	EnH	EnH	EnH	EnH
Keycode Mode								
ASCII Key Codes <sup>1</sup>	ESC e H	ESC c	same	same	EnH	EnH	EnH	EnH
PC Scan Codes	ESC e I	ESC H	same	same	EnH	EnH	EnH	EnH
Request Modifier Keys St	atus							
Inquiry	n/a		n/a 1(Hex) + <i>a</i> ndicates the	n/a e modifier l	n/a kev being r	n/a pressed as fo	n/a ollows:	n/a
		Bit 0 1 2 3 4	Modifier 1 Caps lock Always 0 Always 0 Scroll lock	<u>Key</u>				
		5 6 7	Ctrl Num lock Shift key	On				
		WYS	SE			TVI		ADDS
Margin Bell	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2

<sup>&</sup>lt;sup>1</sup>Default for all but PCTerm mode.

Table 12–3 (Cont.) Keyboard Processing Control Functions

		WYS	E		TVI			ADDS
Margin Bell	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Sound Bell	Ctrl/G	same	same	same	same	same	same	same
Select Bell tone	ESC c \ <i>Tone</i>	n/a	same	Wyse	n/a	n/a	n/a	EnH
	<u>Tone</u>	Description	<u>n</u>					
	0	Off						
	1	Low pitch						
	2	High pitch						
	3	High pitch	1					
Margin Bell off (default)	ESC e L	ESC n	same	same	EnH	EnH	EnH	EnH
Margin Bell on <sup>2</sup>	ESC e M	ESC o	same	same	EnH	EnH	EnH	EnH
Set Margin Bell at cursor	ESC ` J	n/a	same	same	n/a	n/a	n/a	EnH
Set Margin Bell on and set position	n/a	ESC o	n/a	n/a	n/a	n/a	n/a	n/a
Keyclick								
On (default)	ESC e %	ESC >	same	same	ESC >	ESC >	ESC >	EnH
Off	ESC e \$	ESC <	same	same	ESC <	ESC <	ESC <	EnH
		E			TVI		ADDS	
Redefining Keys <sup>3</sup>	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Program Function keys <sup>4</sup>	ESC z Fkey S	eq DEL						
		n/a	same	same	Wyse	Wyse	Wyse	EnH
	Fkey Unshifte	<u>ed</u>	Fkey Shif	ted VT Ke		Enhance	d PC Keybo	oard
	@		`		F1			
	A		a		F2			
	В		b		F3			
	С		С		F4			
	D		d		F5			
	E		e	F6		F6		
	F		f	F7		F7		
	G		g	F8		F8		
	H		h	F9		F9		
	I		i	F10		F10		
	J		j 1-	F11		F11		
	K		k 1	F12		F12		
	L		1	F13				
	M		m	F14				
	N O		n	F15 F16				
			0					

<sup>&</sup>lt;sup>2</sup>Default = 72 for 80-column mode; 124 for 132-column mode.

<sup>&</sup>lt;sup>3</sup>See Table 12–4 for redefinable keys.

 $<sup>^4</sup>$  Seq is an ASCII character data string sequence. Any 7-bit character except "DEL" (Hex 7F) is legal for the sequence.

## ASCII Escape Sequences 12.3 Keyboard Processing

Table 12–3 (Cont.) Keyboard Processing Control Functions

	-	WYS	SE			TVI		
Program Key Direction	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
		WYS	SE			TVI		ADDS
Program Key Direction	325/160/60	PCTerm	150/120	50/50+	+ 950 925 910		910+	A2
Program Key Direction	ESC Z <i>Dir K</i>	Tey Seq DEL	same	same		Wyse	Wyse	EnH
		ESC   F	Key Dir See	7 Ctrl-Y	ESC	FKey Dir S	eq Ctrl-Y	
<b>Key-Sent direction</b>	ection Communication Mode				finition is	Sent to		
<b>J</b>	Local			•	l screen or			
	Remote			Host onl		J		
	Normal			Dependi	ng on Com	ım mode:		
	Full-dupl	lex		Host	_			
	Half-dup				9	and the term	inal screen	
	Block			Term	inal scree	n only		
	Half Bloo	ck				and the term	inal screen	
	Dir	Key Tran	smission Di	rection				
	0	Normal	-					
	1	Remote (d	default)					
	2	Local	•					
	3	Normal (T	TVI950 and only)	WYSE 32	5/160/60			

	WYSE				TVI			ADDS
Inquire Key Direction	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Inquiry:	ESC Z ~ Key	n/a	same	same	n/a	Wyse	Wyse	EnH
Response:	Dir Key Sequence DEL							
Clear Key Definitions								
Clear Function key direction and definition	ESC z Fkey I	DEL n/a	same	same	Wyse	Wyse	Wyse	EnH
Set key direction and Clear key definition	ESC Z Dir Ke	ey DEL						
	EGG II	n/a	same	same	n/a	Wyse	Wyse	EnH
Clear all redefinable key definitions	ESC c U	n/a	same	same	n/a	n/a	n/a	EnH

Table 12–4 lists the redefinable keys.

Table 12-4 Redefinable Keys

Emulation	Redefinable	Keys		
WYSE 325/160/60, WYSE 150/120, WYSE 50+, TVI925, and TVI 910	<u>Unshifted</u>	Shifted	VT Keyboard	EPC Keyboard
•	SP	%		ESC
	!	&	Tab	Tab
	"	•	Backspace	Backspace
	#	(	Remove	
	\$	)	Return	Enter
	*	/	Select	Home
	+	0	<u> </u>	<u> </u>
	,	1	<u> </u>	<u> </u>
	-	2	<u>←</u> ⇒	<u></u>
		3 4	⇒ Enter	⇒j Enter (keypad)
	S	p	PF4	Insert
	q r	W W	117	Page Down
	}	z	PF3	r ago zomi
	5	6	PF2	Delete
	7	8	PF1	
	R	X		Print Screen
	:	;		Page Up
	\	]		End
	Q	W	F17	
	S T	Y Z	F18	
	P	V V	F19 F20	
	1	V	1 20	
WYSE 325/160/60	Fkey Unshi	fted	VT Keyboard	EPC Keyboard
PCTerm	1	!	F1	F1
	2	: @	F2	F2
	3	#	F3	F3
	4	\$	F4	F4
	5	%	F5	F5
	6	^	F6	F6 F7
	7	&	F7	
	8	*	F8	F8
	9 0	(	F9 F10	F9 F10

## ASCII Escape Sequences 12.3 Keyboard Processing

Table 12-4 (Cont.) Redefinable Keys

Emulation	Redefinab	Redefinable Keys								
TVI 950	Fkey	Fkey	VT Keyboard	Enhanced PC Keyboard						
	1	<	F1	F1						
	2	=	F2	F2						
	3	>	F3	F3						
	4	?	F4	F4						
	5	@	F5	F5						
	6	Α	F6	F6						
	7	В	F7	F7						
	8	C	F8	F8						
	9	D	F9	F9						
	:	E	F10	F10						
	;	F	F11	F11						
	G	L	F12	F12						
	Н	M	F13							
	I	N	F14							
	J	O	F15							
	K	P	F16							

## 12.4 Screen Processing

Table 12–5 lists the screen processing control functions. The word "same" in this table signifies the same control sequences as in the WYSE 325/160/60 column.

Table 12–5 Screen Processing Control Functions

		WYS	E			TVI		ADDS
Video Display Features	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Border Display (Overscan On/Off)	ESC c ] Inter	nsity						
		n/a	same	same	n/a	n/a	n/a	EnH
Parameters:	Intensity 0	Overscan Off (defau	ılt)					
	1	On						
Screen Display On (default)	ESC`9	ESC N	same	same	ESC n	ESC n	ESC n	EnH
Screen Display Off	ESC`8	ESC O	same	same	ESC o	ESC o	ESC o	EnH
Normal background <sup>1</sup>	ESC ^ 0	ESC d	same	same	ESC d	ESC d	ESC d	EnH
Reverse background	ESC ^ 1	ESC b	same	same	ESC b	ESC b	ESC b	EnH
Screen Saver on (default)	ESC e Q	n/a	same	same	EnH	EnH	EnH	EnH
Screen Saver off	ESC e P	n/a	same	same	EnH	EnH	EnH	EnH

<sup>\*</sup>Assigning parameters "6," "7" or "A" clears previously defined write-protected attributes. "B" through "G" add on top of previous attribute(s) and display a combination of new and old display attributes.

Table 12–5 (Cont.) Screen Processing Control Functions

		WYS	SE			TVI		ADDS
Scroll Type	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
WYSE Mode	ESC ` Scroll	n/a	same	same	n/a	n/a	n/a	EnH
Parameters:	<u>Scroll</u> @ <, = >, ?	Slow Smo	Type <sup>2</sup> roll (default) ooth Scroll ooth Scroll					
TVI - Smooth scroll off TVI - Smooth scroll on	n/a n/a	n/a n/a	n/a n/a	n/a n/a	ESC 9 ESC 8	ESC 9 ESC 8	ESC 9 ESC 8	n/a n/a
Character Cell								
Select $10 \times 16$ size (def) Select $10 \times 13$ size	ESC e > ESC e ?	n/a n/a	same same	Wyse Wyse	EnH EnH	EnH EnH	EnH EnH	EnH EnH
Column Display								
Select 80-column display (default)	ESC `:	n/a	same	same	n/a	n/a	n/a	EnH
Select 132-column display	ESC`;	n/a	same	same	n/a	n/a	n/a	EnH
Display Data Lines								
24 data lines (default) 25 data lines	ESC e ( ESC e )	n/a ESC ^	same same as 325/160	same same as 325/160	EnH EnH	EnH EnH	EnH EnH	EnH EnH
42 data lines	ESC e *	n/a	/60 same	/60 same	EnH	EnH	EnH	EnH
43 data lines	ESC e +	ESC _	same as 325/160 /60	same as 325/160 /60	EnH	EnH	EnH	EnH
	In ASCII emu	ulation mod	de, the VT52	20 displays	four types	of data line	es:	
	<ul><li>25 data</li><li>42 data</li></ul>	a lines, 1 st a lines, 1 st	tatus line, a tatus line, a tatus line, a tatus line, a	nd 1 label l nd 2 label l	ine ines <sup>4</sup>			

 $<sup>^2</sup>$  Users can change the scrolling rate by entering keys from the keyboard. Pressing  $\boxed{\text{Ctrl/Shift/} \uparrow}$  to increase the rate and Ctrl/Shift/ 

to decrease it.

<sup>&</sup>lt;sup>4</sup>Because of hardware limitations, selecting 42 or 43 data lines forces the screen size to be 53 lines.

#### ASCII Escape Sequences 12.4 Screen Processing

Table 12–5 (Cont.) Screen Processing Control Functions

Fill Page with "H"s	÷	TVI			ADDS			
in PCTerm Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Fill page with "H"s	n/a	ESC F	n/a	n/a	n/a	n/a	n/a	n/a
Width-Change-Clear Mode								
Width-change-clear off	ESC e .	n/a	same	same	EnH	EnH	EnH	EnH
Width-change-clear on (default)	ESC e /	n/a	same	same	EnH	EnH	EnH	EnH
Page Size								
Set Page Size <sup>5</sup>	ESC w Lengt	ESC \ <i>Length</i> <sup>6</sup>			e ESC \ <i>Length</i> <sup>6</sup>			EnH
WYSE 325/160/60, WYSE 50+ Parameters:	Length	Size of a	Page	Description				
	G	1*lines		Page nui	mber = curi	ent screen	data lines	
	Н	2*lines		Page nui	mber = curi	ent screen	data lines *	2
	I	4*lines		Page nui	mber = curi	ent screen	data lines *	4
	J	*		One page number = screen data lines; the contains rest of lines in memory.				
WYSE 325/160/60 PCTerm and TVI	Length	Size of a	Page	Descript		o m memor,	<i>,</i> .	
Parameters:	1	1*lines		Page nui	mber = curi	ent screen	data lines	
	2	2*lines		Page nui	mber = curi	ent screen	data lines *	2
	3	4*lines		Page nui	mber = curi	ent screen	data lines *	4
	4	*		One page number = screen data lines; the oth contains rest of lines in memory.				
Display Page								
Display Previous Page <sup>7</sup>	ESC w B or ESC J	n/a	same	same	ESC J	ESC J	ESC J	EnH
Display Next Page <sup>8</sup>	ESC w C or ESC K	n/a	same	same	ESC K	ESC K	ESC K	n/a
Display Specific Page	ESC w Page	n/a	same	same	n/a	n/a	n/a	EnH

 $<sup>^{5}</sup>$  Upon receipt of the Set Page Size command, the terminal:

- Clears the display memory to NUL (0/0) characters.
  Displays first page "page 0."
  Moves the cursor to its home position.

- Changes the split screen to a full screen format.
   Turns off the Protect mode.
- Unlocks the locked line.

<sup>&</sup>lt;sup>6</sup>Enhanced Mode off.

<sup>&</sup>lt;sup>7</sup> In WYSE mode, command "ESC J" works only when the screen is not split. If the screen is split, refer to "Activate Other Window or Page" command. Command "ESC w B" in WYSE modes works when the screen is not split or the split screen is caused by an adjustable split. It does not work when the split screen is a result of a simple split. Users can use local function keys to display the previous page. On a VT keyboard, press Ctrl/Prev; on an Enhanced PC keyboard, press Ctrl/Page Up

<sup>&</sup>lt;sup>8</sup> Users can use a local function key to display the next page. Press Ctrl/N, where N is a number on the numeric keypad key equivalent to the page number, on both VT and Enhanced PC keyboard.

Table 12-5 (Cont.) Screen Processing Control Functions

		WYS	SE .			TVI		ADDS
Split Screen	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Split screen horizontally	ESC x A Line	n/a	same	same	n/a	n/a	n/a	n/a
Adjustable horiz split	ESC x C Line	n/a	same	same	n/a	n/a	n/a	n/a
Split screen horizontally and Clear data	ESC x 1 Line	n/a	same	same	n/a	n/a	n/a	n/a
Adjustable horiz split screen and Clear data	ESC x 3 Line	n/a	same	same	n/a	n/a	n/a	n/a
Lower horiz split	ESC x P	n/a	same	same	n/a	n/a	n/a	n/a
Raise horiz split	ESC x R	n/a	same	same	n/a	n/a	n/a	n/a
Windows								
Activate upper window	ESC ]	n/a	same	same	n/a	n/a	n/a	n/a
Activate lower window	ESC }	n/a	same	same	n/a	n/a	n/a	n/a
Activate other window or page	ESC J or ESC K	n/a	same	same	n/a	n/a	n/a	n/a
Roll window up in page	ESC w E	n/a	same	same	n/a	n/a	n/a	n/a
Roll window down in page	ESC w F	n/a	same	same	n/a	n/a	n/a	n/a
Redefine screen as one window	ESC x @	n/a	same	same	n/a	n/a	n/a	n/a
Redefine screen as one window and Clear page	ESC x 0	n/a	same	same	n/a	n/a	n/a	n/a
Cursor Drag Mode								
Cursor drag mode on (default)	ESC d)	n/a	same	same	n/a	n/a	n/a	n/a
Cursor drag mode off	ESC d (	n/a	same	same	n/a	n/a	n/a	n/a
Status Line Display								
Editing Status line on	ESC`a	n/a	same	same	n/a	n/a	n/a	EnH
Standard Status line on (default)	ESC`b	n/a	same	same	n/a	n/a	n/a	EnH
Status line off	ESC ` c	n/a	same	same	n/a	n/a	n/a	EnH
	Starts at Colu	mn	Standard	Status Lin	e	Editing	Status Line	•
	26		HH:MM	AM (or PM)	<u></u>	PROT (	Protect mod	e is on)
	31					WRPT	(Write prote	ct is on)
	35		Column-F	Row (Curson	r)			
	36					INS (In	sert mode is	on)
Messages:	Message		Description	_		•		ŕ
	LOCK		Keyboard					
	COMP			se process				
	NUM		NUM LO					
	CAPS			s Lock key				
	1		Page indi	cation (No	message d	isplayed for	r page 0)	
	*		Monitor r	node state				
	FDX		Full-dupl	ex mode				

# ASCII Escape Sequences 12.4 Screen Processing

Table 12-5 (Cont.) Screen Processing Control Functions

` ,		•						
Status Line Display								
	BLK		Block mo	de				
	HBLK			lex block mo	ode			
Messages:	Message		Descripti	on				
•	LCL		Local mo	de				
	HLD		Hold stat	e				
	%		Page Pri	nting				
	>		Autoprin	t mode				
	=		Controlle	r print mod	e			
	PBSY		Printer is	s busy or no	printer is	attached.		
	PTR		Printer is					
	<aux< td=""><td></td><td>Terminal</td><td>is in auxilia</td><td>ary receive</td><td>mode.</td><td></td><td></td></aux<>		Terminal	is in auxilia	ary receive	mode.		
		WYS	E			TVI		ADDS
Computer Message	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Program/Display	ESC F Mess	age CR						
computer message		n/a	same	same	Wyse	Wyse	Wyse	EnH
Clear computer message	ESC F CR	n/a	same	same	same	same	same	EnH
Function Key Label Displa	ıy							
Display F key label	ESC z Field							
a	T00 T11	n/a	same	same	Wyse <sup>9</sup>	Wyse	Wyse	EnH
Clear F key label	ESC z <i>Field</i>							
TI 11 D		n/a	same	same	Wyse	Wyse	Wyse	EnH
Field Parameters:	17	II	Field	Cl.: (A. J	17	I I1. : 0 1	Field	Cl.:G. J
	Key F1	Unshifted 0		Shifted P	Key F9	Unshifted 8		Shifted X
	F1 F2	1			F10	9		Y Y
	F3	2		Q R	F10 F11			Z
	F4	3		S	F12	•		[
	F5	4		T	F12 F13	, <		1 \
	F6	5		U	F14	=		1
	F7	6		V	F15	>		V 1
	F8	7		W	F16	?		
Label Parameters:	Emulation M	-	Column I			m Length		_
	Hidden	1000	80	· roue	9	in Zengen		
	Hidden		132		7			
	Embedded		80		8			
	Embedded		132		7			
		WYS	E			TVI		ADDS
Label Line Display	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Program/Display	ESC z ( Text	CR	same	same as	ESC f te			EnH
computer message on unshifted Label line.		ESC f text ESC f text		325/160 /60	ESC f te	xt Ctrl-M		
Program/Display	ESC z ) text							
computer message on		n/a	same	same	n/a	n/a	n/a	EnH

<sup>&</sup>lt;sup>9</sup>Unshifted key label only; the Shifted Key label is not available for TVI modes.

Table 12–5 (Cont.) Screen Processing Control Functions

	WYSE					TVI			
Label Line Display	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2	
shifted Label line. Clear unshifted Label line.	ESC z ( CR	ESC f CR or ESC f		same as 325/160 /60	ESC f (			EnH	
Clear shifted Label line. Disable shifted Label line.	ESC z ) CR ESC z DEL	n/a n/a	same same	same same	n/a n/a	n/a n/a	n/a n/a	EnH EnH	

#### **WYSE and ADDS Enhanced Modes:**

There are two distinct label lines when the terminal is using 24 or 42 data lines:

- The upper one is for shifted label line (shifted function key label line).
- The lower one is for unshifted label line (unshifted function key label line).

When using the 25 or 43 data line configuration mode, only one label line is available at a time. By default, it displays the unshifted label line (or unshifted function key label line). This line becomes a shifted label line (or shifted function key label) whenever the Shift key is pressed. Releasing the Shift key returns the line to be the unshifted display line.

#### TVI and PCTerm Modes:

Only an unshifted label line (unshifted function label line) is available. To be visible, the label line must be explicitly turned on by the command "Turn on User Line."

For TVI personalities, the label line is displayed only when data line is set to 24 or 42 data lines.

For PCTerm mode, turning on the display line forces the terminal to 24 or 42 data lines. If the cursor is at the 25th or 43rd line before the line is set, then the cursor moves to the same column at line 24 or 42, and the entire data area scrolls up one line. The label line is displayed at the 25th or 43rd line, respectively.

#### Text Parameter:

The parameter *text* is a character string to be entered in the label line. The allowable size of *text* varies among emulation modes and column modes. In embedded emulation mode, the first character shown on the user line is an attribute space

the first character shown on the user line is an attribute space.										
<b>Emulation Mode</b>	Column Mode	Maximum Number	Column Position							
Hidden	80	80	1—80							
Hidden	132	132	1—132							
Embedded	80	79	2—80							
Embedded	132	131	2—132							

## ASCII Escape Sequences 12.4 Screen Processing

Table 12–5 (Cont.) Screen Processing Control Functions

	WYSE						TVI	
Color	325	160/60	PCTerm	150/120	50+/50	925	910+	VP A2
Select ASCII Color Mode	ESC d z Ctrl/B	same	ESC Sp # Ctrl/B	same	same	same	same	EnH
Select Mono Mode	ESC d z Ctrl/C	same	ESC Sp # Ctrl/C	same	same	same	same	EnH
Select Color Palette	ESC d z Palette	same	ESC Sp # <i>Palette</i>	same	EnH	EnH	EnH	EnH
	## <i>Palette</i> nun	nbers run f	rom 0 to 9 a	and . kpd.				
Customize Color Palette	ESC d y F-Co	olor B-Color	Attribute			EnH	EnH	EnH
			ESC Sp #	F-Color B-	Color Attrib	ute		
Parameters:	$\frac{F - or B - Color}{1} \frac{\text{Description}}{\text{Black}} \frac{Attrib}{1}$				Attribute	Description Normal		
	2	Blue			2	Reverse/Blank		
	3	Green			3	Dim		
	4	Cyan			4	Dim, Reverse/Blank		
	5	Red			5	Underline		
	6	Magenta			6	Underline, Reverse/Blank		
	7	Yellow			7	Underline, Dim		
	8	White			8	Underline, Dim, Reverse /Blank		
Enable/Disable Intensity At	tribute							
Dim intensity attribute On (default)	ESC e }	same	ESC SP	same	n/a	n/a	n/a	n/a
Dim intensity attribute Off	ESC e	same	ESC SP	same	n/a	n/a	n/a	n/a
Reverse and Blank Attribut	te							
Map the Reverse attribute (default)	ESC d	same	ESC SP &	same	n/a	n/a	n/a	n/a
Map the Blank attribute	ESC d {	same	ESC SP %	same	n/a	n/a	n/a	n/a

Table 12-5 (Cont.) Screen Processing Control Functions

User Label Line Display for TVI Mode			ADDS					
	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Turn off User line	n/a	ESC e or						
(default)		ESC h	same	n/a	ESC h	ESC h	ESC h	n/a
Turn on User line	n/a	ESC g	n/a	n/a	ESC g	ESC g	ESC g	n/a
Character Attributes								
Assign character attribute (main display area)	ESC G Attr	ESC G Attribute	same	same	same	same	same	EnH
Parameters:								
Wyse 325, 10 160/60, 150 /120, 50+, and ADDS	<u>Attr</u>	Display Attributes						
	SP	Space character						
	0	Normal	0, p					
	1	Invisible <sup>10</sup>					1, q	
	2	Blink	2, r					
	3	Invisible and blink						
	4	Reverse						
	5	Reverse and invisible					5, u	
	6	Reverse and blink						
	7	Reverse, blink, invisible						
	8	Underline 8 Underline and invisible 9						
	9	Underline and invisible						
	:	Underline and blink						
	;	Underline, blink, invisible						
	<	Underline and reverse						
	=	Underline, reverse, invisible Underline, reverse, blink					=, }	
	> ?						>, ~ ?, DEL	
		Dim						
	p q	Dim and invisible						
	r	Dim and blink						
	s	Dim, blink, invisible						
	t	Dim and reverse						
	u	Dim, reverse, invisible						
	$\mathbf{v}$	Dim, reverse, blink						
	w	Dim, reverse, blink, invisible						
	x	Dim and underline						
	y	Dim, underline, invisible						
	z	Dim, underline, blink						
	{	Dim, underline, blink, invisible						
		Dim, underline, reverse						
	}			rse, invisib	le			
	~		erline, reve					
	DEL	Dim, underline, reverse, blink, invisible						

 $<sup>\</sup>dagger$  All the 7-bit ASCII codes are legal in this sequence. Example: "A" turns on the dim attribute, "T" turns on the reverse attribute, "S" turns on dim, blink and reverse attributes.

#### ASCII Escape Sequences 12.4 Screen Processing

Table 12–5 (Cont.) Screen Processing Control Functions

PCTerm Mode	Attribute		Display Attributes								
	0, @, P, `, p			Normal							
	1, A, Q, a, q			Invisible							
	2, B, R, b, r		Blink Invisible and blink								
	3, C, S, c, s										
	4, D, T, d, t		Reverse								
	5, E, U, e, u		Reverse and invisible								
	6, F, V, f, v		Reverse and blink Reverse, blink, invisible Underline								
	7, G, W, g, w	7									
	8, H, X, h, x										
	9, I, Y, i, y :, J, Z, j, z			Underline and invisible							
				Underline and blink							
	;, K, [, k, {	v		Underline, blink, invisible							
	<, L \ , l,   =, M, ], } >, N, ^, n, ~		Underline and reverse Underline, reverse, invisible Underline, reverse, blink								
	?, O, _, o, DEL		Underline, reverse, blink, invisible								
Selecting		WYS	SE		TVI			ADDS			
Display Attribute Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2			
Char attribute mode on <sup>11</sup>	ESC e 1	n/a	same	n/a	n/a	n/a	n/a	n/a			
Char attribute mode off	ESC e 0	n/a	same	n/a	n/a	n/a	n/a	n/a			
Page attribute mode on 12	ESC e 2	n/a	same	same	EnH	EnH	EnH	EnH			
Line attribute mode on	ESC e 3	n/a	same	same	EnH	EnH	EnH	EnH			
Assign display attribute	ESC A Area	Attr									
to a message field		n/a same same			ESC \	EnH					
Parameters:	Area		Descripti			(_	,				
	0		Data Area								
	1		Label Line								
	2				ald on Sta	tus I ina					
	3		Terminal message Computer messag								
	3		Compute	i message i	neiu on sia	itus Eme					
Assign write-protect character attribute	ESC ` Wpca	n/a	same	same	n/a	n/a	n/a	EnH or ESC 0 Spca			
Parameters using WYSE sequences:*	<u>Wpca</u>	Description	Description		ters - 10de†	Spca	Description				
wide sequences.	6	Reverse				0	Dim				
	7	Dim (defa	ault)			1	Blink				
	A	Normal				2	Invisible				
	В	Blink			3	Normal					
	C	Invisible			4	Reverse					
	E		Underline			5	Underlin	A			
	F		Reverse			J	Chachill	·			
	G	Dim									
	u	Dilil									

<sup>\*</sup>Assigning parameters "6," "7" or "A" clears previously defined write-protected attributes. "B" through "G" add on top of previous attribute(s) and display a combination of new and old display attributes.

 $<sup>\</sup>dagger$  All the 7-bit ASCII codes are legal in this sequence. Example: "A" turns on the dim attribute, "T" turns on the reverse attribute, "S" turns on dim, blink and reverse attributes.

<sup>‡</sup> Example: Dim + Reverse + Invisible reports VTS (8AH) + a.

 $<sup>^{\</sup>rm 12} Default$  for embedded emulation.

Table 12-5 (Cont.) Screen Processing Control Functions

Selecting		WYS	Ε			TVI		ADDS
Display Attribute Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Clear unprotected page to display attribute	n/a	n/a	n/a	ESC! Attr	n/a	Wyse	Wyse	EnH
Request attribute under cursor	n/a	ESC D	n/a	n/a	n/a	n/a	n/a	n/a
Response:‡	Two bytes—	the Bit for a	ttribute un	der the curso	r, then "a".			
	<u>Bit</u>	Attribute		Bit	Attribute			
	0	Underline	<b>)</b>	4	Always 0			
	1	Reverse		5	Always 0			
	2	Blink		6	Always 0			
	3	Invisible		7	Dim			
Assign Line Attributes								
Assign line attributes	ESC G LineAttr	n/a	same	same	n/a	n/a	n/a	EnH
Parameters:	LineAttr		Line Attr	ibute				
	@		Single he	ight, single v	vidth (defa	ult)		
	A		Single he	ight, double	width			
	В		Top-half	of double heigh	ght, single	width		
	C		Bottom-h	alf of double	height, sin	gle width		
	D		Top-half	of double heig	ght, double	width		
	E			alf of double				
1.5.								

### ASCII Escape Sequences 12.4 Screen Processing

Table 12–6 lists the data protection control functions. The word "same" in Table 12–6 signifies the same control sequences as in the WYSE 325/160/60 column.

Table 12-6 Data Protection Control Functions

		WYSE				TVI			
Write-Protect Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2	
Write-protect mode off (default)	ESC (	same	same	same	same	same	same	EnH or Ctrl/O	
Write-protect mode on <sup>1</sup>	ESC)	same	same	same	same	same	same	EnH or Ctrl/N	
Protect Mode									
Protect mode off (default) Protect mode on	ESC ′ ESC &	same same	same same	same same	same same	same same	same Wyse	EnH EnH	

Turning on Write-Protect mode does not start protecting the data. It only defines the range of data that needs to be protected. Not until Protect mode is turned on does the data become protected. Changing personality does not change the Write-Protect mode. Graphic characters range from 1/0 to 1/15, and embedded attributes are automatically write-protected even when Write-Protect mode is off.

Table 12–7 lists the cursor control functions. The word "same" in Table 12–7 signifies the same control sequences as in the WYSE 325/160/60 column.

Table 12-7 Cursor Control Functions

		WYS	SE .			TVI		ADDS
Autopage Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
On	ESC d +	n/a	same	same	ESC v	ESC v	ESC v	EnH
Off (default)	ESC d *	n/a	same	same	ESC w	ESC w	ESC w	EnH
Autoscrolling Mode								
On (default)	ESC O	n/a	same	same	n/a	n/a	n/a	EnH
Off	ESC N	n/a	same	same	n/a	n/a	n/a	EnH
Cursor Display Feature								
Set cursor appearance	ESC ` Cursor	ESC . Cursor	same as 325/160 /60	same as 325/160 /60	ESC . Cu	ırsor		EnH <sup>1</sup>
Parameters:	Cursor	Description						
	0		isplay Off					
	1	Cursor D						
	2		ock Cursor					
	3	Blinking	Line Cursoi	•				
	4	Steady Li	ne Cursor					
	5	Blinking	Block Curso	or				
End-of-Line Wrap Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
On (default)	ESC d/	ESC ~	same as 325/160 /60	same as 325/160 /60	n/a	n/a	n/a	EnH
Off	ESC d.	ESC 0	same as 325/160 /60	same as 325/160 /60	n/a	n/a	n/a	EnH
	When the cu page with w							
	Autopage	Autoscrol	<u>l</u>	Page Mod	<u>le</u>	Cursor N	Moves to	_
	On	-		Single		Home population page.	sition of the	e active
				Multiple		Home population page.	sition of the	e next
	Off	On		Multiple			gin of botto croll is perfo	
	Off	Off		Multiple		Home popage.	sition of the	e active

<sup>1 |</sup> Ctr|/W | = Cursor off; | Ctr|/X | = Cursor on.

### **ASCII Escape Sequences** 12.4 Screen Processing

Table 12-7 (Cont.) Cursor Control Functions

		WYS	E			TVI		ADDS
Received CR Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
CR (default)	ESC e 4	ESC 9	same as 325/160 /60	same as 325/160 /60	EnH	EnH	EnH	EnH
CRLF	ESC e 5	ESC 8	EnH	same as 325/160 /60	EnH	EnH	EnH	EnH
Lock Cursor Line Mode								
On	ESC ` H	n/a	same	same	ESC!1	n/a	n/a	EnH
Off (default)	ESC`I	n/a	same	same	ESC! 2	n/a	n/a	EnH
Recognize DEL Mode								
On (default)	ESC e E	EnH	same	same	EnH	EnH	EnH	EnH
Off	ESC e D	EnH	same	same	EnH	EnH	EnH	EnH
Cursor Movement								
Cursor Left (Back Space)	Ctrl/H	same	same	same	same	same	same	Wyse or Ctrl/U
	Autopage	Page Mode	e	Cursor M	oves to	_		
	On	Multiple		even thou Under th	igh the bott is command	om right i l, the Prot	eceding page margin is pr ect mode fe er to Protect	rotected. ature
	Off	Single			ght margin margin is p		ive page eve	en though
Cursor Left (Delete)	DEL	same	same	same	same	same	same	same
Cursor Right	Ctrl/L	same	same	same	same	same	same	Ctrl/F
	Autopage	Autoscroll	Page	Cursor M	oves to			
	On	-	Multiple	Protect m this comm	node is on) on mand, the P	of the next Protect mo	rotected pos page (if and de feature co otect mode fo	y). Under arries
	Off	On	Single <sup>2</sup>	_	gin of the bo		gin line afte	
	Off	Off	Single <sup>3</sup>	Home pos	sition of the	active pa	ge.	

 $<sup>^2</sup>$ Autopage mode is either set to off, or the terminal is in Single Page mode and Autoscroll mode is on.

 $<sup>^3</sup>$ Autopage mode is either set to off, or the terminal is in Single Page mode and Autoscroll mode is off.

Table 12-7 (Cont.) Cursor Control Functions

		WYS	E			TVI		ADDS
Cursor Up	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Cursor Up—No Scroll Cursor Up—Scroll (Payerse Linefeed)	Ctrl/K ESC j	same same	same same	same same	same same	same same	same Wyse	Ctrl/Z EnH
(Reverse Linefeed)	This comma Autopage	nd moves the Autoscroll	Page Single	ollows: Protect	Cursor 1 (Comma	ed.)		
	On	-	Multiple	On or Off	this com	line of the p mand, the l through all j	Protect mod	
	Off	On	Multiple	Off	Top mar	gin of the a scroll is per	ctive page	after a
	Off Off	On Off	Multiple Multiple	On -		and is ignore and is ignore	_ :	
Cursor Down								
Cursor Down—No Scroll	Ctrl/V	same	same	same	same	same	same	same
Cursor Down—Scroll (Linefeed)	Ctrl/J	same	same	same	same	same	same	same
	Autopage Off	Autoscroll Off	Page Mode	2	Top man	Moves to rgin line of tination posinoves right	the active p	ected, the
	On	-	Single		the dest	gin line of tination posi noves right cted position	tion is prot or down to	ected, the
	On	-	Multiple		Top mar this com carries t	rgin line of tomand, the line all property in	he next pag Protect mod	le feature
	Off	On	Multiple			line of the a performed.	active page	after a
Cursor to Start								
Cursor to start of line	Ctrl/M	same	same	same	same	same	same	same
Cursor to start of next line	Ctrl/_	same	same	same	same	same	same	EnH
	Autopage Off	Page Single <sup>4</sup>		ition of the	<u>-</u> e current p	page or the Protect mod		ected
	On	Multiple	Home posi	tion of the t page if P ode feature	e next page Protect mod	e or the first e is on. Und rough all p	unprotecte der this con	nmand, the

 $<sup>^4\</sup>mathrm{Either}$  Autopage mode or Single Page mode is enabled.

### ASCII Escape Sequences 12.4 Screen Processing

Table 12-7 (Cont.) Cursor Control Functions

	WYSE				TVI			ADDS
Address Cursor	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Cursor to Home	Ctrl/^ or ESC	C {						EnH or
		Ctrl/^	same	same	Ctrl/^	same	same	Ctrl/A
Address Cursor to a specific column ( <i>Col</i> )	ESC _ Col	n/a	same	same	ESC ] Co.	l		EnH or Ctrl/P <i>Col</i>
Address Cursor to a specific line	ESC [ Line	n/a	same	same	same	same	same	EnH or Ctrl/K <i>Line</i>
Address Cursor in	ESC = Line (	Col						EnH or
Current Page		same	same	same	same	same	same	ESC Y
Address Cursor in specific page	ESC h page	n/a	same	same	n/a	n/a	n/a	EnH
								Line Col
Address Cursor in specific	ESC w @ Pag	ge Line Col						
page, line, and column		n/a	same	same	ESC - Pa	ge Line Co	<b>P</b>	EnH
Address Cursor in specific	ESC - Windo	w/Page Lii	ne Col <sup>6</sup>					
Window/Page		same	same	same	EnH	EnH	EnH	EnH
Address Cursor in 80/132	ESC a <i>Line</i> F							
column current Page		n/a	same	same	ESC d Li	ne R <i>Col</i> C		EnH
Read Cursor								
Read Cursor address in current Page	ESC ?	same	same	same	same	same	same	EnH
Read Window, Page no., and Cursor address	ESC /	same	same	same	same	same	same	EnH
Read Cursor address in Current 80/132-col page	ESC b	n/a	same	same	n/a	n/a	n/a	EnH
Read Page number and Cursor address	ESC w` ESC w . ESC w , ESC w`	n/a	same	same	n/a	n/a	n/a	EnH

 $<sup>^5{\</sup>rm Enhanced}$  Mode off.

The terminal responds to the Read Cursor command in the following

The terminal responds to the Read Cursor command in the following format: lll R ccc C

The two parameter values, lll and ccc, are the 3-byte decimal values for the line/column location of the cursor. For example, "019R010C" indicates the cursor is at line 19, column 10. The sequence with parameters "001" (3/0)(3/0)(3/1) and "001" (3/0)(3/0)(3/1) indicates the cursor is at the home position.

 $<sup>^6</sup>$ When screen is split, "0" = upper window; "1" = lower window.

Table 12-8 lists the ASCII editing control functions. The word "same" in Table 12-8, Table 12-10, and Table 12-11 signify the same control sequences as in the WYSE 325/160/60 column.

Table 12-8 ASCII Editing Control Functions

		WYSE				TVI			
Local Edit Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2	
Off <sup>1</sup> (default) On <sup>2</sup>	ESC l ESC k	n/a n/a	same same	same same	same same	same same	same same	n/a n/a	

<sup>&</sup>lt;sup>1</sup>Duplex Edit Mode On.

In local edit mode, instead of sending keycodes to the host, some function keys send codes directly to the terminal to speed up the editing process. Table 12-9 lists these local edit functions and their operating keys for both the VT keyboard and the Enhanced PC keyboard.

Table 12-9 Local Edit Mode Function Keys

Function	VT Keyboard	EPC Keyboard	Sequence
Insert Character	PF1		ESC Q
Insert Line	Shifted PF1		ESC E
Delete Character	PF2	Delete	ESC W
Delete Line	Shifted PF2	Shifted Delete	ESC R
Clear Line	PF3	End	ESC T
Clear Screen	Shifted PF3	Shifted End	ESC Y
Insert		Insert	ESC q
Replace		Shifted Insert	ESC r
Next Page		Page Down	ESC K
Previous Page		Page Up	ESC J
Send			ESC 7
Print		Print	ESC P
Home		Shift Home	ESC {
Tab		Shift Tab	ESC I

<sup>&</sup>lt;sup>2</sup>Duplex Edit Mode Off.

### **ASCII Escape Sequences** 12.4 Screen Processing

Table 12-10 lists the tab stop control functions.

Table 12-10 Tab Stop Control Functions

		WYS	SE			TVI		ADDS
Tab Stop Function	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Clear All Tab Stops	ESC 0	ESC 3	same as 325/160 /60	same as 325/160 /60	ESC 3	ESC 3	ESC 3	n/a
Clear Tab Stop	ESC 2	same	same	same	same	same	same	EnH
Set Tab Stop	ESC 1	same	same	same	same	same	same	EnH
Tabulate Cursor or Field Tab <sup>1</sup>	ESC i or Ctrl/I	same	same	same	same	same	same	EnH
	The cursor n	noves as foll	ows:					
	Autopage	Autoscrol	l	Page Mod	le	Cursor N	Moves to	
	On	-	_	Single		Top mar page	gin line of t	he active
	On	-		Multiple		Top margin line of the o page.		he other
	Off	On		Multiple		Bottom margin of the active page after a sperformed.		
	Off	Off		Multiple		Top mar page.	gin line of t	he active
Backtab or Field Tab <sup>2</sup>	ESC I	same	same	same	same	same	same	EnH
	The cursor n	noves as foll	ows:					
	Autopage	Autoscrol	<u>l</u>	Page Mod	<u>le</u>	Cursor N	Moves to	<u>.                                    </u>
	On	-	_	Single		Home		<u> </u>
	On	-		Multiple			margin line page if any	
	Off	On		Multiple		Bottom active pa	margin line nge.	of the
	Off	Off		Multiple		Bottom active pa	margin line nge.	of the

 $<sup>^{1}\</sup>mathrm{Executes}$  "tabulate cursor" when protect mode is off.

Executing a Backtab from an unprotected page to a previous protected page changes its protect mode to "unprotected."

<sup>&</sup>lt;sup>2</sup>If protect mode is on, this command executes a "field tab" to move the cursor left to the first unprotected character position after the nearest protect field. The tab stop setting is completely ignored. The cursor moves backward from the first position of an unprotected area to the first position of another unprotected area.

Table 12–11 lists the page edit control functions.

Table 12-11 Page Edit Control Functions

		TVI			ADDS			
Page Edit Mode	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Off (default)	ESC e "	n/a	same	same	ESC O	ESC O	ESC O	EnH
On	ESC e #	n/a	same	same	ESC N	ESC N	ESC N	EnH
Insert/Replace Mode								
Replace mode On (default)	ESC r	same	same	same	same	Wyse	Wyse	EnH
Insert mode On	ESC q	ESC z	same as 325/160 /60	same as 325/160 /60	same as 325/160 /60	Wyse	Wyse	EnH
Insert Characters								
Insert Space Character	ESC Q	same	same	same	same	same	same	EnH
Insert Line of Spaces	ESC E	same	same	same	same	same	same	EnH of
Insert Column of NULs	ESC c M	n/a	same	same	n/a	n/a	n/a	EnH
Deleting Data on Current P	age Only							
Delete Cursor Character	ESC W	same	same	same	same	same	same	EnH
Delete Cursor Line	ESC R	same	same	same	same	same	same	EnH
Delete Cursor Column	ESC c J	n/a	same	same	n/a	n/a	n/a	EnH
Erasing Data on Page Fund	ction							
Clear Page to NULs	ESC *	same	same	same	same	same	same	EnH
Clear Page to spaces	ESC +	n/a	same	same	n/a	n/a	n/a	EnH of Ctrl/L
Clear page to write- protected spaces	ESC ,	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected page to write-protected spaces	n/a	ESC,	n/a	n/a	ESC ,	ESC,	ESC,	n/a
Clear unprotected page to NULs	ESC:	same	same	same	same	same	same	ESC : (EnH)
Clear unprotected page to spaces	ESC ; or Ctrl/Z	same or ESC +	same as 325/160 /60	same as 325/160 /60	same or ESC+	same or ESC+	same or ESC+	EnH
Clear unprotected page to a specific character <sup>1</sup>	ESC . Char	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected page to NULs from cursor	ESC y	same	same	same	same	same	same	EnH
Clear unprotected page to spaces from cursor	ESC Y	same	same	same	same	same	same	ESC k
Clear unprotected page foreground to NULs from cursor position	ESC c Q	n/a	same	same	n/a	n/a	n/a	EnH

<sup>&</sup>lt;sup>1</sup>"*Char*" is an ASCII character. Any 8-bit code is treated as a 7-bit code since the most significant bit of the code is stripped off.

# ASCII Escape Sequences 12.4 Screen Processing

Table 12-11 (Cont.) Page Edit Control Functions

Erasing Data on		WYS	E			TVI		ADDS
Page Function (cont.)	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Clear unprotected page foreground to spaces from cursor position	ESC c P	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected area to end of line with NULs	ESC c L	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected area to end of line with spaces	ESC c O	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected line from cursor position to NULs	ESC t	same	same	same	same	same	same	EnH
Clear unprotected line from cursor position to spaces	ESC T	same	same	same	n/a	n/a	n/a	ESC K
Clear unprotected line foreground from cursor position to NULs	ESC c S	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected line foreground from cursor position to spaces	ESC c R	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected position to NULs	ESC c K	n/a	same	same	n/a	n/a	n/a	EnH
Clear unprotected column to a specific character <sup>1</sup>	ESC c I <i>Char</i>	n/a	same	same	n/a	n/a	n/a	EnH
Clear column to write- protected space	ESC V	same	same	same	same	same	same	EnH

 $<sup>^{1}</sup>$ " Char" is an ASCII character. Any 8-bit code is treated as a 7-bit code since the most significant bit of the code is stripped off.

#### 12.4.1 Rectangular Area Operations

Upon execution, a rectangle that is drawn with line drawing characters and normal attributes is displayed on the screen. If the four lines that form the rectangle are occupied with data before the command execution, then the data is replaced.

The parameters *Line*, *Column*, and the line, column number of the cursor decide where the rectangle will be located. See Table 12–12.

The parameters *Line* and *Column* in format 1 are ASCII characters whose decimal values are the desired numbers plus 31.

The parameter *Column* in format 2 is an ASCII character whose decimal value is the desired column number plus 31 and minus 80.

The symbol " $\sim$ " in escape sequences indicates number "80" to be added to the "Column" value. The result of executing this command draws a rectangle 80 columns wider than the rectangle drawn by the command without the " $\sim$ " symbol. Therefore, this command is not recommended for 80-column mode.

*Char* is an ASCII character. If an 8-bit code is entered as a parameter value, then the most significant bit of the code is stripped off.

Table 12–12 lists the rules for locating the rectangle.

Table 12-12 Rules for Locating Rectangle

If	And Column	Then, the rectangle is located from the	
Line value is	value is	cursor	And
<b>Larger</b> than the cursor line	<b>Larger</b> than the cursor column	<b>Down</b> to the line number indicated by <i>Line</i>	<b>Right</b> to column number indicated by <i>Column</i> .
<b>Larger</b> than the cursor line	<b>Smaller</b> than the cursor column	<b>Down</b> to the line number indicated by <i>Line</i>	<b>Left</b> to column number indicated by <i>Column</i> .
<b>Smaller</b> than the cursor line	<b>Larger</b> than the cursor column	<b>Up</b> to the line number indicated by <i>Line</i>	<b>Right</b> to column number indicated by <i>Column</i> .
<b>Smaller</b> than the cursor line	<b>Smaller</b> than the cursor column	<b>Up</b> to the line number indicated by <i>Line</i>	<b>Left</b> to column number indicated by <i>Column</i> .
<b>Equal</b> to the cursor line	<b>Equal</b> to the cursor column	At the same location	A single box character is displayed.

The rectangle extends to the bottom of the screen only. If an out of range line parameter is entered, then the bottom line of the rectangle is located at the bottom margin. The command is ignored if the rectangle covers a locked line.

In 80-column mode, if the entered parameter extends the rectangle to over 80 columns but within the 132-column area, then the over 80 column part is not displayed. Changing to 132-column mode displays the whole rectangle.

In 132-column mode, if an out of range column number is entered, then the right line of the rectangle is located at the right margin.

Whether or not the protect mode is on when the command executes, the rectangle line is drawn write protected.

# ASCII Escape Sequences 12.4 Screen Processing

Table 12–13 lists the rectangle area control functions. The word "same" signifies the same control sequences as in the WYSE 325/160/60 column.

Table 12-13 Rectangle Area Control Functions

Draw Rectangle in 80/132		WYS	SE			TVI				
column Current Page	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2		
Format 1	ESC c G Lin	e Col								
E 4 01	ECC - C Lt	n/a	same	same	n/a	n/a	n/a	EnH		
Format 2 <sup>1</sup>	ESC c G <i>Lin</i>	e ~ <i>Coi</i> n/a	same	same	n/a	n/a	n/a	EnH		
Fill Rectangle with a Specif	fic Character in	n 80/132-col	lumn Curso	r Page						
Format 1	ESC c H Lin	e Col Char								
E	EGG II.	n/a	same	same	n/a	n/a	n/a	EnH		
Format 2 <sup>1</sup>	ESC c H <i>Lin</i>	n/a	same	same	n/a	n/a	n/a	EnH		
Fill unprotected Rectangle	with a specific	character								
Format 1	ESC c F Lin	e Col Char								
		n/a	same	same	n/a	n/a	n/a	EnH		
Format 2 <sup>1</sup>	ESC c F <i>Lin</i>	e ~ <i>Col Cha</i> n/a	r same	same	n/a	n/a	n/a	EnH		
Draw Rectangle <sup>2</sup>										
Draw rectangle area to	ESC c N Wie	dth Height								
right and below cursor.		n/a	same	same	n/a	n/a	n/a	EnH		
Swap/Copy/Move <sup>3</sup>	WYSE 325/1	60/60								
Swap, copy, or move the data in a rectangle to another rectangle.	ESC c ^ Acti	ion S_page I	P S_n1 R S_	_n2 C S_n3	8 R <i>S_n4</i> C	C D_page P	D_n1 R D_n	2 C		
Parameters:	Action	Description	on							
	0	-				estination r	0			
	1		e content og the conte				nation recta	ngle,		
	2		0			U	tion rectang	le. clearir		
			e rectangle.		8					
	Parameter	Description								
	S_page	-	nber of the		_	wla (tam laft				
	S_n1 S_n2					gle (top left tangle (top				
	S_n2 S_n3						right corner)			
	S_n4	_			_		_			
	D_page	Ending column number of the source rectangle (bottom right corner)  Page number of the destination rectangle								

<sup>&</sup>lt;sup>1</sup>Not recommended for 80-column mode.

 $<sup>^2\</sup>mathrm{Parameters}$  Line and Column are ASCII characters whose decimal values are the desired numbers plus 31. See Section 12.4.1.1.

<sup>&</sup>lt;sup>3</sup>See Section 12.4.1.2.

Table 12–13 (Cont.) Rectangle Area Control Functions

WYSE 325	WYSE 325/160/60									
D_n1 D_n2	U			3 . 1						
	PCTerm	150/120	50/50+	950	925	910+	A2			
	n/a	same as 325/160 /60	same as 325/160 /60	n/a	n/a	n/a	EnH			
	D_n1	D_n1 Starting I D_n2 Starting o	$D_{-}n1$ Starting line number $D_{-}n2$ Starting column num Starting column num PCTerm 150/120 $n/a$ same as $325/160$	$D_{-}n1$ Starting line number of the dest $D_{-}n2$ Starting column number of the of Starting column number of the dest Starting column number of the of Starting column num	$D_{-}n1$ Starting line number of the destination re Starting column number of the destination PCTerm 150/120 50/50+ 950 $n/a$ same as same as $n/a$ $325/160$ $325/160$	$D_{-}n1$ Starting line number of the destination rectangle (to $D_{-}n2$ Starting column number of the destination rectangle PCTerm 150/120 50/50+ 950 925 $n/a$ same as same as $n/a$ $n/a$ $325/160$ $325/160$	$D_{-}n1$ Starting line number of the destination rectangle (top left corner) $D_{-}n2$ Starting column number of the destination rectangle (top left corner) $PCTerm$ 150/120 50/50+ 950 925 910+ $n/a$ same as same as $n/a$ $n/a$ $n/a$ $n/a$			

#### 12.4.1.1 Draw Rectangle

The rectangle extends to the bottom of the screen only. If an out of range line parameter is entered, then the bottom line of the rectangle is located at the bottom margin.

- In 80-column mode, if the entered parameter extends the rectangle to over 80 columns but within a 132-column area, the over 80-column part is not displayed. After changing to 132-column mode, the entire rectangle is displayed.
- In 132-column mode, if an out of range column number is entered, then the right line of the rectangle is located at the right margin.

Whether or not protect Mode is turned on, the rectangle line is drawn write protected. This command is ignored if the targeted rectangle covers a locked line.

#### 12.4.1.2 Swap/Copy/Move

In the Swap/Copy/Move command, the parameters s\_n1, s\_n2, s\_n3, s\_n4, d\_n1 and d\_n2 are screen coordinates, expressed as decimal numbers. The first four parameters define the two diagonal corners of the source rectangle; the later two define the top-left corner of the destination rectangle.

Only data, not its attribute, is moved in any of the rectangular actions. The protect mode and the line lock mode are ignored during the movement.

This command sequence is ignored when the column parameters (s\_n2, s\_n4, d\_n2) are beyond the right margin of the page.

An out of range of the row parameters (s\_n1, s\_n3, d\_n1) causes the rectangle to be limited to the bottom margin line.

An out of range of the action parameter causes the command sequence to be aborted.

An out of range of the page parameter causes the command to be ignored.

### 12.5 Printing/Sending Data

This section describes commands to print and send data.

#### 12.5.1 Sending Data

This section describes commands to send a defined area of data on the screen through the main communication port (Comm1) using ASCII control functions. Individual commands address the specific data to be sent.

In send operations, delimiter characters are sent along with data to mark a line end, transfer complete, or the protect data and its area. Table 12–14 lists the possible delimiter types. Depending on the scope of data (line, page) and the type of data (protected, unprotected) that has been sent, different delimiter characters are enclosed. The individual commands explain which delimiter should be sent with each command.

Table 12–14 lists the types of delimiters to send data.

Table 12-14 Send Data Delimiters

Delimiter Type	Sent
End of the line	At the end of each line but not at the end of the page (block).
Transfer complete	After each Send Data action, except for a "Send the Cursor Character" command.
Field separator	To take the position of the protected field data when "Send Unprotected" command is executed and Protect mode is on.
Start protect field and End protect field	To mark the beginning and the ending of a write-protected field of data when Protect mode is on.

All the send data actions in this section, except "Send the Cursor Character" command, use the following rules:

- The attributes are not sent along with their data. But a Space character (Hex 20) is inserted between two distinct attribute data to indicate the attribute difference.
- During the process of sending characters, the cursor moves to the location of the character being sent.
  - Protect mode on: The cursor does not move.
  - **Protect mode off:** The cursor moves to the left margin of the next line.
- Null characters on the screen are not sent.
- Delimiter characters:
  - TVI modes and WYSE 325/160/60 PCTerm modes: Defined by command "Define Delimiters" (Refer to the command for details.)
  - **Other personalities:** See Table 12–15.

Table 12–15 Delimiters for Other Personalities

Delimiter	Terminal sends
End of line	Either "US" or "CRLF" depending on the Set-Up Block End selection.
End of transmission	Either "CR" or "ETX" depending on the Set-Up Block End selection.
Protected field	A single FS (Hex 1C).
Protected field separator	Native mode: "ESC )" and "ESC (" when the protect field attribute is Dim or Normal; "ESC )sp" and "ESC (sp" when the protect field attribute is any other combination.
	Other modes: "ESC )" and "ESC ("

- If any line on the screen is locked, then the line is not sent; however, the end of line delimiter is still sent to indicate a line has been skipped.
- If the first character sent is a protected character, then the ESC ) sequence is not sent before the first character; if the last character sent is a protected character, then the ESC (sequence is not sent before the terminator.
- If the cursor position is located at the right margin of the bottom margin line and the Protect mode is off:

Autopage	Autoscroll	Page Mode	Cursor moves to
On	-	Single	Home position of the active page.
On	-	Multiple	Home position of the other page.
Off	On	Multiple	Left margin of the bottom line after a scroll is performed.
Off	Off	Multiple	Home position of the active page.

Table 12–16 lists the print/send control functions.

Table 12-16 Print/Send Control Functions

	WYSE			TVI					
Function	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2	
Define delimiters	n/a	ESC x Di	mtr Char1	Char2					
			n/a	n/a	ESC x	Dlmtr Chai	·1 Char2	n/a	
Parameters:	Dlmtr		Descripti	on					
	0		Protected Field separator						
	1	1 Start protect field							
	2		End protect field						
	3		End of th	e line					
	4	Termination							
	Parameters (	Char1 and	Char2 are A	SCII chara	acters.				
	Delimiter		Default ASCII Character						
	Field separat	or	FS NUL (1/12 0/0)						
	Start protect	field	ESC ) (1/	11 2/9)					

### ASCII Escape Sequences 12.5 Printing/Sending Data

Table 12–16 (Cont.) Print/Send Control Functions

			ADDS					
Function	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
	End protect	field	ESC ( (1/	11 2/8)				
	End of the li	ine	US NUL	(1/15 0/0)				
	Termination		CR NUL	(1/13 0/0)				
	A NUL char	acter that is	defined in	a delimiter	is not sen	t out.		
Begin Print/Send								
Begin Print/Send at Top of Page	ESC d`	n/a	same	same	n/a	n/a	n/a	EnH
Begin Print/Send at Top of Screen	ESC d &	n/a	same	same	n/a	n/a	n/a	EnH
Sending a Character or Lin	e							
Send the Cursor Character	ESC M	n/a	same	same	n/a	n/a	n/a	n/a
Send the Cursor Line	ESC 6	same	same	same	same	same	same	n/a
Send unprotected Cursor Line	ESC 4	same	same	same	same	same	same	n/a
Sending a Page								
Send Page	ESC 7	same	same	same	same	same	same	EnH
Send an unprotected Page	ESC 5	same	same	same	same	same	same	n/a
Sending a Block								
Mark Block Beginning	ESC 8	n/a	same	same	n/a	n/a	n/a	EnH
Mark Block Ending <sup>1</sup>	ESC 9	n/a	same	same	n/a	n/a	n/a	EnH
Send Block <sup>2</sup>	ESC s	same	same	same	same	same	same	EnH
Send an unprotected Character in a Block	ESC S	same	same	same	same	same	same	EnH
1								

<sup>•</sup> Replace mode on: "STX" or "ETX" replaces the existing character at the active position and moves the cursor right one position

#### ASCII emulations do not send:

- Initialization codes
- Ending sequences to designated character sets and display attributes
- "Fallbacks" to represent data that cannot be printed by the attached printer

<sup>•</sup> **Insert mode on:** Writing "STX" or "ETX" moves all characters and their attributes one position to the right of the cursor position (inclusive) in the current line without wraparound.

<sup>•</sup> **Protect mode on:** Unprotected data is sent as is; protected data, enveloped between "start of protect field" and "end of protect field" delimiters, is sent.

<sup>•</sup> Protect mode off: All the data in the range, protected or unprotected, is sent.

### **ASCII Escape Sequences** 12.5 Printing/Sending Data

The only factors that affect printing data are data and parity settings.

Data/Parity Setting	Characters are printed
8-bit	As is
7-bit	After stripping off the most significant bit

Table 12–17 lists the printing data control functions.

**Table 12–17 Printing Data Control Functions** 

		WYS	SE .			ADDS		
Autoprint Mode <sup>1</sup>	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Off (default) On	Ctrl/T Ctrl/R	ESC A ESC @	Ctrl/T Ctrl/R	Ctrl/T Ctrl/R	ESC A or			Ctrl/T Ctrl/R
Control Print Mode <sup>3</sup>								
Off On	Ctrl/T ESC d # or Ctrl/X <sup>2</sup>	ESC a ESC ′	Ctrl/T same as 325/160 /60	Ctrl/T same as 325/160 /60	ESC a ESC `	ESC a ESC	ESC a ESC `	ESC 4 ESC 3 ESC d# (EnH)
Aux Receive Mode								
Off (default) On	ESC d Sp ESC d!	n/a n/a	same same	same same	n/a n/a	n/a n/a	n/a n/a	EnH EnH
Bidirectional Mode <sup>4</sup>								
Off (default)	ESC d \$	Ctrl/T	same as 325/160 /60	same as 325/160 /60	Ctrl/T	Ctrl/T	Ctrl/T	EnH
On	ESC d %	Ctrl/R	same as 325/160 /60	same as 325/160 /60	Ctrl/R	Ctrl/R	Ctrl/R	EnH
Print Page to the Curso	r Position							
Formatted Page <sup>5</sup> Formatted Page (unprotected)	ESC P ESC @	same n/a	same same	same same	same n/a	same n/a	Wyse n/a	EnH EnH
Unformatted Page <sup>5</sup>	ESC p or ESC L	n/a	same	same	ESC L	n/a	n/a	ESC p

<sup>&</sup>lt;sup>1</sup> The symbol ">" is displayed in the status line when in Autoprint mode.

<sup>&</sup>lt;sup>2</sup>Enhanced mode is off.

 $<sup>^3\</sup>mbox{The symbol}$  "=" is displayed in the status line when in Autoprint mode.

<sup>&</sup>lt;sup>4</sup> Turning off Bidirectional mode turns off Aux Receive mode and forces a normal print mode.

<sup>&</sup>lt;sup>5</sup> The time prints out in a format such as "TIME AM/PM 00:00." At the end of the time message, the following is sent to the printer port: **NUL Ctrl/F NUL**The page prints as formatted data. The terminal sends an "ACK" to the host at the end of a print operation if ACK mode

### ASCII Escape Sequences 12.5 Printing/Sending Data

Table 12-17 (Cont.) Printing Data Control Functions

Print the Page		WYS	SE .			ADDS		
with Time Message <sup>5</sup>	325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
	n/a	ESC L	n/a	n/a	n/a	ESC L	ESC L	n/a
Pass a Character to the	Printer Port							
	Ctrl/P Char	Wyse	same	same	Wyse	Wyse	Wyse	n/a
Define the Page Print Te	rminator							
	n/a	ESC p Ps	<i>Char</i> n/a	n/a	ESC p (	Char		n/a

<sup>&</sup>lt;sup>5</sup> The time prints out in a format such as "TIME AM/PM 00:00." At the end of the time message, the following is sent to the printer port: **NUL Ctrl/F NUL**The page prints as formatted data. The terminal sends an "ACK" to the host at the end of a print operation if ACK mode is on.

### 12.5.2 Graphics Characters

Table 12-18 lists the graphic characters.

Table 12-18 Graphic Characters

	TVI			ADDS			
325/160/60	PCTerm	150/120	50/50+	950	925	910+	A2
ESC H or Ctrl/B	ESC \$	same as 325/160 /60	same as 325/160 /60	ESC \$ or Wyse	ESC \$ or Wyse	ESC \$ or Wyse	EnH
ESC H or Ctrl/C	ESC %	same as 325/160 /60	same as 325/160 /60	ESC % or Wyse	ESC % or Wyse	ESC % or Wyse	EnH
ESC H Char	n/a	same	same	n/a	n/a	n/a	EnH
	ESC H or Ctrl/B ESC H or Ctrl/C	325/160/60 PCTerm  ESC H or ESC \$ Ctrl/B  ESC H or ESC %	ESC H or Ctrl/B	325/160/60         PCTerm         150/120         50/50+           ESC H or Ctrl/B         ESC \$ same as 325/160 /60 /60 /60         same as 325/160 /60 /60           ESC H or Ctrl/C         ESC % same as 325/160 /60 /60 /60         same as 325/160 /60 /60	325/160/60         PCTerm         150/120         50/50+         950           ESC H or Ctrl/B         ESC \$ same as 325/160	325/160/60         PCTerm         150/120         50/50+         950         925           ESC H or Ctrl/B         ESC \$ same as 325/160	325/160/60         PCTerm         150/120         50/50+         950         925         910+           ESC H or Ctrl/B         ESC \$ same as 325/160 /60 /60         same as 325/160 /60         ESC \$ or Wyse

With Graphics mode on, all received codes in the range of 00 to 7E are displayed as characters in the range of Hex 00 to Hex 1F in the same character set.

This is done by stripping off the highest 3 bits of the code. For example:

Receiving	Displays
21, 41, or 61 (Hex)	01 (Hex) character
2C, 4C, or 6C (Hex)	0C (Hex) character
31, 51, or 71 (Hex)	11 (Hex) character

### **ASCII Escape Sequences** 12.5 Printing/Sending Data

Most character sets in ASCII emulation contain characters in the range of Hex 00 and Hex 1F. For example, the Native character set contains 16 line-drawing graphics characters from Hex 10 to Hex 1F and 16 CRM characters from Hex 00 to 0F. But in most of the cases, Hex codes 00 to 1F are treated as control codes. To display these graphic characters, Graphic mode has to be turned on.

When the Graphic mode is on, new characters entered have normal attributes regardless of the state of the Write-Protect mode attribute. With Protect mode on, all the entered characters, except CRM characters, are protected.

To design a character font, see Chapter 13.

## **Defining and Loading ASCII Character Fonts**

This chapter defines the ASCII character fonts and describes how to load the

### 13.1 Character Sets

In WYSE mode and ADDS Enhanced mode, desired characters can be acquired by loading them from various built-in character sets or by designing them using a pixel pattern\*.

### 13.1.1 PCTerm on US Keyboard

The default and only character set supported for PCTerm on the US Keyboard is the PC International character set. This is a 256-character set, of which the first 128 characters form the PC Standard character set\*.

#### 13.1.2 WYSE and ADDS Enhanced Personalities

WYSE mode and ADDS enhanced mode support ten built-in ROM character sets and four font banks, which are physical locations in memory. Each character set has 128 characters (Hex 00 to Hex 7F), thus each font bank has the same space allocation.

The character set must be loaded into a font bank to become an "active" character set. Characters cannot be displayed directly by calling their physical locations; they can only be displayed through a series of steps to make them active. First, the primary and secondary logical character sets are defined by pointing to the desired font banks. Then, the active character set is defined for the terminal to display and receive codes. See Table 13-1 on how to display and load character sets.

Table 13-1 Display and Load Character Sets

Step		Description
1.	Load font bank with built-in character set	Load a target character set from one of the ten built-in character sets into a font bank.
	or Define and load character	Design a character and load it into a font bank.
2.	Define logical character set	Define primary or secondary character set to point to the font bank.
3.	Select active character set	Set active character set to point to either a primary or a secondary character set.

Notes \_


**WYSE 160:** You can display all 512 characters in the four font banks on the screen at the same time.

Refer to the IBM Code Page 437.

WYSE 50+: You can only display one font bank on the screen at a time.

Figure 13–1 shows the process for selecting character sets.

Figure 13-1 Process of Selecting Character Sets



MA-0027-93.GRA

The VT520 selects a character set from one of the built-in character sets by the following process. Refer to Table 13-1 for details.

- 1. Load the character sets into the font banks.
- Define the primary and secondary character set from the font buffers.
- Select which character set will be the active characters set.

### **Defining and Loading ASCII Character Fonts** 13.1 Character Sets

Note
Changing a character set in a font bank may change the active character set if the active character set and primary/secondary character set happen to point to the same font bank.

### 13.2 Loading, Defining, and Selecting Character Sets

Table 13-2 shows how to load, define, and select the character sets. The word "same" in Table 13–2 signifies the same control sequences as in the WYSE 160/60 column.

Table 13-2 Loading Font Bank

	WYSE TVI							ADDS
Load Font Bank <sup>1</sup>	160/60	PCTerm 150/120		50/50+	950	925	910+	A2
Load ROM-resident character set into one	ESC c @ B	ank Charset						
of the four font banks. <sup>2</sup>		n/a	same	same	n/a	n/a	n/a	EnH
Parameters:	Bank	Descript						
	0	Font Bar						
	1	Font Bar	nk 1					
	2	Font Bar	nk 2					
	3	Font Bar	nk 3					
	Charset			Characte	er Set Sele	ected		
	@ (4/0) or `	(6/0)		Native				
	A (4/1) or a	(6/1)		PC Mult				
	B (4/2) or c	(6/3) or d (6	/4)	Standard	d ASCII			
	C (4/3)			Graphics	s 1			
	D (4/4) or b	(6/2)		PC stand				
	E (4/5)			Graphics	s 2			
	F (4/6)			Graphics				
	G (4/7) or I	H (4/8) or g (	6/7)	US ANS				
	N (4/14) or	N (4/14) or j (6/10) ISO Latin-1 Suppleme						
	I (4/9) or e	(6/5)		ANSI Su	ıpplement	al		
Define Logical Character S	Set							
Primary Character Set	ESC c B B	ank n/a	same	same	n/a	n/a	n/a	EnH
Secondary Character Set	ESC c C B	ank n/a	same	same	n/a	n/a	n/a	EnH
Select Active Character Se	et <sup>3</sup>							
Primary Character Set (default)	ESC c D	n/a	same	same	n/a	n/a	n/a	EnH

<sup>&</sup>lt;sup>1</sup> If not redefined, the default primary character set is Native/Wyse 50+ in Font Bank 0; the secondary character set is PC Multinational in Font Bank 1.

 $<sup>^2</sup>$  Example: To load Bank 1 with the Multinational character set, enter: ESC c @ 1 A This sequence is sent to the terminal. If ACK mode is on, the terminal returns an ACK to indicate that the font has loaded successfully.

<sup>&</sup>lt;sup>3</sup>The default active character set, including that for TVI mode, is Native/Wyse 50+.

### **Defining and Loading ASCII Character Fonts** 13.2 Loading, Defining, and Selecting Character Sets

Table 13–2 (Cont.) Loading Font Bank

Select Active Character Se	et <sup>3</sup>							
Secondary Character Set	ESC c E	n/a	same	same <sup>4</sup>	n/a	n/a	n/a	EnH
Automatic Font Loading								
On (default)	ESC e O	n/a	same	same	n/a	n/a	n/a	n/a
Off	ESC e N	n/a	same	same	n/a	n/a	n/a	n/a
		WYS	SE			TVI		ADDS
Clear Font Bank	160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Erase a character set from one of the four font banks. <sup>1</sup>	ESC c? Ba	<i>ank</i> n/a	same	same	n/a	n/a	n/a	EnH

 $<sup>^1</sup>$  If not redefined, the default primary character set is Native/Wyse 50+ in Font Bank 0; the secondary character set is PC Multinational in Font Bank 1.

\_\_\_\_\_ Note \_\_\_\_

**Wyse 50+ Mode:** Because Wyse 50+ can only display one font bank at any given time, executing the sequence has a side effect of converting the existing screen characters into new characters that have equivalent positions as the old characters in the original character sets.

For example, a screen full of "!" characters are displayed when the active character set is Native/Wyse 50+. Executing **Select Secondary Character Set** to select the PC Multinational as the active character set causes the "!" on the screen to be converted to "í ". The character "!" occupies Hex 21 in Native/Wyse 50+ character set; whereas, "í " occupies Hex 21 in the PC Multinational character set.

 $<sup>^3</sup>$ The default active character set, including that for TVI mode, is Native/Wyse 50+.

<sup>&</sup>lt;sup>4</sup>See Note on the following page.

### 13.3 Designing a Character Font

Table 13–3 shows how to design a character font.

Table 13-3 Design a Character Font

Define and		WYS	Ε			ADDS		
Load a Character	160/60	PCTerm	150/120	50/50+	950	925	910+	A2
Design a character font	ESC c A Bank Pp bbbb Ctrl/Y							
•		n/a	same	same	n/a	n/a	n/a	EnH

The sequence in Table 13–3 defines the bb..bb string and loads it in the Pp position of the Bank font bank.

Bank is the font bank that holds a defined character set. Refer to Table 13-2.

*Pp* is a 2-byte Hex code in the range of 00 to 7F specifying a position in that font bank.

bb...bb is a Hex code string defining the bit pattern of the defined character. The string contains one of the following:

- 16 2-byte Hex codes for a  $10 \times 16$  cell size character
- 13 2-byte Hex codes for a 10  $\times$  13 cell size character
- 10 2-byte Hex codes for a  $10 \times 10$  cell size character

The command aborts if Ctrl/Y in the sequence is received before the expected number of Hex codes in *bb...bb* is received.

Perform the following steps to draw a graphic character in a  $10 \times 16$  cell:

- 1. Divide the cell into  $10 \times 16$  pixels and draw the desired font pattern. Observe the following rules:
  - a. Start the pattern from the left column in the cell.
  - For an alphanumeric character, the pattern should occupy only the left seven columns; for other graphic characters, the pattern can extend to the eighth column. (The ninth and tenth column follow whatever you place in the eighth column.)
  - c. If possible, leave some space at both the top and bottom pixels to allow for spacing.
- 2. Turn the font pattern into a value represented as 1s and 0s; where "1" represents a filled pixel, and "0" represents an empty pixel.
- 3. Encode the bit pattern, 4 bits (a *nibble*) at a time, row by row, into hexadecimal numbers 0 to F. (Do not encode the right two columns.)
- 4. Form the two nibbles per row into a 2-byte Hex code.
- 5. Feed the 16 Hex codes into the *bb...bb* string. See the following example.

### **Defining and Loading ASCII Character Fonts** 13.3 Designing a Character Font

Load the the following character into position 31 (Hex) in Font Bank 3.

		M	SE	3					Ι	LSE	3			
Bit	>		7	6	5	4	3	2	1	0	Α	В	Hex	Code
		1 2 3 4 5 6	X X X	Х	Х	Х	Х	Х	Х	X X X			00 00 FF 81 81	
	1	7 8 9 0 1 2	X X X X	X	X	X	X	X	X	X X X X X			81 FF 81 81 81	
	1 1	3 4 5 6	Х	Х	X	Х	Х	Х	Х	X			FF 00 00 00	

Use the following sequence to load this graphic character:

```
ESC c A 3 31 00 00 FF 81 81 81 81 FF 81 81 81 81 81 FF 00 00 Ctrl/Y
```

Once loaded, the font remains in the font bank until:

- The terminal is powered off
- This font bank is explicitly re-loaded or cleared
- This font bank is implicitly re-loaded by changing the terminal's personality or the terminal changes between a 24-line and a 44-line display while Automatic Font Load is on. Refer to Table 13-2.

# **VT Keyboard Legend Data**

This appendix describes the Compose processing, non-spacing diacritical marks, and keyboard layouts for the VT keyboard layouts.

### A.1 Compose Processing and Non-spacing Diacritical Marks

Of the new keyboard dialects added to the VT520, only Hebrew and SCS allows three-stroke compose sequences. Pressing "Hebrew" (the Compose key) initiates a compose sequence. Ctrl/Hebrew is used to switch between Group 1 and Group 2.

The other new keyboard dialects employ a Group Shift mechanism to access additional characters so there is no Compose key and no three-stroke compose sequences. Three keyboards have non-spacing diacritical marks in Group 1 or Group 2. These keystrokes initiate a two-stroke "auto-compose" sequence.

Table A-1 lists the VT keyboard non-spacing diacritical marks. The brackets in Table A-1 are not part of the non-spacing diacritical marks.

Table A-1 VT Keyboard Non-Spacing Diacritical Marks

VT Keyboard <sup>1</sup>	Acute	Caron	Circumflex	Dieresis	Ring	Tonos
Czech VT	[′]	[^]	[^] <sup>2</sup>	["]	[°] <sup>3</sup>	
Greek VT				[ <sup></sup> ] <sup>4</sup>		[ <sup>!</sup> ] <sup>4</sup>
Slovak VT	[′]	[']	[^]2	["]	[°] <sup>3</sup>	

<sup>&</sup>lt;sup>1</sup>Hebrew, Hungarian, Polish, Romanian, Russian, SCS, Turkish-Q and Turkish-F keyboards have no non-spacing diacritical marks.

### A.2 VT Keyboards

The VT keyboard layouts are shown in the figures that follow:

Note
The keyboards shipped with the product may not look exactly like those illustrated here. Different fonts may be used, and some characters may not look the same.

<sup>&</sup>lt;sup>2</sup>Circumflex over O/o can be produced with caron and O/o.


<sup>&</sup>lt;sup>3</sup>Ring over U/u can also be produced with caron and U/u.

<sup>&</sup>lt;sup>4</sup>Greek iota with diaeresis and accent can be produced by pressing diaeresis, accent, then iota. Greek upsilon with diaeresis and accent can be produced by pressing diaeresis, accent, then upsilon.


Figure A-1 Austrian/German VT Keyboard LJ-03232-TI0 F20 Ein-gabe F19 6 9 က F18 2 œ ~ F17 0 Bild Lö: schen Ausführen ₩ Ein-fügen  $\triangleleft$  $\triangleright$ Selek-tieren Hilfe  $\nabla$ F14 F13 ≀ \* \* † :: :: :: < F12 :∢ F11 ۰. م o :0 ₾ ··· ØO × X 8 ြ၈ F10 \_ ਹ⊐ **Σ**  $-\infty$ Е 0 × Z Z F8 I **%** Ω F7 Ö **5** 1/2 F a > P6 @ • \_ ຶ≎່ວ &4 \\_{\delta} ~ o o o Λ \* ш <u>></u> ∵; ຕ ် ဗ X യ ന 8 ▼ | |-AÆ × = 0 **F**4 ď  $\bigcirc \ \overline{\bigcirc}$ ۸۷ F3 Gruppen umsch K! ⑦ F2 Ctrl Ŧ

LJ-03277-TI0 F20 Vali-der F19 ြ 9 F18 lω 2 7 F17 Eff. texte Suiv. Exécuter Préc.  $\triangleleft$  $\triangleright$ Aide  $\times$ F13 <sup>®</sup> # MAJ. F12 F11 + 11 Σ Ь **0**-0 0 စြပ F10 ¥ ∞ -F3 Ē Z 8 4 ᆂ В **9** ග F7 G |> ro-F6 ~ ပ ₽ ш × က = F5 ဟ ≥ **⊘**-∞ **F**4 Ø F3 ۸۷ F2 MAJ. Ŧ

Figure A-2 Belgian/French VT Keyboard



A-4 VT Keyboard Legend Data



VT Keyboard Legend Data A-5

MA-0326-93.GRA F20 Enter F19 F18 F17 Next Δ å Insert Here Prev ◁  $\triangleright$ 윰 Select  $\nabla$ F4 Ŧ3 F12 Compose Character Ξ F10 6 œ Н F1 9 % 比 Alt Function 7 o( 7) ⋖ æ

ଐ

댦

Shift

Figure A-5 Czech VT Keyboard

F2

Σ






Figure A-7 Dutch VT Keyboard LJ-03229-T10 F20 Voer F19 9 6 က F18 8 2 0 Volg Wis Blok Voeg Vorig  $\triangleleft$  $\triangleright$ Help Zoek  $\bigvee$  $\overline{\times}$ F13 + 11 Д 0 ۸. 0 F10 - ი ¥ Σ \* œ Ь9 Z **∞** ► В I В ۷ 9 F7 G ကွ F6 ш 2 <del>&</del> 4 ပ ۵ ш ∓ %€ × ဟ >  $\bigcirc \ \, \mathbb{H}$ ® **⊘** Z Ε4 ⋖ Ø F3 Samengest Teken  $\forall \exists$ F2 Ŧ


A-8 VT Keyboard Legend Data





A-10 VT Keyboard Legend Data

Figure A-10 Greek VT Keyboard



# VT Keyboard Legend Data A.2 VT Keyboards

Figure A-11 Hebrew VT Keyboard F20 F19 £ F17 Δ 8 Insert Here Prev ⊲  $\triangleright$ Find Select  $\nabla$ Help F1 5 Compose Character F12 £ Alt Function F10 æ æ Ŀ စ 9<u>4</u> F2 Alt Function **4** £ €] F2 Ε CŧrI Shift

A-12 VT Keyboard Legend Data





Figure A-12 Hungarian VT Keyboard

Figure A-13 Italian VT Keyboard LJ-03326-T10 F20 Invio in F19 9 6 က F18 8 2 0 Succ Inser Prec  $\triangleleft$  $\triangleright$ Ricer  $\bigvee$  $\overline{\times}$ F13 დი**∗** જ છ %.⊃ II --Σ Д **0**-a 0 ၈၀⁄ F10 ¥ ∞ < Е Z В I 9 | В F7 G رى د F6 ш 2 ပ 4 -Δ Ш × က = ဟ 7  $\bigcirc \ \, \mathbb{H}$ ≥ **O**√0 Ε4 ⋖ Ø @ F3  $\forall \exists$ F2 Ŧ


A-14 VT Keyboard Legend Data



VT Keyboard Legend Data A-15

MA-0330-93.GRA 23 Enter F19 F18 F17 Next Δ 8 Prev ◁  $\triangleright$ 윰 Find Select  $\nabla$ £ F13 F12 Compose Character Ξ 0 윤 5 œ Ŀ മ £ ш ۵ £ ٠<u>٠</u> တ Alt Function 7 E ଐ **F**2 Σ Shift £

Figure A-15 Polish VT Keyboard



VT Keyboard Legend Data A-17

MA-0331-93.GRA 23 F19 F18 F17 Next Δ 8 Prev ⊲  $\triangleright$ 윰 Select Find  $\nabla$ ¥ F3 F12 Compose Character Ξ 윤 6 æ ш Ŀ £ ۵ 比 7 Ø E € F2 Σ 돌

Figure A-17 Romanian VT Keyboard





Figure A-19 SCS VT Keyboard F20 Enter F19 F18 œ






Figure A-20 Slovak VT Keyboard

F20 Vali-dar F19 PF3 6 9 က F18 ω 2 7 F17 Sigte. Previa Inser-tar  $\triangleleft$  $\triangleright$ Loca-lizar F14 × F13 l ov F12 @| O| F11 ž 4 Funci Alt II O 0 \_\_\_\_\_ F10 У **-∞** Σ Е 2 Z F8 I ಶ ಅ В F7 Ō က% > F6 R a ш × **₩**₩ ဟ ≥ 0 4 7 = 0 Ε4 4 Ø F3 ۸۷ K! F2 Ŧ

Figure A-21 Spanish VT Keyboard

LJ-03276-TI0




Figure A-22 Swedish VT Keyboard

Figure A-23 Swiss-French VT Keyboard F20 Vali-der F19 PF3 6 9 က F18 2 7 ∞ F17 Page suiv. Eff. texte Exécuter Page précéd  $\triangleleft$  $\triangleright$ Aide F14 × \* F13 **⊹⊹ \$** MAJ. F12 מ-ם: := -ø F11 :o ~o <u>a</u> 11 0 0 \_\_\_\_ F10 ¥ **-∞** Σ Е 2 Z F8 I 7 ∞ ಅ В F7 Ō က% > F6 R \0\**4** Ω ш \* m × ဟ ≥ 0 4 = 0 Ε4 4 Ø F3 ۸۷ K! F2 MAJ. Ŧ

LJ-03275-TI0

F20 Ein-gabe LJ-03234-TI0 F19 PF3 6 9 က F18 2 7 ∞ F17 Bild Lö: schen Ausführen ₹ <sub>Pill</sub> Ein-fügen  $\triangleleft$  $\triangleright$ Hilfe F14 × \* F13 ખ છ F12 <u>©:⊃</u> F11 <u>ر</u>o: e-₾ 0 \_ ი F10 ¥ Σ  $\sim$   $\infty$ Е 2 z F8 I 7 В 80 F7 Ō ည% > F6 R **@** a ш \* m × F2 ဟ ≥ 0 4 = 0 Ε4 4  $\bigcirc \ \overline{\bigcirc}$ Ø F3 ۸۷ Kombi-zeichen K! ⑦ F2 F

Figure A-24 Swiss-German VT Keyboard

MA-0335-93.GRA 23 F19 F18 F17 Next Δ 8 Prev ◁  $\triangleright$ 윰 Find Select  $\nabla$ ¥ F13 ≥ چ چ F12 Compose Character Ξ В 윤 6 82 Ŀ æ 比 മ 7 E € **F**2 Σ 돌

Figure A-25 Turkish-F VT Keyboard

MA-0336-93.GRA F20 Enter F19 F18 F17 Next Δ å Prev ⊲  $\triangleright$ 윰 Select  $\nabla$ F4 F13 Compose Character F12 Ξ Ś Alt Function F10 F3 œ I ω F1 ပာ Δ 比 တ Alt Function 7 ⋖ æ Compose Character Ø F2 Σ Shift 돌

Figure A-26 Turkish-Q VT Keyboard

## **Enhanced PC Keyboards**

This appendix shows the non-spacing diacritical marks and the keyboard layouts for VT520 Enhanced PC keyboards.

#### **B.1 Summary of Non-Spacing Diacritical Marks**

Table B-1 lists the non-spacing diacritical marks within square brackets [].

Table B-1 Enhanced PC Keyboard Non-Spacing Diacritical Marks

EPC Keyboard	Acute	Breve	Caron	Cedilla	Circumflex	Dieresis	Dot
Austrian/German	[′]				[^]		
Belgian	[′]				[^]	["]	
Canadian (French)	[1]			[,]	[^]	["]	
Czech	[1]		[^]			["]	
Danish	[1]				[^]	["]	
Dutch	[1]			[,]	[^]	["]	
Finnish	[1]				[^]	["]	
French					[^]	["]	
Greek						["]	
Hebrew (none)							
Hungarian	[′]	[~]	[^]	[']	[^]	["]	[ ]
Italian (none)							
Latin American	[′]				[^]	["]	
Norwegian	[′]				[^]	["]	
Polish	[′]						
Portuguese	[′]				[^]	["]	
Romanian	[′]	[~]	[^]	[']	[^]	["]	[ ]
Russian (none)							
SCS (none)							
Slovak	[′]		[']			["]	
Spanish	[1]				[^]	["]	
Swedish	[′]				[^]	["]	
Swiss-French	[′]				[^]	["]	
Swiss-German	[′]				[^]	["]	
Turkish-Q							

(continued on next page)

#### **Enhanced PC Keyboards B.1 Summary of Non-Spacing Diacritical Marks**

Table B-1 (Cont.) Enhanced PC Keyboard Non-Spacing Diacritical Marks

EPC Keyboard	Double acute	Grave	Ogonek	Ring	Tilde	Tonos
German		[`]				
Belgian		[`]			[~]	
Canadian (French)		[`]				
Czech		[1]				
Danish		[1]			[~]	
Dutch		[1]			[~]	
Finnish		[1]			[~]	
French						
Greek						[¹]
Hebrew (none)						
Hungarian	["]	[1]	$[\iota]$	[°]	[~]	
Italian (none)						
Latin American		[`]				
Norwegian		[`]			[~]	
Polish			$[\iota]$			
Portuguese		[`]			[~]	
Romanian	["]	[`]	$[\iota]$	[°]	[~]	
Russian (none)						
SCS (none)						
Slovak		[`]				
Spanish		[`]				
Swedish		[`]			[~]	
Swiss-French		[1]			[~]	
Swiss-German		[1]			[~]	
Turkish-Q		[1]				

### **B.2 Enhanced PC Keyboards**

The Enhanced PC keyboards for use with the VT520 video terminal are shown in the figures that follow. In the figures, the shading on the keycaps indicates a non-spacing diacritical character. Exceptions: Hebrew, Hungarian, Polish, Romanian, and Russian.

Note
The keyboards shipped with the product may not look exactly like those illustrated here. Different fonts may be used, and some characters may not look the same.

LJ-03212-TI0 Pild ★ 3 Bild ← **₽** Entf ∱ ي ∞+ 2 حہ **O** Einfg **₹**□ ₽ → ₩ ← **†** Pos 1 Ende  $\rightarrow$ Einfg Entf + Strg F11 l F10 :∢ :⊃ F9 :0 d II O <u>ه</u> F8 ~െ ¥ F7 ≥ œ F6 Z I Z F5 ∞ ಅ В G 22% Ь4 2 ပ <del>\$</del>4 ۵ F3 Ξ တက F2 ഗ > ΑĦ 4 Ø ۸۷ Strg

Figure B-1 Austrian/German Enhanced PC Keyboard

Figure B-2 Belgian Enhanced PC Keyboard




Figure B-3 British/U.K. Enhanced PC Keyboard





Figure B-4 Canadian-English/North American Enhanced PC Keyboard



LJ-03225-TI0 Entr φŤ ო∰ ი# ∞← 2 ~> o Inser Mun **†** Arrét défil Ē K  $\rightarrow$ + Ctrl F11 ۸ v F10 ---AltCar F9 **Ш** -۵ 0 1/4 ഗ്ര 0 F8 က -– റ ¥ 7 F7 Σ  $\infty$ ) F6 Z **∞** ► I F5 ω 0 ج G > က်ွ Ε4 ш œ \$ <del>4</del> ပ ۵ F3 Ш Gγ × **(**M ഗ F2 ≥ (6) ¥ Ν 8 ⋖ Ø **☆** ¥

Fix Maj

Ctrl

Figure B-5 Canadian-French Enhanced PC Keyboard

MA-0300-93.GRA Scroll Lock Caps Lock Num Lock E Page Down Page Up Saroll Home 펿 F12 £ Ξ Shift 윤 £ ¥ æ 4 æ % 7 æ 22 ¥ Caps Lock Shift 돨 Tab

Figure B-6 Czech Enhanced PC Keyboard

Figure B-7 Danish Enhanced PC Keyboard




Figure B-8 Dutch Enhanced PC Keyboard




Figure B-9 Finnish Enhanced PC Keyboard




Figure B-10 French Enhanced PC Keyboard






Figure B-11 Greek Enhanced PC Keyboard



#### Enhanced PC Keyboards B.2 Enhanced PC Keyboards






Figure B-13 Hungarian Enhanced PC Keyboard

Figure B-14 Italian Enhanced PC Keyboard





Figure B-15 Latin American Enhanced PC Keyboard



LJ-03214-TI0 **9** မ PgDn Pel φŧ ∞← 2 7→ Num **o** = Page Down Page Up **†** Scroll Lock End **→** + Ctrl F11 7 F10 AltGr ∘∢ F9 Ø Ь 110 0 Ь8 \_ ი ¥ F7 Σ n F6 z I F2 Ω જ ಅ G 22% > F4 ш **∝** ₩ ပ **¤4** ۵ F3 Ш 3 # 3 # × ഗ F2 ≥ ΑĦ Ν = 0 ⋖ Ø ۸۷ Caps

Figure B-16 Norwegian Enhanced PC Keyboard

Figure B-17 Polish Enhanced PC Keyboard





Figure B-18 Portuguese Enhanced PC Keyboard




MA-0301-93.GRA Scroll Lock Caps Lock Num Lock End Page Down Scroll Lock 뎚 F12 돌 Ξ Shift 5 F9 ¥ œ F7 æ 52 (8) 7 Ф 23 F2 ¥ ø Shift Caps 돌

Figure B-19 Romanian Enhanced PC Keyboard

## **Enhanced PC Keyboards B.2 Enhanced PC Keyboards**

Figure B-20 Russian Enhanced PC Keyboard Scroll Lock - E Page Down Page Up Scroll End Backspace F12 Enter Ę Ξ Shift F10 :[-] F9 Ä % 2 o ы 8 Ħ Р E P6 F2 В Σ 4 ပ В æ S PI F2 Ε Ð Shift Caps Ę Tab

Figure B-21 SCS Enhanced PC Keyboard



MA-0302-93.GRA Scroll Lock Caps Lock Num Lock E Page Down Page Up Saroll Home 펿 F12 £ Ξ Shift 윤 අ ¥ æ 4 æ % 7 **∝** ပ æ 22 (9) ≥ ¥ Caps Lock Shift 돨 Tab

Figure B-22 Slovak Enhanced PC Keyboard

Figure B-23 Spanish Enhanced PC Keyboard




Figure B-24 Swedish Enhanced PC Keyboard





Figure B-25 Swiss-French Enhanced PC Keyboard



LJ-03220-T10 Pild ★ 3 Bild ← ∱ ي ∞← 2 ح⊳ **O** Einfg **₹**□ ₽ → **†** Pos 1 Ende **→** Einfg Entf + Strg F11 \_\_ : **⊹**\$ 1 F10 ~a:a •:= F9 Φ:0 Ъ 110 0 F8 \_ი ¥ F7 ઇ્ય Σ N F6 z I 7 % O F5 8 G ည% > Ь4 ш ∝ ပ o∿**4** ۵ F3 Ш \* × က ഗ F2 >

(6)

Ø

⋖

Caps Lock

= 0

¥

Strg

Figure B-26 Swiss-German Enhanced PC Keyboard

MA-0303-93.GRA Scroll Lock Caps Lock Num Lock E Page Down Saroll ם F12 £ Ξ Shift 윤 අ ¥ œ Ŀ ድ 8 ß 23 ¥ (9) ø Esc Caps Lock Shift 돌

Figure B-27 Turkish Enhanced PC Keyboard

### **ASCII Keycodes and Local Functions**

### C.1 PC Keyboard

Table C-1 through Table C-11 list the keycodes sent by individual keys in each mode for the PC keyboard. The Alt key does not effect the keycode sent unless specified.

Table C-1 WYSE and TVI Modes Function Keys for PC Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
F1	SOH @ CR	SOH ' CR	80 (Hex)	90 (Hex)
F2	SOH A CR	SOH a CR	81 (Hex)	91 (Hex)
F3	SOH B CR	SOH b CR	82 (Hex)	92 (Hex)
F4	SOH C CR	SOH c CR	83 (Hex)	93 (Hex)
F5	SOH D CR	SOH d CR	84 (Hex)	94 (Hex)
F6	SOH E CR	SOH e CR	85 (Hex)	95 (Hex)
F7	SOH F CR	SOH f CR	86 (Hex)	96 (Hex)
F8	SOH G CR	SOH g CR	87 (Hex)	97 (Hex)
F9	SOH H CR	SOH h CR	88 (Hex)	98 (Hex)
F10	SOH I CR	SOH i CR	89 (Hex)	99 (Hex)
F11	SOH J CR	SOH j CR	8A (Hex)	9A (Hex)
F12	SOH K CR	SOH k CR	8B (Hex)	9B (Hex)
Print Screen	ESC P	ESC P	Toggle Autoprint	Toggle Autoprint
Scroll Lock	Hold	Hold	Hold	Hold
Pause	Disconnect	Send Answerback	Break	Toggle Block Mode

Table C-2 WYSE and TVI Modes Function Keys for PC Keyboard

Key	Alt	Alt/Shift	Alt/Ctrl	Alt/Shift/Ctrl
Print Screen	Set-Up	Soft Reset	ESC P	Toggle Autoprint (Note)
Pause	SOH N CR	SOH n CR	Break	9E (Hex) (Note)

#### **ASCII Keycodes and Local Functions** C.1 PC Keyboard

Table C-3 WYSE and TVI Modes Editing Keys for PC Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
Insert	ESC q	ESC r	Toggle Insert Mode	Toggle Insert Mode
Home	1E (Hex)	ESC {	Toggle Auto Panning	Home Cursor and Clear Page
Page Up	ESC J	ESC J	Display Previous Page	Display Previous Page
Delete	ESC W	ESC R	ESC W	ESC R
End	ESC T	ESC Y	ESC T	Screen Saver
Page Down	ESC K	ESC K	Display Next Page	Display Next Page

Table C-4 WYSE and TVI Modes Cursor Keys on PC Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
$\uparrow$	VT	VT†	Roll Active Page Up	Speed Scrolling Rate
$\downarrow$	LF‡	LF	Roll Active Page Down	Slow Scrolling Rate
$\Rightarrow$	FF	FF	Change Status Line Type	Change Status Line Type
<b>=</b>	BS	BS	BS	BS

<sup>†&</sup>quot;ESC j" for TVI 925 and TVI 950 emulations.

Table C-5 WYSE and TVI Modes Numeric Keys for PC Keyboard, NumLock = Off

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
0	ESC r	ESC q	Display Page 0	ESC q
1	ESC T	ESC Y	Display Page 1	Toggle Monitor Mode
2	$LF^1$	LF	Display Page 2	LF
3	ESC K	ESC K	Display Page 3	ESC K
4	BS	BS	Display Page 4	BS
5	5	5	Display Page 5	5
6	FF	FF	FF	6
7	1E (Hex)	ESC {	1E (Hex)	ESC {
8	VT	$\mathrm{VT}^2$	VT	VT
9	ESC J	ESC J	ESC J	ESC J
/	1	/	/	/
*	*	*	*	*
-	-	-	Raise Split Line	Toggle Split Screen Mode
+	+	+	+	+
	7F (Hex)	7F (Hex)	7F (Hex)	Print Page
Enter	CR	Toggle Keyclick	CR	CR

 $<sup>^1\</sup>mbox{\tt"}16$  (Hex)" for TVI 925 and TVI 950 emulations.

<sup>‡&</sup>quot;16 (Hex)" for TVI 925 and TVI 950 emulations.

 $<sup>^2\</sup>hbox{\tt "ESC}\ j\hbox{\tt "}$  for TVI 925 and TVI 950 emulations.

Table C-6 WYSE 160 and TVI Modes Numeric Keys for PC Keyboard, NumLock = On

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
0	0	0	0	0
1	1	1	1	1
2	2	2	2	2
3	3	3	3	3
4	4	4	4	4
5	5	5	5	5
6	6	6	6	6
7	7	7	7	7
8	8	8	8	8
9	9	9	9	9
/	/	/	/	1
*	*	*	*	*
-	-	-	-	-
+	+	+	+	+
				-
Enter	CR	CR	CR	CR

Table C-7 ADDS A2 Function Keys on PC Keyboard

Key	Unmodified	Shift	Ctrl (Hex)	Shift/Ctrl (Hex)
F1	STX 1 CR	STX!CR	80	90
F2	STX 2 CR	STX " CR	81	91
F3	STX 3 CR	STX # CR	82	92
F4	STX 4 CR	STX \$ CR	83	93
F5	STX 5 CR	STX % CR	84	94
F6	STX 6 CR	STX & CR	85	95
F7	STX 7 CR	STX ' CR	86	96
F8	STX 8 CR	STX (CR	87	97
F9	STX 9 CR	STX ) CR	88	98
F10	STX : CR	STX * CR	89	99
F11	STX; CR	STX + CR	8A	9A
F12	STX < CR	STX , CR	8B	9B

## ASCII Keycodes and Local Functions C.1 PC Keyboard

Table C-8 ADDS A2 Editing Keys on PC Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
Insert	ESC q	ESC r	Toggle Insert Mode	Toggle Insert Mode
Home	SOH	SOH	Toggle Auto Panning	Home Cursor and Clear Page
Page Up	ESC J	ESC J	Display Previous Page	Display Previous Page
Delete	ESC W	ESC l	ESC W	ESC I
End	ESC K	ESC k	ESC K	Screen Saver
Page Down	ESC J	ESC J	Display Next Page	Display to Next Page

Table C-9 ADDS A2 Cursor Keys on PC Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
$\uparrow$	1A (Hex)	1A (Hex)	Roll Active Page Up	Speed Scrolling Rate
$\downarrow$	LF	LF	Roll Active Page Down	Speed Scrolling Rate
$\Rightarrow$	ACK	ACK	Change Status Line Type	Change Status Line Type
<b>=</b>	15 (Hex)	15 (Hex)	15 (Hex)	15 (Hex)

Table C-10 ADDS A2 Mode Numeric Keypad Keys on PC Keyboard; NumLock = Off

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
0	ESC r	ESC q	Display Page 0	ESC q
1	ESC K	ESC K	Display Page 1	Toggle Monitor Mode
2	LF	LF	Display Page 2	LF
3	ESC J	ESC J	Display Page 3	ESC J
4	15(Hex)	15(Hex)	Display Page 4	15(Hex)
5	5	5	Display Page 5	5
6	ACK	ACK	ACK	6
7	SOH	SOH	SOH	SOH
8	1A(Hex)	1A(Hex)	1A(Hex)	1A(Hex)
9	ESC J	ESC J	ESC J	ESC J
/	/	/	/	/
*	*	*	*	*
-	-	-	Raise Split Line	Toggle Split Screen Mode
+	+	+	+	+
	7F (Hex)	7F (Hex)	7F (Hex)	Print Page
Enter	CR	Toggle Keyclick	CR	CR

# ASCII Keycodes and Local Functions C.1 PC Keyboard

Table C-11 ADDS A2 Mode Numeric Keypad Keys on PC Keyboard; NumLock = On

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
0	0	0	0	0
1	1	1	1	1
2	2	2	2	2
3	3	3	3	3
4	4	4	4	4
5	5	5	5	5
6	6	6	6	6
7	7	7	7	7
8	8	8	8	8
9	9	9	9	9
/	/	/	/	/
*	*	*	*	*
-	-	-	-	-
+	+	+	+	+
	•			
Enter	CR	CR	CR	CR

## **ASCII Keycodes and Local Functions** C.2 DEC VT Keyboard

#### C.2 DEC VT Keyboard

Table C-12 through Table C-19 list the keycodes sent by individual keys in each mode for VT keyboards. The Alt key does not effect the keycode sent unless specified.

Table C-12 WYSE and TVI Modes Function Keys for DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
F1	Toggle Hold Screen	Toggle Hold Screen	Toggle Hold Screen	Toggle Hold Screen
F2	ESC P	ESC P	Toggle AutoPrint	Toggle AutoPrint
F3	Setup	Soft Reset	82 (Hex)	92 (Hex)
F4	Toggle Block Mode	ESC 7	Toggle Block Mode	ESC 7
F5	Break	Disconnect	Send Answerback	Toggle Block Mode
F6	SOH E CR	SOH e CR	85 (Hex)	95 (Hex)
F7	SOH F CR	SOH f CR	86 (Hex)	96 (Hex)
F8	SOH G CR	SOH g CR	87 (Hex)	97 (Hex)
F9	SOH H CR	SOH h CR	88 (Hex)	98 (Hex)
F10	SOH I CR	SOH i CR	89 (Hex)	99 (Hex)
F11	SOH J CR	SOH j CR	8A (Hex)	9A (Hex)
F12	SOH K CR	SOH k CR	8B (Hex)	9B (Hex)
F13	SOH L CR	SOH l CR	8C (Hex)	9C (Hex)
F14	SOH M CR	SOH m CR	8D (Hex)	9D (Hex)
F15	SOH N CR	SOH n CR	8E (Hex)	9E (Hex)
F16	SOH O CR	SOH o CR	8F (Hex)	9F (Hex)
F17	SOH P CR	SOH p CR	SOH P CR	SOH p CR
F18	SOH Q CR	SOH q CR	SOH Q CR	SOH q CR
F19	SOH R CR	SOH r CR	SOH R CR	SOH r CR
F20	SOH S CR	SOH s CR	SOH S CR	SOH s CR

Table C-13 WYSE and TVI Modes Editing Keys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
Find	n/a	n/a	n/a	n/a
Insert	ESC Q	ESC E	ESC Q	ESC E
Remove	7F (Hex)	7F (hex)	7F (Hex)	7F (Hex)
Select	n/a	n/a	n/a	n/a
Prev	ESC J	ESC J	Move to Previous Page	Move to Previous Page
Next	ESC K	ESC K	Move to Next Page	Move to Next Page

Table C-14 WYSE and TVI Modes Cursor Keys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
$\Box$	VT	$VT^1$	Roll Active Page Up	Speed Scrolling Rate
$\downarrow$	$\mathrm{LF}^2$	LF	Roll Active Page Down	Speed Scrolling Rate
⇒	FF	FF	Change Status Line Type	Change Status Line Type
<b>=</b>	BS	BS	BS	BS

 $<sup>^1\</sup>mbox{"ESC}\ j\mbox{"}$  for TVI 925 and TVI 950 emulations.

Table C-15 WYSE and TVI Modes Numeric Keypad PF Keys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
PF1	ESC Q	ESC E	ESC Q	ESC E
PF2	ESC W	ESC R	ESC W	ESC R
PF3	ESC T	ESC Y	ESC T	Screen Saver
PF4	ESC r	ESC q	Toggle Insert Mode	Toggle Insert Mode
0	0	0	Display Page 0	0
1	1	1	Display Page 1	Toggle Monitor Mode
2	2	2	Display Page 2	2
3	3	3	Display Page 3	3
4	4	4	Display Page 4	4
5	5	5	Display Page 5	5
6	6	6	6	6
7	7	7	7	7
8	8	8	8	8
9	9	9	9	9
-	-	-	Raise Split Line	Toggle Split Screen Mode
,	,	,	Lower Split Line	Cursor Drag Mode
				Print Page
Enter	CR	Toggle Keyclick	CR	CR

Table C-16 ADDS A2 Function Keys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
F1	Toggle Hold Screen	Toggle Hold Screen	Toggle Hold Screen	Toggle Hold Screen
F2	ESC P	ESC P	Toggle AutoPrint	Toggle AutoPrint
F3	Setup	Soft Reset	82 (Hex)	92 (Hex)
F4	Toggle Block Mode	ESC 7	Toggle Block Mode	ESC 7
F5	Break	Disconnect	Send Answerback	Toggle Block Mode
F6	STX 6 CR	STX & CR	85 (Hex)	95 (Hex)
				(continued on next page)

 $<sup>^2\</sup>mbox{\tt"}16$  (Hex)" for TVI 925 and TVI 950 emulations.

## **ASCII Keycodes and Local Functions** C.2 DEC VT Keyboard

Table C-16 (Cont.) ADDS A2 Function Keys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
F7	STX 7 CR	STX ' CR	86 (Hex)	96 (Hex)
F8	STX 8 CR	STX (CR	87 (Hex)	97 (Hex)
F9	STX 9 CR	STX ) CR	88 (Hex)	98 (Hex)
F10	STX: CR	STX * CR	89 (Hex)	99 (Hex)
F11	STX; CR	STX + CR	8A (Hex)	9A (Hex)
F12	STX < CR	STX, CR	8B (Hex)	9B (Hex)
F13	STX = CR	STX - CR	8C (Hex)	9C (Hex)
F14	STX > CR	STX . CR	8D (Hex)	9D (Hex)
F15	STX?CR	STX / CR	8E (Hex)	9E (Hex)
F16	STX @ CR	STX 0 CR	8F (Hex)	9F (Hex)
F17	STX A CR	STX 1 CR	STX A CR	STX 1 CR
F18	STX B CR	STX 2 CR	STX B CR	STX 2 CR
F19	STX C CR	STX 3 CR	STX C CR	STX 3 CR
F20	STX D CR	STX 4 CR	STX D CR	STX 4 CR

Table C-17 ADDS A2 Editing Keys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
Find	n/a	n/a	n/a	n/a
Insert	ESC Q	ESC M	ESC Q	ESC M
Remove	7F (Hex)	7F (Hex)	7F (Hex)	7F (Hex)
Select	n/a	n/a	n/a	n/a
Prev	ESC J	ESC J	Move to Previous Page	Move to Previous Page
Next	ESC J	ESC J	Move to Next Page	Move to Next Page

Table C-18 ADDS A2 Cursor Keys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
$\uparrow$	1A (Hex)	1A (Hex)	Roll Active Page UP	Speed Scrolling Rate
$\downarrow$	LF	LF	Roll Active Page Down	Speed Scrolling Rate
$\Rightarrow$	ACK	ACK	Change Status Line Type	Change Status Line Type
<b>=</b>	15 (Hex)	15 (Hex)	15 (Hex)	15 (Hex)

Table C-19 ADDS A2 Numeric Keypad PFKeys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
PF1	ESC Q	ESC M	ESC Q	ESC M
PF2	ESC W	ESC l	ESC W	ESC l

Table C-19 (Cont.) ADDS A2 Numeric Keypad PFKeys on DEC VT Keyboard

Key	Unmodified	Shift	Ctrl	Shift/Ctrl
PF3	ESC K	ESC k	ESC K	Screen Saver
PF4	ESC r	ESC q	Toggle Insert Mode	Toggle Insert Mode
0	0	0	Display Page 0	0
1	1	1	Display Page 1	Toggle Monitor Mode
2	2	2	Display Page 2	2
3	3	3	Display Page 3	3
4	4	4	Display Page 4	4
5	5	5	Display Page 5	5
6	6	6	6	6
7	7	7	7	7
8	8	8	8	8
9	9	9	9	9
-	-	-	Raise Split Line	Toggle Split Screen Mode
,	,	,	Lower Split Line	Cursor Drag Mode
				Print Page
Enter	CR	Toggle Keyclick State	CR	CR

#### **C.3 ASCII Local Functions**

Table C-20 and Table C-21 list the local functions in ASCII code mode and PC scancode mode. In the tables, keypad is abbreviated as (kpd).

Table C-20 Local Functions in ASCII Code Mode

Function	DEC VT Layout	EPC Layout
±Hold Screen	F1	Scroll Lock
Print page	Ctrl/Shift/ . (kpd)	Ctrl/Shift/ . (kpd)
Set-Up	F3	Alt/Print Screen
	Caps Lock/F3	Caps Lock/Print Screen
Break	F5	Ctrl/Pause
Hard Reset	Ctrl/F3 in Set-Up	
Soft Reset	Shift/F3	Alt/Shift/Print Screen
±Autoprint Mode	Ctrl/F2	Ctrl/Print Screen
	Ctrl/Shift/F2	Ctrl/Shift/Print Screen
		Alt/Ctrl/Shift/Print Screen
Disconnect	Shift/F5	Pause
Send Answerback	Ctrl/F5	Shift/Pause
Display Next Page	Ctrl/Next	Ctrl/Page Down
		(continued on next page)

# ASCII Keycodes and Local Functions C.3 ASCII Local Functions

Table C-20 (Cont.) Local Functions in ASCII Code Mode

Function	DEC VT Layout	EPC Layout
	Shift/Ctrl/Next	Ctrl/Shift/Page Down
Active Other Window	Ctrl/Next or Ctrl/Prev	Ctrl/Page Down or
		Ctrl/Shift/Page Down
		or Ctrl/Page Up or Ctrl/Shift/Page Up
Display Prev. Page	Ctrl/Prev	Ctrl/Page Up
Display 1 Tev. 1 age	Shift/Ctrl/Prev	Ctrl/Shift/Page Up
Display Page 0	Ctrl/0 (kpd)	Ctrl/0 (kpd)
Display Page 1	Ctrl/1 (kpd)	Ctrl/1 (kpd)
Display Page 2	Ctrl/2 (kpd)	Ctrl/2 (kpd)
Display Page 3	Ctrl/3 (kpd)	Ctrl/3 (kpd)
Display Page 4	Ctrl/4 (kpd)	Ctrl/4 (kpd)
Display Page 5	Ctrl/5 (kpd)	Ctrl/5 (kpd)
±Block Mode	F4	Ctrl/Shift/Pause
IBIOCK MODE	Ctrl/F4	Ouvermen adde
	Shift/Ctrl/F5	
Change Status Line Display	Ctrl/⇒	Ctrl/⇒
	Ctrl/Shift/⇒	Ctrl/Shift/⇒
±Insert Mode	Ctrl/PF4	Ctrl/Insert
	Ctrl/Shift/PF4	Ctrl/Shift/Insert
±Monitor Mode	Ctrl/Shift/1 (kpd)	Ctrl/Shift/1 (kpd)
Screen Saver	Ctrl/Shift/PF3	Ctrl/Shift/End
Speed Scroll Rate	Ctrl/Shift/↑	Ctrl/Shift/介
Slow Scroll Rate	Ctrl/Shift/↓	Ctrl/Shift/↓
Home cursor and Clear Display		Ctrl/Shift/Home
Roll Active Window Up In Page	Ctrl/介	Ctrl/介
Roll Active Window Down In Page	Ctrl/↓	Ctrl/U
±Toggle Split screen	Ctrl/Shift/ - (kpd)	Ctrl/Shift/ - (kpd)
Raise Split Line	Ctrl/ - (kpd)	Ctrl/ - (kpd)
Lower Split Line	Ctrl/, (kpd)	n/a
Adjust Window to Include Cursor		Ctrl/Home
±Cursor Drag Mode	Ctrl/Shift/ , (kpd)	n/a
±Caps Lock State	Lock	Caps Lock
±Num Lock State	n/a	NumLock
±Keyclick State	Shift/Enter (kpd)	Shift/Enter (kpd)

# ASCII Keycodes and Local Functions C.3 ASCII Local Functions

Table C-21 Local Functions in PC Scancode Mode

Function	DEC VT Layout	EPC Layout
Set-Up	Alt/Print Screen	Caps Lock/Print Screen or Caps Lock/F3
Hard Reset	Ctrl/Shift/F3	Ctrl/Shift/Select
Turn On Block Mode	Compose/PF1	L Alt/NumLock
Turn Off Block Mode	Compose/PF1	Shift/Ctrl/Pause

### VT520 Termcap Data

#### **D.1 Termcap Emulations**

The VT520 and the VT525 terminals have multiple terminal emulations. The following "termcap" and "terminfo" data is for use with the ANSI VT emulations. The ASCII emulations use existing termcap and terminfo data commonly found on UNIX systems.

The VT525 is a color version of the VT520. Color capabilities are not standardized across UNIX and are not included here. Except for color, VT525 emulations are the same as the VT520. In the Termcap Data and Termcap Info code examples, you may change the "vt520" entry names to vt525 if desired.

#### D.1.1 Termcap Data:

```
d1|vt100|vt-100|pt100|pt-100|dec vt100:\
   :am:co#80:1i#24:c1=50\E[;H\E[2J:bs:cm=5\E[%i%d;%dH:nd=2\E[C:up=2\E[A:\V]]]
   \texttt{:ce=3} \\ \texttt{E[K:cd=50} \\ \texttt{E[J:so=2} \\ \texttt{E[7m:se=2} \\ \texttt{E[m:us=2} \\ \texttt{E[m:ue=2} \\ \texttt
   is=E>E[?11]E[?31]E[?41]E[?51]E[?7h]E[?8h:
    :if=/usr/lib/tabset/vt100:ku=\E[A:kd=\E[B:kr=\E[C:kl=\E[D:\E]]]
   :kh=\E[H:k1=\EOP:k2=\EOQ:k3=\EOR:k4=\EOS:pt:xn:sr=5\EM:\
   mb=E[5m:md=E[1m:me=E[0m:]]
   :GS=\E(0:GE=\E(B:\
   :GV=x:GH=q:G1=k:G2=1:G3=m:G4=j:GU=v:\
   :GD=w:GC=n:GL=u:GR=t:\
   :CL=\EOP:CR=\EOQ:WL=\EOR:WR=\EOS:\
   :UK=\E[A:DK=\E[B:LK=\E[D:RK=\E[C:\
    :PN=\E[5i:PS=\E[4i:\
    :cs=%i\E[%2;%2r:
d0 vt100n vt100 w/no init:\
   :is@:if@:tc=vt100:
# vt100 entry for use without automargins set
dn|vt100nam|vt100-nam|pt100nam|pt-100nam|DEC VT100 without automargins:\
    :am@:tc=vt100:
ds|vt100s|vt-100s|pt100s|pt-100s|dec vt100 132 cols 14 lines:\
   :li#14:tc=vt100w:
dt|vt100w|vt-100w|pt100w|pt-100w|dec vt100 132 cols:\
    co#132:li#24:is=\E>\E[?3h\E[?4l\E[?5l\E[?7h\E[?8h:\]]]
   :vs=\E[?3h:tc=vt100:
d6|vt420|DEC VT420 :\
   :am:mi:xn:xo:bs:pt:\
   :co#80:li#24:kn#3:\
   :ae=4\E(B:al=\E[L:as=2\E(0:cd=50\E[J:ce=3\E[K:\E]))
   :cl=50\E[;H\E[2J:cm=10\E[%i%d;%dH:cs=\E[%i%d;%dr:\]]
    dc=E[P:d]=E[M:e]=E[4]:ho=E[H:\
   :if=/usr/lib/tabset/vt100:\
                             \lim E[4h:\
```

### VT520 Termcap Data D.1 Termcap Emulations

#### D.1.2 Terminfo Data:

```
vt420 | DEC VT420 ,
                                                                                                               am, mir, xenl, xon,
                                                                                                                 cols#80, lines#24, vt#3,
                                                                                                               bel=^G, blink=\times[5m$<2>,
                                                                                                                 acsc='aaffqqjjkkllmmnnooppqqrrssttuuvvwwxxyyzz{{||}}~~,
                                                                                                               bold=E[1m$<2>, clear=E[;H]E[2J$<50>, cr=\r,
                                                                                                                 csr=\E[\%i\%p1\%d;\%p2\%dr, cub1=\b, cud1=\E[B, cuf1=\E[C,
                                                                                                                 cup=\E[%i%p1%d;%p2%dH$<10>, cuu1=\E[A, dch1=\E[P,
                                                                                                               dl1=\E[M, ed=\E[J$<50>, el=\E[K$<3>, home=\E[H, ht=\t,
                                                                                                                 if=/usr/lib/tabset/vt100, ill=\E[L, ind=\ED,
                                                                                                                   is2=E[1;24r]E[24;1H, is3=E[?67h]E[64;1"p,
                                                                                                                 kbs=^H, kcub1=\E[D, kcud1=\E[B, kcuf1=\E[C, kcuu1=\E[A, kcuf1=\E[C, kcuu1=\E[A, kcuf1=\E[C, kcuu1=\E[A, kcuf1=\E[C, kcuu1=\E[A, kcuf1=\E[A, kcuf1=
                                                                                                                 \label{eq:kf0} $$ kf0=\E[29^{,} kf1=\EOP, kf2=\EOQ, kf3=\EOR, kf4=\EOS, kf5=\E[17^{,} kf4=\EOS, kf5=\E[17^{,} kf4=\EOS, kf5=\E[17^{,} kf4=\EOS, kf5=\E[17^{,} kf4=\EOS, kf5=\EOS, kf5=\E
                                                                                                                 kf6=\E[18\sim, kf7=\E[19\sim, kf8=\E[20\sim, kf9=\E[21\sim, kf10=\E[29\sim, kf9=\E[21\sim, kf10=\E[29\sim, kf9=\E[21\sim, kf10=\E[29\sim, kf9=\E[21\sim, kf10=\E[29\sim, kf9=\E[21\sim, kf10=\E[29\sim, kf9=\E[21\sim, kf10=\E[29\sim, kf10=\E[29\sim, kf9=\E[21\sim, kf10=\E[29\sim, 
                                                                                                               rc=\E8, rev=\E[7m$<2>, rf=/usr/lib/tabset/vt100, ri=\EM,
                                                                                                               rmacs=\E(B$<4>, rmir=\E[41, rmso=\E[m, rmul=\E[m,
                                                                                                               rs3=\E[?67h\E[64;1"p,
                                                                                                                 rmsc=\E[?0;0r\E>\E[?31\E[?41\E[?51\E[?7h\E[?8h,
                                                                                                                 kfnd=\E[1\sim, kich1=\E[2\sim, kdch1=\E[3\sim,
                                                                                                                 knp=\E[6~, kpp=\E[5~, kslt=\E[4~,
                                                                                                                   sgr=\E[0%?%p6%t;1%;%?%p2%t;4%;%?%p4%t;5%;%?%p1%p3%|%t;7%;m%?%p9%t
                                                                                                                                                                               \E(0%e\E(B%;,
                                                                                                                   sgr0=\E[m$<2>, smacs=\E(0$<2>, smir=\E[4h, smso=\E[7m,
                                                                                                                   smul=\E[4m]
vt420nam|vt420-nam|v420n|DEC VT420 in vt100 emul. mode with NO AUTO WRAP mode,
         am@, use=vt420,
vt420pc | DEC VT420 w/PC keyboard,
         pctrm=USR_TERM:vt420pcdos:,
           kdch1=^?, khome=\E[H, kend=\E[4\sim]
           kf1=\E[11\sim, kf2=\E[12\sim, kf3=\E[13\sim, kf4=\E[14\sim, kf5=\E[15\sim, kf4=\E[14\sim, kf5=\E[15\sim, kf4=\E[14\sim, kf5=\E[15\sim, kf4=\E[14\sim, kf4=\E[14\sim, kf5=\E[15\sim, kf4=\E[14\sim, kf4=
                                                                                                                   kf6=\E[17-, kf7=\E[18-, kf8=\E[19-, kf9=\E[20-, kf10=\E[21-, kf9-\E[20-, kf10=\E[21-, kf9-\E[20-, kf10-\E[21-, kf9-\E[20-, kf10-\E[21-, kf9-\E[20-, kf10-\E[20-, kf10-\E[20-
                                                                                                                 kf11=\E[23\sim, kf12=\E[24\sim,
         kf13 = E[11;2^{,} kf14 = E[12;2^{,} kf15 = E[13;2^{,} kf16 = E[14;2^{,} kf16 = E[1
         kf17 = E[15;2^{,} kf18 = E[17;2^{,} kf19 = E[18;2^{,} kf20 = E[19;2^{,} kf17 = E[18;2^{,} kf20 = E[19;2^{,} kf20 = E[1
         kf21=\E[20;2\sim, kf22=\E[21;2\sim, kf23=\E[23;2\sim, kf24=\E[24;2\sim, kf24
         kf25=\E[23\sim, kf26=\E[24\sim, kf27=\E[25\sim, kf29=\E[28\sim, kf30=\E[29\sim, kf31=\E[31\sim, kf3
                                                                                                                                                                                                                                                                                                                                                                                                                                                      kf27=\E[25\sim, kf28=\E[26\sim, kf31=\E[31\sim, kf32=\E[32\sim,
                                                                                                               kf33=\E[33\sim, kf34=\E[34\sim, kf35=\E[35\sim, kf36=\E[36\sim,
      kf37 = E[23;2^{\circ}, kf38 = E[24;2^{\circ}, kf39 = E[25;2^{\circ}, kf40 = E[26;2^{\circ}, kf37 = E[26
         kf41=\E[28;2\sim, kf42=\E[29;2\sim, kf43=\E[31;2\sim, kf44=\E[32;2\sim, kf44
         kf45=\E[33;2\sim, kf46=\E[34;2\sim, kf47=\E[35;2\sim, kf48=\E[36;2\sim,
```

### VT520 Termcap Data D.1 Termcap Emulations

```
DECUDK
                                               if (key < 16) then value = key;
                                               else if (key < 21) then value = key + 1;
#
                                               else if (key < 25) then value = key + 2;
                                               else if (key < 27) then value = key + 3;
                                               else if (key < 30) then value = key + 4;
                                               else value = key + 5;
  pfx=\EP1;1|%?%{16}%p1%>%t%{0}%e%{21}%p1%>%t%{1}%e%{25}%p1%>%t
                                    \{2\}ee\{27\}$p1\}>$t8\{3\}8e8\{30\}$p1\}>$t8\{4\}8e8\{5\}8;$p1\}+8d/$p2\}8s\E\\,
  use=vt420,
vt420pcdos | DEC VT420 w/PC for DOS Merge,
  smsc=\E[?1;2r\E[34h]
                       rmsc=\E[?0;0r\E>\E[?31\E[?41\E[?51\E[?7h\E[?8h,
  dispc=%?%p2%{19}%=%t\E\023\021%e%p2%{32}%<%t\E%p2%c%e%p2%{127}%=%t
                                          E\177%e%p2%c%;,
  sgr@,
  sgr0=\E[0m]
  lines#25,
  use=vt420pc,
vt420f|DEC VT420 with VT kbd; VT400 mode; F1-F5 used as Fkeys,
  kdch1=^?, khome=\E[H,
   kf1 = \langle E[11^{-}, kf2 = \langle E[12^{-}, kf3 = \langle E[13^{-}, kf4 = \langle E[14^{-}, kf5 = \langle E[15^{-}, kf4 = \langle E[14^{-}, kf5 = \langle E[15^{-}, kf4 = \langle E[14^{-}, kf4 = \langle E
 lf1=\EOP, lf2=\EOQ, lf3=\EOR, lf4=\EOS,
  use=vt420,
# Use v420fn and v420pcn for LYRIX
vt420f-nam|v420fn|DEC VT420 no auto margins,
 am@, use=vt420f,
vt420pc-nam|v420pcn|DEC VT420 PC keyboard no auto margins,
  am@, use=vt420pc,
# vt520:
##
vt520 | DEC VT520,
vt520nam|vt520-nam|v520n|DEC VT520 in vt100 emul. mode with NO AUTO WRAP mode,
use=vt420nam,
vt520pc | DEC VT520 w/PC keyboard,
 use=vt420pc,
vt520pc-nam|v520pcn|DEC VT520 PC keyboard no auto margins,
 am@, use=vt420pc,
vt520pcdos DEC VT520 w/PC for DOS Merge,
  use=vt420pcdos,
```

### **ANSI Control Function Index**

#### **E.1 ANSI Index by Final Character**

This index lists the ANSI host interface commands according to their final character for reference in software programs. Each command has a mnemonic reference, which is in Chapter 5.

Table E-1 ANSI Control Functions Index by Final Character

<b>Control Function</b>	Description	Reference
BEL	Bell	
BS	Backspace	
OSC 2 1; <name></name>	Set Window Title	DECSWT
OSC 2 L; <name></name>	Set Icon Name	DECSIN
ESC # 3	Double Height Line Top	DECDHL
ESC # 4	Double Height Line Bottom	DECDHL
ESC # 5	Single Width Line	DECSWL
ESC # 6	Double Width Line	DECDWL
ESC 6	Back Index	DECBI
ESC 7	Save Cursor	DECSC
ESC 8	Restore Cursor	DECRC
ESC # 8	Screen Alignment Pattern	DECALN
ESC 9	Forward Index	DECFI
ESC xx	Display PC character xx (hex) (SCO Console)	SCODPCC
ESC) 1	DDD1 - Set DECRLM, DECHEBM, and DECHCEM	DDD1
ESC ) B	DDD2 - ASCII to G1; reset DECRLM2	DDD2
ESC (1	DDD3 - ASCII to G0	DDD3
A		
CSI Pl A	Cursor Up	CUU
CSI Pn a	Horizontal Position Relative	HPR
В		
CSI Pl B	Cursor Down	CUD

## ANSI Control Function Index E.1 ANSI Index by Final Character

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

Control Function	Description	Reference
С		
CSI Pc C	Cursor Forward	CUF
CSI c or CSI 0 c	Device Attributes	DA1
CSI ? <i>Psc ; PS1 ; Psn</i> c	Response to Device Attributes	DA1
CSI > c or CSI > 0 c	Secondary Device Attributes	DA2
CSI > 64; <i>Pv</i> ; 0 c	VT520 response to Sec Device Attributes (VT keyboard)	DA2
CSI > 64; <i>Pv</i> , 1 c	VT520 response to Sec Device Attributes (PC keyboard)	DA2
CSI > 65; <i>Pv</i> ; 0 c	VT525 response to Sec Device Attributes (VT keyboard)	DA2
CSI > 65; <i>Pv</i> , 1 c	VT525 response to Sec Device Attributes (PC keyboard)	DA2
CSI = c  or  CSI = 0 c	Tertiary Device Attributes	DA3
CSI ? 1; 2 c	VT100 terminal ID	DECTID
CSI ? 1; 0 c	VT101 terminal ID	DECTID
CSI ? 6 c	VT102 terminal ID	DECTID
CSI ? 62; 1; 2; 7; 8 c	VT220 North American	DECTID
CSI ? 62; 1; 2; 7; 8; 9 c	VT220 International	DECTID
CSI ? 63; 1; 2; 7; 8 c	VT320 North American	DECTID
CSI ? 63; 1; 2; 7; 8; 9 c	VT320 International	DECTID
CSI ? 64; 1; 2; 6; 7; 8; 9; 15; 18; 21 c	VT420	DECTID
CSI ? 65;1;2;6;7;8;9;12;23;24;46 c	VT520 level 1	DECTID
CSI ? 65;1;2;6;7;8;9;12;15;18;19; 21;23;24;42;44;45;46 c	VT520 level 2-4	DECTID
CSI ? 65;1;2;7;9;12;18;19;21;23;24; 42;44;45;46 c	VT520 level 4	DECTID
CSI ? 65;1;2;6;7;8;9;12;15;18;19;21; 22;23;24;42;44;45;46 c	VT525 level 2-4	DECTID
CSI ? 65;1;2;7;9;12;18;19;21;22;23; 24;42;44;45;46 c	VT525 level 5	DECTID
ESC c	Reset to Initial state	RIS
D		
CSI Pc D	Cursor Backward	CUB
CSI <i>Pn</i> d	Vertical Line Position Absolute	VPA
ESC D	Index	IND
E		
CSI Pn E	Cursor Next Line	CNL
CSI <i>Pn</i> e	Vertical Position Relative	VPR
ESC E	Next Line	NEL

#### **ANSI Control Function Index E.1 ANSI Index by Final Character**

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

Control Function	Description	Reference
F		
CSI Pl; Pc f	Horizontal/Vertical Position	HVP
CSI Pn F	Cursor Previous Line	CPL
ESC SP F	Send 7-bit C1 Control character to host	S7C1T
G		
CSI Pn G	Cursor Horizontal Absolute	CHA
CSI Ps g	Clear Tabs	TBC
ESC SP G	Send 8-bit C1 Control character to host	S8C1T
Н		
CSI Pl; Pc H	Cursor Position	CUP
CSI P1Pn h	Set Mode	SM
CSI ? 1 h	Set Cursor Keys mode (application)	DECCKM
CSI 2 h CSI 3 h	Set Keyboard Action Mode Set Show Control Character Mode	KAM CRM
CSI ? 3 h	Set Column Mode (132 columns)	DECCOLM
CSI 4 h	Set Insert Mode	IRM
CSI ? 4 h	Set Scrolling Mode (smooth)	DECSCLM
CSI ? 5 h	Set Screen Mode (light)	DECSCNM
CSI ? 6 h	Set Origin Mode (in margins)	DECOM
CSI ? 7 h	Set Autowrap Mode	DECAWM
CSI ? 8 h	Set Autorepeat mode	DECARM
CSI 12 h	Set Send/Receive mode (Local echo off)	SRM
CSI ? 18 h	Set Print Form Feed Mode	DECPFF
CSI ? 19 h	Set Printer Extent Mode	DECPEX
CSI 20 h	Set Line Feed/New Line (NL)	LNM
CSI ? 25 h	Set Text Cursor Enable Mode (visible)	DECTCEM
CSI ? 34 h	Set Right-to-Left Mode	DECRLM
CSI ? 35 h CSI ? 36 h	Set Hebrew Keyboard Map Mode	DECHEBM DECHEM
CSI ? 30 II CSI ? 42 h	Set Hebrew Encoding Mode to 8-bit characters Set National 7-bit character	DECNEM
CSI ? 42 II	Set N.A./Greek Selection to N.A.	DECNAKB
CSI ? 58 h	Set (enter) ProPrinter Emulation Mode	DECIPEM
CSI ? 60 h	Set Horizontal Cursor	DECHCCM
CSI ? 61 h	Set Vertical Cursor Coupling	DECVCCM
CSI ? 64 h	Set Page Cursor Coupling	DECPCCM
CSI ? 66 h	Set Numeric Keypad Mode	DECNKM
CSI ? 67 h	Set Backarrow key mode (BS)	DECBKM
CSI ? 68 h	Set Data Processing Keys	DECKBUM
CSI ? 69 h	Set Vertical Split Screen Mode	DECVSSM
CSI ? 73 h	Set Transmit Rate Limiting	DECXRLM
CSI ? 81 h	Set Key Position Mode	DECKPM

## ANSI Control Function Index E.1 ANSI Index by Final Character

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

<b>Control Function</b>	Description	Reference
Н		
CSI ? 95 h	Set no clear screen on column change	DECNCSM
CSI ? 96 h	Set Right-to-Left Copy	DECRLCM
CSI 97 h	Set CRT Save Mode	DECCRTSM
CSI ? 98 h	Set Auto Resize	DECARSM
CSI ? 99 h	Set Modem Control Mode	DECMCM
CSI ? 100 h	Set Auto Answerback Mode	DECAAM
CSI ? 101 h	Set Conceal Answerback Message	DECCANSM
CSI ? 102 h	Set Ignore Null Mode	DECNULM
CSI ? 103 h	Set Half-Duplex Mode	DECHDPXM
CSI ? 104 h	Set Enable Secondary Keyboard Language Mode	DECESKM
CSI ? 106 h	Set Overscan Mode	DECOSCNM
CSI ? 108 h	Set Num Lock Mode	DECNUMLK
CSI ? 109 h	Set Caps Lock Mode	DECCAPSLK
CSI ? 110 h	Set Keyboard LED's Host Indicator Mode	DECKLHIM
CSI ? 111 h	Set Framed Windows Mode	DECFWM
CSI ? 112 h	Set Review Previous Lines	DECRPL
CSI ? 113 h	Set Host Wake-Up Mode	DECHWUM
CSI ? 114 h	Set Alternate Text Color Underline Mode	DECATCUM
CSI ? 115 h	Set Alternate Text Color Blink Mode	DECATCBM
CSI ? 116 h	Set Bold and Blink Style Mode	DECBBSM
CSI ? 117 h	Set Erase Color Mode	DECECM
ESC H	Set Horizontal Tabs	HTS
Ī		
CSI Pn I	Cursor Horizontal Forward Tab	CHT
CSI Ps i	Media Copy	MC
CSI 6 i	Start Printer-to-Host Session	MC
CSI 7 i	Stop Printer-to-Host Session	MC
CSI ? Ps i	Media Copy (DEC)	MC
CSI ? 8 i	Stop Printer-to-Host Session	MC
CSI ? 9 i	Start Printer-to-Host Session	MC
ESC I Dscs	Designate Character Set	SCS
J		
CSI Ps J	Erase in Display	ED
CSI ? Ps J	Selective Erase in Display	DECSED
К		
CSI Ps K	Erase in Line	EL
CSI ? Ps K	Selective Erase in Line	DECSEL
	(contin	ued on next page

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

<b>Control Function</b>	Description	Reference
L		
CSI Pn L	Insert Line	IL
CSI <i>P1Pn</i> l	Reset Mode	RM
CSI ? 1 l	Reset Cursor Keys mode (Cursor)	DECCKM
CSI 2 l	Reset Keyboard Action Mode	KAM
CSI ? 2 l	ANSI Mode	DECANM
CSI 3 l	Reset Show Control Character Mode	CRM
CSI ? 3 l	Reset Column Mode (80 columns)	DECCOLM
CSI 4 l	Reset Insert Mode (Replace)	IRM
CSI ? 4 l	Reset Scrolling Mode (jump)	DECSCLM
CSI ? 5 l	Reset Screen Mode (dark)	DECSCNM
CSI ? 6 l	Reset Origin Mode (upper left)	DECOM
CSI ? 7 l	Reset Autowrap Mode	DECAWM
CSI ? 8 l	Reset Autorepeat mode	DECARM
CSI 12 l	Reset Send/Receive mode (Local echo on)	SRM
CSI ? 18 l	Reset Print Form Feed Mode	DECPFF
CSI ? 19 l	Reset Printer Extent Mode	DECPEX
CSI 20 l	Reset Line Feed (LF)/New Line	LNM
CSI ? 25 l	Reset Text Cursor Enable Mode (invisible)	DECTCEM
CSI ? 34 l	Reset Right-to-Left Mode	DECRLM
CSI ? 35 l	Reset Hebrew Keyboard Map Mode to N.A.	DECHEBM
CSI ? 36 l	Reset Hebrew Encoding Mode to 7-bit characters	DECHCEM
CSI ? 42 l	Reset Multinational 8-bit characters	DECNRCM
CSI ? 57 l	Reset N.A./Greek Selection to Greek	DECNAKB
CSI ? 58 l	Reset (return from) ProPrinter Emulation Mode	DECIPEM
CSI ? 60 l	Reset Horizontal Cursor	DECHCCM†
CSI ? 61 l	Reset Vertical Cursor Coupling	DECVCCM
CSI ? 64 l	Reset Page Cursor Coupling	DECPCCM
CSI ? 66 l	Reset Numeric Keypad Mode	DECNKM
CSI ? 67 l	Reset Backarrow key mode (DEL)	DECBKM
CSI ? 68 l	Reset to Typewriter Keys	DECKBUM
CSI ? 69 l	Reset Vertical Split Screen Mode	DECVSSM
CSI ? 73 l	Reset Transmit Rate Limiting	DECXRLM
CSI ? 81 l	Reset Key Position Mode	DECKPM
CSI ? 95 l	Reset no clear screen on column change	DECNCSM
CSI ? 96 l	Reset Right-to-Left Copy	DECRLCM
CSI 97 l	Reset CRT Save Mode	DECCRTSM
CSI ? 98 l	Reset Auto Resize	DECARSM
CSI ? 99 l	Reset Modem Control Mode	DECMCM
CSI ? 100 l	Reset Auto Answerback Mode	DECAAM
CSI ? 101 l	Reset Conceal Answerback Message Mode	DECCANSM
CSI ? 102 l	Reset Ignore Null Mode	DECNULM
CSI ? 103 l	Reset Half-Duplex Mode	DECHDPXM
CSI ? 104 l	Reset Enable Secondary Keyboard Language Mode to Primary keyboard mapping	DECESKM
CSI ? 106 l	Reset Overscan Mode	DECOSCNM
CSI ? 108 l	Reset Num Lock Mode	DECNUMLK
CSI ? 109 l	Reset Caps Lock Mode	DECCAPSLK
CSI: 103 I		
	Reset Keyboard LED's Host Indicator Mode	DECKLHIM
CSI ? 110 l CSI ? 111 l	Reset Keyboard LED's Host Indicator Mode Reset Framed Windows Mode	DECKLHIM DECFWM

## ANSI Control Function Index E.1 ANSI Index by Final Character

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

Control Function	Description	Reference
L		
CSI ? 113 l	Reset Host Wake-Up Mode	DECHWUM
CSI ? 114 l	Set Alternate Text Color Underline Mode	DECATCUM
CSI ? 115 l	Reset Alternate Text Color Blink Mode	DECATCBM
CSI ? 116 l	Reset Bold and Blink Style Mode	DECBBSM
CSI ? 117 l	Reset Erase Color Mode	DECECM
M		
CSI Pn M	Delete Line(s)	DL
CSI Ps; ; Ps m	Select Graphic Rendition	SGR
ESC M	Reverse Index	RI
N		
CSI 0 n	DSR—Operating Status Response	DSR-Op
CSI 3 n	DSR—Operating Status Response	DSR-Op
CSI 5 n	DSR—Operating Status Request	DSR-Op
CSI 6 n	Cursor Position Report Request or DSR—CPR	CPR or
	• •	DSR-CPR
CSI ? 6 n	Extended Cursor Position Request, or	DECXCPR,
	DSR—Extended CPR	DSR-ExCPR
CSI ? 10 n	DSR—Printer Port Response	DSR-Print
CSI ? 11 n	DSR—Printer Port Response	DSR-Print
CSI ? 13 n	DSR—Printer Port Response	DSR-Print
CSI ? 15 n	DSR—Printer Port Request	DSR-Print
CSI ? 18 n	DSR—Printer Port Response	DSR-Print
CSI ? 19 n	DSR—Printer Port Response	DSR-Print
CSI ? 20 n	DSR—User-Defined Keys Response	DSR-UDK
CSI ? 21 n	DSR—User-Defined Keys Response	DSR-UDK
CSI ? 25 n	DSR—User-Defined Keys Request	DSR-UDK
CSI ? 26 n	DSR—Keyboard Status Request	DSR-KeyBd
CSI ? 27 ; <i>Pn</i> ; <i>Pst</i> ; <i>Ptyp</i> n	DSR—Keyboard Response	DSR-KeyBd
CSI ? 62 n	DSR—Macro Space Report Request	DECDMAC,
		DSR-MSR
CSI ? 63; <i>Pid</i> n	Memory Checksum Report Request or	DECCKSR,
	DSR—Memory Checksum Request	DSR-Mem
CSI ? 70 n	DSR—Data Integrity Report Response	DSR-Data
CSI ? 71 n	DSR—Data Integrity Report Response	DSR-Data
CSI ? 73 n	DSR—Data Integrity Report Response	DSR-Data
CSI ? 75 n	DSR—Data Integrity Report Request	DSR-Data
CSI ? Ps n	Response to Device Status Report	DSR
ESC N	Single Shift Two	SS
ESC n	Locking Shift Two	LS
0		
ESC O	Single Shift Three	SS
ESC o	Locking Shift Three	LS

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

Control Function	Description	Reference
P		
CSI Pn P	Delete Character	DCH
CSI Pn SP P	Page Position Absolute	PPA
CSI Pr + p	Secure Reset	DECSR
CSI Ps p	Select Set-Up Language	DECSSL
CSI <i>Ps</i> - p	Auto Repeat Rate	DECARR
CSI Ps SP p	Set Scroll Speed	DECSSCLS
CSI Pa \$ p	Request Mode (ANSI) Host to Terminal	DECRQM
CSI ? <i>Pd</i> \$ p	Request Mode (DEC) Host to Terminal	DECRQM
CSI ! p	Soft Terminal Reset	DECSTR
CSI Ps * p	Select ProPrinter Character Set	DECSPPCS
CSI Ps) p	Select Digital Printed Data Type	DECSDPT
CSI 6 <i>Ps1</i> ; <i>Ps2</i> ; " p	Select Conformance Level	DECSCL
CSI <i>Ps1; Ps2</i> , p	Load Time of Day	DECLTOD
DCS <i>Ps</i> \$ p <i>DD</i> ST	Restore Terminal State	DECRSTS
DCS 2 \$ p <i>DD</i> ST	Color Table Restore	DECCTR
DCS 2 \$ p Pc;Pu;Px;Py;Pz/ST	Color Table Restore	DECCTR
Q		
CSI Pn SP Q	Page Position Relative	PPR
CSI Pr * q	Secure Reset Confirmation	DECSRC
CSI Ps - q	CRT Saver Timing	DECCRTST
CSI Ps q	Load LEDs	DECLL
CSI Ps SP q	Set Cursor Style	DECSCUSR
CSI <i>Ps</i> " q	Select Character Protection Attribute	DECSCA
CSI <i>Ps1</i> , q	Select Terminal ID	DECTID
CSI Ps \$ q	Select Disconnect Delay Time	DECSDDT
CSI <i>Pf1; PC1;Pfn; Pcn</i> + q	Enable Local Functions	DECELF
DCS \$ q DD ST	Request Selection or Setting	DECRQSS
ESC Q Fn String	Define Function Key (SCO Console)	SCODFK
R		
CSI Pl; Pc R	Response to Cursor Position Report (CSI 6 n) or DSR—CPR	CPR or DSR-CPR
CSI Pl; Pc; Pp R	Response to Extended Cursor Position Request (CSI ? 6 n) or DSR—Extended CPR	DECXCPR, DSR-ExCPR
CSI Pn SP R	Page Position Backwards	PPB
CSI Ps * r	Select Communication Speed	DECSCS
CSI <i>Ps</i> - r	Energy Saver Timing	DECSEST
CSI <i>Ps1; Ps2</i> * r	Select Communication Speed	DECSCS
CSI ? <i>Ps1; Ps2</i> r	Enter/Exit PCTerm Mode	DECPCTERM
CSI <i>Ps</i> SP r	Set Key Click Volume	DECSKCV
CSI Pt; Pb r	Set Top and Bottom Margin	DECSTBM
CSI <i>Pt;Pl;Pb;Pr; Ps1;Psn</i> \$ r	Change Attribute in Rectangle	DECCARA
CSI <i>Pm1;Pf1;Pmn;Pfn</i> + r	Select Modifier Key Reporting	DECSMKR
DCS Ps r DD ST	Load Banner Message	DECLBAN
DCS Ps \$ r DD ST	Report Selection or Setting	DECRQSS

## ANSI Control Function Index E.1 ANSI Index by Final Character

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

<b>Control Function</b>	Description	Reference
S		
CSI s	Save Current Cursor Position (SCO Console)	SCOSC
CSI Pn S	Pan Down	SU
CSI Pl; Prs	Set Left and Right Margin	DECSLRM
CSI Ps \$ s	Select Printer Type	DECSPRTT
CSI Ps * s	Select Flow Control Type	DECSFC
CSI <i>Ps1; Ps2; Ps3; Ps4</i> * s	Select Flow Control	DECSFC
DCS 1 \$ s DD ST	Reply to Terminal State Report to Host	DECTSR
DCS 2 \$ s DD ST	Color Table Report	DECCTR
DCS Ps \$ s DD ST	Reply to Terminal State Report	DECRQTSR
Т		
CSI Pn T	Pan Up	SD
CSI Pn t	Set Lines Per Page	DECSLPP
CSI Ps SP t	Set Warning Bell Volume	DECSWBV
CSI Pt;Pl;Pb;Pr Ps1;Psn \$ t	Reverse Attribute in Rectangle	DECRARA
DCS <i>Ps</i> \$ t <i>DD</i> ST	Restore Presentation State	DECRSPS
DCS PS & C DD S1	Restore Presentation State	DECRSPS
U		
CSI u	Restore Saved Cursor Position (SCO Console)	SCORC
CSI Pn U	Next Page	NP
CSI & u	Request User-Preferred Supplemental Set	DECRQUPSS
CSI 1 \$ u	Request Terminal State Report	DECTSR
CSI Ps \$ u	Request Terminal State Report	DECRQTSR
CSI 2; <i>Pu</i> \$ u	Color Table Request	DECCTR
CSI Ps, u	Key Type Inquiry	DECRQKT
CSI Ps SP u	Set Margin Bell Volume	DECSMBV
CSI Ps * u	Select Communication Port	DECSCP
CSI <i>Ps1; Ps2</i> * u	Select Communication Port	DECSCP
CSI Ps " u	Set Transmit Rate Limit	DECSTRL
CSI <i>Ps1; Ps2</i> " u	Set Transmit Rate Limit	DECSTRL
DCS 1 \$ u DD ST	Cursor Information Report	DECCIR
DCS 2 \$ u DD ST	Tab Stop Report	DECTABSR
DCS Ps! u Dscs ST	Assign User-Preferred Supp Set	DECAUPSS
V		
CSI Pn V	Preceding Page	PP
CSI Ps SP v	Set Lock Key Style	DECSLCK
CSI " v	Request Displayed Extent	DECRQDE
CSI <i>Ps1</i> ; <i>Ps2</i> , v	Report Key Type	DECRPKT
CSIPts;Pls;Pbs;Prs;Pps;Ptd;Pld;Ppd\\$v		DECCRA
DCS Ps v DD ST	Load Answerback Message	DECLANS
W		
CSI ? 5 W	Set Tab at every 8 columns	DECST8C
CSI Ps + w	Set Port Parameter	DECSPP
CSI <i>Ps1</i> ; <i>Ps2</i> , w	Key Definition Inquiry	DECRQKD
- , - , - , - , - , - , - , - , - , - ,	J TT J	<b>-</b>

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

Control Function	Description	Reference
W		
CSI <i>Ps1; Ps2; Ps3; Ps4</i> + w	Set Port Parameter	DECSPP
CSI <i>Ph;Pw;Pml;Pmt;Pmp;</i> " w	Report Displayed Extent	DECRPDE
CSI Ps \$ w	Request Presentation State Report	DECRQPSR
X		
CSI Pn X	Erase Character(s)	ECH
CSI 1 II X	Enable Session	DECES
CSI Pch; Pt;Pl;Pb;Pr \$ x	Fill Rectangular Area	DECFRA
CSI <i>Pn1;Pn2;Pn3;Pn4</i> , x	Session Page Memory Allocation	DECSPMA
CSI Ps * x	Select Attribute and Change Extent	DECSACE
CSI + x	Program Key Free Memory Inquiry	DECRQPKFM
DCS " x DD ST	Program Function Key	DECPFK
Y		
CSI <i>Pa; Ps</i> \$ y	Donout Mode (AMSI) Terminal to Hest	DECRPM
CSI <i>Pa; Ps</i> \$ y	Report Mode (ANSI) Terminal to Host Report Mode (DEC) Terminal to Host	DECRPM
CSI ? Fd, FS \$ y CSI Pid;Pp;Pt;Pl;Pb;Pr * y	Request Checksum of Rectangle Area	DECRPM
CSI FIG.F.P.F.F.F.F.F.F.F. y CSI 4; Ps;; Ps y	Invoke Confidence Test	DECTST
CSI 4 , FS , , FS y CSI Ps1; Ps2 + y	Program Key Free Memory Report	DECISI
CSI PSI, PSZ + y CSI PS, y	Update Session	DECUS
DCS " y DD ST	Program Alphanumeric Key	DECPAK
DOS	Trogram Amphantameric Rey	BLOTTIN
Z		
CSI <i>Pt;Pl;Pb;Pr</i> \$ z	Erase Rectangular Area	DECERA
CSI Pid * z	Invoke Macro	DECINVM
CSI Pn Z	Cursor Backward Tabulation	CBT
CSI Ps, z	Down Line Load Allocation	DECDLDA
CSI Ps + z	Program Key Action	DECPKA
DCS <i>Pid;Pdt;Pen</i> ! z <i>DD</i> ST	Define Macro	DECDMAC
DCS " z DD ST	Copy Key Default	DECCKD
ESC Z	Identify Device (Use DA1 instead.)	DECID
Other Characters		
APC : ppp mm ST	Extended Keyboard Report	DECEKBD
CSI Pn @	Insert Character	ICH
CSI Ps1;Ps2;Ps3,	Assign Color	DECAC
CSI Pn *	Select number of lines per screen	DECSNLS
CSI \$	Set 80 columns per page	DECSCPP
CSI Ps \$	Set <i>Ps</i> columns per page	DECCOLM
CSI 80 \$	Set 80 columns per page	DECSCPP
CSI 132 \$	Set 132 columns per page	DECSCPP
DCS!   DD ST	Report Terminal Unit ID, response	DA3 and
	to Tertiary Device Attributes	DECRPTUI
DCS <i>Ps1; Ps2; Ps3</i>   DD ST	User Defined Key	DECUDK
ESC	Locking Shift Three Right	LS
•		

(continued on next page)

# ANSI Control Function Index E.1 ANSI Index by Final Character

Table E-1 (Cont.) ANSI Control Functions Index by Final Character

Other Characters		
CSI Pn * {	Macro Space Report Response	DECMSR, DSR–MSR
CSI Ps) {	Select Color Look-Up Table	DECSTGLT
CSI Ps, {	Select Zero Symbol	DECSZS
CSI Pt;Pl;Pb;Pr \$ {	Selective Erase Rectangular Area	DECSERA
DCS! { DD ST	Set Terminal Unit ID	DECSTUI
DCS Pfn; Pcn; Pe; Pcmw; Pss; Pu; Pcmh; Pcss { <dscs> <sixel-font-patterns> ST</sixel-font-patterns></dscs>	Dynamically Redefinable Character Sets Extension (Down-line Load)	DECDLD
CSI Pn'}	Insert Column	DECIC
CSI Ps \$ }	Select Active Status Display	DECSASD
CSI <i>Ps1; Ps2; Ps3</i> , }	Alternate Text Colors	DECATC
CSI Ps1; Ps2 SP }	Keyboard Language Selection	DECKBD
CSI Pk1; Pf1; Pk2; Pf2* }	Local Function Key Control	DECLFKC
DCS " } DD ST	Report Function Key Definition	DECRPFK
ESC }	Locking Shift Two Right	LS
CSI Pn '	Horizontal Position Absolute	HPA
CSI Pn ' ~	Delete Column(s)	DECDC
CSI Ps SP ~	Terminal Mode Emulation	DECTME
CSI Ps \$ ~	Set Status Display (Line) Type	DECSSDT
CSI <i>Ps1</i> ; <i>Ps2</i> ~	Function Key	DECFNK
CSI <i>DD</i> , ~	Play Sound	DECPS
DCS " ~ DD ST	Report all Modifiers/Alphanumeric Key State	DECRPAK
DCS Pid! ~ DD ST	Response to Memory Checksum Report Request	DECRQCRA, DECCKSR, or
ESC ~	Looking Chift One Dight	DSR–Mem LS
ESC ~ ESC ( Dscs	Locking Shift One Right G0 94-character set	SCS
	G0 94-character set G1 94-character set	SCS
ESC ) Dscs ESC * Dscs	G2 94-character set	SCS
ESC + Dscs	G2 94-character set G3 94-character set	SCS
ESC + Dscs	G1 96-character set	SCS
ESC - DSCS ESC . Dscs	G2 96-character set	SCS
ESC / Dscs	G3 96-character set	SCS
ESC / DSCS ESC =	Set Keypad Application Mode	DECKPAM
ESC <	Exit ANSI (VT52) Mode	DECANM
ESC >	Reset Keypad to numeric characters	DECKPNM
S0	Locking Shift One	LS

### **Glossary**

#### **Active Session**

The session to which keyboard input is currently directed.

#### **ANSI**

American National Standards Institute; ANSI character set.

#### **ANSI Standard Color**

Support for specifying text colors using the Select Graphic Rendition (SGR) command and parameters defined in ANSI X3.64.

#### **ANSI Terminal**

A video terminal that complies with prominent ANSI standards, which usually include:

ANSI X3.4, ASCII, American Standard Code for Information Exchange ANSI X3.41 Controls for use with ASCII ANSI X3.64 Additional Controls for use with ASCII

#### **ASCII**

American Standard Code for Information Interchange; ASCII character set.

#### **ASCII Terminal**

A video terminal that complies with:

ANSI X3.4 ASCII, American Standard Code for Information Exchange ANSI X3.41 Controls for use with ASCII

But an ASCII terminal may not comply with control sequences, the protocol defined by ANSI X3.64, *Additional Controls for use with ASCII*.

#### **Character Set**

A one-to-one mapping between the character codes and the symbols produced. The differences are as follows:

Character Set	Character Codes	Control Codes
ASCII 7-bit	96	32
ASCII 8-bit	192	64
PC	256	0
PCTerm	256	16 (typically)

#### **Control Codes**

Binary codes representing control data, rather than graphic data, to perform non-printable functions, such as tab, form feed, bell, and so on.

- C0 control codes are defined for 7-bit character sets.
- C0 and C1 control codes are defined for 8-bit character sets.

#### **Control Function**

A general term for control codes, escape sequences, control sequences, and control strings.

#### **Control Sequence**

The ANSI standards define the protocol for extending the meaning of character set data to be control data. As such, a control sequence has a prefix called a *control sequence introducer* (CSI) followed by the command and its parameters. For example, **Esc** [ is the CSI used for 7-bit ANSI control sequences.

#### **DRCS**

Dynamically Redefinable Character Set. A feature that allows user specified character sets (soft sets) to be downloaded by host software.

#### **EPC Keyboard**

An Enhanced PC (PCXAL) 101- or 102-key layout keyboard.

#### **Function Key**

A key that sends control codes or control sequences that are usually interpreted by a host computer to perform some function. In *PCTerm mode,* a keyboard mapping process in the host computer determines the function to be performed.

#### **Graphic Key**

An alphanumeric key.

#### **Keyboard Dialect**

A mapping from keystrokes on the main key array to the characters produced. The names of the *keyboard dialects* are based on the geographical region, country, or language for which the keyboard is primarily intended.

#### **Keyboard Language**

Another term for a keyboard dialect.

#### **Keyboard Layout**

A physical arrangement of keys and keycap legends on a keyboard.

#### **Keyboard Scan Codes**

The numeric codes transmitted from a keyboard to a terminal or computer. Within a keyboard, scan codes are generated by scanning a physical key array to detect key switch transitions. Scan codes represent the physical position of the keys in the key matrix. The host defines the meaning of the scan codes, mapping them to alphanumeric, function, or "hot" keys for DOS application use.

#### **Local Function Key**

A key that invokes a local terminal function (Examples: Print Screen, Set-Up).

#### MPR II

A Swedish standard that sets limits for low frequency magnetic energy emitted from electronic equipment.

#### **PCTerm**

A terminal mode that emulates the console of an industry-standard PC, while communicating with a host over a serial communications line. PCTerm mode allows you to run an application on a host as if the application was running locally on the terminal. In PCTerm mode, the terminal transmits the same PC keyboard *scan codes* that a console keyboard attached to a PC would send.

#### Session

A connection between a single virtual terminal and a host computer.

#### **Set-Up Summary Line**

A line of text that appears at the bottom of the screen any time the terminal is in Set-Up. This line summarizes how the terminal is configured. If the terminal is unable to communicate with a host for some reason, the *Set-Up Summary Line* can be used to quickly find any mismatched settings.

#### **Soft Key Mapping**

The ability to modify the correspondence between keystrokes to character codes or functions for all keys on the keyboard.

#### **Status Display**

A separate logical display that usually appears as a single line near the bottom or top of the screen to provide status information.

#### TD/SMP

Terminal Device/Session Management Protocol. A communications protocol that allows multiple sessions to share a single comm port.

#### **User Defined Key**

A *function key* that can be reprogrammed by the user or by a control sequence from the host.

#### **Virtual Terminal**

A virtual terminal appears to be a real physical terminal to a host computer but may in fact share resources with other virtual terminals (keyboard and display) to create the effect of more than one terminal within a single device. Virtual terminals maintain the full state and context of real physical terminals.

#### VT Keyboard

An LK450 (LK411) 108-key layout keyboard.

#### XOFF/XON

Control codes that the terminal uses to stop and resume transmission when its receive buffer (or the host's receive buffer) is full or empty.

### **XPC**

A remapping of transmitted XOFF and XON control codes to unused PC scan codes. While in PCTerm mode, these control codes would interfere with the scan codes that the host expects to receive. The terminal, however, still responds to received XOFF and XON control codes.

## Index

	ANSI control sequences
A	by Control Function (cont'd)
	CSI + x (DECRQPKFM), 5–111
Aborting	CSI 0 \$   (select 80 columns/page), 5–125
print operations, 10–7	CSI 0 n (DSR—operating status), 5–177
Accessibility aids, 2–6, 8–15	CSI 1 2 h (SRM set), 5–204
Actions menu, 2–7, 2–9	CSI 1 2 l (SRM reset), 5-204
banner message, 2–11	CSI 1 3 2 \$   (select 132 columns/page),
calculator, 2–11	5–125
clear communications, 2-9	CSI 2 0 h (LNM set), 5-186
clear display, 2–9	CSI 2 0 l (LNM reset), 5–186
clock, 2–11	CSI 2; Pu \$ u (DECCTR), 5-114
reset this session, 2–10	CSI 2 h (KAM set), 5–185
restore factory defaults, 2-10	CSI 2 l (KAM reset), 5–185
show character sets, 2-11	CSI 3 h (CRM set), 5-6
ADDS mode, 13–1	CSI 3 l (CRM reset), 5–6
Alignment, screen, 2–27	CSI 3 n (DSR—operating status: problem),
Alternate text colors, 2–30	5–177
ANSI	CSI 4; <i>Ps ; Ps</i> y (DECTST), 5–162
code summary, 4–1	CSI 4 h (IRM set), 5–185
conformance levels, 5–1	CSI 4 l (IRM reset), 5–185
control characters, 4-1	CSI 5 n (DSR—request operating status),
control functions, 5–1	5–177
audible attributes, 4–18	CSI 6 1 " P (VT Level 1 mode), 5–122
color selection, 4–18	CSI 6 n " P (VT Level 4 mode, 8-bit
communications, 4–39	controls), 5–122
defined, 4–1	CSI 6 n (CPR request), 5–5, 5–173
editing, 4–21	CSI 6 n; 0 " P (VT Level 4 mode, 8-bit
graphic character sets, 4–25	controls), 5–122
index by final character, E-1	CSI 6 n; 1 " P (VT Level 4 mode, 7-bit
keyboard processing, 4–27	controls), 5–122
printer, 4–33	CSI 6 n; 2 " P (VT Level 4 mode, 8-bit
reports, 4–42	controls), 5–122
sessions, 4–16	CSI 8 0 \$   (select 80 columns/page),
terminal management, 4–34	5–125
defined, 4–15	CSI 8 1 h (DECKPM set), 5–66
terminal synchronization, 4–41	CSI 8 1 l (DECKPM reset), 5–66
text processing, 4–22	CSI = c  or  CSI = 0  c (DA3 request), 5-12
visual attributes, 4–20	CSI > 61; $Pv$ ; 0 c (DA2 request from VT)
control sequences, 5–1	Keyboard), 5–11
ANSI control sequences	CSI > 61; $Pv$ ; 1 c (DA2 request from PC
by Control Function	Keyboard), 5–11
APC: ppp mm ST (DECEKBD), 5-49	CSI > c or $CSI > 0$ c (DA2), 5-11
CSI ! p (DECSTR), 5–150	CSI ? 100 h (enable DECAAM), 5-15
CSI " v (DECRQDE), 5–105	CSI ? 100 l (disable DECAAM (default)),
CSI \$   (select 80 columns/page), 5–125	5–15
CSI & u (DECRQUPSS), 5–115 CSI & x (enable session), 5–53	CSI ? 101 h (DECCANSM), 5–27
CSI & x (enable session), 0-00	

ANSI control sequences ANSI control sequences by Control Function (cont'd) by Control Function (cont'd) CSI ? 101 l (DECCANSM ), 5-27 CSI ? 3 6 h (DECHEM set), 5-57 CSI ? 1 0 2 h (DECNULM set), 5-76 CSI ? 3 6 l (DECHEM reset), 5-57 CSI ? 3 h (DECCOLM set), 5-34 CSI ? 1 0 2 l (DECNULM reset), 5-76 CSI ? 1 0 3 h (DECHDPXM enabled CSI ? 3 l (DECCOLM reset), 5-34 /half-duplex enabled), 5-56 CSI? 42 h (DECNRCM set), 5-75 CSI ? 1 0 3 l (DECHDPXM disabled CSI ? 4 2 l (DECNRCM reset), 5-75 /full-duplex enabled), 5-56 CSI ? 4 h (DECSCLM set), 5-123 CSI ? 1 0 4 h (secondary keyboard mapping CSI ? 4 l (DECSCLM reset), 5-123 - DECESKM), 5-53 CSI ? 5 7 h (DECNAKB set), 5-74 CSI ? 1 0 4 l (primary keyboard mapping -CSI ? 5 7 l (DECNAKB reset), 5-74 DECESKM), 5-53 CSI ? 58 h (DECIPEM - enter IBM CSI? 106 h (DECOSCNM set), 5-77 ProPrinter emulation mode), 5-62 CSI? 106 l (DECOSCNM reset), 5-77 CSI ? 58 l (DECIPEM - exit IBM ProPrinter CSI ? 10 n (DSR-printer ready), 5-178 emulation mode), 5-62 CSI ? 111 h (enable (set) framed windows CSI ? 5 h (DECSCNM set), 5-123 mode - default), 5-56 CSI ? 5 l (DECSCNM reset), 5-123 CSI ? 111 l (disable (reset) framed windows CSI ? 5 W (DECST8C), 5-149 CSI ? 6 1 h (DECVCCM set), 5-170 mode), 5-56 CSI ? 112 h (enable (set) review previous CSI ? 6 1 l (DECVCCM reset), 5-170 lines mode), 5-97 CSI ? 62 n (DSR—macro space request), CSI ? 112 l (disable (reset) review previous 5 - 176lines mode - default), 5-97 CSI ? 63; Pid n (DSR-memory checksum CSI ? 113 h (enable (set) host wake-up), request), 5-177 5 - 59CSI ? 65; Ps1; ...; Psn c (DA1 response), CSI ? 113 l (disable (reset) host wake-up CSI ? 6 6 h (DECNKM set), 5-75 mode), 5-59 CSI ? 11 n (DSR-printer assigned to other CSI ? 6 6 l (DECNKM reset), 5-75 session), 5-178 CSI ? 6 7 h (DECBKM set), 5-26 CSI ? 6 7 l (DECBKM reset), 5-26 CSI ? 11 n (DSR-printer not ready), 5-178 CSI? 68 h (DECKBUM set), 5-65 CSI ? 6 8 l (DECKBUM reset), 5-65 CSI ? 13 n (DSR—no printer), 5-178 CSI ? 15 n (DSR—printer port request), CSI ? 6 9 h (DECLRMM set), 5-72 5 - 178CSI ? 6 9 l (DECLRMM reset), 5-72 CSI ? 1 8 h (DECPFF set), 5-83 CSI ? 6 h (DECOM set), 5-77 CSI? 18l (DECPFF reset), 5-83 CSI ? 6 l (DECOM reset), 5-77 CSI ? 18 n (DSR—printer busy), 5-178 CSI? 6 n (CPR request), 5-174 CSI ? 1 9 h (DECPEX set), 5-83 CSI ? 70 n (DSR-data integrity report), CSI ? 1 9 l (DECPEX reset), 5-83 5 - 174CSI? 1 h (DECCKM set), 5-32 CSI ? 71 n (DSR—data integrity report), CSI ? 1 l (DECCKM reset), 5-32 5 - 174CSI ? 20 n (DSR-UDKs unlocked), 5-179 CSI ? 7 3 h (DECXRLM set), 5-171 CSI ? 21 n (DSR-UDKs unlocked), 5-179 CSI ? 7 3 l (DECXRLM reset), 5-171 CSI ? 2 5 h (DECTCEM set), 5-157 CSI ? 73 n (DSR—data integrity report), CSI? 2 5 l (DECTCEM reset), 5-157 5 - 174CSI ? 75 n (DSR—data integrity request), CSI ? 25 n (DSR-UDK request), 5-179 CSI ? 26 n (DSR- keyboard status 5 - 174request), 5-175 CSI ? 7 h (DECAWM set), 5-25 CSI ? 27; Pn; Pst; Ptyp n (DSR-keyboard CSI ? 7 l (DECAWM reset), 5-25 status reply), 5-175 CSI? 8 h (DECARM set), 5-19 CSI ? 2 l (DECANM), 5-18 CSI? 8 l (DECARM reset), 5-19 CSI? 3 4 h (DECPCCM set), 5-80 CSI ? 9 5 h (DECNCSM set), 5-74 CSI ? 3 4 h (DECRLM set), 5-93 CSI ? 9 5 l (DECNCSM reset), 5-74 CSI ? 3 4 l (DECPCCM reset), 5-80 CSI ? 9 6 h (DECRLCM disabled), 5-92 CSI ? 3 4 l (DECRLM reset), 5-93 CSI ? 9 6 h (DECRLCM enabled), 5-92 CSI ? 3 5 h (DECHEBM reset), 5-58 CSI ? 97 h (CRT saver enabled), 5-37

CSI ? 97 l (CRT saver disabled), 5-37

CSI? 35 l (DECHEBM set), 5-58

ANSI control sequences ANSI control sequences by Control Function (cont'd) by Control Function (cont'd) CSI ? 98 h (enable DECARSM), 5-21 CSI Pn \* | (DECSNLS), 5-140 CSI ? 98 l (disable DECARSM), 5-21 CSI Pn1; Pn2; Pn3; Pn4, x (session page CSI ? 99 h (DECMCM set), 5-73 memory allocation), 5-141 CSI Pn @ (ICH), 5-183 CSI ? 99 l (DECMCM reset), 5-73 CSI Pn A (CUU), 5-8 CSI ? Pd \$ p (DECRQM), 5-108 CSI Pn a (HPR), 5-181 CSI ? Pd ; ... ; Pd l (RM), 5-195 CSI ? Pd; ...; Pd h (SM), 5-206 CSI Pn B (CUD), 5–7 CSI ? Ps 114 h (enable (set) alternate text CSI Pn C (CUF), 5-7 color underline mode), 5-23 CSI Pn D (CUB), 5-7 CSI ? Ps 114 l (disable (reset) alternate text CSI Pn d (VPA), 5-208 color underline mode), 5-23 CSI Pn E (CNL), 5-4 CSI Pn e (VPR), 5-208 CSI ? Ps 115 h (enable (set) alternate text color blink mode), 5-23 CSI Pn F (CPL), 5–5 CSI ? Ps 115 l (disable (reset) alternate text CSI Pn G (CHA), 5–3 color blink mode), 5-23 CSI *Pn* I (CHT), 5–4 CSI ? Ps 116 h (enable (set) bold and blink CSI Pn L (IL), 5-184 style mode), 5-25 CSI Pn M (DL), 5-172 CSI ? Ps 116 l (disable (reset) bold and CSI Pn P (DCH), 5-13 blink style mode), 5–25 CSI *Pn* S (SU), 5–207 CSI ? Ps 117 h (enable (set) erase color CSI *Pn* sp P (PPA), 5–192 CSI Pn sp Q (PPR), 5-193 mode), 5-48 CSI Pn sp R (PPB), 5-193 CSI ? Ps 117 l (disable (reset) erase color mode - default), 5-48 CSI Pn t (DECSLPP), 5-136 CSI ? Ps1; Ps2 \$ y (DECRPM), 5-98 CSI Pn T (SD), 5-200 CSI? Ps1; Ps2 r (DECPCTERM), 5-81 CSI Pn U (NP), 5-191 CSI ? Ps i (MC), 5-188 CSI Pn V (PP), 5-192 CSI ? Ps J (DECSED), 5-129 CSI Pn X (ECH), 5-179 CSI ? Ps K (DECSEL), 5-131 CSI Pn Z (CBT), 5–3 CSI Pn ' (HPA), 5-181 CSI c or CSI 0 c (DA1), 5-9 CSI Pa \$ p (DECRQM—ANSI mode), CSI Ps " q (DECSCA), 5-121 CSI Ps \$ - (DECSSDT), 5-147 5 - 108CSI Pch; Pt; Pl; Pb; Pr \$ x (DECFRA), CSI Ps \$ q (DECSDDT), 5-128 CSI Ps \$ s (DECSPRTT), 5-144 CSI Ps \$ u (DECRQTSR), 5-113 CSI Pf1; Pc1; Pf2; Pc2; ... + q (DECELF), CSI Ps \$ w (DECRQPSR), 5-111 5 - 51CSI Ph; Pw; Pml; Pmt; Pmp; "w CSI Ps \$ } (DECSASD), 5-120 CSI Ps) p (DECSDPT), 5-129 (DECRPDE), 5-95 CSI Pid \* i (DECINVM), 5-61 CSI Ps ) { (select color look-up table), CSI Pid; Pp; Pt; Pl; Pb; Pr ... \* y 5 - 151(DECRQCRA), 5-105 CSI Ps \* x (DECSACE), 5-119 CSI Pk1; Pf1 . . . Pkn; Pfn \* } (DECLFKC), CSI Ps + z (DECPKA), 5-87 CSI Ps, u (DECRQKT), 5-107 5 - 70CSI Pl; Pc; Pp R (DECXCPR report), CSI Ps, y (update session), 5-169 CSI Ps, z (DECDLDA), 5-47 5 - 174CSI Pl; Pc f and CSI f (HVP), 5-183 CSI Ps, { (select zero symbol), 5-155 CSI P1; Pc H (CUP), 5-8 CSI *Ps1*, q (DECTID), 5–158 CSI Pl: Pc R (CPR report), 5-173 CSI Ps1: Ps2 " u (DECSTRL), 5-152 CSI Pl; Pc R (CPR response), 5-5 CSI Ps1; Ps2 \$ y (DECRPM), 5-98 CSI Pl; Prs (DECSLRM), 5-137 CSI Ps1; Ps2 \* r (DECSCS), 5-126 CSI Ps1; Ps2 \* u (DECSCP), 5-124 CSI *Pm1; Pf1; Pmn; Pfn;* + r, 5–139 CSI Pn'} (DECIC), 5-59 CSI Ps1; Ps2 + y (DECPKFMR), 5-88 CSI Pn' ~ (DECDC), 5-37 CSI Ps1; Ps2, p (DECLTOD), 5-72 CSI Pn \* p (DECSPPCS), 5-143 CSI Ps1; Ps2, v (DECRPKT), 5-96 CSI Pn \* { (DECMSR), 5-73 CSI Ps1; Ps2, w (DECRQKD), 5-106 CSI Pn \* { (DSR—macro space report), CSI Ps1; Ps2; Ps3, | (assign color), 5-16

5 - 176

ANSI control sequences	ANSI control sequences
by Control Function (cont'd)	by Control Function (cont'd)
CSI Ps1; Ps2; Ps3, } (alternate text color),	DCS $Pid! \sim DD$ ST (DSR —memory
5-22	checksum report), 5–177
CSI <i>Ps1 ; Ps2 ; Ps3 ; Ps4</i> * s (DECSFC),	DCS Pid; Pdt; Pen! z D D ST
5–133	(DECDMAC), 5-45
CSI <i>Ps1</i> ; <i>Ps2</i> ; <i>Ps3</i> ; <i>Ps4</i> + w (DECSPP),	DCS <i>Ps</i> \$ p <i>DD</i> ST (DECRSTS), 5–117
5–142	DCS $Ps$ \$ r $D \dots D$ ST (DECRPSS), 5–102
CSI <i>Ps1</i> ; <i>Ps2</i> SP } (DECKBD), 5–63	DCS $Ps$ \$ t $DD$ ST (DECRSPS), 5–116
CSI <i>Ps</i> ; <i>Ps</i> ; <i>Ps</i> m (SGR), 5–201	DCS $Ps1$ ; $Ps2$ ; $Ps3 \mid D \dots D$ ST
CSI <i>Ps</i> g (TBC), 5–207	(DECUDK), 5–163
CSI <i>Ps</i> i (MC - ANSI standard), 5–188	DCS Ps r $D \dots D$ ST (DECLBAN), 5–69
CSI <i>Ps</i> J (ED), 5–180	DCS Ps v D D ST (DECLANS), 5–68
CSI <i>Ps</i> K (EL), 5–180	ESC # 3 (top), ESC # 4 (bottom) (DECDHL),
CSI Ps p (DECSSL), 5–148	5–38
CSI Ps - p (select auto repeat rate), 5-20	ESC # 5 (DECSWL), 5–154
CSI Ps - q (CRT saver timing), 5–36	ESC # 6 (DECDWL), 5-48
CSI Ps - r (energy saver timing), 5-130	ESC # 8 (DECALN), 5-17
CSI Ps SP p (DECSSCLS), 5-146	ESC (1 (DDD3), 5-14
CSI Ps SP q (DECSCUSR), 5–127	ESC ) 1 (DDD1), 5-14
CSI Ps SP r (DECSKCV), 5–135	ESC ) B (DDD2), 5-14
CSI Ps SP t (DECSWBV), 5-154	ESC 6 (DECBI), 5-26
CSI Ps SP u (DECSMBV), 5-138	ESC 7 (DECSC), 5-120
CSI Ps SP v (DECSLCK), 5–135	ESC 8 (DECRC), 5-92
CSI $Ps$ SP ~ (DECTME), 5–159	ESC 9 (DECFI), 5-54
CSI Pt; Pb r (DECSTBM), 5–149	ESC < (exit DECANM), 5–19
CSI <i>Pt</i> ; <i>Pl</i> ; <i>Pb</i> ; <i>Pr</i> \$ z (DECERA), 5–52	ESC = (DECKPAM), 5-66
CSI <i>Pt</i> ; <i>Pl</i> ; <i>Pb</i> ; <i>Pr</i> \$ { (DECSERA), 5–132	ESC > (DECKPNM), 5-67
CSI Pt; Pl; Pb; Pr; Ps1; Psn \$ r	ESC c (RIS), 5–194
(DECCARA), 5–28	ESC I Dscs (SCS), 5–197
CSI <i>Pt</i> ; <i>Pl</i> ; <i>Pb</i> ; <i>Pr</i> ; <i>Ps1</i> ; <i>Psn</i> \$ t	ESC n (locking shift G2), 5–187
(DECRARA), 5-90	ESC o (locking shift G3), 5–187
CSI Pts; Pls; Pbs; Prs; Pps; Ptd; Pld;	ESC Q Fn String (SCODFK), 6–7
Ppd \$ v (DECCRA), 5–35	ESC sp F (S7C1T), 5–196
CSI Prolume; Pduration; Pnote, ~ (play	ESC sp <i>final</i> (ANSI conformance level),
sound), 5–89	5–1
CSI s (SCOSC), 6–9	ESC sp G (S8C1T), 5–196
CSI u (SCORC), 6–9	ESC Z (DECID), 5–60
DCS! { DD ST (DECSTUI), 5–153	ESC [ ? 108 h (DECNUMLK set), 5–76
DCS!   DD ST (DA3 response), 5–12	ESC [? 108 l (DECNUMLK reset), 5–76
DCS!   DD ST (DECRPTUI), 5–104	ESC [? 109 h (DECCAPSLK set), 5–28
DCS " x D D ST (DECPFK), 5-84	ESC [? 109 l (DECCAPSLK reset), 5–28
DCS " y D D ST (DECPAK), 5-78	ESC [ ? 110 h (DECKLHIM set), 5–65
DCS " z <i>DD</i> ST (DECKN), 5–31	ESC [? 110 ll (DECKLHIM reset), 5–65
DCS " } D D ST (DECRPFK), 5–96	ESC [ Pr * q (DECSR), 5–146
DCS " $\sim D \dots D$ ST (DECRPAK), 5–94	ESC [ $Pr + p$ (DECSR), $5-140$
DCS $\ q D \dots D ST \ (DECRQSS request),$	ESC [ $Ps$ q (DECLL), 5–71
5–112	ESC   (locking shift G3 right), 5–187
DCS 1 \$ s <i>DD</i> ST (DECTSR), 5–160	, ,
	ESC } (locking shift G2 right), 5-187
DCS 1 \$ u <i>DD</i> ST (DECCIR), 5–30	ESC ~ (locking shift G1 right), 5–187
DCS 2 \$ p <i>DD</i> ST (DECRSTS), 5–118	HT (HT), 5-182
DCS 2 \$ p <i>DD</i> ST (DECTSR), 5–161	HTS (HTS), 5–182
DCS 2 \$ u DD ST (DECTABSR), 5-157	OSC 2 DD ST (set icon name), 5–134
DCS Dscs! u Pd ST (DECAUPSS), 5-24	OSC 2 DD ST (set window title), 5–156
DCS Pfn; Pcn; Pe; Pcmw; Pss; Pu; Pcmh;	SI (locking shift G0), 5–187
Pcss { <dscs><sixel-font-pattern> ST</sixel-font-pattern></dscs>	SO (locking shift G1), 5–187
(DECDLD), 5–39	SS2 (single shift G2), 5–205
	SS3 (single shift G3), 5–205

ANSI control sequences (cont'd)	ANSI control sequences
by Control Sequence	by Mnemonic (cont'd)
CSI ? 6 3; <i>Pid n</i> (DECCKSR request),	DECCKD (copy key default), 5-31
5–33	DECCKM (cursor keys mode), 5-32
DCS $Pid! \sim D \dots D$ ST (DECCKSR	DECCKSR (memory checksum), 5-33,
response), 5–33	5–177
ESC D (IND), 5–184	DECCOLM (column mode), 5-34
ESC E (NEL), 5-191	DECCRA (copy rectangular area), 5-35
by Mnemonic	DECCRTSM (set/reset CRT save mode),
CBT (cursor backward tabulation), 5-3	5–37
CHA (cursor horizontal absolute), 5-3	DECCRTST (CRT saver timing), 5–36
CHT (cursor horizontal forward tabulation),	DECCTR (color table request), 5–114
5–4	DECDC (delete column), 5-37
CNL (cursor next line), 5-4	DECDHL (double-width, double-height
CPL (cursor previous line), 5–5	line), 5-38
CPR (cursor position report), 5-5, 5-173	DECDLD (dynamically redefinable
CRM (show control character mode), 5-6	character sets extension), 5-39
CUB (cursor backward), 5-7	DECDLDA (down-line load allocation),
CUD (cursor down), 5-7	5–47
CUF (cursor forward), 5-7	DECDMAC (define macro), 5-45
CUP (cursor position), 5–8	DECDWL (double-width, single-height
CUU (cursor up), 5–8	line), 5–48
DA1 (primary device attributes), 5–9	DECECM (Erase color mode), 5-48
DA2 (secondary device attributes), 5–11	DECEKBD (extended keyboard report),
DA3 (tertiary device attributes), 5–12	5–49
DCH (delete character), 5-13	DECELF (enable local functions), 5-51
DDD1 (DDD1), 5-14	DECERA (erase rectangular area), 5-52
DDD2 (DDD2), 5-14	DECES (Enable session), 5–53
DDD3 (DDD3), 5-14	DECESKM (enable secondary keyboard
DECAAM (set/reset auto answerback	language mode), 5-53
mode), 5–15	DECFI (forward index), 5–54
DECAC (Assign color), 5-16	DECFRA (fill rectangular area), 5-55
DECALN (screen alignment pattern), 5–17	DECFWM (Set/reset framed windows
DECANM (ANSI mode), 5–18	mode), 5–56
DECANM (exiting ANSI (VT52) mode),	DECHDPXM (set/reset half-duplex mode),
5–19	5-56
DECARM (autorepeat mode), 5-19	DECHEBM (Hebrew/N-A keyboard
DECARR (Select auto repeat rate), 5-20	mapping), 5–58
DECARSM (set/reset auto resize mode),	DECHEM (Hebrew encoding mode), 5-57
5–21	DECHWUM (Host wake-up mode), 5-59
DECATC (Alternate text color), 5-22	DECIC (insert column), 5–59
DECATCBM (Set/reset alternate text color	DECID (identify device), 5-60
blink mode), 5–23	DECINVM (invoke macro), 5-61
DECATCUM (Set/reset alternate text color	DECIPEM (enter/return from IBM
underline mode), 5–23	ProPrinter emulation mode), 5-62
DECAUPSS (assigning user-preferred	DECKBD (keyboard language selection),
supplemental sets), 5–24	5-63
DECAWM (autowrap mode), 5-25	DECKBUM (keyboard usage mode), 5-65
DECBBSM (bold and blink style mode),	DECKLHIM (keyboard LEDs host indicator
5–25	$\mathbf{mode}),  5-65$
DECBI (back index), 5–26	DECKPAM (keypad application mode),
DECBKM (backarrow key mode), 5-26	5–66
DECCANSM (conceal answerback message	DECKPM (key position mode), 5-66
mode), 5–27	DECKPNM (keypad numeric mode), 5-67
DECCAPSLK (caps lock mode), 5-28	DECLANS (load answerback message),
DECCARA (change attributes in	5-68
rectangular area), 5–28	DECLBAN (load banner message), 5-69
DECCIR (cursor information report), 5-30	-

ANSI control sequences ANSI control sequences by Mnemonic (cont'd) by Mnemonic (cont'd) DECLFKC (local function key control), DECRQM (request mode), 5-108 DECRQPKFM (request program key free DECLL (load LEDs), 5-71 memory), 5-111 DECLRMM (vertical split screen mode), DECRQPSR (request presentation state report), 5-111 DECLTOD (load time of day), 5-72 DECRQSS (request selection or setting), DECMCM (modem control mode), 5-73 DECMSR (macro space report), 5-73 DECRQTSR (request terminal state report), DECNAKB (Greek/N-A keyboard mapping), 5 - 1135 - 74DECRQUPSS (request user-preferred DECNCSM (no clearing screen on column supplemental set), 5-115 change), 5-74 DECRSPS (restore presentation state), DECNKM (numeric keypad mode), 5-75 5 - 116DECNRCM (character set mode), 5-75 DECRSTS (restore terminal state), 5-117 DECNULM (null mode), 5-76 color table, 5-118 DECNUMLK (Num lock mode), 5-76 DECSACE (select attribute change extent), DECOM (origin mode), 5-77 5 - 119DECOSCNM (set/reset overscan mode), DECSASD (select active status display), 5 - 775 - 120DECPAK (program alphanumeric key), DECSC (save cursor), 5-120 DECSCA (select character protection DECPCCM (page cursor-coupling mode), attribute), 5-121 DECSCL (select conformance level), 5-122 DECPCTERM (enter/exit PCTerm or DECSCLM (scrolling mode), 5-123 scancode mode), 5-81 DECSCNM (screen mode: light or dark DECPEX (print extent mode), 5-83 screen), 5-123 DECPFF (print form feed mode), 5-83 DECSCP (select communication port), DECPFK (program function key), 5-84 5 - 124DECPKA (program key action), 5-87 DECSCPP (set columns per page), 5-125 DECPKFMR (program key free memory DECSCS (select communication speed), 5 - 126report), 5-88 DECPS (play sound), 5-89 DECSCUSR (set cursor style), 5-127 DECRARA (reverse attributes in DECSDDT (select disconnect delay time), rectangular area), 5-90 DECRC (restore cursor), 5-92 DECSDPT (select Digital printed data type), 5-129 DECRLCM (right-to-left copy mode), 5-92 DECRLM (right-to-left mode), 5-93 DECSED (selective erase in display), DECRPAK (report all modifiers 5 - 129/alphanumeric key state), 5-94 DECSEL (selective erase in line), 5-131 DECRPDE (report displayed extent), 5-95 DECSERA (selective erase rectangular DECRPFK (report function key definition), area), 5-132 5 - 96DECSEST (Energy saver timing), 5-130 DECRPKT (report key type), 5-96 DECSFC (select flow control), 5-133 DECRPL (review previous lines mode), DECSIN (Set icon name), 5-134 DECSKCV (set key click volume), 5-135 5 - 97DECSLCK (set lock key), 5-135 DECRPM (report mode), 5-98 DECRPSS (report selection or setting), DECSLPP (set lines per page), 5-136 5 - 102DECSLRM (set left and right margins), DECRPTUI (report terminal unit ID), 5 - 137DECSMBV (set margin bell volume), 5 - 104DECRQCRA (request checksum of 5 - 138rectangular area), 5-105 DECSMKR (select modifier key reporting), DECRQDE (request displayed extent), DECSNLS (set number of lines per screen), DECRQKD (request key definition), 5-106 5 - 140

DECRQKT (request key type), 5-107

ANSI control sequences	ANSI control sequences by Mnemonic (cont'd)
by Mnemonic (cont'd)	•
DECSPMA (Session page memory allocation), 5–141	HPR (horizontal position relative), 5–181 HT (horizontal tab), 5–182
DECSPP (set port parameters), 5-142	HTS (horizontal tab set), 5-182
DECSPPCS (select ProPrinter character	HVP (horizontal and vertical position),
set), 5–143	5-183
DECSPRTT (select printer type), 5-144	ICH (insert character), 5-183
DECSR (secure reset), 5–144	IL (insert line), 5–184
DECSRC (secure reset confirmation),	IND (index), 5–184
5–146	IRM (insert/replace mode), 5-185
DECSSCLS (set scroll speed), 5-146	KAM (keyboard action mode), 5-185
DECSSDT (select status display (line)	LNM (line feed/new line mode), 5-186
type), 5–147	Locking shift (LS), 5–187
DECSSL (select set-up language), 5-148	LS0 (maps G0 into GL), 5–187
DECST8C (set tab at every 8 columns),	LS1 (maps G1 into GL), 5–187
5–149	LS1R (maps G1 into GR), 5-187
DECSTBM (set top and bottom margins),	LS2 (maps G2 into GL), 5-187
5–149	LS2R (maps G2 into GR), 5-187
DECSTGLT (Select color look-up table),	LS3 (maps G3 into GL), 5-187
5–151	LS3R (maps G3 into GR), 5-187
DECSTR (soft terminal reset), 5-150	MC (media copy), 5-188
DECSTRL (set transmit rate limit), 5-152	NEL (next line), 5–191
DECSTUI (set terminal unit ID), 5-153	NP (next page), 5–191
DECSWBV (set warning bell volume),	PP (preceding page), 5-192
5–154	PPA (page position absolute), 5-192
DECSWL (single-width, single-height line),	PPB (page position backward), 5-193
5–154	PPR (page position relative), 5-193
DECSWT (Set window title), 5-156	RIS (reset to initial state), 5-194
DECSZS (select zero symbol), 5-155	RM (reset mode), 5–195
DECTABSR (tab stop report), 5-157	S7C1T (send 7-bit C1 control character to
DECTCEM (text cursor enable mode),	host), 5–196
5–157	S8C1T (send 8-bit C1 control characters),
DECTID (select terminal ID), 5–158	5-196
DECTME (terminal mode emulation),	SCODFK (define function key), 6-7
5–159	SCODFK (save cursor position (SCO)), 6-9
DECTSR (terminal state report), 5-160	SCODPCC (display PC character (SCO)),
color table report, 5-161	6–8
DECTST (invoke confidence test), 5-162	SCORC (SCO) (restore cursor), 6-9
DECUDK (user-defined keys), 5-163	SCS (select character set), 5–197
DECUS (Update session), 5-169	SD (pan up), 5-200
DECVCCM (vertical cursor-coupling mode),	SGR (select graphic rendition), 5-201
5–170	SM (set mode), 5–206
DECXCPR (extended cursor position	SRM (send/receive mode—local echo),
report), 5-170, 5-174	5-204
DECXRLM (transmit rate limiting), 5-171	SS2 (maps G2 into GL), 5-205
DL (delete line), 5–172	SS3 (maps G3 into GL), 5-205
DSR (data integrity report), 5-174	SU (pan down), 5-207
DSR (device status report, keyboard),	TBC (tab clear), 5–207
5–175	VPA (vertical line position absolute), 5-208
DSR (macro space report), 5-176	VPR (vertical position relative), 5-208
DSR (operating status), 5–177	by Name, 4–16
DSR (printer port), 5–178	Alternate text color (DECATC), 4-18, 5-22
DSR (user-defined keys), 5–179	Alternate text color blink mode
ECH (erase character), 5-179	(DECATCBM), 4-19, 5-23
ED (erase in display), 5-180	Alternate text color underline mode
EL (erase in line), 5–180	(DECATCUM), 4-19, 5-23
HPA (horizontal position absolute), 5-181	ANSI conformance level, 4–36, 5–1
	· · · · · · · · · · · · · · · · · · ·

ANSI control sequences ANSI control sequences by Name (cont'd) by Name (cont'd) ANSI mode (DECANM), 4-36, 5-18 Define function key (SCO) (SCODFK), Assign color (DECAC), 4-18, 5-16 4-28, 6-7Define macro (DECDMAC), 4-42, 5-45 Assigning user-preferred supplemental sets (DECAUPSS), 4-25, 5-24 Delete character (DCH), 4-21, 5-13 Auto answerback mode (DECAAM), 4-38, Delete column (DECDC), 4-21, 5-37 5 - 15Delete line (DL), 4-21, 5-172 Autorepeat mode (DECARM), 4-27, 5-19 Device attributes Autorepeat rate (DECARR), 4-27, 5-20 primary (DA1), 4-35, 5-9 Auto resize mode (DECARSM), 4-17, 5-21 secondary (DA2), 4-35, 5-11 Autowrap mode (DECAWM), 4-22, 5-25 tertiary (DA3), 4-35, 5-12 Backarrow key mode (DECBKM), 4-27, Device status report 5 - 26cursor position (CPR), 5-173 Back index (DECBI), 4-24, 5-26 data integrity (DSR), 4-42, 5-174 Bold and blink style mode (DECBBSM), extended cursor position (DECXCPR), 4-19, 5-25 4-23, 5-174Caps lock mode (DECCAPSLK), 4-31, keyboard (DSR), 4-28, 5-175 5 - 28macro (DSR), 4-42, 5-176 Change attributes in rectangular area memory checksum (DSR), 4-42, 5-177 Device status report (DSR), 4-42, 5-173 (DECCARA), 4-22, 5-28 Character set mode (DECNRCM), 4-26, Double-width, double-height line (DECDHL), 4-20, 5-38 5 - 75Clear tabs (TBC), 4-24 Double-width, single-height line Color table request/report/restore (DECDWL), 4-20, 5-48 (DECCTR), **4-19**, 4-44, 5-114 Down-line load (DECDLD), 4-25, 5-39 Column mode (DECCOLM), 4-24, 5-34 Down-line load allocation (DECDLDA), 4-25, 5-47 Conceal answerback message mode (DECCANSM), 4-38, 5-27 Dynamically redefinable character sets Copy key default (DECCKD), 4-27, 5-31 extension (DECDLD), 4-25, 5-39 Copy rectangular area (DECCRA), 4-22, Enable local functions (DECELF), 4-28, 5 - 355 - 51CRT save mode (DECCRTSM), 4-34, 5-37 Enable secondary keyboard language mode CRT saver timing (DECCRTST), 4-34, (DECESKM), 4-28, 5-53 5 - 36Enable session (DECES), 4–16, 5–53 Cursor backward (CUB), 4-22, 5-7 Energy saver timing (DECSEST), 4-34, Cursor backward tabulation (CBT), 4-22, 5 - 130Enter/exit IBM ProPrinter emulation mode (DECIPEM), 4-34, 5-62 Cursor down (CUD), 4-22, 5-7 Cursor forward (CUF), 4-22, 5-7 Enter/exit PCTerm mode from VT mode (DECPCTERM), 4-36, 5-81 Cursor horizontal absolute (CHA), 4-22, Erase character (ECH), 4-21, 5-179 5 - 3Cursor horizontal forward tabulation Erase color mode (DECECM), 4-19, 5-48 (CHT), 4-22, 5-4 Erase in display (ED), 4-21, 5-180 Cursor information report (DECCIR), Erase in line (EL), 4-21, 5-180 4-22, 5-30Erase rectangular area (DECERA), 4-22, Cursor keys mode (DECCKM), 4-28, 5-32 5-52Exiting ANSI (VT52) mode (DECANM), Cursor next line (CNL), 4-22, 5-4 Cursor position (CUP), 4-23, 5-8 4-36, 5-19 Cursor position report (CPR), 4-23, 5-5, Extended cursor position report 5 - 173(DECXCPR), 4-23, 5-170, 5-174 Cursor previous line (CPL), 4-23, 5-5 Extended keyboard report (DECEKBD), 4-28, 5-49 Cursor up (CUU), 4-23, 5-8 Data integrity report (DSR), 4-42, 5-174 Fill rectangular area (DECFRA), 4-22, DDD1 (DDD1), 4-43, 5-14 DDD2 (DDD2), 4-43, 5-14 Forward index (DECFI), 4-24, 5-54 DDD3 (DDD3), 4-43, 5-14 Framed windows mode (DECFWM), 4-17,

5 - 56

ANSI control sequences ANSI control sequences by Name (cont'd) by Name (cont'd) Greek/N-A keyboard mapping (DECNAKB), Locking shift G1 (LS1), 4-2, 4-27, 5-187 Locking shift G1 right (LS1R), 4-27, 5-187 4-29.5-74Half-duplex mode (DECHDPXM), 4-41, Locking shift G2 (LS2), 4-27, 5-187 Locking shift G2 right (LS2R), 4-27, 5-187 5-56Locking shift G3 (LS3), 4-27, 5-187 Hebrew encoding mode (DECHEM), 4-28, Locking shift G3 right (LS3R), 4-27, 5-187 5 - 57Hebrew/N-A keyboard mapping Macro space report (DECMSR), 4-42, 5-73 (DECHEBM), 4-28, 5-58 Macro space report (DSR), 4-42, 5-176 Horizontal and vertical position (HVP), Media copy (MC), 4-33, 5-188 4-23, 5-183 Memory checksum (DECCKSR), 4-42, Horizontal cursor coupling (DECHCCM), 5-33, 5-177 4-17, 5-100 Modem control mode (DECMCM), 4-41, Horizontal position absolute (HPA), 4-23, National replacement character set mode 5 - 181Horizontal position relative (HPR), 4-23, (DECNRCM), 4-26, 5-75 Next line (NEL), 4-23, 5-191 5 - 181Next page (NP), 4-25, 5-191 Horizontal tab (HT), 4-23, 5-182 Horizontal tab set (HTS), 4-24, 5-182 No clearing screen on column change Host wake-up mode (DECHWUM), 4-34, (DECNCSM), 4-24, 5-74 Null mode (DECNULM), 4-41, 5-76 Identify device (DECID), 4-35, 5-60 Numeric keypad mode (DECNKM), 4-29, Index (IND), 4-24, 5-184 5 - 75Num lock mode (DECNUMLK), 4-31, 5-76 Insert character (ICH), 4-21, 5-183 Insert column (DECIC), 4-21, 5-59 Operating status (DSR), 4-42, 5-177 Insert line (IL), 4-21, 5-184 Origin mode (DECOM), 4-24, 5-77 Insert/replace mode (IRM), 4-21, 5-185 Overscan mode (DECOSCNM), 4–36, 5–77 Invoke confidence test (DECTST), 4-38, Page cursor-coupling mode (DECPCCM), 4-17, 5-80 5 - 162Invoke macro (DECINVM), 4-42, 5-61 Page position absolute (PPA), 4-25, 5-192 Keyboard action mode (KAM), 4-28, 5-185 Page position backward (PPB), 4-25, Keyboard language selection (DECKBD), 5 - 1934-28, 5-63Page position relative (PPR), 4-25, 5-193 Keyboard LEDs host indicator mode Pan down (SU), 4-17, 5-207 (DECKLHIM), 4-31, 5-65 Pan up (SD), 4-17, 5-200 Keyboard usage mode (DECKBUM), 4-29, Play sound (DECPS), 4-18, 5-89 Preceding page (PP), 4-25, 5-192 Presentation state report (DECPSR), 4-42, Keypad application mode (DECKPAM), 4-28, 5-665 - 116Keypad numeric mode (DECKPNM), 4-29, Primary device attributes (DA1), 4-35, 5-9 Printer port (DSR), 4-33, 5-178 Key position mode (DECKPM), 4-29, 5-66 Print extent mode (DECPEX), 4-33, 5-83 Left right margin mode (DECLRMM), Print form feed mode (DECPFF), 4-33, 4-24, 5-725-83 Program alphanumeric key (DECPAK), Line feed/new line mode (LNM), 4-23, 4-30, 5-78 5 - 186Program function key (DECPFK), 4-30, Load answerback message (DECLANS), 4-38, 5-68 Load banner message (DECLBAN), 4-38, Program key action (DECPKA), 4-30, 5-87 Program key free memory report Load LEDs (DECLL), 4-31, 5-71 (DECPKFMR), 4-30, 5-88 Load time of day (DECLTOD), 4-34, 5-72 Report displayed extent (DECRPDE), Local echo: send/receive mode (SRM), 4-17, 5-95 4-38, 5-204 Report function key definition (DECRPFK), Local function key control (DECLFKC), 4-31, 5-96 Report key type (DECRPKT), 4-31, 5-96 4-29.5-70

Locking shift G0 (LS0), 4-2, 5-187

Report mode (DECRPM), 4-38, 4-42, 5-98

ANSI control sequences ANSI control sequences by Name (cont'd) by Name (cont'd) Report modifiers/alphanumeric key state Select active status display (DECSASD), (DECRPAK), 4-31, 5-94 4-39, 5-120 Report selection or setting (DECRPSS), Select attribute change extent (DECSACE), 4-43, 5-102 4-22, 5-119 Report terminal unit ID (DECRPTUI), Select character protection attribute 4-35, 5-104 (DECSCA), 4-21, 5-121 Request and report selection or setting Select character set (SCS), 4-25, 5-197 (DECRQSS), 4-43, 5-112 Select color look-up table (DECSTGLT), Request checksum of rectangular area 4-19, 5-151 (DECRQCRA), 4-42, 5-105 Select columns per page (DECSCPP), Request displayed extent (DECRQDE), 4-24, 5-125 4-17, 5-105 Select communication port (DECSCP), Request key definition (DECRQKD), 4-31, 4-39, 5-124 5 - 106Select communication speed (DECSCS), Request key type (DECRQKT), 4-31, 4-39, 5-126 5-107 Select conformance level (DECSCL), 4-36, Request mode (DECRQM), 4-42, 5-108 5 - 122Request presentation state report Select Digital printed data type (DECRQPSR), 4-42, 5-111 (DECSDPT), 4-33, 5-129 Request program key free memory Select disconnect delay time (DECSDDT), (DECRQPKFM), 4-30, 5-111 4-41, 5-128 Request terminal state report Select flow control (DECSFC), 4-41, 5-133 (DECRQTSR), 4-43, 5-113 Select graphic rendition (SGR), 4-20, Request user-preferred supplemental set 5-201 (DECRQUPSS), 4-26, 5-115 Selective erase in display (DECSED), Reset mode (RM), 4-38, 5-195 4-21, 5-129 Reset to initial state (RIS), 4-39, 5-194 Selective erase in line (DECSEL), 4-21, Restore cursor (DECRC), 4-23, 5-92 5 - 131Restore presentation state (DECRSPS), Selective erase rectangular area (DECSERA), 4-22, 5-132 4-44, 5-116 Select modifier key reporting (DECSMKR), Restore saved cursor (SCO) (SCORC), 4-23, 6-94-31, 5-139 Restore terminal state (DECRSTS), 4-44, Select printer type (DECSPRTT), 4–33, 5-144 5 - 117color table, 5-118 Select ProPrinter character set Reverse attributes in rectangular area (DECSPPCS), 4-33, 5-143 (DECRARA), 4-22, 5-90 Select set-up language (DECSSL), 4-34, Reverse index (RI), 4-24 5 - 148Review previous lines (DECRPL), 4-17, Select status display (line) type (DECSSDT), 4-39, 5-147 5 - 97Right-to-left copy mode (DECRLCM), 4-23, Select terminal ID (DECTID), 4-35, 5-158 Select zero symbol (DECSZS), 4-26, 5-155 Right-to-left mode (DECRLM), 4-23, 5-93 Send 7-bit C1 control character to host Save cursor (DECSC), 4-23, 5-120 (S7C1T), 4-27, 5-196 Save cursor position (SCO) (SCOSC), 4-23, Send 8-bit C1 control characters (S8C1T), 6 - 95 - 196Screen alignment pattern (DECALN), 5-17 Send 8-bit C1 control character to host Screen mode: light or dark screen (S8C1T), 4-27 (DECSCNM), 4-20, 5-123 Session page memory allocation Scrolling mode (DECSCLM), 4-24, 5-123 (DECSPMA), 4-16, 5-141 Set cursor style (DECSCUSR), 4-23, 5-127 Secondary device attributes (DA2), 4-35, Set icon name (DECSIN), 4-17, 5-134 Secure reset (DECSR), 4-39, 5-144 Set key click volume (DECSKCV), 4-31, Secure reset confirmation (DECSRC), 4-39. 5-146 Set left and right margins (DECSLRM),

4-24, 5-137

ANSI control sequences	ANSI control sequences
by Name (cont'd)	by Name (cont'd)
Set lines per page (DECSLPP), 4–24, 5–136	User-preferred supplemental set (DECRQUPSS), 4–26, 5–115
Set lock key style (DECSLCK), 4–31, 5–135	Vertical cursor-coupling mode (DECVCCM) 4–17, 5–170
Set margin bell volume (DECSMBV), 4–18, 5–138	Vertical line position absolute (VPA), 4-23 5-208
Set mode (SM), 4–36, 5–206	Vertical position relative (VPR), 4-23,
Set number of lines per screen (DECSNLS),	5–208
4-17, 5-140	VT52 mode, 4–45
Set port parameters (DECSPP), 4–40, 5–142	Answerback concealed, 2–51
Set scroll speed (DECSSCLS), 4–24, 5–146	enabling, 2–50
Set tab at every 8 columns (DECST8C),	message, 2–50
4-24, 5-149	Application
Set terminal unit ID (DECSTUI), 4–35,	cursor keys, 2–43
5–153	keypad mode, 2–44
Set top and bottom margins (DECSTBM),	Arrow keys, 5–32
4-24, 5-149	ASCII
Set transmit rate limit (DECSTRL), 4-40,	boarder display, 12-10
5–152	character sets
Set warning bell volume (DECSWBV),	defining, 13–1
4–18, 5–154	emulation mode, 3-7
Set window title (DECSWT), 4–17, 5–156	loading, 13–3
Show control character mode (CRM), 4–27,	code table
4-36, 5-6	7-bit, 4–15
Single shift (SS), 4-27, 5-205	8-bit, 4–15
Single shift 2 (SS2), 4–27, 5–205 Single shift 3 (SS3), 4–27, 5–205	color mode, 2–32 communications
Single-width line (DECSWL), 4–20, 5–154	answerback message, 12–1
Soft terminal reset (DECSTR), 4–20, 5–134	monitor mode, 12–1
5–150	serial port, 12–2
Switch between ASCII character and	serial port control, 12-1
Scancode mode (DECPCTERM), 4-36,	control functions, 11–1
5–81	controlling cursor, 12-21
Tab clear (TBC), 4-24, 5-207	defined, Glossary-1
Tab stop report (DECTABSR), 4-44, 5-157	display attribute
Terminal identification (DECID), 4–35,	control functions, 12–17
5–60	editing control functions, 12–25
Terminal mode emulation (DECTME),	emulation
4–36, 5–159	features, 2–35
Terminal state report color table report (DECCTR), 4-44,	menu, 2–35 emulations, 11–1
5–114	enhanced mode, 11–2
Terminal state report (DECTSR), 4–44,	graphic characters, 12–36
5–160	keyboard
color table report, 5-161	processing, 12–5
Tertiary device attributes (DA3), 4–35, 5–12	program key direction, 12–8 redefinable keys, 12–9
Text cursor enable mode (DECTCEM),	selections, 11–3
4–23, 5–157	local functions
Transmit rate limiting (DECXRLM), 4–40,	ASCII code mode, C-10
5–171	PC scancode mode, C-11
Update session (DECUS), 4-16, 5-169	overscan on/off, 12–10
User-defined keys (DECUDK), 4-32, 5-163	page edit, 12–27
User-defined keys (DSR), 4-32, 5-179	page memory, 12-12
	PC keycodes

ASCII	ASCII control functions (cont'd)
PC keycodes (cont'd)	ESC`8 (screen display off), 12-10
ADDS mode, C-4	ESC 8 (smooth scroll on, TVI), 12-11
TVI mode, C-1	Esc 9 (mark block ending), 12-34
WYSE mode, C-1	ESC 9 (received CR), 12–22
printer selection, 11–3	ESC 9 (screen display on), 12-10
printing data, 12–34	ESC 9 (smooth scroll off, TVI), 12–11
print/send operations, 12–33	ESC : (80-column display), 12-11
protecting data, 11–3, 12–20	Esc: (clear page to NULs), 12–27
rectangular area operations, 12–28	ESC ; (132-column display), 12-11
screen processing, 12–10	Esc; (clear page to spaces), 12–27
split screen, 12–12	ESC < (keyclick off), 12–7
windows, 12–13	ESC > (keyclick on), 12–7
selecting character sets, 13–3	ESC ? (read cursor address), 12-24
sending data, 12-32, 12-34	Esc @ (autoprint on), 12-35
status lines, 12–13	ESC @ (num lock off), 12-6
swap/copy/move, 12-31	Esc @ (print formatted page), 12-35
terminal management, 12–4	Esc A (autoprint off), 12–35
VT keycodes	Esc a (control print mode off), 12-35
ADDS mode, C-8	ESC `a (editing status line on), 12–13
TVI mode, C-6	ESC a <i>line</i> R <i>col</i> C (address cursor), 12–24
WYSE mode, C-6	ESC \ area attr (assign display attribute),
ASCII control functions	12–18
color selection, 12-16	ESC B (block mode on), 12-3
ESC! 1 (lock cursor line on), 12-22	ESC b (read cursor address), 12-24
ESC! 2 (lock cursor line off), 12–22	ESC b (reverse background), 12-10
ESC! attr (clear page), 12-19	ESC `b (standard status line on), 12-13
ESC " (lock keyboard), 12–5	ESC c (ASCII key codes), 12-6
ESC # (lock keyboard), 12-5	ESC C (block mode off), 12-3
Esc \$ (graphics mode on), 12-36	ESC c (set local mode), 12-3
Esc % (graphics mode off), 12-36	ESC `c (status line off), 12-13
ESC & (protect mode on), 12–20	ESC c 0 (serial port parameters), 12-2
ESC ( (write-protect off), 12-20	ESC c 1 (set comm2 parameters), 12-2
Esc `(control print mode on), 12-35	ESC c 2 (set comm1 receive), 12-2
ESC (protect mode off), 12-20	ESC c 3 (set comm2 receive), 12-3
ESC / (read window, page, cursor), 12-24	ESC c 4 (set comm1 transmit), 12-3
ESC ) (write-protect on), 12–20	ESC c 5 (set comm2 transmit), 12-3
Esc * (clear page to NULs), 12-27	ESC c 6 Max (transmit speed), 12–3
Esc + (clear page to spaces), 12-27	ESC c 7 Max (function keys), 12-3
Esc , (clear page to protected spaces), 12-27	ESC c 8 hr min (set time of day), 12-5
Esc . char (clear page to character), 12-27	ESC c; answer Ctrl/Y (answerback message),
ESC . cursor (set cursor), 12-21	12–1
Esc 0 (clear all tabs), 12–26	ESC c < (send answerback), 12-1
ESC 0 (EOL wrap off), 12-21	ESC $c = (conceal \ answerback), 12-1$
ESC 0 spca (write-protect), 12–18	Esc c? bank (clear font bank), 13-4
Esc 1 (set tab stop), 12–26	Esc c @ bank charset (load font bank), 13-3
Esc 2 (clear tab stop), 12-26	Esc c A bank Pp bbbb Ctrl-Y (define & load
Esc 3 (clear all tabs), 12–26	character), 13–5
Esc 3 (control print mode on), 12-35	Esc c B <i>bank</i> (define primary char. set), 13–3
Esc 4 (control print mode off), 12-35	Esc c C bank (define secondary char. set), 13–3
Esc 4 (send cursor line), 12-34	Esc c D (select primary char. set), 13-3
ESC 5 (lock keyboard), 12-5	Esc c E (select secondary char. set), 13–3
Esc 5 (send page), 12–34	Esc c F <i>line col char</i> (fill rectangle), 12–30
ESC 6 (lock keyboard), 12-5	Esc c F <i>line</i> ~ <i>col char</i> (fill rectangle), 12–30
Esc 6 (send cursor line), 12-34	Esc c G <i>line col</i> (draw rectangle), 12–30
Esc 7 (send page), 12–34	Esc c G <i>line</i> ~ <i>col</i> (draw rectangle), 12–30
Esc 8 (mark block beginning), 12–34	Esc c H <i>line col char</i> (fill rectangle), 12–30
ESC 8 (received CRLF), 12-22	Esc c H <i>line</i> ~ <i>col char</i> (fill rectangle), 12–30

ASCII control functions (cont'd)	ASCII control functions (cont'd)
Esc c I <i>char</i> (clear column to character), 12-28	ESC e 0 (char attribute mode off), 12-18
Esc c J (delete cursor column), 12-27	ESC e 1 (char attribute mode on), 12-18
Esc c K (clear position to NUL), 12–28	ESC e 2 (page attribute mode on), 12-18
Esc c L (clear to EOL with NULs), 12–28	ESC e 3 (line attribute mode on), 12–18
Esc c M (insert column of NULs), 12-27	ESC e 4 (received CR), 12-22
Esc c N width height (draw rectangle), 12–30	ESC e 5 (received CRLF), 12-22
Esc c O (clear to EOL with spaces), 12–28	ESC e 6 (ACK mode off), 12-1
Esc c P (clear foreground to spaces), 12–28	ESC e 7 (ACK mode on), 12-1
Esc c Q (clear foreground to NULs), 12–27	ESC e 8 (assign serial ports), 12–1
Esc c R (clear foreground to spaces), 12-28	ESC e 9 (s1=comm2), 12-1
Esc c S (clear foreground to NULs), 12–28	ESC e > (character cell size), 12-11
ESC c T (set default all modes), 12-5	ESC e ? (character cell size), 12-11
ESC c \ tone (select bell), 12–7	ESC e A (num lock on), 12-6
ESC c U (clear all key definitions), 12-8	ESC e B (scroll lock off), 12-6
ESC `cursor (set cursor), 12–21	ESC e C (scroll lock on), 12-6
ESC c V (save Set-Up modes), 12-4	ESC e D (DEL mode off), 12-22
ESC c W (save Set-Up modes), 12-4	ESC e E (DEL mode on), 12-22
ESC c X (power on reset), 12–5	ESC e H (ASCII key codes), 12-6
ESC c ] <i>Intensity</i> (border display), 12–10	ESC e I (PC scan codes), 12-6
Esc c ^ (swap, copy, move data), 12-30	ESC e L (bell off), 12-7
Esc d! (aux mode on), 12-35	ESC e M (bell on), 12-7
Esc d # (control print mode on), 12-35	Esc e N (font loading off), 13-4
Esc d \$ (bidirectional mode off), 12-35	Esc e O (font loading on), 13-4
Esc d % (bidirectional mode on), 12-35	ESC e P (screen saver off), 12-10
Esc d & (begin print), 12–34	ESC e Q (screen saver on), 12-10
ESC d ( (cursor drag off), 12-13	ESC e R (ignore null characters), 12-1
Esc d`(begin print), 12–34	ESC e S (accept null characters), 12-2
ESC d / (EOL wrap on), 12–21	ESC e Sp (answerback off), 12-1
ESC d (normal background), 12-10	ESC e T (lock key), 12-6
ESC D (request attribute under cursor), 12–19	ESC e U (lock key), 12–6
ESC d) (cursor drag on), 12–13	ESC e V (lock key), 12-6
ESC d * (autopage off), 12–21	ESC e   (intensity off), 12–16
ESC d + (autopage on), 12–21	ESC e } (intensity on), 12–16
ESC d. (EOL wrap off), 12–21	ESC f (clear label line), 12–15
ESC D F (set full-duplex), 12–3	ESC F (fill page H's), 12–12
ESC D H (set half-duplex), 12–3	ESC F CR (clear computer message), 12–14
ESC d line R col C (address cursor), 12–24	ESC f CR (clear label line), 12–15
Esc d Sp (aux mode off), 12–35	ESC F <i>message</i> CR (display computer message)
ESC d { (blank attribute), 12–16	12–14
ESC d   (reverse on), 12-16	ESC f text CR (display computer message),
Esc e! (answerback on), 12–1	12–14
Esc e " (page edit off), 12–27	ESC g (user line on), 12–17
Esc e # (page edit on), 12–27	ESC G Attr (assign character attribute), 12–17
ESC e \$ (keyclick off), 12-7	ESC G <i>LineAttr</i> (assign line attribute), 12–19
ESC e % (keyclick on), 12–7	ESC H (lock cursor line on), 12–22
ESC e & (caps lock on), 12-6	ESC H (PC scan codes), 12–6
ESC e ( (set 24 data lines), 12–11	ESC h (user line off), 12–17
ESC e ' (caps lock off), 12-6	Esc H <i>char</i> (display character), 12–36 Esc H Ctrl-B (graphics mode on), 12–36
Esc E (insert line of spaces), 12–27	Esc H Ctrl-B (graphics mode off), 12–36 Esc H Ctrl-C (graphics mode off), 12–36
ESC e - (key repeat on), 12–5 ESC e (user line off), 12–17	ESC h page (address cursor), 12–24
ESC e / (width-change-clear on), 12–12	Esc I (back tab cursor), 12–26 ESC`I (lock cursor line off), 12–22
ESC e ) (set 25 data lines), 12–11 ESC e * (set 42 data lines), 12–11	Esc i (tab cursor), 12–26
ESC e + (set 42 data lines), 12–11 ESC e + (set 43 data lines), 12–11	ESC J (activate other window), 12–13
ESC e , (key repeat off), 12–5	ESC j (cursor up), 12–23
ESC e . (width-change-clear off), 12–12	ESC J (display page), 12–12
(with change tien on), 16 16	(alopia) page/, in in

ASCII control functions (cont'd)	ASCII control functions (cont'd)
ESC ` J (set margin bell), 12-7	ESC v 4 (set WYSE 160/60 personality), 12-4
ESC K (activate other window), 12-13	ESC v 5 (set WYSE 160/60 PCTerm), 12-4
Esc k (clear foreground to NULs), 12-27	ESC v 6 (set VT52 personality), 12-4
Esc K (clear to EOL with spaces), 12–28	ESC v; (set VT100 personality), 12-4
ESC K (display next page), 12-12	ESC v < (set VT520, 7-bit), 12-4
Esc k (local edit on), 12-25	ESC $v = (set VT520, 8-bit), 12-4$
Esc l (local edit off), 12-25	ESC v Sp (enhanced mode off), 12-4
Esc L (print page), 12–35	ESC w (autopage off), 12-21
Esc L (print page with time), 12–36	Esc W (delete cursor character), 12-27
Esc L (print unformatted page), 12-35	ESC w ´ (read page number), 12-24
ESC \ length (page size), 12-12	ESC w ` (read page number), 12-24
ESC m (select terminal defaults), 12-5	ESC w, (read page number), 12-24
Esc M (send cursor character), 12-34	ESC w . (read page number), 12-24
ESC M (send terminal ID), 12-4	ESC w @ page line col (address cursor), 12-24
ESC N (autoscroll off), 12-21	ESC w B (display page), 12-12
ESC n (bell off), 12-7	ESC w C (display next page), 12-12
Esc N (page edit on), 12-27	ESC w E (roll window up), 12-13
ESC n (screen display on), 12-10	ESC w F (roll window down), 12-13
ESC N (screen display on), 12-10	ESC - win/page line col (address cursor),
ESC O (autoscroll on), 12–21	12–24
ESC o (bell on), 12–7	ESC w <i>length</i> (page size), 12–12
Esc O (page edit off), 12-27	ESC w <i>page</i> (display page), 12–12
ESC o (screen display off), 12-10	ESC ` wpca (write-protect), 12–18
ESC O (screen display off), 12–10	ESC X (monitor mode off), 12–1
ESC o (set margin bell), 12-7	ESC x 0 (redefine screen), 12–13
Esc P (print page to cursor), 12–35	ESC x 1 <i>line</i> (horiz split screen), 12–13
Esc p (print unformatted page), 12-35	ESC x 3 <i>line</i> (horiz split screen), 12–13
ESC - page line col (address cursor), 12–24	ESC x @ (redefine screen), 12–13
Esc p <i>char</i> (define terminator), 12–36	ESC x A <i>line</i> (split screen), 12–13
Esc q (insert mode on), 12–27	ESC x C <i>line</i> (horiz split screen), 12–13
Esc Q (insert space), 12–27	Esc x <i>dlmtr c1 c2</i> (define delimiters), 12–33
Esc R (delete cursor line), 12–27	ESC x P (lower horiz split), 12–13
Esc r (replace mode on), 12–27	ESC x R (raise horiz split), 12–13
Esc s (send block), 12–34	ESC Y (address cursor), 12–24
Esc S (send character in block), 12–34	Esc y (clear page to NULs from cursor), 12–27
ESC ` Scroll (scroll type), 12–11	Esc Y (clear page to spaces from cursor), 12–27
ESC Sp (send terminal ID), 12–4	ESC z (CR (clear label line), 12–15
ESC Sp 1 (set time of day), 12–5	Esc z (insert mode on), 12–27
ESC Sp 2 (set time of day), 12–5	ESC z) CR (clear shifted label line), 12–15
ESC Sp J (num lock on), 12–6	ESC z) <i>text</i> CR (display computer message),
ESC Sp K (num lock off), 12–6	12–14 ESC a DEL (disable label line) 12–15
ESC Sp L (caps lock on), 12-6	ESC z DEL (disable label line), 12–15
ESC Sp M (caps lock off), 12-6	ESC Z dir key DEL (clear key definition), 12-8
ESC Sp N (scroll lock on), 12–6	ESC Z <i>dir key seq</i> DEL (program key direction), 12–7
ESC Sp O (scroll lock off), 12–6 Esc t (clear to EOL with NULs), 12–28	ESC z <i>field</i> CR (display F key label), 12–14
Esc T (clear to EOL with spaces), 12–28	ESC z <i>Fkey</i> DEL (clear key definition), 12–8
ESC u (monitor mode off), 12–1	ESC z Fkey Seq DEL (program function keys),
ESC U (monitor mode on), 12–1	12–7
ESC v! (set enhanced mode), 12–4	ESC Z ~ <i>Key</i> (inquire key direction), $12-8$
ESC v " (set WYSE 50+ personality), 12–4	ESC [ (request key status), 12–6
ESC v # (set TVI 910 personality), 12–4 ESC v # (set TVI 910 personality), 12–4	ESC [ line (address cursor), 12–24
ESC v \$ (set TVI 910 personality), 12–4 ESC v \$ (set TVI 925 personality), 12–4	ESC ] (activate upper window), 12–13
ESC v % (set ADDS personality), 12–4 ESC v % (set ADDS personality), 12–4	ESC ] <i>answer</i> Ctrl/M (answerback message),
ESC v ( (set TVI 950 personality), 12–4	12–1
ESC v (autopage on), 12–21	ESC ] <i>Col</i> (address cursor), 12–24
Esc V (clear column to spaces), 12–28	ESC ^ (set 25 data lines), 12–11
1 //	* **

ASCII control functions (cont'd)	Bell (cont'd)
ESC ^ 0 (normal background), 12-10	warning, 2–25, 2–42
ESC ^ 1 (reverse background), 12-10	7-bit and 8-bit environments, 4–10
ESC _ (set 43 data lines), 12-11	7-bit ASCII code table, 4–15
ESC _ Col (address cursor), 12-24	8-bit ASCII code table, 4–15
ESC { (cursor home), 12-24	7-bit code extension technique, 4-9
ESC { (set half-duplex), 12-3	7-bit NRCS character sets, 7-2
ESC { baud stop parity word (serial port	Blinking, 5–201
parameters), 12–2	Bold and blink style, 2-32
ESC   Fkey dir seq Ctrl-Y (program key	Bold display, 5-201
direction), 12–8	Break key, 9–15
ESC } (activate lower window), 12–13	British/U.K.
ESC } (set full-duplex), 12–3	PC keyboard, B-5
ESC } baud stop parity word (serial port	VT keyboard, A-4
parameters), 12–2	
ESC ~! (set enhanced mode), 12-4	C
ESC ~ " (set WYSE 50+ personality), 12-4	·
ESC ~ # (set TVI 910 personality), 12–4	C0 control characters, 4–1, <b>4–15</b>
ESC ~ \$ (set TVI 925 personality), 12–4	C1 control characters, 4–1, 4–9, <b>4–15</b>
ESC ~ % (set ADDS personality), 12–4	Calculator, 2–11
ESC ~ ((set TVI 950 personality), 12–4	feature, 3–1
ESC ~ (EOL wrap on), 12–21	enabling, 3–2
ESC ~ 4 (set WYSE 160/60 personality), 12–4	Canadian
ESC ~ 5 (set WYSE 160/60 PCTerm), 12–4	English
ESC ~ 6 (set VT52 personality), 12–4	PC keyboard, B-6
ESC ~; (set VT100 personality), 12–4	VT keyboard, A-4 French
ESC ~ < (set VT520, 7-bit), 12-4	PC keyboard, B-7
ESC $\sim$ = (set VT520, 8-bit), 12-4 ESC Sp (explanaed mode off), 12-4	VT keyboard, A-5
ESC ~ Sp (enhanced mode off), 12–4	CAN character, 4–9
Assign colors, 2–28	Carrier detect, 9–6
Audible attributes	Character
control functions, 4–18 Austrian	delete, 7–3
PC keyboard, B-3	NULL, 7–3
VT keyboard, A-2	space, 7–3
Auto	Character attributes, 5–201
answerback, 2–50	Character encoding, 4–15
repeat rate, 2–43	Characters
resize, 2–20	ASCII graphic, 12–36
wrap, 2-23	Character set codes, 5–198
Automatic font loading, 13–4	Character sets, 2–11, <b>7–1</b>
Autorepeating keys, 5–19	ASCII control functions, 13–1
Autowrapping text, 5–25	ASCII emulation mode, 3-7
TI 8	7-bit NRCS, 2-34, 7-2
D	control characters, 7-3
<u>B</u>	default
Banks, 13-3	PC, 2-34
Banner message, 2-11, 3-1	VT, 2-34
power on, 2–3	designing, 7–6
Baud rate	downloaded, 7–5
menu, 2–48	downloading, 7-13
receive speed, 2–48	mappings
Belgian	ANSI, 7–4
PC keyboard, B-4	PCTerm mode, 7–5
VT keyboard, A-3	PCTerm mode, 7-2, 7-4
Bell	printer, 2–55
margin, 2–42	DEC/ISO, 2–56
visible, 2-43	PC, 2-56

Character sets (cont'd)	Communications (cont'd)
SCO Console mode, 7–5	data link layer, 9–9
selecting, 7–5	disconnect delay, 2-52
ANSI, 7–4	DSR, 9-5, 9-12
designating, 5–197	DTR, 9–5, 9–12
for ProPrinter, 5–143	features, 1–1
Hebrew encoding mode, 5–57	features affected by, 9–13
locking shifts (LS), 5–187	features to control functions, 2–45
mapping, 5–187, 5–199, 5–205	flow control, $9-10$
overview, 5–197	PCTerm mode, 11–3
PCTerm mode, 7–4	half-duplex, 2–50, 9–7
SCO Console mode, 7–5	
	line disconnect, 9–14
single shifts (SS), 5-205	menu, 2–45
user-preferred supplemental sets, 5–24	MMJ port
show, 3–1, 3–7	signals, 9–3
soft, 7–5	modem
structure, 7–3	disconnect, 9–5
support, 1–4	high speed, 2–53
VT mode, 7–1, 7–4	low speed, 2–53
Clear	off line, 9–6
communications, $2-9$ , $9-14$ , $10-7$	supported types, 9-7
display, 2–9	no flow control, 9–11
on change, 2–22	parity, 2–47
printer, 10–7	25-pin ports, 9–1, 9–2
Clock, 2-11	signals, 9–2
feature, 3–1, 3–5	receive buffer, 9-10
Code pages	receive speed, 2–48
defined, 7–1	RLSD, 9-6
Coding conventions, 4–10	RTS, 9-4
Color	RXD, 9-4
assigning, 2-28	select
selection	DECSCP, 4-39
control functions, 4-18	SPDI, 9-6
Colors	SPDS, 9-7
alternate text, 2-30	stop bits, 2-47
ASCII color mode, 2-32	transmit speed, 2–48
bold and blink style, 2-32	two-way, 2-57
defining, 2–31	TXD, 9-4
erase, 2–32	word size, 2–47
intensity, 2–33	XOFF/XON, 9–11
mode, 2–32	XPC flow control, 9–11
reverse and blank, 2–33	Compose, 8–2
Color table request/report/restore (DECCTR),	Context sensitivity, 2–3
4-19	Control
Columns	ANSI functions
per page, 2–22	defined, 4–1
Communications	characters, 7–3
ASCII	functions, 5–1
answerback message, 12–1	ANSI
monitor mode, 12–1	audible attributes, 4–18
serial port, 12-2	color selection, 4–18
serial port control, 12-1	communications, 4–39
break, 9-15	editing, 4–21
carrier detect, 9–6	graphic character sets, 4-25
clear, 9-14	keyboard processing, 4-27
clear printer, 10–7	printer, 4–33
control functions, 4–39	reports, 4–42
CTS, 9-4	sessions, 4–16

Control	Cursor (cont'd)
functions	invisible, 5-157
ANSI (cont'd)	key codes
terminal management, 4-34	SCO Console mode, 6–6
terminal synchronization, 4-41	moving on the page, 5-7
text processing, 4–22	right-to-left mode, 5–93
visual attributes, 4–20	to protected area, 11–4
terminal management	Czech
defined, 4–15	PC keyboard, B-8
sequences, 5–1	VT keyboard, A-6
Control characters	VI Reyboard, A-0
	_
ANSI, 4–1 to 4–4	D
7-bit, 4–1	Danish
8-bit, 4–3	
7-bit and 8-bit equivalents, 4–4	PC keyboard, B-9
C0, <b>4-15</b>	VT keyboard, A-7
C1, <b>4-15</b>	Data link layer, 9–9
control one (C1), 4–3 to 4–4, 4–5, 4–9, 4–10	Data processing
control zero (C0), 4-1 to 4-3, 4-5, 4-10	keys, 2–43
displaying, 4–11 to 4–15	DCS character, 4–8
in control functions, 4–9	DEC-423 port error, 2–3
showing, 2–24	DEC ANSI
Control codes, 8–28	print mode, 10-4
for Set-Up functions, 2-61	with IBM ProPrinter, 10-6
Control functions	DECDLD
ASCII, 11–1	down-line loading, 7–5
control characters, 4-9	DECSCL, 2–33
control sequence format, 4-6	Default
device control string format, 4-8	character set
escape sequence format, 4-6	PC, 2–34
general format, 4–5	VT, 2–34
interrupting, 4–9	parameters, 2-2
numeric parameters, 4–7	Set-Up modes, 2–61
overview, 4–5 to 4–9	Define colors, 2–31
selective parameters, 4-7	Define Key Editor, 2–37
VT52 mode, 4-45	copy of key default, 2-38
Control sequences, format of, 4–6	correcting mistakes, 2-40
Conventions, iv	Delay
Сору	disconnect, 2-52
direction, 2–23	Designating character sets, 5–197
key default, 2-38	Desktop
settings from menu, 2–17	features
Copy and paste, 3–8	banner message, 3-1
limits, 3–8	calculator, 2-11, 3-1, 3-2
Correcting mistakes	clock, 2-11, 3-1, 3-5
Define Key Editor, 2–40	show character sets, 2-11, 3-1, 3-7
Creating new keyboard key output, 2-40	productivity
CRT	features, 1–4
saver, 2–24	Device
CSI character, 4–6	attributes, 5–12, 5–104
CTS, 9-4	status reports, 5-173 to 5-179
Cursor	Device control
control	strings, 4–8
ASCII control functions, 12–21	Diacritical marks
coupling	PC keyboards, B-1
page, 5-80	VT keyboard, A-1
vertical, 2–22, 5–170	•
display, 2–22	

Dim manu itama 9 9	Embadded amulation made 19 15
Dim menu items, 2–3	Embedded emulation mode, 12–15
Dim video, 2–3	Emulation
Disconnect delay, 2–52	mode, 2–33
Display	Emulations
attribute	ASCII, 11–1
control functions, 12–17	Energy saver, 2–24
capabilities, 1–3	Enhanced mode, 11-2
menu, 2–19	Entering Set-Up, 2–1
Display C0 controls as PC characters (SCO)	Erase color, 2–32
(SCODPCC), 4–27	Erasing data
Displaying control characters, 4-11 to 4-15	ASCII control functions, 12–28
Display menu	Ergonomics, 1-4
control functions, 2–19	Error
Down-line loading	character, 4–2
allocation, 5-47	correcting UDK, 2–40
character sets, 7–5, 7–13	Error messages
DECDLD, 7–5	DEC-423 port error, 2–3
DRCS	keyboard error, 2–3
defined, 1–6	NVR error, 2–3
DSR, 9–5	parallel port error, 2–3
DTR, 2-49, 9-5	ROM cartridge error, 2–3
DTR, 2-49, 9-3 DTR/DSR, 10-2	RS-232 port data error, 2-3
	self-test, 2–3
flow control, 2–48, 2–49, 9–12	
printer, 2–57	Escape sequences, format of, 4–6
threshold, 2-49	VT52 mode, 4–45
Duplex	ESC character, 4–6, 4–9
half, 2–50	Exit Set-Up, 2–9
Dutch	
DC 1 1 1 D 10	
PC keyboard, B-10	F
PC keyboard, B–10 VT keyboard, A–8	
	Features
VT keyboard, A–8	Features affected by communications, 9–13
VT keyboard, A-8	Features affected by communications, 9–13 printer port, 10–1
VT keyboard, A-8  Echo, local, 2-50	Features affected by communications, 9–13 printer port, 10–1 Final character
VT keyboard, A-8  Echo, local, 2-50 Editing	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1
VT keyboard, A-8  Echo, local, 2-50 Editing ASCII control functions, 12-25	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish
VT keyboard, A-8  Echo, local, 2-50 Editing ASCII control functions, 12-25 character protection attribute, 5-121, 5-131	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish
VT keyboard, A-8  Echo, local, 2-50 Editing ASCII control functions, 12-25 character protection attribute, 5-121, 5-131 control functions, 4-21	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–179	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–179 in display, 5–180	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5
Echo, local, 2-50 Editing ASCII control functions, 12-25 character protection attribute, 5-121, 5-131 control functions, 4-21 delete character, 5-13 column, 5-37 line, 5-172 erase character, 5-179 in display, 5-180 in line, 5-180	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–179 in display, 5–180 in line, 5–180 insert	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–180 in line, 5–180 insert character, 5–183	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4 Framed windows, 2–26
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–180 in line, 5–180 insert character, 5–183 column, 5–59 line, 5–184	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4 Framed windows, 2–26 French
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–180 in line, 5–180 insert character, 5–183 column, 5–59	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4 Framed windows, 2–26 French PC keyboard, B–12
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–180 in line, 5–180 insert character, 5–183 column, 5–59 line, 5–184 keypad key codes	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4 Framed windows, 2–26 French PC keyboard, B–12 VT keyboard, A–3 French-Canadian
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–180 in line, 5–180 in line, 5–180 insert character, 5–183 column, 5–59 line, 5–184 keypad key codes SCO Console mode, 6–6 selective erase in display, 5–129	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4 Framed windows, 2–26 French PC keyboard, B–12 VT keyboard, A–3 French-Canadian PC keyboard, B–7
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–180 in line, 5–180 in line, 5–180 insert character, 5–183 column, 5–59 line, 5–184 keypad key codes SCO Console mode, 6–6 selective erase in display, 5–129 EIA communications	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4 Framed windows, 2–26 French PC keyboard, B–12 VT keyboard, A–3 French-Canadian PC keyboard, B–7 VT keyboard, A–5
Echo, local, 2–50 Editing ASCII control functions, 12–25 character protection attribute, 5–121, 5–131 control functions, 4–21 delete character, 5–13 column, 5–37 line, 5–172 erase character, 5–180 in line, 5–180 in line, 5–180 insert character, 5–183 column, 5–59 line, 5–184 keypad key codes SCO Console mode, 6–6 selective erase in display, 5–129	Features affected by communications, 9–13 printer port, 10–1 Final character ANSI index, E–1 Finnish PC keyboard, B–11 VT keyboard, A–9 Flemish VT keyboard, A–10 Flow control, 9–10 printer, 10–1 threshold, 2–49 Font designing, 13–5 loading, 13–4 sizes, 1–4 Framed windows, 2–26 French PC keyboard, B–12 VT keyboard, A–3 French-Canadian PC keyboard, B–7

Function keys	Icon name, 2–14		
codes	ID to host, 2-34		
SCO Console mode, 6-2	Ignore missing keyboard, 2-44		
rate limit, 2-49	Ignore null characters, 2-50		
	Inserting and deleting data, 5–183, 5–185, 5–1		
G	5–195		
	Insert/replace mode, 5–185		
German	In-use table, 5–197		
PC keyboard, B-3	Invisible attribute, 5–201		
VT keyboard, A-2	Italian		
Glossary, Glossary-1	PC keyboard, B-16		
Graphic	VT keyboard, A–14		
character sets, 7–1			
7-bit NRCS, 7–2	K		
control characters, 7–3			
mappings	Keyboard		
ANSI, 7–4	arrow keys, 5–32		
PCTerm mode, 7–5	ASCII		
PCTerm mode, 7–2, 7–4	local functions		
selecting	PC scancode mode, C-11		
ANSI, 7–4	processing, 12–5		
PCTerm mode, 7–4	program key direction, 12–8		
SCO Console mode, 7–5	redefinable keys, 12–9		
soft, 7–5	terminal, 11–3		
structure, 7–3	autorepeating keys, 5–19		
VT mode, 7–1, 7–4	autowrap mode, 5–25		
Graphic character sets	control codes and keystrokes, 8-28		
control functions, 4–25	control functions, 2–36		
Greek	enabling local functions, 5-51		
PC keyboard, B-13	encoding menu item, 2–43		
VT keyboard, A-11	error, $2-3$		
Greek/N-A keyboard	extended keyboard report, 5-49		
mapping, 5–74	features, $1-2$ , $1-3$		
11 0	$\leq \mathbb{X}$ function, 5–26		
Н	"hot" keys, Glossary-2		
<u>П</u>	indicator line, 2–6		
Half-duplex	language for Set-Up, 2-37		
communications, 2-50	layouts		
mode, 9–1	PC keyboards, B-2		
signals, 9–7	VT keyboards, A-1		
Hardware flow control, 1-1	line feed/new line mode, 5-186		
Hebrew	local-function key control, 5-70		
PC keyboard, B-14	local functions		
VT keyboard, A-12	ASCII code mode, C-10		
Hebrew/N-A keyboard	locking keyboard, 5-185		
mapping, 5-58	menu, 2-36		
Hidden emulation mode, 12–15	numeric keypad, 5-67, 5-75		
Hungarian	PC		
PC keyboard, B-15	Austrian, B-3		
VT keyboard, A-13	Belgian, B-4		
•	British/U.K., B-5		
1	Canadian-English, B–6		
1	Canadian-French, B–7		
IBM ProPrinter	Czech, B-8		
mode, 10-5	Danish, B-9		
with DEC ANSI, 10-6	Dutch, B-10		
,	Finnish, B–11		
	French, B-12		
	riench, D-12		

Keyboard	Kaybaard
PC (cont'd)	Keyboard VT (cont'd)
	` '
German, B-3	Swiss-German, A-25
Greek, B-13	Turkish-F, A-26
Hebrew, B-14	Turkish-Q, A-27
Hungarian, B-15	VT legend data, A-1
Italian, B-16	VT vs. PC, 1–2, 8–1
Latin American, B-17	Keyboard control functions, 5–163
North American, B-6	Keyboard mapping
Norwegian, B-18	Greek/N-A, 5–74
Polish, B-19	Hebrew/N-A, 5–58
Portuguese, B-20	Keyclick, 2–42
Romanian, B-21	Keycodes
Russian, B-22	PC keyboard
SCS, B-23	ADDS mode, C-4
Slovak, B-24	TVI mode, C-1
Spanish, B-25	WYSE mode, C-1
Swedish, B-26	VT keyboard
Swiss-French, B-27	ADDS mode, C-8
Swiss-German, B–28	TVI mode, C-6
Turkish, B-29	WYSE mode, C-6
PC legend data, B-2	Key editor, 2–37
processing control functions, 4–27	Keypad mode
quick start summary, 3–8	application, 2–44
saving key definitions, 2–42	Keys
scan code, defined, Glossary-2	application cursor, 2–43
select modifier key reporting, 5–139	data processing, 2–43
typewriter or data processing keys, 5–65	
unlocking keyboard, 5–185	L
user-defined keys, 5–163	I andreada
VT	Language
Austrian, A-2	Set-Up, 2–2
Belgian, A-3	Language, Set-Up, 2–37
British/U.K., A-4	Latin American
Canadian, A-4	PC keyboard, B-17
Canadian-French, A-5	Lines
Czech, A-6	per page, 2–20
Danish, A-7	per screen, 2–20
Dutch, A-8	Local
Finnish, A-9	controller mode, 2–8
Flemish, A-10	echo, 2–8, 2–50
French, A-3	Function keys
German, A-2	SCO Console mode, 6–2
Greek, A-11	mode, 2–8
Hebrew, A-12	Lock
Hungarian, A-13	caps, 2–42
Italian, A-14	keyboard, 5–185
North American, A–4	key definitions, 2–42
Norwegian, A-15	user preferences, 2–23
Polish, A-16	Locking-shift (LS) control functions, 5–187
Portuguese, A-17	
Romanian, A-18	M
Russian, A-19	-
SCS, A-20	Macro commands, 5–45
Slovak, A-21	defining, 5–45
Spanish, A–22	Main keypad key codes
Swedish, A-23	SCO Console mode, 6–3
Swiss-French, A–24	

Main menu, 2–8	
Mapping character sets, 5–199	0
locking shifts, 5–187	<u> </u>
single shifts, 5–205	On-line feature, 2–8
Margins	Origin for page addressing, 5–77
left and right, 5–137	Overscan, 2–25
top and bottom, 5-149	
Mistake	Р
correcting using define key editor, 2-40	Dogo
MMJ port	Page
signals, 9–3	coupling, 2–23 edit
Mode description, 4–37	ASCII control functions, 12–27
Model differences, 1–1	memory
Modem	ASCII, 12–12
control mode	controlling the page format, 5–72
reset, 5–73	left and right margins, 5–137
set, 5–73	left right margin mode, 5–72
disconnect delay, 2–52	lines per page, 5–136
features to control functions, 2–45	moving to a new page, 5–193
high speed, 2–53	80 or 132 columns, 5–34, 5–125
low speed, 2–53	page origin, 5-77
menu, 2–52	top and bottom margins, 5–149
supported, 9–7	Panning, 5–200, 5–207
Mode settings, 4–36, 5–195	Parallel port
MPR II, 1-1, Glossary-3	error, 2–3
Multiple sessions	Parity
enabling and controlling configuration, 2–12	communication, 2-47
management, 2–13 pages, 2–14	Paste and copy, 3-8
reset, 2–18	limits, 3–8
selection, 2–14	PC keyboard
session name, $2-14$	Austrian, B–3
setting up, $2-11$	Belgian, B-4
updating, 2–17	British/U.K., B–5
using a terminal server with TD/SMP, 2–12	Canadian-English, B–6
opening another session, 2–12	Canadian-French, B-7
restoring an interrupted session, 2–13	Czech, B–8
using SSU Host software, 2–12	Danish, B-9
asing see flost software, 2 12	Dutch, B-10
N1	Finnish, B-11
N	French, B-12
New line mode, 2–23	German, B-3
North American	Greek, B-13
PC keyboard, B-6	Hebrew, B-14
VT keyboard, A-4	Hungarian, B–15
Norwegian	Italian, B–16
PC keyboard, B-18	Latin American, B-17
VT keyboard, A-15	legend data, B-2
NULL characters, 2–50	North American, B-6
Numeric keypad, 5-67	Norwegian, B-18
Numeric parameters, 4–7	Polish, B-19
Num lock LED, 2-7, 5-86, 8-8	Portuguese, B-20
NVR error, 2–3	Romanian, B-21
	Russian, B-22
	scan codes, 8–23
	SCS, B-23
	Slovak, B-24
	Spanish. B–25

PC keyboard (cont'd)	Printer		
Swedish, B-26	print (cont'd)		
Swiss-French, B-27	terminator, 2-56		
Swiss-German, B-28	receive flow control, 2-57		
Turkish, B-29	receive speed, 2–48		
PCTerm	same as receive, 2–58		
graphic character sets, 7-2	stalls, 10–7		
mode	stop bits, 2–47, 2–58		
communications flow control, 11-3	suspending operations, 10–7		
on US keyboard, 13-1	transmit flow control, 2–57		
scan codes	transmit speed, 2–48		
EPC keyboards, 8–23	type, 2–55		
VT keyboards, 8–27	word size, 2–57		
selecting character sets, 7–4	Printer port control functions, 5–83		
25-pin port, 9–1, 9–2	Printing		
signals, 9–2	data		
Polish	ASCII control functions, 12–34		
PC keyboard, B-19	form feeds, 5–83		
VT keyboard, A-16	full screen or scrolling region, 5-83		
Portuguese	ProPrinter		
PC keyboard, B-20	enter mode, 5–62		
	exit mode, 5–62		
VT keyboard, A-17 Power-on			
	selecting		
banner message, 2–3, 2–11	character set, 5–143		
Presentation state reports, 5–116	code pages, 5–143		
Print	printer type, 5–144		
data	Protecting data		
transmitting, 10–4	ASCII control functions, 12–20		
modes	description, 11–3		
affecting print operations, 10–3			
operations, 10-4	R		
ASCII, 12–33	Recall		
Printer			
aborting operations, 10–7	key definitions, 2–42		
character sets, 2–55	Receive		
DEC/ISO, 2–56	buffer		
PC, 2-56	communications, 9–10		
control functions, 4–33	flow control, 2–49		
controller mode, 10–4	Receive speed, 2–48		
data transmission, 10–5	Rectangular area operations		
features to control functions, 2–55	changing character attributes, 5–90 to 5–91		
flashes on screen, 10-7			
ignous multiple and atoms 9 50	copying, 5–35		
ignore null characters, 2–50	defined, 12-28		
menu, 2–54	defined, 12–28 erasing, 5–52, 5–132		
9	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55		
menu, 2–54	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys		
menu, 2–54 parity, 2–58 port control functions, 5–83	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9		
menu, 2–54 parity, 2–58 port	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys		
menu, 2–54 parity, 2–58 port control functions, 5–83	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports		
menu, 2–54 parity, 2–58 port control functions, 5–83 DSR/DTR, 10–2	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42		
menu, 2–54 parity, 2–58 port control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30		
menu, 2–54 parity, 2–58 port control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1 flow control, 10–1, 10–3	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30 cursor position report, 5–173		
menu, 2–54 parity, 2–58 port control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1 flow control, 10–1, 10–3 parallel, 10–2 signals, 10–2	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30		
menu, 2–54 parity, 2–58 port control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1 flow control, 10–1, 10–3 parallel, 10–2 signals, 10–2 select, 2–54	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30 cursor position report, 5–173		
menu, 2–54 parity, 2–58 port  control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1 flow control, 10–1, 10–3 parallel, 10–2 signals, 10–2 select, 2–54 serial, 10–1	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30 cursor position report, 5–173 data integrity report, 5–174		
menu, 2–54 parity, 2–58 port  control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1 flow control, 10–1, 10–3 parallel, 10–2 signals, 10–2 select, 2–54 serial, 10–1 print	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30 cursor position report, 5–173 data integrity report, 5–174 extended cursor position report, 5–174		
menu, 2–54 parity, 2–58 port  control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1 flow control, 10–1, 10–3 parallel, 10–2 signals, 10–2 select, 2–54 serial, 10–1 print extent, 2–56	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30 cursor position report, 5–173 data integrity report, 5–174 extended cursor position report, 5–174 macro space report, 5–176		
menu, 2–54 parity, 2–58 port  control functions, 5–83 DSR/DTR, 10–2 features, 1–3, 10–1 flow control, 10–1, 10–3 parallel, 10–2 signals, 10–2 select, 2–54 serial, 10–1 print	defined, 12–28 erasing, 5–52, 5–132 filling, 5–55 Redefining keys ASCII, 12–9 Repeat keys, 2–43 Reports control functions, 4–42 cursor information report, 5–30 cursor position report, 5–173 data integrity report, 5–174 extended cursor position report, 5–174 macro space report, 5–176 memory checksum, 5–177		

factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21  SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 ESC Q Fn String (SCODFK), 6–7 ESC xx (SCODPCC), 6–8 by Mnemonic	Reports (cont'd)	
report selection or setting. 5–102 request mode. 5–108 restore presentation state, 5–116 restore terminal state, 5–117 color table. 5–118 secondary device attributes (DA2). 5–11 set mode. 5–206 tab stop report. 5–157 terminal unit ID, 5–104 tertilary device attributes (DA3). 5–12 user-defined keys. 5–179 Resetting modem control mode, 5–73 session. 2–10 terminal state. 5–144 soft reset. 2–10 Resetting the terminal, 5–207 clearing tabs. 5–207 reset to initial state. 5–194 secure reset confirmation. 5–146 Restore factory defaults. 2–10, 2–18 settings. 2–9 for all. 2–16 Restoring an interrupted session. 2–13 Reverse and blank attributes. 2–23 Reverse video. 5–201 Review previous lines. 2–21 buffer. 2–21 Right-to-left mode cursor, 5–93 Rl.—Reverse index. 4–4 RLSD. 9–6 Romanian PC keyboard. A–18 ROM cartridge error. 2–3 RS-232 port data	printer port, 5-178	c
request mode, 5–108 reset mode, 5–108 reset mode, 5–108 restore presentation state, 5–116 restore terminal state, 5–117 set mode, 5–206 tab stop report, 5–157 terminal state, 5–160 color tablic peprt, 5–161 terminal unit ID, 5–104 tertiary device attributes (DA3), 5–12 user-defined keys, 5–179 Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Scan codes sent in PCTerm mode EFC keyboards, 8–23 VT keyboard, 8–27 SCO Console cursor key codes, 6–6 editing keypad key codes, 6–6 editing keypad key codes, 6–6 emulation, 6–1 emulation mode, 5–159 function key codes, 6–2 local function keys, 6–2 main keypad key codes, 6–6 editing keypad key codes, 6–6 emulation, 6–1 emulation mode, 5–159 function key codes, 6–2 local function keys, 6–7 scodpec (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 selecting character sets, 7–5 with ASCII keycodes, 6–1 with Scancode keycodes, 6–1 settings, 2–9 for all, 2–16 Scan codes sent in PCTerm mode EFC keyboards, 8–23 VT keyboard, 8–27 SCO Console cursor key codes, 6–6 editing keypad key codes, 6–6 emulation, 6–1 scancodes, 5–201 scancodes, 5–21 scancodes, 5–81 scancod	report mode, 5–98	<u>3</u>
rester mode, 5–195 restore presentation state, 5–116 restore terminal state, 5–117 color table, 5–118 secondary device attributes (DA2), 5–11 set mode, 5–206 color table report, 5–161 terminal unit ID, 5–104 tertiary device attributes (DA3), 5–12 user-defined keys, 5–179 Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 reset to initial state, 5–194 settings, 2–9 for all, 2–16 Scan codes sent in PCTerm mode EFC keyboards, 8–23 VT keyboards, 8–27 SCO Console cursor key codes, 6–6 editing keypad key codes, 6–8 estings. 7–9 SCODFC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (sa		Save
restore presentation state, 5–116 restore terminal state, 5–118 secondary device attributes (DA2), 5–11 set mode, 5–206 tab stop report, 5–160 color table report, 5–161 terminal unit ID, 5–104 tertitary device attributes (DA3), 5–12 user-defined keys, 5–179 Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Scan codes sent in PCTerm mode EPC keyboards, 8–23 VT keyboards, 8–27 SCO Console cursor key codes, 6–6 editing keypad key codes, 6–6 emulation mode, 5–159 function key codes, 6–2 local function keys, 6–2 main keypad key codes, 6–3 scancodes, 5–81 SCODPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save cursor position), 6–9 SCOSC (save cursor position), 6–9 SCO Control Function key, 6–7 SCOPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 ESC Q Fin String (SCODFK), 6–7 ESC xx (SCODPCC), 6–8 by Mnemonic SCODFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (save current cursor position), 6–9 SAVIN SCONPC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 SCOSC (save current cursor position), 6–	request mode, 5–108	
restore terminal state, 5-117 color table, 5-118 secondary device attributes (DA2), 5-11 set mode, 5-206 color table report, 5-161 terminal unit ID, 5-104 tertiary device attributes (DA3), 5-12 user-defined keys. 5-179 Resetting modem control mode, 5-73 session, 2-10 terminal secure reset, 5-144 soft reset, 2-10 Resetting the terminal. 5-207 clearing tabs, 5-207 reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings. 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Review lines of text, 2-21 Review lines of text, 2-21 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Review previous lines, 2-21 buffer, 2-21 RT-Reverse index, 4-4 RLSD, 9-6 Romamian PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RTS, 9-4 RXD, 9-4  Scan codes sent in PCTerm mode EPC keyboards, 8-23 VT keyboards, 8-27 SCO Console cursor key codes, 6-6 entitiate, keypand key codes, 6-6 entitiation, 6-1 entuation,		<del>-</del>
color table, 5–118 secondary device attributes (DA2), 5–11 set mode, 5–206 tab stop report, 5–167 terminal state, 5–160 color table report, 5–161 terminal unit ID. 5–104 tertiary device attributes (DA3), 5–12 user-defined keys, 5–179 Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabls, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restorre factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Reptice provided cursor, 5–93 RT.—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, A–18 ROM cartridge error, 2–3 RTS, 9–4 RRUSSian PC keyboard, A–19 RXD, 9–4		
secondary device attributes (DA2), 5–11 set mode, 5–206 tab stop report, 5–157 terminal state, 5–160 color table report, 5–161 terminal unit ID, 5–104 tertlary device attributes (DA3), 5–12 user-defined keys, 5–179 Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Review lines of text, 2–21 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Replaced, 5–81 RC-Reverse index, 4–4 RLSD, 9–6 ROM cartridge error, 2–3 RTS, 9–4 RUSSIAN PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  EPC keyboards, 8–23 VT keyboards, 8–27 SCO Console cursor key codes, 6–6 editing keypad key codes, 6–6 editing keypad key codes, 6–6 emulation, 6–1 emulation mode, 5–159 function keys. 6–2 main keypad key codes, 6–8 scancedes, 5–81 SCODFK (define function key), 6–7 SCODFC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save cursor positi		
set mode. 5-206 tab stop report, 5-157 terminal state, 5-160 color table report, 5-161 terminal unit ID, 5-104 tertitary device attributes (DA3), 5-12 user-defined keys, 5-179 Resetting modem control mode, 5-73 session, 2-10 terminal secure reset, 5-144 soft reset, 2-10 Resetting the terminal, 5-207 clearing tabls, 5-207 reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse video, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Review previous lines, 2-21 Review previous lines, 2-21 Reviere previous lines, 2-21 Scoop K (define function key), 6-7 ESC Xx (SCODPCC), 6-8 SCORC (restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 SCOSC (save current cursor position), 6-9 Scopp C (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 Scopp C (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 Scopp C (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 Scopp C (dest, 6-2 mulation mode, 5-159 function key, 6-2 main keypad key codes, 6-1 SCOPPK (define function key),		
tab stop report, 5–167 terminal state, 5–160 color table report, 5–161 terminal unit ID, 5–104 tertiary device attributes (DA3), 5–12 user-defined keys, 5–179 Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse wide, 5–201 Review previous lines, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RISD, 9–6 ROmanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RS-32 port data error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  settings (2–2) RXD, 9–4  secondes, 5–81 SCO Console cursor key codes, 6–6 editing keypad key codes, 6–6 emulation, 6–1 emulation mode, 5–159 function key codes, 6–2 local function key, 6–7 scoder, 6–2 main keypad key codes, 6–2 scan function key, 6–7 SCOPCC (display PC characters), 6–8 SCOR		
terminal state, 5–160 color table report, 5–161 terminal unit ID, 5–104 tertitary device attributes (DA3), 5–12 user-defined keys, 5–179 Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 ROM cartridge error, 2–3 RTS, 9–4 RUSSian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  settings (DA3), 5–12 editing keypad key codes, 6–6 emulation, 6–1 emulation mode, 5–159 function keys, 6–2 main keypad key codes, 6–6 emitiation mode, 5–159 function keys, 6–2 main keypad key codes, 6–6 emitiation, 6–1 emulation mode, 5–159 function keys, 6–2 main keypad key codes, 6–6 emiting keypad key codes, 6–6 emiting tweppad key codes, 6–8 emulation mode, 5–159 function keys, 6–2 main keypad key codes, 6–8 emulation mode, 5–159 function keys, 6–2 main keypad key codes, 6–8 emulation mode, 5–159 function keys, 6–2 main keypad key codes, 6–2 maliton mode, 5–159 function keys, 6–2 main keypad key codes, 6–2 main keypad key co		<u>s</u>
color table report, 5-161 terminal unit ID, 5-104 tertiary device attributes (DA3), 5-12 user-defined keys, 5-179 Resetting modem control mode, 5-73 session, 2-10 terminal secure reset, 5-144 soft reset, 2-10 Resetting the terminal, 5-207 clearing tabs, 5-207 reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Resetring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse video, 5-201 Review previous lines, 2-21 buffer, 2-21 Right-to-left mode cursor, 5-93 RI—Reverse index, 4-4 RISD, 9-6 Romanian PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RS 232 port data error, 2-3 RTS, 9-4 RUSSian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  emulation, 6-1 emulation mode, 5-159 function key codes, 6-2 local function keys, 6-2 main keypad key codes, 6-6 emulation, 6-1 emulation mode, 5-159 function key codes, 6-2 local function keys, 6-2 main keypad key codes, 6-2 emulation mode, 5-159 function key codes, 6-2 local function keys, 6-2 main keypad key codes, 6-2 local function key, 6-7 SCODFC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 selecting character sets, 7-5 with ASCII keycodes, 6-1 with Scancode keycodes, 6-1 with Scancode keycodes, 6-1 with Scancode keycodes, 6-1 with Scancode keycodes, 6-1 with ASCII keycode, 6-9 CSI u (SCORC),		
terminal unit ID, 5-104 tertiary device attributes (DA3), 5-12 user-defined keys, 5-179 Resetting modem control mode, 5-73 session, 2-10 terminal secture reset, 5-144 soft reset, 2-10 Resetting the terminal, 5-207 clearing tabs, 5-207 reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse and blank attributes, 2-33 Reverse video, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Right-to-left mode cursor, 5-93 RI-Reverse index, 4-4 RLSD, 9-6 Romanian PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  RXD, 9-4  emulation mode, 5-159 function key codes, 6-2 main keypad key codes, 6-3 scancodes, 5-81 SCODFK (define function key), 6-7 SCODFC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 ESC Q Fn String (SCODFK), 6-7 ESC XX (SCODPCC), 6-8 by Mnemonic SCODFK (define function key), 6-7 SCODPCC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 by Name Define function key, 6-7 SCODPCC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 by Name Define function key, 6-7 SCODPCC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 SCORC (restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 SCOSC (sav		
tertiary device attributes (DA3), 5–12 user-defined keys, 5–179  Resetting modem control mode, 5–73 session, 2–10 terminal secure reset, 5–144 soft reset, 2–10  Resetting the terminal, 5–207 clearing tabs. 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Review lines of text, 2–21 Review previous lines, 2–21 suffer, 2–21 Rejht-to-left mode cursor, 5–93 RT-Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 RCM cartridge error, 2–3 RS-232 port data error, 2–3 RS-232 port data error, 2–3 RS-232 port data error, 2–3 RSD, 9–4  emulation mode, 5–159 function key codes, 6–2 local function keys, 6–2 main keypad key codes, 6–3 scancodes, 5–81 SCODFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save cursor position) CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 CSI u (SCOPCC), 6–8 by Mnemonic SCOPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCSC (save current cursor position), 6–9 SCSC (save current cursor position), 6–9 by Name Define function key, 6–7 SCOPPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCSC (save current cursor position), 6–9 SCSC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCSC (crestore saved cursor position), 6–9 SCSC (crestore saved cursor position), 6–9 SCSC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCSC (crestore saved cursor		
user-defined keys, 5-179  Resetting modem control mode, 5-73 session, 2-10 terminal secure reset, 5-144 soft reset, 2-10 Resetting the terminal, 5-207 clearing tabs, 5-207 reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse and blank attributes, 2-33 Reverse wideo, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Right-to-left mode cursor, 5-93 RI-Reverse index, 4-4 RLSD, 9-6 Romanian PC keyboard, A-18 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, B-22 VT keyboard, A-19 RXD, 9-4  RXD, 9-4  RXD, 9-4  RXD, 9-4  Function key, 6-2 main keypad key codes, 6-3 scancodes, 5-81 SCOBFK (define function key), 6-8 SCOSC (save cursor position), 6-9 selecting character sets, 7-5 with ASCII keycodes, 6-1 with Scal robe saved cursor position), 6-9 SEC Q. Fn String (SCODFK), 6-7 ESC XX (SCODPC), 6-8 by Memonic SCODPK (define function key), 6-7 SCODPC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 SCOSC (save cursor position), 6-9 selecting character sets, 7-5 with ASCII keycodes, 6-1 SCO control sequences by Control Function CSI s (SCOSC), 6-9 ESC Q. Fn String (SCODFK), 6-7 ESC XX (SCODPC), 6-8 by Memonic SCODPK (define function key), 6-7 SCODPC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 SCOSC (save cursor position), 6-9 SCOSC (save current cursor position), 6-9 SCO voltrol Function CSI s (SCOSC), 6-9 SCO voltrol Function CSI s (SCOSC), 6-9 SCO voltrol Function CSI s (SCODPC), 6-8 by Memonic SCODPK (define function key), 6-7 ESC XX (SCODPC), 6-8 by Memonic SCO prik (define function key), 6-7 SCOSC (save current cursor position),		
modem control mode, 5-73 modem control mode, 5-73 session, 2-10 terminal secure reset, 5-144 soft reset, 2-10 Resetting the terminal, 5-207 clearing tabs, 5-207 reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse video, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 Review previous lines, 2-21 Review previous lines, 2-21 Review previous lines, 2-21 Romannian PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 RUSD, 9-6 RESECTING (Afine function key), 6-7 SCODPCC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 RESC xx (SCODPCC), 6-8 Restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 RESC xx (SCODPCC), 6-8 Restore saved cursor position), 6-9 RESC xx (SCODPCC), 6-8 Restore saved cursor position), 6-9 SCOSC (save current cursor position), 6-9 SCOSC (save current cursor position), 6-9 RESC xx (SCODPCC), 6-		
moden control mode, 5-73 session, 2-10 session, 2-10 secure reset, 5-144 soft reset, 2-10 Resetting the terminal, 5-207 clearing tabs, 5-207 reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse video, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Right-to-left mode cursor, 5-93 RI—Reverse index, 4-4 RISD, 9-6 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 Russian PC keyboard, A-19 RXD, 9-4 RXD, 9-4 READ ROM cartridge arror, 2-2 RXD, 9-4 RXD, 9-4 RXD, 9-4 RXD, 9-4 READ ROM cartridge arror, 2-2 RXD, 9-4 RXD, 9-4 RXD, 9-4 RXD, 9-4 RXD, 9-4 RAD		
session, 2–10 terminal secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Resetoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review previous lines, 2–21 buffer, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RISD, 9–6 Romanian PC keyboard, B–21 VT keyboard, B–21 VT keyboard, A–18 RSS-232 port data error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4 RXD, 9–4  RXD, 9–4  RXD, 9–4  Rasian Rain keypad key codes, 6–3 scancodes, 5–81 SCODFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSDFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 SCONCC (restore saved cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCOSC), 6–9 Save current cursor position (SCOSC), 6–9 Saver, 2–22 display control functions, 5–147 to 5–148 processing		
terminal secure reset, 5–144 soft reset, 2–10  Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RISD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  scancodes, 5–81 SCODFK (define function key), 6–7 SCOSC (save cursor position), 6–9 SCOSC (socodes, 6–1 SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 ESC xx (SCODFCC), 6–8 by Mnemonic SCODFK (define function key), 6–7 ESC xx (SCODFCC), 6–8 by Mnemonic SCODFK (define function key), 6–7 ESC xx (SCODFCC), 6–8 by Mnemonic SCODFK (define function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 ESC xx (SCODFCC), 6–8 by Mnemonic SCODFK (define function key), 6–7 ESC xx (SCODFCC), 6–8 by Mnemonic SCODFC (display PC characters), 6–8 by Mnemon		
secure reset, 5–144 soft reset, 2–10 Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 RIGht-to-left mode cursor, 5–93 RI-Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RS-232 port data error, 2–3 RTS, 9–4 RUSSI RXD, 9–4  SCODFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 SCOSC (save cursor position), 6–9 selecting character sets, 7–5 with ASCII keycodes, 6–1 with Scancode keycodes, 6–1 SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 CSI u (SCORC), 6–9 ESC Q Fn String (SCODFK), 6–7 ESC xx (SCODPCC), 6–8 by Mnemonic SCOPC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 by Name Define function key), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCOSC), 6–9 Save current cursor position (SCOSC), 6–9 Save current cursor position, 6–9 selecting character sets, 7–5 with ASCII keycodes, 6–1 with Scancode keycodes, 6–1 SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 ESC xx (SCODPCC), 6–8 by Mnemonic SCORC (restore saved cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCOSC), 6–9 Save current cursor position (SCOSC), 6–9 Save cursor posit		<b>5.1 5</b>
soft reset, 2–10  Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 RCSCOSC Reverse video, 4–201 RCSC (save cursor position), 6–9 by Name Define function key), 6–7 Display PC characters, 6–8 SCORC (restore saved cursor position), 6–9 selecting character sets, 7–5 with ASCII keycodes, 6–1 SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 CSI u (SCORC), 6–9 ESC Q Fn String (SCODFK), 6–7 ESC xx (SCODPCC) (de-play PC characters), 6–8 SCORC (restore saved cursor position) CSI s (SCOSC) SCOSC (seve current cursor position) CSI s (SCOSC), 6–9 SCOSC (save current cursor position), 6–9 by Mame Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCOSC), 6–9 Save current cursor position (SCOSC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling		
Resetting the terminal, 5–207 clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review previous lines, 2–21 Review previous lines, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RS-232 port data error, 2–3 RTS, 9–4 RUSD, 9–4  RXD, 9–4  RXD, 9–4  SCORC (restore saved cursor position), 6–9 SCOSC (save cursor position), 6–9 SCOSC (save cursor position), 6–9 SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 CSCORC (save current cursor position (SCORC), 6–9 CSCORC (save current curs		
clearing tabs, 5–207 reset to initial state, 5–194 secure reset confirmation, 5–146 Restore  factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 Bright-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RS-232 port data error, 2–3 RS-232 port data error, 2–3 RXD, 9–4 RXD, 9–4 RXD, 9–4  SCOSC (save cursor position), 6–9 selecting character sets, 7–5 with ASCII keycodes, 6–1 With Scancode keycodes, 6–1 SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 CSI u (SCORC), 6–9 CSI u (SCORC), 6–9 ESC Q Fn String (SCODFK), 6–7 ESC Xx (SCODPCC), 6–8 by Mnemonic SCODPC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22	•	
reset to initial state, 5-194 secure reset confirmation, 5-146 Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse video, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Right-to-left mode cursor, 5-93 RI—Reverse index, 4-4 RISD, 9-6 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 RXD, 9-4  selecting character sets, 7-5 with ASCII keycodes, 6-1 SCO control sequences by Control Function CSI s (SCOSC), 6-9 CSI u (SCORC), 6-9 ESC Q Fn String (SCODFK), 6-7 ESC xx (SCODPCC), 6-8 by Mnemonic SCODFK (define function key), 6-7 SCODPCC (display PC characters), 6-8 SCOSC (save current cursor position), 6-9 by Name Define function key (SCODFK), 6-7 Display PC characters (SCODPCC), 6-8 Restore saved cursor position (SCORC), 6-9 Save current cursor position (SCOSC), 6-9 Screen alignment, 2-27 background, 2-22 display control functions, 5-147 to 5-148 processing ASCII, 12-10 saver, 2-24 Scrolling jump, 2-22 mode, 2-22 rate, 2-22		•
secure reset confirmation, 5–146 Restore Restore factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RSTS, 9–4 Russian PC keyboard, B–22 VT keyboard, B–22 VT keyboard, A–19 RXD, 9–4  RXD, 9–4  with Scancode keycodes, 6–1 SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 ESC xx (SCODPCC), 6–8 by Mnemonic SCOPFK (define function key), 6–7 ESC xx (SCODPCC), 6–8 SCOPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22		
Restore factory defaults, 2-10, 2-18 settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse video, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Relstore, 5-93 RI—Reverse index, 4-4 RLSD, 9-6 Romanian PC keyboard, B-21 VT keyboard, A-18 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  RXD, 9-4  RESTORE (Reverse index setting) RXD, 9-4  RXD, 9-4  With Scancode keycodes, 6-1  SCO ontrol sequences by Control Function CSI s (SCOSC), 6-9 CSI u (SCORC), 6-8 by Mnemonic SCODFK (define function key), 6-7 SCODPCC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 by Name Define function key (SCODFK), 6-7 Display PC characters (SCODPCC), 6-8 Restore saved cursor position (SCORC), 6-9 Save current cursor position (SCOSC), 6-9 Screen RITS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  ASCII, 12-10 Saver, 2-24 Scrolling Jump, 2-22 mode, 2-22 rate, 2-22	_	
factory defaults, 2–10, 2–18 settings, 2–9 for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Rejth-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 RS-232 port data error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, B–22 VT keyboard, A–19 RXD, 9–4  RXD, 9–4  SCO control sequences by Control Function CSI s (SCOSC), 6–9 CSI u (SCORC), 6–9 ESC Q Fn String (SCODFK), 6–7 ESC Xx (SCODPCC), 6–8 by Mnemonic SCODFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22	Restore	
settings, 2-9 for all, 2-16 Restoring an interrupted session, 2-13 Reverse and blank attributes, 2-33 Reverse video, 5-201 Review lines of text, 2-21 Review previous lines, 2-21 buffer, 2-21 Right-to-left mode cursor, 5-93 RI—Reverse index, 4-4 RLSD, 9-6 Romanian PC keyboard, A-18 ROM cartridge error, 2-3 RFS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  by Control Function CSI s (SCOSC), 6-9 CSI u (SCORC), 6-9 ESC Q Fn String (SCODFK), 6-7 ESC xx (SCODPCC), 6-8 by Mnemonic SCODFK (define function key), 6-7 SCODPCC (display PC characters), 6-8 SCORC (restore saved cursor position), 6-9 by Name Define function key (SCODFK), 6-7 Display PC characters (SCODPCC), 6-8 Restore saved cursor position (SCORC), 6-9 Save current cursor position (SCORC), 6-9 Screen alignment, 2-27 background, 2-22 display control functions, 5-147 to 5-148 processing ASCII, 12-10 saver, 2-24 Scrolling jump, 2-22 mode, 2-22 rate, 2-22	factory defaults, 2-10, 2-18	<del>-</del>
for all, 2–16 Restoring an interrupted session, 2–13 Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 Bight-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RCSD, 9–6 RCSD (save current cursor position), 6–9 By Name Romanian PC keyboard, B–21 VT keyboard, A–18 RCSD, 9–4 RUSD, 9–8 RUSD		
Reverse and blank attributes, 2–33 Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RSS-232 port data error, 2–3 RTS, 9–4 RUSD, 9–4 RSD, 9–8 RSDD, 9–8 RSDD	for all, 2-16	<u>v</u>
Reverse video, 5–201 Review lines of text, 2–21 Review previous lines, 2–21 Review previous lines, 2–21 SCODFK (define function key), 6–7 buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RTS, 9–4 RUSDA RTS, 9–4 RUSDA RYD keyboard, B–22 VT keyboard, B–22 VT keyboard, B–24 VT keyboard, B–24 VT keyboard, B–25 RTS, 9–4 RUSDA ROM cartridge error, 2–3 ROSCC (save current cursor position), 6–9 By Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 ROM cartridge error, 2–3 RTS, 9–4 RESTOR Cartridge error, 2–3 RTS, 9–4 RESTOR Cartridge error, 2–3 RTS, 9–4 RESTOR Cartridge error, 2–3 RESTOR Cartridge error, 2–3 ROM cartridge error, 2–3 RESTOR Cartridge error, 2–3 ROM cartridge error, 2–3 RESTOR Cartridge error, 2–3 ROM cartridge error, 2–3 RESTOR Cartridge error, 2–	Restoring an interrupted session, 2–13	CSI u (SCORC), 6-9
Review lines of text, 2–21 Review previous lines, 2–21 buffer, 2–21 SCODFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RS-232 port data error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  RXD, 9–4  RXD, 9–4  RXD, 9–4  By Mnemonic SCODFK (define function key), 6–7 SCODPCC (display PC characters), 6–8 SCORC (restore saved cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22	Reverse and blank attributes, 2-33	ESC Q Fn String (SCODFK), 6–7
Review previous lines, 2-21 buffer, 2-21 SCODFK (define function key), 6-7 SCODFC (display PC characters), 6-8 Right-to-left mode cursor, 5-93 RI—Reverse index, 4-4 RLSD, 9-6 Romanian PC keyboard, B-21 VT keyboard, A-18 RS-232 port data error, 2-3 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4 RXD, 9-7 RXD, 9-8	Reverse video, 5–201	ESC xx (SCODPCC), 6–8
buffer, 2–21 Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 ROM cartridge error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, B–22 VT keyboard, B–21 Screen RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  RXD, 9–4  SCOSC (save current cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22	Review lines of text, 2–21	by Mnemonic
Right-to-left mode cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 RS-232 port data error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, B–22 VT keyboard, A–19 RXD, 9–4  RXD, 9–4  RXD, 9–4  RXD, 9–4  RXD, 9–4  RXD, 9–4  RESCORC (restore saved cursor position), 6–9 SCOSC (save current cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22	Review previous lines, 2-21	
cursor, 5–93 RI—Reverse index, 4–4 RLSD, 9–6 Romanian PC keyboard, B–21 VT keyboard, A–18 RSOM cartridge error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  RXD, 9–4  RXD, 9–4  RXD, 9–4  RISD, 9–6  SCOSC (save current cursor position), 6–9 by Name Define function key (SCODFK), 6–7 Display PC characters (SCODPCC), 6–8 Restore saved cursor position (SCORC), 6–9 Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22		- v
RI—Reverse index, 4-4 RLSD, 9-6 Romanian PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4 R		SCORC (restore saved cursor position),
RLSD, 9-6 Romanian PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  RXD, 9-4  RXD, 9-4  RXD, 9-4  By Name Define function key (SCODFK), 6-7 Display PC characters (SCODPCC), 6-8 Restore saved cursor position (SCORC), 6-9 Save current cursor position (SCOSC), 6-9 Screen alignment, 2-27 background, 2-22 display control functions, 5-147 to 5-148 processing ASCII, 12-10 saver, 2-24 Scrolling jump, 2-22 mode, 2-22 rate, 2-22		
Romanian  PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  RXD, 9-4  ROM cartridge error, 2-3  RS-232 port data error, 2-3  Screen alignment, 2-27 background, 2-22 display control functions, 5-147 to 5-148 processing ASCII, 12-10 saver, 2-24  Scrolling jump, 2-22 mode, 2-22 rate, 2-22	T. CT	
PC keyboard, B-21 VT keyboard, A-18 ROM cartridge error, 2-3 RS-232 port data error, 2-3 RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  Display PC characters (SCODPCC), 6-8 Restore saved cursor position (SCORC), 6-9 Save current cursor position (SCOSC), 6-9 Screen alignment, 2-27 background, 2-22 display control functions, 5-147 to 5-148 processing ASCII, 12-10 saver, 2-24 Scrolling jump, 2-22 mode, 2-22 rate, 2-22		
VT keyboard, A-18  ROM cartridge error, 2-3  RS-232 port data error, 2-3  RTS, 9-4  Russian PC keyboard, A-19  RXD, 9-4  RXD, 9-4  Restore saved cursor position (SCORC), 6-9  Save current cursor position (SCOSC), 6-9  Screen alignment, 2-27 background, 2-22 display control functions, 5-147 to 5-148 processing ASCII, 12-10 saver, 2-24  Scrolling jump, 2-22 mode, 2-22 rate, 2-22		
ROM cartridge error, 2–3 RS-232 port data error, 2–3 RTS, 9–4 Russian PC keyboard, B–22 VT keyboard, A–19 RXD, 9–4  RXD, 9–4  RXD, 9–4  RXD, 9–4  ROM cartridge Save current cursor position (SCOSC), 6–9 Screen alignment, 2–27 background, 2–22 display control functions, 5–147 to 5–148 processing ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22	· ·	1 V
error, 2–3  RS-232 port data error, 2–3  RTS, 9–4  Russian  PC keyboard, B–22  VT keyboard, A–19  RXD, 9–4  Save current cursor position (SCOSC), 6–9  Screen  alignment, 2–27  background, 2–22  display control functions, 5–147 to 5–148  processing  ASCII, 12–10  saver, 2–24  Scrolling  jump, 2–22  mode, 2–22  rate, 2–22		
RS-232 port data error, 2–3  RTS, 9–4  Russian  PC keyboard, B–22  VT keyboard, A–19  RXD, 9–4  Screen  alignment, 2–27  background, 2–22  display control functions, 5–147 to 5–148  processing  ASCII, 12–10  saver, 2–24  Scrolling  jump, 2–22  mode, 2–22  rate, 2–22	0	
RTS, 9-4 Russian PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  ASCII, 12-10 saver, 2-24 Scrolling jump, 2-22 mode, 2-22 rate, 2-22		
Russian  PC keyboard, B-22  VT keyboard, A-19  RXD, 9-4  ASCII, 12-10  saver, 2-24  Scrolling  jump, 2-22  mode, 2-22  rate, 2-22		
PC keyboard, B-22 VT keyboard, A-19 RXD, 9-4  ASCII, 12-10 saver, 2-24 Scrolling jump, 2-22 mode, 2-22 rate, 2-22		
VT keyboard, A–19  RXD, 9–4  ASCII, 12–10  saver, 2–24  Scrolling  jump, 2–22  mode, 2–22  rate, 2–22		
ASCII, 12–10 saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22	<b>5</b>	
saver, 2–24 Scrolling jump, 2–22 mode, 2–22 rate, 2–22		
Scrolling jump, 2–22 mode, 2–22 rate, 2–22	ivib, o i	
jump, 2–22 mode, 2–22 rate, 2–22		
mode, 2–22 rate, 2–22		<u> </u>
rate, 2–22		

SCS	Set-Up
PC keyboard, B-23	communications (cont'd)
VT keyboard, A-20	local echo, 2-50
Select Select	modem menu, 2–52
color mode, 2–32	receive flow control, 2-49
Selecting	receive speed, 2–48
character sets	select sessions, 2–46
ASCII control functions, 13–3	stop bits, 2-47
Selective parameters, 4–7	transmit flow control, 2-48
Self-test	transmit rate limit, 2-49
error messages, 2–3	transmit speed, 2–48
Sending data	word size, 2–47
ASCII, 12–32	communications menu, 2-45
ASCII control functions, 12–34	context sensitivity, 2–3
Session Session	control codes to set features, 2-61
menu, 2–13	copy settings from menu, 2-17
Sessions, 1–6	CRT saver, 2-24
control functions, 4–16	cursor coupling
management, 4-16	vertical, 2–22
multiple, 2–11	cursor display, 2-22
enabling and controlling configuration,	default character set
2–12	PC, 2-34
management, 2–13	VT, 2-34
pages, 2–14	defaults, 2–61
selection, 2–14	define colors, 2–31
using a terminal server with TD/SMP,	define key editor, 2-37
2–12	copy key default, 2-38
opening another session, 2–12	correcting a mistake, 2-40
restoring an interrupted session, 2–13	creating a new function, 2-39
using SSU Host software, 2–12	creating a new key definition, 2-40
reset, 2–18	user-defined keys, 2–41
session name, 2–14	desktop features
switching, 3–8	banner message, 3-1
updating, 2–17	calculator, 3-1, 3-2
Setting modem control mode, 5–73	clock, 3-1, 3-5
Set-Up, 2–1	show character sets, 3-1, 3-7
actions menu, $2-7$ , $2-9$	dim menu items, 2–3
alternate text colors, $2-30$	display menu, 2-19
ASCII color mode, 2–32	effects of entering, 2–2
ASCII emulation menu, 2–35	emulation mode, 2-33
assign colors, 2–28	energy saver, 2–24
auto repeat rate, 2–43	entering, 2–1
auto resize, 2–20	erase color, 2–32
auto resize, $z=z_0$ auto wrap, $z=23$	exiting, 2–9
banner message, 2–11	framed windows, 2-25
7-bit NRCS, 2–34	keyboard encoding, 2-43
bold and blink style, 2–32	keyboard language, 2-37
calculator, 2–11	keyboard menu, 2-36
caps lock, 2–42	keyclick, 2–42
clear communications, 2–9	languages, 2–2
clear display, 2-9	lines per page, 2-20
clock, 2-11	lines per screen, 2–20
columns per page, 2–22	lock key definitions, 2-42
communications	lock out, 2–1
auto answerback, 2–50	lock user preferences, 2–23
Fkey rate limit, 2–49	main menu, 2-7, 2-8
half-duplex, 2–50	margin bell, 2–42
ignore null characters, 2–50	modem
ignore nun characters, 2-30	

Set-Up	Set-Up (cont'd)
modem (cont'd)	transmit 7-bit controls, 2-34
disconnect delay, 2-52	warning bell, 2-25, 2-42
enable modem control, 2-52	writing direction, 2-23
speed, 2–53	zero symbol, 2–23
modem menu, 2–52	Show
multiple sessions, 2–11	character sets, 2-11
management, 2–13	control characters, 2-24, 4-11
pages, 2–14	C0 control characters, 4-15
reset, 2–18	C1 control characters, 4–15
selection, 2–14	Single-shift (SS) commands, 5-205
session name, 2–14	Slovak
updating, 2–17	PC keyboard, B-24
using a terminal server with TD/SMP,	VT keyboard, A-21
2–12	Soft character set
opening another session, 2–12	clearing, 7–16
restoring an interrupted session, $2-13$	example, 7–15
using SSU Host software, 2–12	Soft character sets, 7–5 to 7–16
new line mode, 2–23	coding, 7–9
page coupling, 2–23	designating, 7–14
power-on settings, 2–2	designing, 7–6
printer	downloading, 7–13
character sets, 2–55	Soft key mapping, Glossary-3
flow control, 2–57	Soft terminal reset, 2–10
ignore null characters, 2–50	Software flow control, 1–1
mode, 2–54	Sound
parity, 2-58	notes available, 2-60
port select, 2–54	types of, 2–59
print extent, 2–56	Spanish
print terminator, 2–56	PC keyboard, B-25
speed, 2–56	VT keyboard, A-22
stop bits, 2–58	SPDI, 9-6
type, 2-55	SPDS, 9–7
word size, 2–57	Split screen, 12–12
printer menu, 2–54	Status
recall key definitions, 2–42	display, 2–22
reset this session, 2–10	lines
resetting and restoring defaults, 2–18	ASCII control functions, 12–13
restore factory defaults, 2–10, 2–18	messages, 2–5
restore settings, 2–9	Sticky keys, 2–6
restore settings for all, 2–16 reverse and blank, 2–33	See Accessibility aids
review previous lines, 2–21	Stop bits, 2–47
save key definitions, $2-42$	SUB character, 4–9
save key definitions, $z=4z$ save settings, $z=9$	Supplemental character sets
save settings, $z=0$ save settings for all, $z=16$	See User-preferred supplemental character sets
screen background, 2–22	Suspending
scrolling, 2–22	printer operations, 10-7
select color mode, 2–32	Swedish
session menu, 2–13	PC keyboard, B-26
show character sets, 2–11	VT keyboard, A-23
show control characters, 2–24	Swiss
soft character sets, 2–16	French
status messages, 2–5	PC keyboard, B-27
summary line, 2–5	VT keyboard, A-24
tabs, 2–58	German
terminal ID to host, 2–34	PC keyboard, B-28
terminal type, 2–33	VT keyboard, A–25
v =	

	VT52 mode
T	escape sequences, 4–45
·	VT keyboard
Tabs	Austrian, A–2
dialog box, 2–59	Belgian, A–3
setting, 2–58	British/U.K., A-4
Tabulation	Canadian, A–4
ASCII control functions, 12–26	Canadian-French, A–5
Terminal	Czech, A–6
ID, 1-6	Danish, A–7
ID to host, 2–34	Dutch, A-8
management	Finnish, A–9
ASCII, 12–4	Flemish, A-10
type menu, 2–33	French, A–3
Terminal management	German, A–2
control functions, 4–34	Greek, A–11
defined, 4–15	Hebrew, A-12
Terminal state reports, 5–117	Hungarian, A–13
color table, 5–118	Italian, A–14
Terminal synchronization	legend data, A–1
control functions, 4–41	North American, A–4
Testing the terminal	Norwegian, A-15
screen alignment pattern, 5–17	Polish, A-16
Text	Portuguese, A-17
capabilities, 1–3	Romanian, A-18
processing, 4–22	Russian, A-19
Transmit	scan codes, 8–27
7-bit controls, 2–34	SCS, A-20
flow control, 2–48	Slovak, A-21
rate limit, 2–49	Spanish, A–22
speed, 2–48	Swedish, A-23
Transmitting print data, 10–4	Swiss-French, A–24
Turkish-F	Swiss-German, A–25
VT keyboard, A-26	Turkish-F, A-26
Turkish-Q	Turkish-Q, A–27
PC keyboard, B-29	VT keyboards, A-1
VT keyboard, A-27	
Two-way communications, 2–57	W
TXD, 9-4	-
	Warning bell, 2–25
U	Window
UDK	adjustment, 3–8
correcting mistakes, 2–40	framed, 2–25
Underlining, 5–201	Windowing, 2–25
Unlocking keyboard, 5–185	two windows, 2–26 Windows
Use of VT420 keyboards, 1–6	ASCII control functions, 12–13
User-defined keys, 2–41, 5–163	Word size, 2–47
User-preferred supplemental character sets, 5–24	
eser preferred suppremental character sets, o 21	Writing
V	direction, 2–23
V	WYSE Enhanced mode, 13-1
Vertical	
coupling, 2–22	
Visible bell, 2-43	
Visual attributes	

control functions, 4-20

### X

XON/XOFF, 9–11 description, 11–3 XPC flow control, 9–11

 $\frac{\textbf{Z}}{\text{Zero symbol}, 2-23}$